



ADDENDUM NO.: 1
DATE OF CMR ADDENDUM: 01.16.2013

**Notice of Construction Manager-at-Risk (CMR)
Addendum
on behalf of the
CT Department of Construction Services (CT DCS)**

Project Name:	Southern Connecticut State University Buley Library Renovation
Project Location:	New Haven, CT
Project Description:	Core & Shell & Fit-Out
Project Construction Budget:	20.7 Million
CT DCS Project Number:	BI-RS-225B CMR

The Construction Manager-at-Risk (CMR) is issuing a **Notice of CMR Addendum** for this State of CT Department of Construction Services (CT DCS) Project. Specific Addendum Information is available as noted below. If you have any questions, please contact the CMR as noted below.

CMR Information:

CMR Firm:	Skanska USA Building Inc.
Address:	545 Long Wharf Drive, 6 th Floor
Contact Name:	Kate Westrin
Contact Phone Number:	203-859-7708
Contact Email Address:	Kate.westrin@skanska.com

Addendum Information is available as follows:

CMR Website and/or FTP Site:	https://partners.myskanska.com/usa/clients/scsu/Buley/SitePages/Home.aspx
Printing Company:	Service Point USA - 203-624-0079

Copies: DCS Project Manager DCS Process Management (randy.daigle@ct.gov)
 DCS Process Management (peter.babey@ct.gov)



January 16th, 2013

ADDENDUM NO. 1

BID DUE DATE: **Friday, February 8th, 2013**
TIME: Reference Bid Receipt and Opening Schedule in Division 0
PROJECT: SCSU Buley Library Renovations
Project No. BI-RS-225B CMR
SUBMITTED TO: Michael J. Adanti Student Center
Southern Connecticut State University
501 Crescent Street
New Haven, Connecticut 06515

C/O: Skanska USA Building Inc.
Attention: Kate Westrin

I. GENERAL ITEMS:

1. Please note the following bid dates have changed:
 - A. **BIDS DUE: FRIDAY FEBRUARY 8TH, 2013 at 11AM**
 - B. **Post Bid Scope Review Meeting Schedule- See Attached**

2. Please incorporate the attached revised Table of Contents into Division 0. This document reflects:
 - A. Issuance of Revised 00 41 00 Bid Proposal Form (See Item #3, below)
 - B. Issuance of Revised 00 31 25 Existing Inventory Materials list (See Item #4, below)
 - C. Issuance of Revised 00 70 00 Exhibit B Drawings, Sketches, Specifications & Other Documents (See Item #5 below)

3. Please incorporate the revised 00 41 00 Bid Proposal Form- Addendum #1. The following changes were made to this document:
 - A. **REVISED** 'Bid Due Date/Time' on page 1 to reflect the February 8th, 2013 date, and 11AM time as noted in Item 1A, above.
 - B. **REVISED** Section 3 EXISTING INVENTORY MATERIALS reflecting revised Addendum #1 issuance.
 - C. **REVISED** Section 5 ADDENDA
 - D. **REVISED** Section 14 BID PROPOSAL FORM ATTACHMENTS omitting 'Small Contractor & Minority Business Enterprise Goals and/or Good Faith Effort Contractor Filled out in Attachment IIIa.

4. Please incorporate the revised 00 31 25 Existing Inventory Materials List. The following changes were made to this document:
 - A. **REVISED** Stored Materials Narrative
 - B. Selective Revisions to Inventory Item Bid Package Assignments
 - C. Existing Material Inventory List Sorted by Bid Package Responsibility
 - D. Unusable Items Shaded

5. Please incorporate the revised 00 70 00 Exhibit B Drawings, Sketches, Specifications & Other Documents. The following changes were made to this document:
 - A. OMIT Drawing FPD-105
 - B. ADD Drawing FP-105
 - C. REVISE Specification Section 23 34 23 to Read 'Specification Section 23 34 33'

II. SCOPE CLARIFICATIONS/CHANGES:

To Be Issued in a Future Addendum.

III. SUBCONTRACTOR RFIs:


To Be Issued in a Future Addendum.

IV. SPECIFICATION CLARIFICATIONS/CHANGES:

None

Bidders shall acknowledge receipt of Addendum 1 under 'Addenda' on page 2 of the bid form.

Sincerely,
Skanska USA Building, Inc.



Richard Murphy, LEED® AP
Project Executive

cc: Service Point USA at 85 Willow St., Bldg. 12. New Haven, CT
Skanska Share Site: <https://partners.myskanska.com/usa/clients/UCONN/NSSB/EBPS/default.aspx>

Post-Bid Scope Review Meeting Schedule

Addendum #1

Skanska Main Office, 545 Long Wharf Drive, 6th Floor, New Haven

Tuesday, February 12th

- 9AM BP-02 Sitework
- 11AM BP-02A Landscaping
- 1PM BP-05A Miscellaneous Metals

Wednesday, February 13th

- 9AM BP-03 Concrete
- 11AM BP-02C Site Concrete
- 1PM BP-04 Masonry/Precast

Thursday, February 14th

- 9AM BP-10 Toilet Partitions & Accessories
- 11AM BP-07B Applied Fireproofing
- 1PM BP-10A Signage

Friday, February 15th

- 9AM BP-05 Structural Steel
- 11AM BP-06 Millwork
- 1PM BP-13 Fire Protection

Monday, February 18th

- 9AM BP-07 Roofing
- 11AM BP-14 Elevators
- 1PM BP-09B Painting / Wallcovering

Tuesday, February 19th

- 9AM BP-08 Curtainwall / Storefront
- 11AM BP-08A Doors, Frames & Hardware
- 1PM BP-09 Gypsum Board Assemblies

Wednesday, February 20th

- 9AM BP-15 Plumbing
- 11AM BP-15A HVAC
- 1PM BP-15B HVAC Controls

Thursday, February 21st

- 9AM BP-09A Acoustical Ceilings
- 11AM BP-17 Final Cleaning
- 1PM BP-16 Electrical

Friday, February 22nd

- 9AM BP-13A Intrusion Detection, Security Access, Video Surveillance
- 11AM BP-13B Fire Alarm
- 1PM BP-13C Communications Cabling

Monday, February 25th

- 9AM BP-09C Tile /Linoleum & Carpet
- 11AM BP-09D Poured Terrazzo
- 1PM BP-12 Window Shades

Southern Connecticut State University – Buley Library Renovation BI-RS-225B CMR

DOCUMENT 00 01 10 - TABLE OF CONTENTS

VOLUME 1 OF 1

Division 0 – PROCUREMENT AND CONTRACTING REQUIREMENTS

00 11 16	Invitation to Bid
00 11 17	Subcontractor Acknowledgement of Bidding (Mandatory)
00 21 13	Instructions to Bidders
00 24 13	Scopes of Work (<u>Ref. Sec. 00 7000 Exhibit 'A' General Requirements</u>)
00 31 13	Project Schedule / Construction Schedule Narrative
00 31 19	Site Logistics Plan
00 31 19.1	SL-01 Campus Map
00 31 19.2	SL-02 Reserved
00 31 25	Existing Materials (Inventory Sheets for Existing Stored Materials) ADDENDUM #1
00 31 25.1	RCx Deficiency Issues Log & Proposed Energy Conservation Measures to Investigate
00 31 26.26	Existing Lead Information
00 41 00	Bid Proposal Form (<i>Required at time of bid</i>) ADDENDUM #1
00 43 13	AIA 310 Bid Bond Form (<i>Required at time of bid</i>)
00 43 28	SCSU Tax Exempt Certificate
00 43 39.1	CHRO Affirmative Action Plan
00 43 39.2	CHRO Attachment IIIA (<i>Required at time of bid</i>) ADDENDUM #1: Attachment not required
00 43 43	Certified Payroll & Contractors Wage Rate Certification Form (<i>Required at time of bid</i>)
00 45 13	Subcontractor Qualification Form (<i>Required at time of bid</i>)
00 45 19	Non-Collusive Affidavit (<i>Required at time of bid</i>)
00 45 19.1	State of Connecticut Guide to the Code of Ethics & OPM Ethics Form 6 (<i>Required at time of bid</i>)
00 61 13	Consent of Surety Form (<i>Required at time of bid</i>)
00 63 13	Request for Information (RFI) Form
00 63 57	Proposed Change Form
00 70 00	Skanska Sample Subcontractor Agreement (Exhibits A thru Y): Exhibit A Scope of Work (<u>Ref. Sec. 00 2413 for Specific Requirements</u>) Exhibit B Drawings Sketches Specifications & Other Documents Exhibit C Alternates Unit Price & Labor Rates Exhibit D Project Schedule & Milestones Exhibit E Standard Subcontract Terms & Conditions Exhibit F Skanska Code of Conduct Exhibit G Skanska Insurance Requirements Exhibit H Interim Estimate for Payment, Waiver & Release Exhibit I Interim & Unconditional Waiver & Release of Liens & Claims Exhibit J Subcontractor Standard Subcontractor EH&S Requirements Exhibit K Skanska Standard Change Order Exhibit N Supplemental Terms & Conditions for use in the State of CT

Southern Connecticut State University – Buley Library Renovation BI-RS-225B CMR

	Exhibit O Payment and Performance Bonds
	Exhibit Q Skanska Standard Environmental Insurance Requirements
	Exhibit U Subcontractor Identification
	Exhibit V Guarantee to Owner
	Exhibit X Site Requirements and Logistics
	Exhibit Y Terms & Conditions for Subcontractor Design Responsibility
00 70 01	Standard Form of Agreement Between Owner and CMR
00 73 19	Skanska Safety & Health Management Program
00 73 43	Prevailing Wage Rates

BID PROPOSAL FORM

Project: Buley Library Renovations BI-RS-225B CMR

Bid Package: _____

Bid Package No.: _____

Bid Due Date/Time: Friday, February 8th, 2013 – 11am

(BIDDER MUST SUBMIT SEPARATE BID FORMS WHEN BIDDING MULTIPLE PACKAGES)

Proposal Submitted By:

Company Name _____
Address _____

Telephone _____
Fax _____

Subcontractor License No. _____

Subcontractor EMR Rate _____

Federal Tax ID No. _____

Business Classification MBE WBE SBE

1. BASE BID

The above noted Bidder hereby proposes to provide for all work as defined in the Contract Documents and any incidental work necessary to construct a complete, working, and fully operational system for all work as defined herein, for the totally inclusive lump sum amount, including all applicable sales and use taxes of:

(Written) _____ \$ _____

Note #1 - The award of subcontracts for a specific bid package will be based on the lowest qualified and responsible Subcontractor base bid plus those Supplemental Bids selected. The selection of supplemental bids will be determined after the bid opening and is contingent on the available project funds.

Note #2 - The award of supplemental bids will be taken in order as they appear in section 6 of the Subcontractor Proposal Form. If project funds do not allow for a supplemental bid to be taken in its entirety, the owner reserves the right to add portions of the supplemental bid. The definition of "Supplemental Bid" is outlined in the Section # of the Instruction to Bidders.

Southern Connecticut State University – Buley Library Renovation BI-RS-225B CMR

Note #3 - If project funds do not allow for a supplemental bid to be taken in its entirety, the owner reserves the right to add portions of the supplemental bid in following order from first to last: BP15A, BP15, BP16, BP13, BP13B, BP09, BP08A, BP09A, BP08A, BP06, BP09B, BP09C, BP06, BP12, BP10A, and BP13A. Remaining trades not listed will be selected at the owner's discretion.

2. CONTRACT

Bidder has reviewed the Skanska USA Building Inc. Subcontract Agreement, acknowledges all requirements are included in the above lump sum price, and agrees to sign upon contract award without modification:

Acknowledged (box must be marked)

3. EXISTING INVENTORY MATERIALS

Bidder has reviewed the Existing Inventory Materials list included in section **00 31 25, and subsequent Addendum #1 Inventory Update** and has included those materials assigned to your specific bid package for use on this project. Bidder is responsible for the transportation of inventory materials from storage facilities to your shop for fabrication or to the project site for installation. Any unused materials assigned to your bid package will be the responsibility of this Subcontractor to remove from storage and legally dispose of at no additional cost to the project unless specifically identified to be turned over to the owner at the completion of the project. Materials currently stored on site shall be removed by the responsible trades prior to the start of construction. Delivery of any and all materials to the jobsite shall be coordinated with the Project Schedule and reviewed with Skanska's Superintendent. *Refer to section 01 35 16 – 2.2 Salvaged Materials for those materials that are to be turned over to the owner at project completion.*

Acknowledged (box must be marked)

**4. COMMISSION ON HUMAN RIGHTS AND OPPORTUNITIES
(SELECT NON-SET ASIDE BID PACKAGES)**

Select Non Set-Aside Subcontractors, as identified in the Invitation to Bid, shall award twenty five (25%) percent or more of the value of this Subcontract to DAS certified SBE's. This Subcontractor shall also award ten (10%) percent or more to DAS certified M/WBE's.

Note: All SBE Set-Aside bidders will be required to award five (5%) percent or more of the value of this subcontract to DAS certified M/WBE's.

Within five (5) days of Bid Opening, this apparent lowest bidder will disclose its estimated costs for the named SBE and M/WBE Sub-Subcontracts to verify compliance with this requirement.

By submitting this bid, this Subcontractor has acknowledged and agreed to this requirement.

Acknowledged (box must be marked)

Failure to acknowledge and verify compliance with these requirements will result in a bid that is non-responsive and will be rejected.

5. ADDENDA

Southern Connecticut State University – Buley Library Renovation BI-RS-225B CMR

Receipt of the following Addenda is hereby acknowledged:

Addendum No. 1	Date	01-15-13
Addendum No.	Date	
Addendum No.	Date	

6. SUB-SUBCONTRACTORS

The following Sub-Subcontractors are included with this proposal:

Sub-Subcontractor	Scope of Work	Business Classification (SBE, MBE, WBE)	EMR
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____

7. SUPPLEMENTAL BIDS

Provide supplemental bid pricing to reflect the work of the bid package under which this bid proposal was submitted. The supplemental pricing indicated shall remain valid for the life of the project and include all costs for complete installation.

A. Supplemental Bid 1: Add to complete 2nd Floor Fit-Out \$ _____

Note: 3rd and 4th floor fit-out work identified in the contract documents is not part of his project and may be bid as a separate project at a future date.

8. UNIT PRICES

Specification Section 012000 – Contract Considerations identifies established unit price rates for specific scopes of work. By submitting this bid, this Subcontractor has acknowledged and agreed to the rates applicable to the Scope of Work related to this proposal.

Acknowledged (box must be marked)

9. LABOR & EQUIPMENT RATES

A. LABOR RATES

Skanska may elect to have Subcontractor provide labor (or additional labor) in connection with its Scope. All additional labor shall be billed at the applicable rate as required by law. Each specified rate is inclusive of all of Subcontractor’s costs and expenses to furnish the additional labor in accordance with all requirements of the Subcontract/Purchase Order.

This Subcontractor shall complete the requested information noted below based on their Scope of

Southern Connecticut State University – Buley Library Renovation BI-RS-225B CMR

Work. This shall be used as reference only and does not constitute acceptance. This Subcontractor will be required to provide a complete breakdown in accordance with Exhibit C prior to issuance of a Subcontract.

Trade	Straight Time	Premium Time	Double Time
1. Foreman	\$ _____ /hr	\$ _____ /hr	\$ _____ /hr
2. Journeyman	\$ _____ /hr	\$ _____ /hr	\$ _____ /hr
3. Apprentice	\$ _____ /hr	\$ _____ /hr	\$ _____ /hr
4. Laborer	\$ _____ /hr	\$ _____ /hr	\$ _____ /hr
5.	\$ _____ /hr	\$ _____ /hr	\$ _____ /hr
6.	\$ _____ /hr	\$ _____ /hr	\$ _____ /hr

10. EQUIPMENT

Skanska may elect to have Subcontractor provide any of the following equipment in connection with its Scope at the applicable "Hourly", "Daily", "Weekly", or "Monthly" rate specified. Each specified rate is inclusive of all of Subcontractor's costs and expenses to furnish the equipment in accordance with all requirements of the Subcontract/Purchase Order, including but not limited to the following: transportation, delivery, pickup, fuel, energy costs, consumables, connections, maintenance, wear and tear, repair, depreciation, storage, tax, overhead, and profit. If an hourly rate is used, equipment shall be charged based upon actual usage within ½ hour.

This Subcontractor shall complete the requested information noted below based on their Scope of Work. This shall be used as reference only and does not constitute acceptance. This Subcontractor will be required to provide a complete breakdown in accordance with Exhibit C prior to issuance of a Subcontract.

Equipment Description	Rate			
	Hourly	Daily	Weekly	Monthly

Rental costs of Subcontractor equipment not shown on the list above shall be charged as follows:

- 80% of the rates shown in the latest edition of "Nationally Averaged Rental Rate and Model Reference Data for Construction Equipment" prepared by Associated Equipment Distributors, Chicago, Illinois ("AED"); or if not shown in AED,
- 80% of the rates shown in the latest edition of "Tool and Equipment Rental Guide" prepared by Mechanical Contractors Association of America ("MCA"); or if not shown in MCA,
- 60% of the rates shown in the latest edition of "Rental Rate Blue Book for Construction Equipment" published by Equipment Guidebook Company, Palo Alto, CA ("Blue Book"); or if not shown in the Blue Book,
- 60% of the rates shown in the latest edition of "Tool and Equipment Rental Schedule" published by National Electrical Contractors Association, Bethesda, MD ("NECA").

Southern Connecticut State University – Buley Library Renovation BI-RS-225B CMR

11. CHANGE ORDERS/ALLOWABLE MARKUPS

Subcontractor/Seller shall apply the following overhead and profit markups for changes in the Scope:

	OH&P % Markup
A. Labor The markup on labor shall be reflected in the labor rates stated in Section V and shown in the Labor Rate Breakdown.	15%
B. Material The markup on material shall be applied after all applicable discounts and rebates due Subcontractor/Seller are considered.	15%
C. Third Party Rentals The markup on third party rentals shall be applied to the direct invoiced cost. Equipment owned by the Subcontractor/Seller is not eligible for markup, and is subject to the rates shown in Subcontract Exhibit C Section IV.	5%
D. Sub-subcontractor/Subsupplier Work/Supply The markup on Sub-subcontractor/Subsupplier work/supply in connection with a change in Scope shall be applied to the direct invoiced cost from the Sub-subcontractor/Subsupplier. Sub-subcontractor's/Subsupplier's markup for its own direct cost shall not exceed the percentages listed above for labor, material, and third party rentals.	5%
E. Additional Bond & Insurance Premium The additional bond and insurance premium on a change in Scope shall be applied to the direct cost of the change and is not eligible for markup.	-

Overhead and profit shall be inclusive of the following: home office costs, management, supervision, training, vehicles and pickups, travel, reproduction, temporary facilities, computers, office equipment, small tools, and other incidentals. Small tools are defined as tools that do not have a new unit cost in excess of \$750.00.

12. COST BREAKDOWN

The following information is required at time of bid:

Material Cost	\$ _____
Labor Cost (Total Hours ___ / Avg. Crew ___)	\$ _____
Equipment Cost	\$ _____
Insurance, Bond, Other Costs	\$ _____
Tax, as Required	\$ _____

Southern Connecticut State University – Buley Library Renovation BI-RS-225B CMR

Total Cost (Must Equal Base Bid) \$ _____

In addition to the above cost breakdown, Skanska reserves the right to request additional cost breakdowns at the time of scope review and prior to Contract Award.

By submitting this bid, this Subcontractor has acknowledged and agreed to this requirement.

Acknowledged (box must be marked)

13. QUANTITY BREAKDOWN

Skanska reserves the right to request quantity breakdowns at the time of scope review and prior to Contract Award.

By submitting this bid, this Subcontractor has acknowledged and agreed to this requirement.

Acknowledged (box must be marked)

14. BID PROPOSAL FORM ATTACHEMENTS
(MUST BE SUBMITTED WITH BID PROPOSAL)

- Proposal Form
- Skanska Qualification Form
- DAS Prequalification Certificate (If Bid is in excess of \$500,000)
- Bid Bond
- Consent of Surety
- Non-Collusion Affidavit
- State of Connecticut OPM Ethics Form 6
- Contractors Wage Certification Form
- Requirement Omitted via Addendum*

SUBCONTRACTOR: _____

SIGNATURE: _____

PRINT NAME: _____

TITLE: _____

TELEPHONE: _____

TELEFAX: _____

DATE: _____

(Affix Corporate Seal –if Corporation)

END OF BID PROPOSAL FORM

Southern Connecticut State University – Buley Library Renovation BI-RS-225B CMR

ADDENDUM #1 UPDATE:

Attached material inventory has been sorted by Bid Package Responsibility. Please note, some inventory items have been reallocated to a different bid package.

Shaded inventory items have been identified by the design team as not intended for use on this project. Follow the requirements of Specification Sections 01 35 16 and 00 31 25 for turn-over and/or legal disposal for all items not installed. Contractors are responsible for proper handling of all materials not utilized, whether shaded or not. The shaded designation does not relieve the contractor of material inspection and conformance with the plans and specifications.

Stored Locations have been updated in this Addendum #1. Contractors shall assume that materials with 1st Floor storage locations indicated are currently stored at William B. Meyer.

For all materials stored at William B. Meyer, contractors shall assume transportation of materials is necessary from the jobsite to the responsible contractor's facilities. All material transportation will be coordinated with Skanska and the Owner's Representative with signed material tickets.

ATTACHED: ADDENDUM #1 INVENTORY UPDATE

This section includes a complete inventory of all stored materials delivered to the project site at the completion of the Library Addition project. The intent is to re-use some or all of the materials identified within this section in the construction of the Library Renovation project. The re-use of materials is contingent on 1) the quantity of available materials identified in the inventory list as it compares to the design 2) the condition of the stored materials.

All inventoried materials have been assigned to a specific bid package for inclusion in the Subcontractor's bid proposal.

Each bidder is responsible for the transportation of inventory materials from the storage facilities to your shop for fabrication or to the project site for installation. Any unused materials assigned to your bid package will be the responsibility of the assigned subcontractor to remove from storage and legally dispose of at no additional cost to the project unless specifically identified to be turned over to the owner. *Refer to specification section 01 35 16 for additional information concerning existing stored "salvaged" materials. Note: Bid Packages that have been assigned the responsibility for light fixtures, VAV's, and carpet as part of their bid package will be required to transport all surplus materials left over at the end of the project back to the project site and stored on one of the uncompleted floor areas within the library. Bid Package that has been assigned the responsibility of the brick shall transport 1,000 left over brick to a location on site designated by the owner. All other excess materials shall be the responsibility of this subcontractor to remove and dispose at no additional cost to the project.*

Any additional materials required to complete the design over and beyond the inventory will be the responsibility of the subcontractor who has been assigned the materials.

Bidders are advised that all materials currently stored on site, as described in Specification Section 01 35 16 (ie. bricks and light fixtures) must be removed from the site by the responsible trade to their own storage facility prior to the start of construction. Material deliveries back to the site shall be in accordance with the project schedule, as coordinated with Skanska's superintendent.

Each bidder will be responsible for reviewing and accepting all materials prior to installation. Depending on the material, the Subcontractor may be required to provide third party inspections from vendors in order to recertify that equipment is in good working order and functions properly. If

Southern Connecticut State University – Buley Library Renovation BI-RS-225B CMR

a Subcontractor or its vendor determines that materials or equipment is deemed unusable, the subcontractor and or its vendor will be required to submit a written report identifying the unusable material and will be required to provide a detailed description as to why the material is unusable. If this occurs, and Skanska agrees that the material is unusable, Skanska will work with the Subcontractor to determine a replacement cost for the materials.

OFFSITE STORAGE LOCATIONS:

Storage Location A

William B. Meyer, Inc.
175 Great Pond Drive
Windsor, CT 06095

Storage Location B

William B. Meyer, Inc.
255 Long Beach Blvd
Stratford, CT 06615



**Buley Library Project
Inventory Sheet**

ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/10/2009		N/A	50	Feet, corrugated 4" dia black plastic tubes	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-02
3/10/2009		N/A	1	Each, 24" Concrete Manhole Sections, 35" in total height	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-02
3/10/2009		N/A	1	Each, 48" Concrete manhole in 2 sections, 54" in total height (used)	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-02
3/12/2009		N/A	75	Rolls, 10" width, wire mesh (plastic)	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-02
3/12/2009		-	9349	Bricks, State Island, velour Type 8, modular cored		Yard	BP-04
3/12/2009		-	169547	Bricks, State Island, velour Type 8, modular cored		Yard	BP-04
3/12/2009		HB 6/5 711AS	38	3' 8" x 6' 5" Concrete slabs, 6" thick		Yard	BP-04
3/12/2009		HC 5 711AS	14	3' 2" x 4' 4" Concrete slabs, 6" thick		Yard	BP-04
3/12/2009		HC 2 711AS	36	6' 0" x 2' 0" Precast Concrete slab		Yard	BP-04
3/12/2009		PD 103/102 711AS	20	2' 0" x 2' 0" x 2' 6" Precast Concrete slab (5" Thick)		Yard	BP-04
3/12/2009		HB 7 711AS	2	2' 0" x 2' 0" x 6' 6" Precast Concrete slab (5" Thick)		Yard	BP-04
3/12/2009		HC 4 711AS	7	2' 0" x 2' 0" x 6' 6" Precast Concrete slab (5" Thick)		Yard	BP-04
3/12/2009		H 5 711S	16	1' 6" x 4' 6" Splayed Edge (5" Thick)		Yard	BP-04
3/12/2009		H 6 711AS	8	32" x 20" Precast Block (5" Thick)		Yard	BP-04
3/12/2009		HA 1 711AS	3	30" x 30" Precast Concrete slab, square (5" Thick)		Yard	BP-04
3/12/2009		H4 1 711AS	20	20" x 64" Precast Concrete slab (5" Thick)		Yard	BP-04
3/12/2009		H2 1 711AS	10	20" x 52" Precast Concrete slab (5" Thick)		Yard	BP-04
3/12/2009		RW1 711AS	2	10" x 54" Precast Concrete slab (5" Thick)		Yard	BP-04
3/12/2009		RW2 711AS	2	45" x 54" Precast Concrete slab (5" Thick)		Yard	BP-04
3/12/2009		V2 711AS	4	60" x 24" Precast Concrete slab (5" Thick)		Yard	BP-04
3/12/2009		V1 711AS	2	60" x 18" Precast Concrete slab (5" Thick)		Yard	BP-04
3/12/2009		RX1 711AS	1	46" x 60" Precast Concrete slab (5" Thick)		Yard	BP-04
3/12/2009		R21 711AS	1	31" x 77" Precast Concrete slab (5" Thick)		Yard	BP-04
3/12/2009		RV1 711AS	1	42" x 77" Precast Concrete slab (5" Thick)		Yard	BP-04
3/12/2009		HB1 711AS	3	25" x 36" Precast Concrete slab (5" Thick)		Yard	BP-04
3/12/2009		N/A	132	16" x 7" x 6" Precast Concrete block		Yard	BP-04
3/12/2009		N/A	60	16" x 6" x 5" Precast Concrete block		Yard	BP-04
3/12/2009		N/A	100	7 3/4" x 5" x 7 1/2" Precast Concrete block, slotted		Yard	BP-04
3/12/2009		N/A	11	7" x 12" x 16" Jumbo Concrete block		Yard	BP-04
3/12/2009		N/A	36	16" x 3" x 5" Precast Concrete block		Yard	BP-04
3/12/2009		N/A	36	16" x 8" x 4" Precast Concrete block		Yard	BP-04
3/12/2009		NLTBUFF - 13	5 Bags	Spec Mix - 800 lbs/bag		Yard	BP-04
3/12/2009		-	82	5' x 2" x 1' Cut Insulation		Yard	BP-04
3/12/2009		-	9	4' x 1" x 1' Cut Mesh Filter		Yard	BP-04
3/12/2009		-	13 Stacks, Qty 48	8' Long Masonry Ties		Yard	BP-04
3/12/2009		N/A	250	Approx. Each Masonry Facade Connections (see diagram)	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-04
3/10/2009		N/A	2	Each, Steel tube 6'x4"	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-05
3/10/2009		N/A	3	Each, Steel tube 4'x5"	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-05
3/10/2009		N/A	1	Each, Steel tube 8'x2"	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-05
3/10/2009		N/A	1	Each, Steel tube 5'x3"	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-05
3/13/2009		N/A	10	Each, 6-1/2" dia, 7' long, galvanized bollards	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-05A
3/11/2009			19	L wooden trim 8-1/2" L (1/2" thick)	Existing	Middle of basement, near Bay 10	BP-06
3/11/2009			72	misc door trim 1/8" x 7' L	Existing	Middle of basement, near Bay 10	BP-06
3/11/2009		(24)5W104	18	Poly pad 20" x 25" x 2" air handlers	Existing	Middle of basement, near Bay 10	BP-07
3/18/2009			17	16 1/2' x 100' Rolled Roof Sheathing, 6mil	3/18/2009	Western Corner, Yard	BP-07
3/24/2009			869	Insulation/ Foam Board - 1X24X96"	3/24/2009	2nd Floor	BP-07
3/24/2009			2510	Insulation/ Foam Board - 2X24X96"	3/24/2009	2nd Floor	BP-07
3/24/2009			422	Insulation/ Foam Board - 24X96", Misc width	3/24/2009	2nd Floor	BP-07
3/24/2009			10	Insulation/ Foam Board - AA - (.5-1.5)X24X96"	3/24/2009	2nd Floor	BP-07
3/24/2009			353	Insulation/ Foam Board - C - (1.5-2)X24X96", B - (1-1.5)X24X96"	3/24/2009	2nd Floor	BP-07
3/24/2009			507	Insulation/ Foam Board - A - (.5-1)X24X96", D - (2-2.5)X24X96"	3/24/2009	2nd Floor	BP-07
3/24/2009			54	Insulation/ Foam Board - AA - (.5-1.5)X24X96", BB - (1.5-2.5)X24X96"	3/24/2009	2nd Floor	BP-07
3/24/2009			736	Insulation/ Foam Board - A - (.5-1)X24X96", B - (1-1.5)X24X96"	3/24/2009	2nd Floor	BP-07
3/24/2009			540	Insulation/ Foam Board - G - (1-1.25)X24X96", F - (.75-1)X24X96"	3/24/2009	2nd Floor	BP-07
3/24/2009			363	Insulation/ Foam Board - E - (.5-.75)X24X96", H - (1.25-1.5)X24X96"	3/24/2009	2nd Floor	BP-07
3/24/2009			138	Insulation/ Foam Board - G - (1-1.25)X24X96"	3/24/2009	2nd Floor	BP-07
3/24/2009			7	Roofing Sheets, 16.5'(W)X100'(L), Whole Rolls	3/24/2009	Roof	BP-07



ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/24/2009			9	Roofing Sheets, 16.5'(W)X100'(L), Majority of Roll 75+%	3/24/2009	Roof	BP-07
3/24/2009			3	Roofing Sheets, 16.5'(W)X100'(L), 50% or less of Roll	3/24/2009	Roof	BP-07
3/9/2009	2020 - 2050	205 831	100	Schucko DPN 78.1.A2 Torx T 25 Ducromet ST5.5 x 40mm	3/12/2009	Basement Bay 8	BP-08
3/11/2009		264491	150	aluminum brackets	Existing	Basement Bay 3 and 4	BP-08
3/12/2009			50	2'x1.5" window frame flashing (rusted)	3/14/2009	1st Floor Bay 4	BP-08
3/12/2009			50	1'x1.5" window frame flashing (rusted)	3/14/2009	1st Floor Bay 4	BP-08
3/12/2009	-		9 Stacks, 9 x 100pc	Fiberboard		Yard	BP-08
3/12/2009	-		2	Trudite Industries Ltd., 47 1/2" x 58 7/8, WIS-15A/Typend/inch OA/Lowe SD#2, 1" glass double		Yard	BP-08
3/12/2009	-		3	Trudite Industries Ltd., 57 7/8" x 43 7/8, 1" glass double pane		Yard	BP-08
3/12/2009	-		2	Trudite Industries Ltd., 57 7/8" x 43 7/8, 1" glass double pane		Yard	BP-08
3/12/2009	-		2	Trudite Industries Ltd., 31" x 43 7/8, 1" glass double pane		Yard	BP-08
3/12/2009	-		1	Trudite Industries Ltd., 30 3/4" x 42 7/8, 1" glass double pane		Yard	BP-08
3/12/2009	-		10	Neoprene Pipe Gaskets, 8" SB, Quik Tite WARCO		Yard	BP-08
3/12/2009	-		20 pc	Neoprene Pipe Gaskets, 5" SV, Quik Tite WARCO		Yard	BP-08
3/12/2009	-		20 pc	Neoprene Pipe Gaskets, 2" SV, Quik Tite WARCO		Yard	BP-08
3/12/2009	-		20 pc	Neoprene Pipe Gaskets, 3" SV, Quik Tite WARCO		Yard	BP-08
3/12/2009	-		33 rolls	Neoprene Pipe Gaskets, 18" Self Adhesive		Yard	BP-08
3/16/2009		110950	22	Schuco Cover cap	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324090	2	Schuco Vertical mullion	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		110910	24	Schuco Cover cap	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324480	3	Schuco Transom (Horizontal mullion)	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324460	25	Schuco Transom (Horizontal mullion)	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		110950	30	Schuco Cover cap	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324030	30	Schuco Vertical mullion	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324030	20	Schuco Vertical mullion	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324030	6	Schuco Vertical mullion	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324080	1	Schuco - Stocklengths	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324050	24	Schuco Vertical mullion Misc. lengths	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324040	5	Schuco Vertical mullion	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324070	2	Schuco - Stocklengths	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324030	2	Schuco Vertical mullion	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324490	5	Schuco Transom (Horizontal mullion)	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		134350	2	Schuco Aluminum channel	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		110950	2	Schuco Cover cap	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324480	1	Schuco Transom (Horizontal mullion)	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324480	2	Schuco Transom (Horizontal mullion)	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324490	2	Schuco Transom (Horizontal mullion)	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		134350	15	Schuco Aluminum channel	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324050	14	Schuco Vertical mullion	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324090	2	Schuco Vertical mullion	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		336270	5	Schuco Mullion	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		162880	10	Schuco pressure plate	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324530	6	Schuco Transom (Horizontal mullion)	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		162880	15	Schuco pressure plate	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324320	2	Schuco Aluminum reinforcing	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		336280	1	Schuco - Stocklengths	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324300	1	Schuco Aluminum reinforcing	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		323130	10	Schuco Reducer	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		323130	20	Schuco Reducer	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		323130	15	Schuco Reducer	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324040	1	Schuco Vertical mullion	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		323130	20	Schuco Reducer	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		323130	15	Schuco Reducer	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		323130	20	Schuco Reducer	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		134350	20	Schuco Aluminum channel	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324440	1	Schuco Horizontal mullion	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08



**Buley Library Project
Inventory Sheet**

ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/16/2009		323130	13	Schuco Reducer	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324680	5	Schuco Vertical mullion	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		323130	20	Schuco Reducer	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324010	3	Schuco Vertical mullion	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324420	2	Schuco Horizontal mullion	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		134350	11	Schuco Aluminum channel	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		323130	18	Schuco Reducer	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		323130	10	Schuco Reducer	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		323130	20	Schuco Reducer	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		323130	20	Schuco Reducer	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		323130	20	Schuco Reducer	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324510	1	Schuco Transom	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324010	4	Schuco Vertical mullion	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324430	2	Schuco Horizontal mullion	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324960	6	Schuco Joint profile	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		224808	10	Schuco Isolater	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		224808	527	Schuco Isolater	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		224814	235	Schuco Perimeter filer	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		162880	450	Schuco pressure plate	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324300	12	Schuco Aluminum reinforcing	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324310	5	Schuco Aluminum reinforcing	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324320	5	Schuco Aluminum reinforcing	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		2889-654	34	Schuco - Stocklengths	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		129590	4	Schuco Shearblocks	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		2889-654	80	Schuco - Stocklengths	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		162880	250	Schuco pressure plate (approx qty)	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		129430	1	Schuco Shearblocks	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		204507	33	Glasdichtung 11mm, Rolls - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		224866	1	Ve = 200m, Roll - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		244160	4	100m, Roll - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		224842	8	Ve = 200m, Roll - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		224850	4	Ve = 100m, Roll - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		224643	2	Roll - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		224297	2	Roll - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		224606	19	Roll - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		224636	2	8mm, 5x10m, Boxes - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		204649	22	Roll - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		224608	14	Roll - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		204507	38	Roll - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		204992	1	Roll - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		224063	1	Roll - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		??	19	Misc. Rolls (Used/Unidentifiable) - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		224063	1	Roll - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		224836	1	Package - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		217585	2	Package - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		238490	1	Package - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		205437	3	Box - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		205436	1	Package - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		205583	1	Box - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		207047	1	Package - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		205439	2	Package - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		208015	1	Package - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		218311	50	Misc. Pieces - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		205827	5	Box - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		228414	1	Package - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		226146	5	Package - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		217923	1	Used Box - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08



ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/16/2009		244737	1	Package - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		217432	1	Package - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		205598	2	Package - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		203087	1	Package - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		207047	1	Package - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		219418	1	Package - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		205462	2	Package, 50 Fastners Each - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		205492	2	Package, 50 Fastners Each - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		205930	1	Box, 100 Fastners Each - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		205082	4	Box, 100 Fastners Each - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		205077	3	Box, 100 Fastners Each - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		205512	1	Box, 100 Fastners Each - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		226087	1	Package, 50 Brackets Each - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		205431	3	Package, 100 Fasteners Each - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		205875	1	Box, 100 Fastners Each - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		234785	16	Window Latches - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		??	1	Box, Misc Window Seals - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		226083	6	Box - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		205431	2	Package, 100 Screws Each - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		205827	4	Package, 100 Screws Each - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		205082	11	Box, 100 Screws Each - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		306493	1	Package, 50 Plastic Safety Hinges - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		233946	1	Package, 40 Hinges - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		224269	1	Roll (8mm, Used) - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		234785	7	Package, Window Handle Assemblies - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		??	1	Tube, 600 ml Silicon Sealant - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		228417	9	Package, Plastic Pane Dividers - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		295432	1	Package, 20 Window Rubber Corner Guards - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		??	1	Partial Roll Window Seal - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		??	1	Partial Roll Window Seal, Double Sided Adhesive - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		244670	1	Partial Roll Felt Window Liner Strip - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		204456	1	Partial Roll Felt Window Liner Strip - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		217917	2	Packages, 100 Plastic Yellow Tabs Each - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		205432	8	Boxes, 100 Fasteners Each - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		??	1	Tube, Latex Caulk 300 ml - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		228390	3	Packages, 3 Inch Alluminun Angle - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		205827	13	Packages - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		395432	1	Package, Small Rubber Seal - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		??	1	Can, .5"-2" Screws, Approx. 400 - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		242524	1	Roll, Foam Water Seal - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		??	1	Box, Misc. Plastic Pane Dividers, 40 Total - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		239122	6	Packages, Large Window Hinges - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		204429	2	Boxes, Felt Window Seal - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		233946	4	Packages - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		226081	7	Packages - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		215587	1	Package, Small Rubber Seal - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		205287	2	Packages, 100 Fasteners Each - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		205082	6	Boxes, 100 Fasteners Each - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		HM88	4	Boxes, Simple Plastic Rubber Blocks, 500 Pieces, 4" Length - Shuco accessor	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		205583	41	Boxes, 100 Fasteners Each - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		205437	40	Boxes, 100 Fasteners Each - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		224968	125	Packages, 4 Way Rubber Seal, 25 Per Package - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		244633	25	Packages, Rubber Corner Joint, 4 Per Package - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		237486	100	Packages, Alluminun Angle, 50 Per Package - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		??	4	Tubes, Bronze Sealant Mix - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		257855	1	Package - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		217907	20	Packages, 100 Plastic Yellow Tabs Each - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08



ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/16/2009		228728	35	Packages, Plastic Window Dividers - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		228692	7	Packages, Joint Clips, 200 Each - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		205436	36	Boxes, 100 Fasteners Each - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		226146	80	Packages, Horizontal Mullion - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		217587	200	Pieces of Alluminum Angle - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		226147	140	Boxes, 10 Each - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		205963	7	Packages, 100 Fasteners Each - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		237855	5	Packages - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		205241	6	Boxes - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		205827	2500	Pieces - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		217587	2	Packages - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		228501	4	Packages - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		218521	1	Package - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		205082	45000	Fastners - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		185482	15	Rolls - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		224295	5	Rolls - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		205831	12500	Fastners - Shuco accessories	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		223965	4	Bundles, 2 Each, 237" - Shuco	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		324030	99	Bundles, 2 Each, 15' Long - Shuco Vertical mullion	3/17/2009	1st Floor Bay 5&9	BP-08
3/16/2009		324090	11	Schuco Vertical mullion	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		336270	5	Schuco Mullion	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324050	27	Schuco Vertical mullion 299"	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324050	27	Schuco Vertical mullion 299"	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324050	27	Schuco Vertical mullion 299"	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324470	8	Schuco Transom (Horizontal mullion) 237"	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324040	24	Schuco Vertical mullion 264"	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324480	24	Schuco Transom (Horizontal mullion) 237"	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324480	24	Schuco Transom (Horizontal mullion) 237"	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324480	24	Schuco Transom (Horizontal mullion) 237"	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324050	7	Schuco Vertical mullion 260"	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324490	15	Schuco Transom (Horizontal mullion)	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324460	1	Schuco Transom (Horizontal mullion)	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		110990	18	Schuco - Stocklengths	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		162880	9	Schuco pressure plate	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324470	2	Schuco Transom (Horizontal mullion)	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324480	24	Schuco Transom (Horizontal mullion) 237"	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324480	24	Schuco Transom (Horizontal mullion) 237"	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324050	27	Schuco - Stocklengths	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324460	45	Schuco Transom (Horizontal mullion) 237"	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		336270	18	Schuco Mullion 299"	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324480	28	Schuco Transom (Horizontal mullion) 237"	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324480	32	Schuco Transom (Horizontal mullion) 237"	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		110910	112	Schuco Cover cap	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		323120	39	Schuco Glaz reb reduct	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		336270	1	Schuco Mullion	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324030	13	Schuco Vertical mullion	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324050	8	Schuco Vertical mullion	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324890	12	Schuco Cover cap	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324030	10	Schuco Vertical mullion	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324480	9	Schuco Transom (Horizontal mullion)	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324480	2	Schuco Transom (Horizontal mullion)	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324500	1	Schuco Transom (Horizontal mullion)	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324040	1	Schuco Vertical mullion	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324030	1	Schuco Vertical mullion	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		336270	6	Schuco Mullion	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		324050	9	Schuco Vertical mullion	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/16/2009		323130	24	Schuco Reducer	3/17/2009	1st Floor Bay 5, 6, 11, 12	BP-08



ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/17/2009		324050	26	Schuco Vertical mullion	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		324490	21	Schuco Transom (Horizontal mullion)	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		224814	230	Schuco Perimeter filer	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		322730	3	Shuco - stocklengths (full description NA)	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		326050	2	Shuco - stocklengths (full description NA)	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		324050	27	Schuco Vertical mullion	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		324030-99	26	Schuco Vertical mullion Length=299"	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		324030	15	Schuco Vertical mullion	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		224808	44	Schuco Isolater	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		324030-99	2	Length=169"	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		224812	7	Schuco Isolater	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		224808	72	Schuco Isolater	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		134080	44	Schuco Angle V shape	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		204734	100	Schuco Attachment Profile	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		224813	10	Schuco PVC-U Attachment profile	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		050513	10	Schuco door subframe	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		050526	12	Shuco - stocklengths (full description NA)	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		134650	14	Schuco Aluminum tube 3/4"x1 1/8"	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		324460	8	Schuco Transom (Horizontal mullion) Full length appr. 237"	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		134650	9	Schuco Aluminum tube 3/4"x1 1/8" Full length appr. 237"	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		324470	1	Schuco Transom (Horizontal mullion)	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		134080	33	Schuco Angle	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		324030	5	Full length 205"	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		324030	2	Schuco Vertical mullion 169"	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		324030	2	Schuco Vertical mullion 92"	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		324030	2	Schuco Vertical mullion 79"	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		324300	1	Schuco Vertical mullion 117"	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		324460	11	Schuco Transom (Horizontal mullion)	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		162180	57	Schuco Cover cap	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		110910	134	Schuco Cover cap	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		110910	96	Schuco Cover cap	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		134350	16	Schuco Aluminum channel	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		324460	1	Schuco Transom (Horizontal mullion)	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		324030	2	Schuco Vertical mullion	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		050513	6	Schuco door subframe	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		050526	3	Shuco - stocklengths (full description NA)	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		???	2	Shuco - stocklengths (full description NA)	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		33320	2	Shuco V shape	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		110910	74	Schuco Cover cap	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		162180	154	Schuco Cover cap	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		324050	17	Schuco Vertical mullion	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		324490	11	Schuco Transom (Horizontal mullion)	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/17/2009		336280	44	Shuco - stocklengths (full description NA)	3/18/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/18/2009		W14A/Offset/Type#3/1" OA/Crate	12	Truelite Industries Limited Type 14 Vents 6MM PPG TMP CLR	3/19/2009	1st Floor Bay 5	BP-08
3/18/2009			8	1 crate - Standard Bent Glass Corp. Glass 1/4+1/4CLR 4-51 5/8 x 42 1/4 4-51 7/16 x 42 1/4	3/19/2009	1st Floor Bay 5	BP-08
3/18/2009			6	1 crate - Standard Bent Glass Corp. Glass 1/4+1/4CLR 4-51 5/16 x 42 1/4 2-51 13/16 x 42 1/4	3/19/2009	1st Floor Bay 5	BP-08
3/18/2009			6	1 crate - Standard Bent Glass Corp. Glass 1/4+1/4CLR 1-56 1/8 x 42 3/4 4-56 3/4 x 42 1/4 1-52 3/8 x 42 1/8 1-59 1/2 x 43 1-40 5/16" x 42 1/4 1-41 5/8 x 41 3/8	3/19/2009	1st Floor Bay 5	BP-08



**Buley Library Project
Inventory Sheet**

ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/18/2009		L980	4	Sargent Exit Device, Box	3/19/2009	1st Floor Bay 5, 6, 11, 12	BP-08
3/18/2009		171A42	4	Penko/ASSA ABLOY (Door Hardware)	3/19/2009	1st Floor Bay 5	BP-08
3/18/2009		171A80	6	Penko/ASSA ABLOY (Door Hardware)	3/19/2009	1st Floor Bay 5	BP-08
3/18/2009		171A60	1	Penko/ASSA ABLOY (Door Hardware)	3/19/2009	1st Floor Bay 5	BP-08
3/18/2009		52-3373	2	Sargent 3540 Power Supply, Box	3/19/2009	1st Floor Bay 5	BP-08
3/18/2009		442/409	3	Rockwood Door Stops	3/19/2009	1st Floor Bay 5	BP-08
3/18/2009		8810F	5	Sargent Exit Device, Box	3/19/2009	1st Floor Bay 5	BP-08
3/18/2009		8876F	2	Sargent Exit Device, Box	3/19/2009	1st Floor Bay 5	BP-08
3/18/2009			17	EFCO, Series D500 Doorleafs	3/19/2009	1st Floor Bay 14	BP-08
3/23/2009			12	24" (W) X 10' (L) X 2" (T), Panels - From TP Builders	3/23/2009	1st Floor, Bay 13	BP-08
3/23/2009			2	30" (W) X 5' (L) X 3" (T), Panels - From TP Builders	3/23/2009	1st Floor, Bay 13	BP-08
3/23/2009		36210178	1	22 ga, 30" (W), Metal Coil, 2110 lbs	3/23/2009	1st Floor, Bay 10	BP-08
3/23/2009		36210177	1	22 ga, 30" (W), Metal Coil, 6000 lbs	3/23/2009	1st Floor, Bay 10	BP-08
3/23/2009		36210178	1	22 ga, 30" (W), Metal Coil, 3750 lbs	3/23/2009	1st Floor, Bay 10	BP-08
3/23/2009		36224167	1	22 ga, 36" (W), Metal Coil, 7110 lbs	3/23/2009	1st Floor, Bay 10	BP-08
3/23/2009		36221057	1	22 ga, 41" (W), Metal Coil, 7500 lbs	3/23/2009	1st Floor, Bay 10	BP-08
3/23/2009		36224167	1	22 ga, 36" (W), Metal Coil, 3210 lbs	3/23/2009	1st Floor, Bay 10	BP-08
3/23/2009		36221057	1	22 ga, 41" (W), Metal Coil, 685 lbs	3/23/2009	1st Floor, Bay 10	BP-08
3/23/2009		36210178	1	22 ga, 30" (W), Metal Coil, 900 lbs	3/23/2009	1st Floor, Bay 10	BP-08
3/9/2009		103, 104, 110M, 110N	4	Each, 10' width, 5'-8" height, 7-1/4" thick metal 6 bay window frame	Existing	Basement East Wall	BP-08A
3/9/2009		124D, 124D1, 124A, 124-1	4	Each 6' width, 10' height, 7-1/4" thick metal door frame	Existing	Basement East Wall	BP-08A
3/9/2009		110N, 199	2	Each, 3' width, 10' height, 7-1/4" thick metal door frame	Existing	Basement East Wall	BP-08A
3/9/2009		199B	1	Each, 3' width, 7' height, 7-1/4" thick metal door frame	Existing	Basement East Wall	BP-08A
3/9/2009		1365890	1	Each, Builder's Hardware, 3' width, 7' height, 1-3/4" thick, cherry finish wood door	Existing	Basement East Wall	BP-08A
3/9/2009		N/A	3	Each, 3' width, 8' height, 8-1/2" thick, metal door frame (looks used)	Existing	Basement East Wall	BP-08A
3/9/2009		N/A	4	Each, 3' width, 8' height, 6" thick, metal door frame (looks used)	Existing	Basement East Wall	BP-08A
3/9/2009		199A1	1	Each, 6'-4" width, 7' height, 6" thick metal door frame	Existing	Basement East Wall	BP-08A
3/9/2009		N/A	1	Each 4'-6" height, 10" width, 7-1/2" thick metal door/Window frame. 3 bay window on one side and top of door frame	Existing	Basement East Wall	BP-08A
3/9/2009		101-2, 124-D	2	Each, 10' width, 5'-8" height, 7-1/4" thick metal Door/Window frame, 9 bay window frame	Existing	Basement East Wall	BP-08A
3/9/2009		N/A	8	Each, 8'-2" height, 3'-4" width, 7" thick metal door frame	Existing	Basement East Wall	BP-08A
3/9/2009		N/A	2	Each, 8'-2" height, 3'-4" width, 6" thick metal door frame	Existing	Basement East Wall	BP-08A
3/9/2009		N/A	1	Each, 8'-2" height, 3'-4" width, 7-1/4" thick metal door frame	Existing	Basement East Wall	BP-08A
3/9/2009		N/A	1	Each, 3' width, 7'-11" height, 3/4" metal door	Existing	Basement East Wall	BP-08A
3/9/2009		105, 101-1, 102-1 (2 not visible)	5	Each, 10' height, 5'-8" width, 7-1/4" thick metal window/door frame,	Existing	Basement East Wall	BP-08A
3/9/2009	0200 - 0255		2	rolls black waterproofing membrane	3/12/2009	Basement Bay 8	BP-09
3/6/2009	0306	VF-5000	2	metal access door 8" x 8" cylinder lock 7 key	3/6/2009	East Wall - Auditorium	BP-09
3/10/2009	0800	2088-9608 185-144	4	chrome door holder semi flush		Basement Bay 10	BP-09
3/10/2009	901 - 932	N/A	13	Each, 26" x 26" access doors	3/11/2009	Basement Bay 7 and Bay 11	BP-09
3/10/2009	901 - 932	N/A	4	Each, 20" x 20" access doors	3/11/2009	Basement Bay 7 and Bay 11	BP-09
3/10/2009	901 - 932	N/A	2	Each, 14" x 14" access doors	3/11/2009	Basement Bay 7 and Bay 11	BP-09
3/9/2009		N/A	8	Each, 4' width, 12' height, 1/2" thick Gypsum boards	Existing	Basement East Wall	BP-09
3/9/2009		N/A	2	18" diamond circular saw blade	Existing	Basement East Wall	BP-09
3/11/2009		506/501.1	16	Curnes Fire rated doors, 1-1/2" thick	Existing	Middle of basement, near Bay 10	BP-09
3/11/2009			7	1/2" x 2" block wood pieces 9' H	Existing	Middle of basement, near Bay 10	BP-09
3/11/2009		81020211	9	1-1/2" SC fire rated door	Existing	Middle of basement, near Bay 10	BP-09
3/10/2009	901 - 932	XL-7342-SG	11	Boxes (60/box)Armstrong Peakform Ceiling Grid 4' Prelude XL Tee	3/11/2009	Basement Bay 7 and Bay 11	BP-09A
3/10/2009	901 - 932	BPG3015G	17	Boxes (1x8 pieces, 16x10 pieces/box), Armstrong Vent Cover Tiles	3/11/2009	Basement Bay 7 and Bay 11	BP-09A
3/10/2009	901 - 932	BPG3015G	5	Pallets of 24 boxes, 10/box), Armstrong Vent Cover Tiles	3/11/2009	Basement Bay 7 and Bay 11	BP-09A
3/10/2009	901 - 932	N/A	200	Pieces, Wire lengths, 25 Pounds	3/11/2009	Basement Bay 7 and Bay 11	BP-09A
3/10/2009	901 - 932	N/A	9	pieces, shaped aluminum plates, 6" x 9" x 1/2"	3/11/2009	Basement Bay 7 and Bay 11	BP-09A
3/10/2009	901 - 932	73015G	6	Boxes, Armstrong 12' heavy MN BM Ceiling Grid Beams	3/11/2009	Basement Bay 7 and Bay 11	BP-09A
3/10/2009	901 - 932	8X6STR10S	3	Boxes, Armstrong Axiom 6" Silver gray 60 LF, 6 pieces	3/11/2009	Basement Bay 7 and Bay 11	BP-09A
3/9/2009		3252A	16	Pieces, Armstrong 2'x4' drop ceiling tiles	Existing	Basement East Wall	BP-09A



**Buley Library Project
Inventory Sheet**

ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/25/2009	Meyer Tag No. 185	51950	26 cartons, 45 Qty each	VCT - 1,170 sq ft.	3/25/2009	Meyer Storage-Manchester, CT-505C	BP-09C
3/25/2009	Meyer Tag No. 192-193		110	Stair treads - Nora 4.25 ft.	3/25/2009	Meyer Storage-Manchester, CT-503D, 501D	BP-09C
3/25/2009	Meyer Tag No. 194		89	Rubber tile - 979 sq ft.	3/25/2009	Meyer Storage-Manchester, CT-502D	BP-09C
3/25/2009	Meyer Tag No. 195		90	Stair treads - Nora 5.25 ft.	3/25/2009	Meyer Storage-Manchester, CT-501C	BP-09C
3/25/2009	Meyer Tag No. 196	835942-0602	1	Carpet - 129' (L) x 12.5' (W)	3/25/2009	Meyer Storage-Manchester, CT-702D	BP-09C
3/25/2009	Meyer Tag No. 197	835942-0101	1	Carpet - 71' (L) x 12.5' (W)	3/25/2009	Meyer Storage-Manchester, CT-703D	BP-09C
3/25/2009	Meyer Tag No. 198	835942-0201	1	Carpet - 74' (L) x 12.5' (W)	3/25/2009	Meyer Storage-Manchester, CT-701D	BP-09C
3/25/2009	Meyer Tag No. 199	836189-0802	1	Carpet - 175' (L) x 12.5' (W)	3/25/2009	Meyer Storage-Manchester, CT-705C	BP-09C
3/25/2009	Meyer Tag No. 200	836188-0101	1	Carpet - 144' (L) x 12.5' (W)	3/25/2009	Meyer Storage-Manchester, CT-701D	BP-09C
3/25/2009	Meyer Tag No. 201	836189-0902	1	Carpet - 68' (L) x 12.5' (W)	3/25/2009	Meyer Storage-Manchester, CT-704D	BP-09C
3/25/2009	Meyer Tag No. 202	836189-0102	1	Carpet - 66' (L) x 12.5' (W)	3/25/2009	Meyer Storage-Manchester, CT-706D	BP-09C
3/25/2009	Meyer Tag No. 203	836189-0703	1	Carpet - 50' (L) x 12.5' (W)	3/25/2009	Meyer Storage-Manchester, CT-701D	BP-09C
3/25/2009	Meyer Tag No. 204	835887-0302	1	Carpet - 51' (L) x 12.5' (W)	3/25/2009	Meyer Storage-Manchester, CT-704D	BP-09C
3/25/2009	Meyer Tag No. 205	853942-1901	1	Carpet - 203' (L) x 12.5' (W)	3/25/2009	Meyer Storage-Manchester, CT-706C	BP-09C
3/25/2009	Meyer Tag No. 206	835942-1002	1	Carpet - 220' (L) x 12.5' (W)	3/25/2009	Meyer Storage-Manchester, CT-704C	BP-09C
3/25/2009	Meyer Tag No. 207	853942-1902	1	Carpet - 200' (L) x 12.5' (W)	3/25/2009	Meyer Storage-Manchester, CT-704C	BP-09C
3/25/2009	Meyer Tag No. 208	835942-1202	1	Carpet - 201' (L) x 12.5' (W)	3/25/2009	Meyer Storage-Manchester, CT-706C	BP-09C
3/25/2009	Meyer Tag No. 209	835942-1201	1	Carpet - 205' (L) x 12.5' (W)	3/25/2009	Meyer Storage-Manchester, CT-705C	BP-09C
3/25/2009	Meyer Tag No. 210	835887-0201	1	Carpet - 93' (L) x 12.5' (W)	3/25/2009	Meyer Storage-Manchester, CT-706D	BP-09C
3/25/2009	Meyer Tag No. 211	835942-0601	1	Carpet - 40' (L) x 12.5' (W)	3/25/2009	Meyer Storage-Manchester, CT-705D	BP-09C
3/25/2009	Meyer Tag No. 212	836189-0402	1	Carpet - 42' (L) x 12.5' (W)	3/25/2009	Meyer Storage-Manchester, CT-704D	BP-09C
3/25/2009	Meyer Tag No. 213	836189-1301	1	Carpet - 93' (L) x 12.5' (W)	3/25/2009	Meyer Storage-Manchester, CT-706D	BP-09C
3/25/2009	Meyer Tag No. 214	836189-0303	1	Carpet - 60' (L) x 12.5' (W)	3/25/2009	Meyer Storage-Manchester, CT-703D	BP-09C
3/25/2009	Meyer Tag No. 215	836189-0803	1	Carpet - 28' (L) x 12.5' (W)	3/25/2009	Meyer Storage-Manchester, CT-705D	BP-09C
3/25/2009	Meyer Tag No. 216	836189-0901	1	Carpet - 36' (L) x 12.5' (W)	3/25/2009	Meyer Storage-Manchester, CT-704D	BP-09C
3/25/2009	Meyer Tag No. 217	835942-0603	1	Carpet - 126' (L) x 12.5' (W)	3/25/2009	Meyer Storage-Manchester, CT-702D	BP-09C
3/25/2009	Meyer Tag No. 218	836189-1201	1	Carpet - 127' (L) x 12.5' (W)	3/25/2009	Meyer Storage-Manchester, CT-705D	BP-09C
3/25/2009	Meyer Tag No. 219	836189-1202	1	Carpet - 127' (L) x 12.5' (W)	3/25/2009	Meyer Storage-Manchester, CT-701C	BP-09C



**Buley Library Project
Inventory Sheet**

ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/25/2009	Meyer Tag No. 220	836189-1102	1	Carpet - 150' (L) x 12.5' (W)	3/25/2009	Meyer Storage-Manchester, CT-706C	BP-09C
3/25/2009	Meyer Tag No. 221	835942-0701	1	Carpet - 134' (L) x 12.5' (W)	3/25/2009	Meyer Storage-Manchester, CT-702C	BP-09C
3/25/2009	Meyer Tag No. 222	853942-1401	1	Carpet - 191' (L) x 12.5' (W)	3/26/2009	Meyer Storage-Manchester, CT-706A	BP-09C
3/25/2009	Meyer Tag No. 223	853942-1701	1	Carpet - 204' (L) x 12.5' (W)	3/26/2009	Meyer Storage-Manchester, CT-704A	BP-09C
3/25/2009	Meyer Tag No. 224	853942-2501	1	Carpet - 204' (L) x 12.5' (W)	3/26/2009	Meyer Storage-Manchester, CT-701C	BP-09C
3/25/2009	Meyer Tag No. 225	835942-2602	1	Carpet - 208' (L) x 12.5' (W)	3/26/2009	Meyer Storage-Manchester, CT-706A	BP-09C
3/25/2009	Meyer Tag No. 226	836189-0101	1	Carpet - 206' (L) x 12.5' (W)	3/26/2009	Meyer Storage-Manchester, CT-704A	BP-09C
3/25/2009	Meyer Tag No. 227	836189-0201	1	Carpet - 168' (L) x 12.5' (W)	3/26/2009	Meyer Storage-Manchester, CT-705A	BP-09C
3/25/2009	Meyer Tag No. 228	853942-2102	1	Carpet - 201' (L) x 12.5' (W)	3/26/2009	Meyer Storage-Manchester, CT-705A	BP-09C
3/25/2009	Meyer Tag No. 229	835942-0401	1	Carpet - 204' (L) x 12.5' (W)	3/26/2009	Meyer Storage-Manchester, CT-703A	BP-09C
3/25/2009	Meyer Tag No. 230	836189-0301	1	Carpet - 105' (L) x 12.5' (W)	3/26/2006	Meyer Storage-Manchester, CT-703C	BP-09C
3/25/2009	Meyer Tag No. 231	853942-1801	1	Carpet - 140' (L) x 12.5' (W)	3/26/2009	Meyer Storage-Manchester, CT-702C	BP-09C
3/25/2009	Meyer Tag No. 232	853942-2001	1	Carpet - 111' (L) x 12.5' (W)	3/26/2009	Meyer Storage-Manchester, CT-704C	BP-09C
3/25/2009	Meyer Tag No. 233	836189-xxxx	1	Carpet - 36' (L) x 12.5' (W)	3/26/2009	Meyer Storage-Manchester, CT-703D	BP-09C
3/25/2009	Meyer Tag No. 234	835942-xxxx	1	Carpet - 45' (L) x 12.5' (W) (estimated)	3/26/2009	Meyer Storage-Manchester, CT-704A	BP-09C
3/25/2009	Meyer Tag No. 235	836189-1302	1	Carpet - 151' (L) x 12.5' (W)	3/26/2009	Meyer Storage-Manchester, CT-703C	BP-09C
3/25/2009	Meyer Tag No. 236	836189-1001	1	Carpet - 200' (L) x 12.5' (W)	3/26/2009	Meyer Storage-Manchester, CT-705A	BP-09C
3/25/2009	Meyer Tag No. 237	836189-1101	1	Carpet - 149' (L) x 12.5' (W)	3/26/2009	Meyer Storage-Manchester, CT-703A	BP-09C
3/25/2009	Meyer Tag No. 238	836189-0601	1	Carpet - 232' (L) x 12.5' (W)	3/26/2009	Meyer Storage-Manchester, CT-706C	BP-09C
3/25/2009	Meyer Tag No. 239	836189-0403	1	Carpet - 242' (L) x 12.5' (W)	3/26/2009	Meyer Storage-Manchester, CT-702C	BP-09C
3/25/2009	Meyer Tag No. 240	836189-0302	1	Carpet - 175' (L) x 12.5' (W)	3/26/2009	Meyer Storage-Manchester, CT-704C	BP-09C
3/25/2009	Meyer Tag No. 241	836189-0801	1	Carpet - 200' (L) x 12.5' (W)	3/26/2009	Meyer Storage-Manchester, CT-706A	BP-09C
3/25/2009	Meyer Tag No. 242	836189-1002	1	Carpet - 203' (L) x 12.5' (W)	3/26/2009	Meyer Storage-Manchester, CT-704A	BP-09C
3/25/2009	Meyer Tag No. 243	835942-0501	1	Carpet - 205' (L) x 12.5' (W)	3/26/2009	Meyer Storage-Manchester, CT-701C	BP-09C
3/25/2009	Meyer Tag No. 244	853942-1402	1	Carpet - 190' (L) x 12.5' (W)	3/26/2009	Meyer Storage-Manchester, CT-703A	BP-09C
3/25/2009	Meyer Tag No. 245	835942-0502	1	Carpet - 204' (L) x 12.5' (W)	3/26/2009	Meyer Storage-Manchester, CT-703A	BP-09C
3/25/2009	Meyer Tag No. 246	835942-0301	1	Carpet -160' (L) x 12.5' (W)	3/26/2009	Meyer Storage-Manchester, CT-705A	BP-09C



**Buley Library Project
Inventory Sheet**

ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/25/2009	Meyer Tag Nos. 181-184, 186-191	51901	237 Cartons, 45 Qty each	VCT - 10, 665 sq ft.	3/25/2009	Meyer Storage-Manchester, CT-512C, 507C, 506C, 506D, 511C, 505D, 504C, 508C, 504D, 503C	BP-09C
3/17/2009		88BIP	75 Boxes, Qty 30	ICC Spa, 8"x8" unpolished, terra paver	3/17/2009	1st Floor, Bay 8	BP-09C
3/17/2009		44SP	11 Boxes, Qty 100	American Olean, 4 1/4 "x 4 1/4" wall, 040 Gris Temp TE	3/17/2009	1st Floor, Bay 8	BP-09C
3/17/2009		44SP	122 Boxes, Qty 100	American Olean, 4 1/4 "x 4 1/4" wall, 0007 Lin Clair	3/17/2009	1st Floor, Bay 8	BP-09C
3/17/2009		449SP	8 Boxes, Qty 100	American Olean, 4 1/4 "x 4 1/4", 0040 Bullnose	3/17/2009	1st Floor, Bay 8	BP-09C
3/17/2009		449SP	3 Boxes, Qty 100	American Olean, 4 1/4 "x 4 1/4", 0104 Bullnose	3/17/2009	1st Floor, Bay 8	BP-09C
3/17/2009		449SP	2 Boxes, Qty 100	American Olean, 4 1/4 "x 4 1/4", 0030 Bullnose	3/17/2009	1st Floor, Bay 8	BP-09C
3/17/2009		449SP	3 Boxes, Qty 100	American Olean, 4 1/4 "x 4 1/4", 0110 Bullnose	3/17/2009	1st Floor, Bay 8	BP-09C
3/17/2009		44SP	2 Boxes, Qty 100	American Olean, 4 1/4 "x 4 1/4" wall, 0030 Olive	3/17/2009	1st Floor, Bay 8	BP-09C
3/17/2009		449SP	1 Box, Qty 100	American Olean, 4 1/4 "x 4 1/4", 0070 Bullnose	3/17/2009	1st Floor, Bay 8	BP-09C
3/17/2009		44SP	3 Boxes, Qty 100	American Olean, 4 1/4 "x 4 1/4" wall, 0110 Burgundy	3/17/2009	1st Floor, Bay 8	BP-09C
3/17/2009			12 Boxes, Qty 4	American Olean, 4 1/4 "x 4 1/4" long, 0526, tile corner	3/17/2009	1st Floor, Bay 8	BP-09C
3/17/2009		89TBIP	24 Boxes, Qty 24	Tiles, 6" x 8" 7T7, Grade I	3/17/2009	1st Floor, Bay 8	BP-09C
3/17/2009			10.5 Boxes, Qty 30	Tiles, 8" x 8", Grey	3/17/2009	1st Floor, Bay 8	BP-09C
3/17/2009		88BIP	13 Boxes, Qty 30	Tiles, 8" x 8", unpolished, 0W66 Terra Paver	3/17/2009	1st Floor, Bay 8	BP-09C
3/17/2009		689TBIP	19 Boxes, Qty 24	Tiles, 6" x 8", 0W6453	3/17/2009	1st Floor, Bay 8	BP-09C
3/17/2009		44SP	187 Boxes, Qty 100	American Olean, 4 1/4 "x 4 1/4" wall, 0007 Lin Clair	3/17/2009	1st Floor, Bay 8	BP-09C
3/17/2009		S4449SP	2 Boxes, Qty 100	Tiles, 4 1/4" x 4 1/4", 0104 Bullnose	3/17/2009	1st Floor, Bay 8	BP-09C
3/17/2009		S4449SP	1 Box, Qty 100	Tiles, 4 1/4" x 4 1/4", 0110 Bullnose	3/17/2009	1st Floor, Bay 8	BP-09C
3/17/2009		S4449SP	1 Box, Qty 100	American Olean, 4 1/4 "x 4 1/4", 0030 Bullnose	3/17/2009	1st Floor, Bay 8	BP-09C
3/17/2009		44SP	1 Box, Qty 100	Tiles, 4 1/4" x 4 1/4", Misc, Various Colors	3/17/2009	1st Floor, Bay 8	BP-09C
3/17/2009		88BIP	60 Boxes, Qty 100	Tiles, 8" x 8", unpolished, Terra Paver	3/17/2009	1st Floor, Bay 8	BP-09C
3/17/2009		44SP	1 Box, Qty 100	American Olean, 4 1/4 "x 4 1/4" wall, 0030	3/17/2009	1st Floor, Bay 8	BP-09C
3/17/2009		S4449SP	1 Box, Qty 100	American Olean, 4 1/4 "x 4 1/4", 0040 Bullnose	3/17/2009	1st Floor, Bay 8	BP-09C
3/17/2009			1 Box, Qty 125	Tiles, 4 1/4" x 4 1/4", Misc, Various Colors	3/17/2009	1st Floor, Bay 8	BP-09C
3/10/2009	922	09706	12	Each Kimberly Clark Dispenser	3/11/2009	Basement Bay 7 and Bay 11	BP-10
3/10/2009	922	0472	19	Box, American Specialist Sanitary napkin Disposal	3/11/2009	Basement Bay 7 and Bay 11	BP-10
3/10/2009	901 - 932	333506	17	Boxes, Construction Specialists Inc. Plastic corners	3/11/2009	Basement Bay 7 and Bay 11	BP-10
3/10/2009	901 - 932	3801-42P	1 + 10	Box and 10 pieces, Bathroom	3/11/2009	Basement Bay 7 and Bay 11	BP-10
3/10/2009	901 - 932	1315-4	1	Each, American Specialist Inc. 36" utility shelf	3/11/2009	Basement Bay 7 and Bay 11	BP-10
3/10/2009	901 - 932	1-0600	14	Each, American Specialist Inc. 18" x 36" bathroom mirror	3/11/2009	Basement Bay 7 and Bay 11	BP-10
3/10/2009	901 - 932	652	5	Each, American Specialist Inc. 18" x 24" bathroom mirror	3/11/2009	Basement Bay 7 and Bay 11	BP-10
3/10/2009	901 - 932	B272NM 2.SGLWM	20	Each, Water Fire Extinguisher	3/11/2009	Basement Bay 7 and Bay 11	BP-10
3/10/2009	901 - 932	C330 USAM	6	Each, CO2 10lbs Fire Extinguishers	3/11/2009	Basement Bay 7 and Bay 11	BP-10
3/10/2009	901 - 932	3566	4	Boxes (4/box), Rubbermaid Rigid Liner	3/11/2009	Basement Bay 7 and Bay 11	BP-10
3/10/2009	901 - 932	7822	3	Each, 7822 profile series container	3/11/2009	Basement Bay 7 and Bay 11	BP-10
3/10/2009	901 - 932	3546	1	Box (4/box) 3546 Rubbermaid 4 pack	3/11/2009	Basement Bay 7 and Bay 11	BP-10
3/10/2009	901 - 932	N/A	5	Each plastic bins 3' x 1-1/2'	3/11/2009	Basement Bay 7 and Bay 11	BP-10
3/10/2009	901 - 932	2964	20	Each, Kimberly Clark 2964	3/11/2009	Basement Bay 7 and Bay 11	BP-10
3/10/2009	901 - 932	0970E30	1	Each, Kimberly Clark	3/11/2009	Basement Bay 7 and Bay 11	BP-10
3/10/2009	901 - 932	N/A	1	Box (1000/box) 3"x3" plastic fittings	3/11/2009	Basement Bay 7 and Bay 11	BP-10
3/10/2009	901 - 932	N/A	1	Box (1000/box) 3" Screens	3/11/2009	Basement Bay 7 and Bay 11	BP-10
3/10/2009	901 - 932	6471	2	Each, Lock Box by American Specialists, Inc.	3/11/2009	Basement Bay 7 and Bay 11	BP-10
3/10/2009	901 - 932	09646	1	Each, Kimberly Clark	3/11/2009	Basement Bay 7 and Bay 11	BP-10
3/10/2009	901 - 932	3801-42P	2	Boxes (2/box) Toilet Rails	3/11/2009	Basement Bay 7 and Bay 11	BP-10
3/10/2009	901 - 932	1315-4	1	36" Utility Shelf	3/11/2009	Basement Bay 7 and Bay 11	BP-10
3/10/2009	901 - 932	AS 3412P	1	36" Utility Shelf	3/11/2009	Basement Bay 7 and Bay 11	BP-10
3/10/2009	901 - 932	30600	1	Each, 78"x30" American Specialist Glass Mirror	3/11/2009	Basement Bay 7 and Bay 11	BP-10
3/10/2009	901 - 932	1600	1	Each, 60"x30" American Specialist Glass Mirror	3/11/2009	Basement Bay 7 and Bay 11	BP-10
3/5/2009	0043	N/A	4	sprinkler valves	3/5/2009	Southwest corner - Auditorium	BP-13
3/10/2009		N/A	3	Each, 4" dia, 20' long steel pipe.	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-13
3/12/2009		N/A	1404	Approx. Each, 3/4" dia, 10' long, galvanized pipe	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-13



ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/12/2009		N/A	660	Approx. Each, 1" dia, 10' long, galvanized pipe	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-13
3/12/2009		N/A	12	Each, 4" dia, 10' long, threaded, galvanized pipes	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-13
3/12/2009		N/A	2	Each, 3" dia, 10' long, threaded, galvanized pipes	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-13
3/12/2009		N/A	14	Each, 4" dia, 10' long, galvanized pipes	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-13
3/12/2009		N/A	5	Each, 5" dia 10' long, threaded, galvanized pipe	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-13
3/12/2009		N/A	45	Each, 1" dia, 10' long pipes with 90 degree bent on one side	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-13
3/12/2009		N/A	81	Each, 3" dia, 10' long, galvanized pipe	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-13
3/13/2009		N/A	3	Each, 3" dia 20' long steel pipe, grooved ends	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-13
3/13/2009		N/A	2	Each, 2-1/2" dia 20' long steel pipes	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-13
3/13/2009		N/A	27	Each, 3" dia, 10' long, grooved, steel pipes	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-13
3/13/2009		N/A	6	Each, 6" dia, 20' long, grooved steel pipes	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-13
3/13/2009		N/A	7	Each, 1-1/2" dia, 20' long, steel pipes	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-13
3/13/2009		N/A	20	Each, 4" dia, 20' long, steel pipes	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-13
3/13/2009		N/A	20	Each, 3" dia, 20' long, steel pipe	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-13
3/13/2009		N/A	10	Each, 3/4" dia, 20' long, steel pipe	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-13
3/13/2009		N/A	29	Each, 4" dia, 10' long, galvanized pipes	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-13
3/13/2009		N/A	50	Each, 2" dia, 10' long, galvanized pipe	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-13
3/13/2009		N/A	25	Each, 1-1/4" dia, 10' long, galvanized pip	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-13
3/11/2009	0800	0626612	10	Fire Alarm - Simplex 4903 True Alert Addressable strobe		Basement Bay 6	BP-13B
3/11/2009	0800	062658	3	boxes Simplex 4904 True Alert Addressable strobe fire alarm - 20 ct each		Basement Bay 6	BP-13B
3/11/2009	0800	54914	10	rolls fire alarm cable 18 AWG solid 2C plenum - red - 1000 ft each		Auditorium near ramp	BP-13B
3/11/2009	0800	4901R60-00	6	rolls fire alarm control cable - red coiled - 1000 ft each		Auditorium near ramp	BP-13B
3/11/2009	0800	4511	1	rolls fire alarm cable 12 AWG solid copper - red - 1000 ft each		Auditorium near ramp	BP-13B
3/6/2009	A001	4903	3	Simplex true alert fire alarm	3/6/2009	East Wall - Auditorium	BP-13B
3/6/2009	A001	0742990	1	Fire release device - sup releases periph. And enclosure	3/6/2009	East Wall - Auditorium	BP-13B
3/6/2009	A001		1	power command annunciator	3/6/2009	East Wall - Auditorium	BP-13B
3/6/2009	A001	2080	1	Simplex apert and Maintenance switch	3/6/2009	East Wall - Auditorium	BP-13B
3/6/2009	A001	0630763	3	Fire alarm switch pull station assembly	3/6/2009	East Wall - Auditorium	BP-13B
3/9/2009	702	670610381891	24	Each, Wade, Plumbing fixture carrier assembly	3/7/2009	Basement Bay 1 and Bay 6	BP-15
3/9/2009	702	670610300465	22	Each, Wade - 1FA, assembly (11") urinals	3/7/2009	Basement Bay 1 and Bay 6	BP-15
3/9/2009	702	670610234319	5	Each, Wade Carrier Assembly (18")	3/7/2009	Basement Bay 10	BP-15
3/9/2009	702	670610414926	10	Each, Wade AM115Q, Bearing Plate Assembly	3/7/2009	Basement Bay 10	BP-15
3/4/2009	0001		145	.25" copper T	3/5/2009	West wall - Auditorium	BP-15
3/4/2009	0002		280	1" copper elbow	3/5/2009	West wall - Auditorium	BP-15
3/4/2009	0002		10	2" copper elbow	3/5/2009	West wall - Auditorium	BP-15
3/4/2009	0003		85	1.25" copper reducing T	3/5/2009	West wall - Auditorium	BP-15
3/4/2009	0003		120	1.25" copper elbow	3/5/2009	West wall - Auditorium	BP-15
3/4/2009	0004		300	1.25" copper tube caps	3/4/2009	West wall - Auditorium	BP-15
3/4/2009	0004		50	1" copper couplings	3/4/2009	West wall - Auditorium	BP-15
3/4/2009	0004		75	1.25" copper elbow	3/4/2009	West wall - Auditorium	BP-15
3/4/2009	0005		470	1" copper elbow	3/5/2009	West wall - Auditorium	BP-15
3/4/2009	0006		20	2" copper elbow	3/5/2009	West wall - Auditorium	BP-15
3/4/2009	0006		10	1.5" copper elbow	3/5/2009	West wall - Auditorium	BP-15
3/4/2009	0006		30	2" copper T	3/5/2009	West wall - Auditorium	BP-15
3/4/2009	0007		52	2" copper reducing T	3/4/2009	West wall - Auditorium	BP-15
3/4/2009	0008		24	2" copper reducing T	3/4/2009	West wall - Auditorium	BP-15
3/4/2009	0008		30	1" copper T	3/4/2009	West wall - Auditorium	BP-15
3/4/2009	0009		175	1" copper T	3/4/2009	West wall - Auditorium	BP-15
3/4/2009	0010		180	1.5" copper elbow	3/4/2009	West wall - Auditorium	BP-15
3/4/2009	0010		4	2" ball valves	3/4/2009	West wall - Auditorium	BP-15
3/4/2009	0010		75	1" copper end caps	3/4/2009	West wall - Auditorium	BP-15
3/4/2009	0010		5	2" copper end caps	3/4/2009	West wall - Auditorium	BP-15
3/4/2009	0010		300	.75" copper test caps	3/4/2009	West wall - Auditorium	BP-15
3/4/2009	0011		150	1" copper T	3/4/2009	West wall - Auditorium	BP-15
3/4/2009	0011		75	1" copper couplings	3/4/2009	West wall - Auditorium	BP-15
3/4/2009	0011		15	2" copper adapter	3/4/2009	West wall - Auditorium	BP-15



ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/4/2009	0011		8	3" copper adapter	3/4/2009	West wall - Auditorium	BP-15
3/4/2009	0011		10	3" copper couplings	3/4/2009	West wall - Auditorium	BP-15
3/4/2009	0012		90	1.5" copper T	3/5/2009	SW corner auditorium	BP-15
3/4/2009	0013		50	2" copper T	3/5/2009	West wall - Auditorium	BP-15
3/4/2009	0014		75	2" copper couplings	3/5/2009	West wall - Auditorium	BP-15
3/4/2009	0015		50	2" copper couplings	3/5/2009	SW corner auditorium	BP-15
3/4/2009	0016		50	2" copper couplings	3/5/2009	West wall - Auditorium	BP-15
3/4/2009	0017		500	.75" copper couplings	3/5/2009	West wall - Auditorium	BP-15
3/4/2009	0018		90	1.5" copper T	3/5/2009	East wall auditorium	BP-15
3/4/2009	0019		90	1.5" copper T	3/5/2009	East wall auditorium	BP-15
3/4/2009	0020		100	1.5" copper T	3/5/2009	West wall - Auditorium	BP-15
3/4/2009	0021		65	1.5" copper T	3/5/2009	West wall - Auditorium	BP-15
3/4/2009	0021		30	1.5" copper elbows	3/5/2009	West wall - Auditorium	BP-15
3/4/2009	0022		90	1.5" copper elbows	3/5/2009	SW corner auditorium	BP-15
3/4/2009	0023		130	1.5" copper couplings	3/5/2009	West wall - Auditorium	BP-15
3/4/2009	0023		15	1.5" copper elbows	3/5/2009	West wall - Auditorium	BP-15
3/4/2009	0024		100	1.5" copper couplings	3/5/2009	SW corner auditorium	BP-15
3/4/2009	0025		100	1.5" copper elbows	3/5/2009	West wall - Auditorium	BP-15
3/5/2009	0026	N/A	150	3/4" copper coupling	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0026	N/A	50	3/4" copper elbow	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0026	N/A	200	3/4" copper end cap	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0026	N/A	75	1" copper adapter	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0027	N/A	105	1/2" copper elbow	3/5/2009	East Wall Auditorium	BP-15
3/5/2009	0028	N/A	50	1/2" copper tee	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0028	N/A	100	1/2" copper end cap	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0028	N/A	250	1/2" copper coupling	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0029	N/A	150	3/4" copper coupling	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0029	N/A	50	1" copper coupling	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0030	N/A	250	1/4" copper coupling	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0030	N/A	10	copper branch coupling	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0030	N/A	20	1 1/4" copper coupling	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0030	N/A	150	1/2" copper coupling	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0031	N/A	70	1" female adapter	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0031	N/A	120	3/4" elbow - 90	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0031	N/A	25	1 1/4" elbow - 90	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0031	N/A	10	1 1/2" elbow - 90	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0031	N/A	2	4" elbow - 90	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0031	N/A	2	4" elbow - 90	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0031	N/A	50	1/2" misc elbows - 90/45	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0032	N/A	50	1/2" copper coupling	3/5/2009	East Wall - Auditorium	BP-15
3/5/2009	0032	N/A	50	1 1/2" copper coupling	3/5/2009	East Wall - Auditorium	BP-15
3/5/2009	0032	N/A	45	1 1/2" copper end cap	3/5/2009	East Wall - Auditorium	BP-15
3/5/2009	0032	N/A	50	1/2" copper adapter	3/5/2009	East Wall - Auditorium	BP-15
3/5/2009	0033	N/A	250	3/4" copper adapter	3/5/2009	East Wall - Auditorium	BP-15
3/5/2009	0033	N/A	15	1 1/2" copper coupling	3/5/2009	East Wall - Auditorium	BP-15
3/5/2009	0034	N/A	25	1 1/2" copper coupling	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0034	N/A	40	1" bronze/copper fitting	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0034	N/A	40	2" copper adapter	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0035	N/A	25	1"x1"x3/4" tee	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0035	N/A	1	3" tee	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0035	N/A	75	3/4" elbow - 45	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0035	N/A	7	2" elbow - 90	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0036	N/A	50	1/2" copper elbow	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0036	N/A	20	1 1/2" copper tee	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0036	N/A	40	1/2" copper tee	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0036	N/A	25	3/4" copper tee	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0036	N/A	3	3" copper tee	3/5/2009	West Wall - Auditorium	BP-15



**Buley Library Project
Inventory Sheet**

ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/5/2009	0036	N/A	5	2" copper tee	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0037	N/A	10	2" copper tee	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0037	N/A	50	1 1/2" copper tee	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0037	N/A	100	1" copper tee	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0038	N/A	1	3" elbow - 90	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0038	N/A	2	4" elbow - 90	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0038	N/A	9	2 1/2" elbow - misc 45, reducing	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0038	N/A	25	1 1/2" misc elbows	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0038	N/A	50	3/4" misc elbows	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0039	N/A	40	1" brass tee	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0039	N/A	30	1" brass end cap	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0039	N/A	7	1 1/4"x 1" aluminum tube	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0039	N/A	6	1/2" brass valve	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0039	N/A	2	1" brass fitting	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0039	N/A	6	1/8"x1" aluminum rods	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0039	N/A	20	2" rubber gaskets	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0039	N/A	4	resin - cans	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0040	N/A	1	3" ball valve	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0040	N/A	4	2" ball valve	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0040	N/A	15	1 1/4" ball valve	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0041	N/A	3	2" ball valve	3/5/2009	Southwest corner - Auditorium	BP-15
3/5/2009	0041	N/A	12	1 1/4" ball valve	3/5/2009	Southwest corner - Auditorium	BP-15
3/5/2009	0042	N/A	45	2" cast iron coupling	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0043	N/A	10	3/4" ball valve	3/5/2009	Southwest corner - Auditorium	BP-15
3/5/2009	0043	N/A	2	3" ball valve	3/5/2009	Southwest corner - Auditorium	BP-15
3/5/2009	0044	N/A	26	3/4" cc union	3/5/2009	Southwest corner - Auditorium	BP-15
3/5/2009	0044	N/A	25	1 1/2" elbow - 90	3/5/2009	Southwest corner - Auditorium	BP-15
3/5/2009	0044	N/A	1	3x3x2 reducing tee	3/5/2009	Southwest corner - Auditorium	BP-15
3/5/2009	0044	N/A	50	3/4" bronze threaded nipple - misc length	3/5/2009	Southwest corner - Auditorium	BP-15
3/5/2009	0044	N/A	20	1/4"x 6" bronze nipple	3/5/2009	Southwest corner - Auditorium	BP-15
3/5/2009	0044	N/A	31	1 1/2" nipple - 1PS ASTM F492P17	3/5/2009	Southwest corner - Auditorium	BP-15
3/5/2009	0044	BAL00/400 05-21	5	1/2" bronze ball valve (Milwaukee)	3/5/2009	Southwest corner - Auditorium	BP-15
3/5/2009	0045	N/A	15	3" rubber gasket	3/5/2009	Southwest corner - Auditorium	BP-15
3/5/2009	0045	N/A	20	2" rubber gasket	3/5/2009	Southwest corner - Auditorium	BP-15
3/5/2009	0045	N/A	5	12" rubber gasket	3/5/2009	Southwest corner - Auditorium	BP-15
3/5/2009	0046	N/A	7	12" rubber gasket	3/5/2009	Southwest corner - Auditorium	BP-15
3/5/2009	0047	N/A	48	3" cast iron no-hub coupling	3/5/2009	Southwest corner - Auditorium	BP-15
3/5/2009	0048	N/A	12	100 watt incandescent lamp	3/5/2009	Southwest corner - Auditorium	BP-15
3/5/2009	0048	BA485B	2	1 1/2" bronze ball valve 600 WOG/150 SWP (Milwaukee)	3/5/2009	Southwest corner - Auditorium	BP-15
3/5/2009	0048		6	1 1/4" bronze ball valve 600 WOG	3/5/2009	Southwest corner - Auditorium	BP-15
3/5/2009	0048	B4485B	3	1" bronze ball valve 600 WOG/ 150SWP (Milwaukee)	3/5/2009	Southwest corner - Auditorium	BP-15
3/5/2009	0048		1	3/4" bronze ball valve 600 WOG	3/5/2009	Southwest corner - Auditorium	BP-15
3/5/2009	0048	BA-150A112	6	1 1/2" bronze ball valve (Milwaukee)	3/5/2009	Southwest corner - Auditorium	BP-15
3/5/2009	0048	BB2,B16.44,175PS.1	1	2" bronze gate valve	3/5/2009	Southwest corner - Auditorium	BP-15
3/5/2009	0053	N/A	15	misc brass fittings	3/5/2009	Southwest corner - Auditorium	BP-15
3/5/2009	0053	N/A	3	chrome stop valve	3/5/2009	Southwest corner - Auditorium	BP-15
3/5/2009	0053	N/A	7	3" brass flange	3/5/2009	Southwest corner - Auditorium	BP-15
3/5/2009	0056	N/A	4	quart black adhesive lube	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0056	N/A	24	toilet handle	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0057	N/A	3	2 1/2" threaded nipple (short)	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0057	N/A	2	1 1/2" clamp (copper)	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0057	N/A	1	1" clamp (copper)	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0057	N/A	1	2" bronze trap ISO Legend T15	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0057	N/A	25	1 1/2" elbows/tees (copper)	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0057	N/A	50	1 1/2" water cup (copper)	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0057	N/A	20	1 1/2" elbow - 90	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0057	N/A	20	1 1/2" elbow - 90	3/5/2009	West Wall - Auditorium	BP-15



ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/5/2009	0057	N/A	10	1 1/2" bronze adapter (Nibco figure 804)	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0057	N/A	10	1 1/2" bronze adapter (Nibco figure 804)	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0057	N/A	20	1 1/2" elbow - 90	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0058	N/A	6	2 lb point lubricant	3/5/2009	East Wall - Auditorium	BP-15
3/5/2009	0058	N/A	6	tube silicone	3/5/2009	East Wall - Auditorium	BP-15
3/5/2009	0058	N/A	15	1" pipe thread tape	3/5/2009	East Wall - Auditorium	BP-15
3/5/2009	0058	N/A	150	dust mask	3/5/2009	East Wall - Auditorium	BP-15
3/5/2009	0058	N/A	7	1/2" threaded water hammer arrestor	3/5/2009	East Wall - Auditorium	BP-15
3/5/2009	0058	N/A	6	quart gasket lubricant	3/5/2009	East Wall - Auditorium	BP-15
3/5/2009	0059	00644IND-12	12	1/2" plastic handle (Corban CFB)	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0059	N/A	12	3/4" plastic handle (Corban CFB)	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0059	N/A	3	1/4"x 1 1/4 concrete screw (Box-100ct)	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0059	PR 500, PPP [N 1/2"]	23	Prime rite trap primer valve	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0059	1D670610353126	7	Strain Assy 6C,DC,1, SQ Hole CWADEJ	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0059		1	Box Assy Nickle Bronze 6"x6" box	3/5/2009	West Wall - Auditorium	BP-15
3/6/2009	0059		10	Threadolet 1" SA/A105 3000	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0060		7	1 1/2" Copper 45° Elbow	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0060		25	1 1/2" copper coupling	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0060		27	1 1/2" Copper 90° elbow	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0060		10	2 1/2" copper misc. (tees & elbows)	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0060		60	1/2" adapter	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0060		27	1 1/2" copper coupling	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0060		75	1 1/2" copper coupling	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0061		4	2" brushes	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0061		10	1/4" elbow copper	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0061		50	3/16 x 1 1/4" concrete anchors	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0061		6	Abrasive cloth 180 grit aluminum oxide	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0061		10	1 1/2" Y bronze	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0061		6	coupling PVC 1/2"	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0061		10	mix. Copper bronze 1"	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0061		1	wall hydrant 10" WCVH10 6500 Series	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0062		42	1 lb. soldering paste (1 whole box)	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0063		5	8" heavy duty no-hub coupling for cast iron sanitary piping	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0063		2	4" heavy duty no-hub coupling for cast iron san. Piping	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0063		2	2" heavy duty no-hub coupling for cast iron piping	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0063		1	Milwaukee Valve 1 1/2" ball valve bronze	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0064		10	8" heavy duty no-hub coupling for cast iron sanitary piping	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0065		10	6" heavy duty no-hub coupling for cast iron san. Piping	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0066		5	Mats of 4' x 2.5' CANUSA WLO QA 50218809BN	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0067		16	Trap seal primer distribution unit 5/8" compression connection MIFAD MI-DV-625	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0067	M1FAB MR-500	12	Prime Rite 1/2" trap prime valve	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0067		1	4" heavy duty no-hub coupling for cast iron san. Piping	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0067		1	4" x 3" cast iron reducer	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0067		2	5 pounds puddie mix	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0067	DHX	1	1 Qt. John Blair Black adhesive lubricant	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0067	15	3	Pounds Harris soldering rods - 15" long	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0067	A31003	3	3/16" Just Better Copper ODS	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0068		12	1" Elbow red. Lt. misc. cast iron	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0068		4	misc. 1" galvanized steel	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0068		4	1/2" copper fittings	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0068		2	pounds misc. bronze (screws, fittings, etc.)	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0068		20	3/8" compression nuts	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0068		1	2" clamp - galvanized steel	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0068		1	4" pipe hanger	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0068		5	1/2" PVC fittings	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0068		5	pounds misc. steel	3/5/2009	West Wall - Auditorium	BP-15



**Buley Library Project
Inventory Sheet**

ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/5/2009	0069	670610240990	41	boxes Wade deck clamp assembly, roof drain, 3500, 53	3/6/2009	East Wall - Auditorium	BP-15
3/5/2009	0070		35	boxes Wade deck clamp assembly, roof drain, 3500, 35	3/6/2009	East Wall - Auditorium	BP-15
3/5/2009	0071	6706102304135	3	Boxes Wade Top Assembly 6000Z, 1, CU, HD, CUR-C	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0071	670610300151	8	Boxes Wade Access cover 8480, R8, S5 w/screw	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0071	67061038836	6	Boxes Wade Top Assembly 3200, roof drain	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0071	670610312789	2	Boxes Wade Top Assembly 3000, SD, C142	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0071	670610385943	2	Boxes Wade Deck Clamp Assembly, 3200-DC-53 RFDR	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0071		48	3" no-hub coupling	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0071		10	12" rubber gaskets	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0071		5	pounds metal misc.	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0071	670610312709	3	boxes Wade top assembly 300, Sd, C1, 42	3/6/2009	East Wall - Auditorium	BP-15
3/5/2009	0071	670610235309	10	boxes Wade body assembly 1103 NH, FLDR	3/6/2009	East Wall - Auditorium	BP-15
3/6/2009	0072	6076103927	18	boxes top assembly 3000, Cl, 42	3/5/2009	East Wall - Auditorium	BP-15
3/6/2009	0072	670610385943	1	Wade deck clamp assembly 3200, DC, 53, RFDR	3/5/2009	East Wall - Auditorium	BP-15
3/5/2009	0080	3940-8R	1	Wade drain outlet 8"	3/6/2009	Mechanical Room	BP-15
3/5/2009	0152		2	6" no-hub coupling for cast iron piping	3/5/2009	West Wall - Auditorium	BP-15
3/5/2009	0180-0182		13	cleanouts cast iron 1-1/2"	3/6/2009	West Wall - Auditorium	BP-15
3/5/2009	0180-0182		9	cleanouts cast iron 2-1/2"	3/6/2009	West Wall - Auditorium	BP-15
3/5/2009	0180-0182		17	cleanouts cast iron 3-1/2"	3/6/2009	West Wall - Auditorium	BP-15
3/5/2009	0180-0182		33	cleanouts cast iron 5"	3/6/2009	West Wall - Auditorium	BP-15
3/5/2009	0180-0182		6	galvanized 90° elbow 2"	3/6/2009	West Wall - Auditorium	BP-15
3/5/2009	0180-0182		1	cast iron 90° elbow 3"	3/6/2009	West Wall - Auditorium	BP-15
3/5/2009	0180-0182		5	bronze 90° elbow 2"	3/6/2009	West Wall - Auditorium	BP-15
3/5/2009	0180-0182		1	victaulic flange 8" 8/741	3/6/2009	West Wall - Auditorium	BP-15
3/5/2009	0180-0182		1	clamp 8" galvanized	3/6/2009	West Wall - Auditorium	BP-15
3/9/2009	0200 - 0255	C800C	7	Metallic non-hub size 142	3/12/2009	Basement Bay 8	BP-15
3/9/2009	0200 - 0255		30	2" clevis hanger	3/12/2009	Basement Bay 8	BP-15
3/9/2009	0200 - 0255	100GI0200	4	boxes lightweight 2" clevis hanger - 100 ct each	3/12/2009	Basement Bay 8	BP-15
3/9/2009	0200 - 0255	110GI0300	8	boxes lightweight 3" clevis hanger - 25 ct each	3/12/2009	Basement Bay 8	BP-15
3/9/2009	0200 - 0255	11GI0400	35	boxes standard 4" clevis hanger - 25 ct each	3/12/2009	Basement Bay 8	BP-15
3/9/2009	0200 - 0255	11GI0400	9	standard 4" clevis hanger	3/12/2009	Basement Bay 8	BP-15
3/9/2009	0200 - 0255		6	linear ft Delta PC pipe insulation	3/12/2009	Basement Bay 8	BP-15
3/9/2009	0200 - 0255		100	PVC 1/2" fittings	3/12/2009	Basement Bay 8	BP-15
3/9/2009	0200 - 0255		100	PVC 1-1/2" fittings	3/12/2009	Basement Bay 8	BP-15
3/9/2009	0200 - 0255		35	3" PVC fittings	3/12/2009	Basement Bay 8	BP-15
3/9/2009	0200 - 0255	1408-007BC	3	Lasco 90° elbow 3/4"	3/12/2009	Basement Bay 8	BP-15
3/9/2009	0200 - 0255	07566	7	replacement center bit w/spring	3/12/2009	Basement Bay 8	BP-15
3/9/2009	0200 - 0255	ACE 43818	4	Ace self-adhesive insulating pipe wrap 2" x 1/8" x 30'	3/12/2009	Basement Bay 8	BP-15
3/9/2009	0200 - 0255	O1056-22	1	Fernco 2" plastic coupling	3/12/2009	Basement Bay 8	BP-15
3/10/2009	0256 - 0275		5	24" hose rack	3/12/2009	Basement Bay 8	BP-15
3/10/2009	0256 - 0275	T31-003	6	Jones Stephens Corp 3" test plug wing nut	3/12/2009	Basement Bay 8	BP-15
3/10/2009	0256 - 0275	T31-002	1	Jones Stephens Corp 2" test plug wing nut	3/12/2009	Basement Bay 8	BP-15
3/10/2009	0256 - 0275	429-007	35	Nibco 3/4" PVC coupling	3/12/2009	Basement Bay 8	BP-15
3/10/2009	0256 - 0275	F-155	18	Matco-Norca grid top PO plug w/4" tall piece	3/12/2009	Basement Bay 8	BP-15
3/10/2009	0256 - 0275	0035010	1	Watts 1/2" hose bibb type boiler drain	3/12/2009	Basement Bay 8	BP-15
3/10/2009	0256 - 0275		14	feet of copper tubing	3/12/2009	Basement Bay 8	BP-15
3/10/2009	0256 - 0275	P38-005	1	Jones Stephens 1-1/2" P-Trap	3/12/2009	Basement Bay 8	BP-15
3/10/2009	0256 - 0275		1	Weiss Thermometer with 3/4" NPT	3/12/2009	Basement Bay 8	BP-15
3/10/2009	0256 - 0275	ETF6603365273	4	Sloan Optima Faucet Sensor Operated	3/12/2009	Basement Bay 8	BP-15
3/10/2009	0256 - 0275	269-1640	1	Dearborn Brass P-Trap and Extension Tube	3/12/2009	Basement Bay 8	BP-15
3/10/2009	0256 - 0275	100137	12	Hydra Zorb 1-3/8" In OK Tube	3/12/2009	Basement Bay 8	BP-15
3/10/2009	0256 - 0275	P1BG507	1	Hydro Air 18 Gall Overlapping DG	3/12/2009	Basement Bay 8	BP-15
3/10/2009	0276 - 0299		1	Wheeling Pittsburgh aluminum drain pan 4 x 4	3/12/2009	Basement Bay 8	BP-15
3/10/2009	0276 - 0299	4010600EG	12	boxes Caddy 6" clevis hanger - 10 ct each	3/12/2009	Basement Bay 8	BP-15
3/10/2009	0276 - 0299	11G10800	3	8" Clevis Hanger	3/12/2009	Basement Bay 8	BP-15
3/10/2009	0276 - 0299		1	10" Clevis Hanger	3/12/2009	Basement Bay 8	BP-15
3/10/2009	0276 - 0299	BA-475B	1	Milwaukee Valve Trim Valve	3/12/2009	Basement Bay 8	BP-15



**Buley Library Project
Inventory Sheet**

ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/10/2009	0276 - 0299	MS-970	225	Marking Services various plastic hot/cold pipe labels	3/12/2009	Basement Bay 8	BP-15
3/10/2009	0276 - 0299	670610392798	2	boxes Wade top, assy dome/ring/roof drain	3/12/2009	Basement Bay 8	BP-15
3/10/2009	0276 - 0299	BA-1505A200	2	Milwaukee Valve Ball Valve	3/12/2009	Basement Bay 8	BP-15
3/10/2009	0276 - 0299		1	QuikCrete - 50 lb bucket	3/12/2009	Basement Bay 8	BP-15
3/10/2009	0276 - 0299		8	Cambridge Lee 18" Copper pipe - 34L	3/12/2009	Basement Bay 8	BP-15
3/10/2009	0276 - 0299		4	50 qt #16 brass single jack chain	3/12/2009	Basement Bay 8	BP-15
3/10/2009	0276 - 0299		2	boxes Brass S hooks - 100 ct each	3/12/2009	Basement Bay 8	BP-15
3/10/2009	0276 - 0299	06306	1	box Powers 3/8" steel drop-in internal plug - 50 ct each	3/12/2009	Basement Bay 8	BP-15
3/10/2009	0276 - 0299		50	1 ft pipe sleepers/supports	3/12/2009	Basement Bay 8	BP-15
3/6/2009	0303		4	tubs Airseal #22 water based duct sealant - 20 pounds each	3/6/2009	West Wall - Auditorium	BP-15
3/6/2009	0303		2	tubs plumber putty - 5 pounds each	3/6/2009	West Wall - Auditorium	BP-15
3/6/2009	0304	731593951550	1	OVL - double frame	3/6/2009	West Wall - Auditorium	BP-15
3/6/2009	0305	TA-300, TA-350	1	Emergency minig valve system	3/6/2009	West Wall - Auditorium	BP-15
3/6/2009	0305	EL154	6	Sloan Accessory optima plumbing #0345154	3/6/2009	West Wall - Auditorium	BP-15
3/6/2009	0305		7	Easy Chop chop saw blade 1-BF 1" , 14" x 3/32	3/6/2009	West Wall - Auditorium	BP-15
3/6/2009	0305		40	plastic handle carbon CFB 1-14" steel brushes	3/6/2009	East Wall - Auditorium	BP-15
3/6/2009	0305		15	pounds copper misc. parts	3/6/2009	East Wall - Auditorium	BP-15
3/6/2009	0305		40	male adapters copper 1/2" OD size 5/8 x 1/2	3/6/2009	East Wall - Auditorium	BP-15
3/6/2009	0305	L414VB-BH	1	water saver faucet co.	3/6/2009	East Wall - Auditorium	BP-15
3/6/2009	0305	CP200	8	band-seal coupling 2"	3/6/2009	East Wall - Auditorium	BP-15
3/6/2009	0306		4	CP Brass grid top 4" tail piece	3/6/2009	East Wall - Auditorium	BP-15
3/6/2009	0306		2000	misc. fasteners	3/6/2009	East Wall - Auditorium	BP-15
3/6/2009	0306		3	boxes 1-1/2" P-trap w/cleanout 7 gauge	3/6/2009	East Wall - Auditorium	BP-15
3/6/2009	0308 - 0312	P1016	1	Chicago Faucets faucet assembly	3/6/2009	Basement Bay 2	BP-15
3/6/2009	0316	P38-012	3	P-Trap w/clean out 17 gauge, 1-1/2"	3/6/2009	Basement Bay 2	BP-15
3/6/2009	0316	141 86B	1	Powers showerhead c/f #621NCP8602	3/6/2009	Basement Bay 2	BP-15
3/6/2009	0316	34352	300	Hilti screws X-DNI 27P8	3/6/2009	Basement Bay 2	BP-15
3/6/2009	0316	06306	100	Powers Fasteners 3/8"	3/6/2009	Basement Bay 2	BP-15
3/6/2009	0316		36	2" Band-Seal coupling CP 200 cast iron	3/6/2009	Basement Bay 2	BP-15
3/6/2009	0316	V2402	4	cans Fast drying enamel spray 10 oz cans	3/6/2009	Basement Bay 2	BP-15
3/6/2009	0316	100087	9	Hydra-zorb 7/8" OD clamp assembly	3/6/2009	Basement Bay 2	BP-15
3/6/2009	0316	0637667	1	2080-9060 abort and maintenance switch surface	3/6/2009	Basement Bay 2	BP-15
3/6/2009	0316		3	misc. band 1-1/2" coupling	3/6/2009	Basement Bay 2	BP-15
3/6/2009	0316		35	3" heavy weight coupling cast iron	3/6/2009	Basement Bay 2	BP-15
3/6/2009	0316	SU3000	7	cans silicone acrylic latex caulk 10.3 fl. Oz.	3/6/2009	Basement Bay 2	BP-15
3/6/2009	0316		1	box Elgen #440 butyl gasket 25 ft rolls - 500 ft each	3/6/2009	Basement Bay 2	BP-15
3/6/2009	0316	J00YSBR	1	Wilkins water reducing valve 3/4"	3/6/2009	Basement Bay 2	BP-15
3/6/2009	0316		1	P.O Plug 176A 4" tail piece	3/6/2009	Basement Bay 2	BP-15
3/6/2009	0316	670610300144	1	Wade Access cover R65S w/screw	3/6/2009	Basement Bay 2	BP-15
3/6/2009	0316	3832	1	Buried service wire splice encapsulator kit	3/6/2009	Basement Bay 2	BP-15
3/6/2009	0316	120929	3	Hyperther shield hand	3/6/2009	Basement Bay 2	BP-15
3/6/2009	0316		3	strainers drain	3/6/2009	Basement Bay 2	BP-15
3/6/2009	0316		1	Byer stop sealant	3/6/2009	Basement Bay 2	BP-15
3/6/2009	0316		1	positive pressure switch	3/6/2009	Basement Bay 2	BP-15
3/6/2009	0316		6	plumbing seal assembly	3/6/2009	Basement Bay 2	BP-15
3/6/2009	0401	J-ADA-35	1	sink trap	3/6/2009	West Wall - Auditorium	BP-15
3/6/2009	0401	J-ADA-35	1	sink trap - not all parts - incomplete set	3/6/2009	West Wall - Auditorium	BP-15
3/9/2009	0453 - 0456	111	1	Sloan Flushometer bypass diaphragm	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-15
3/9/2009	0453 - 0456	670610300144	1	Wade Access cover 8480 (w/screw)	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-15
3/9/2009	0453 - 0456	670610300144	1	Wade Access cover 8480 (w/o screw)	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-15
3/9/2009	0457 - 0460	P38-012	4	1-1/2" P-Trap w/clean out	3/10/2009	Basement Bay 7	BP-15
3/9/2009	0457 - 0460	8799	1	Moen 2 Handle Kitchen Faucet	3/10/2009	Basement Bay 7	BP-15
3/9/2009	0457 - 0460		2	Milwaukee Valve Bronze 25 SWP 1-1/4" Gate Valve 200W0G	3/10/2009	Basement Bay 7	BP-15
3/6/2009	A001		15	misc. flushometer covers	3/6/2009	East Wall - Auditorium	BP-15



**Buley Library Project
Inventory Sheet**

ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/6/2009	n/a		13	C-Channel 201 steel	3/6/2009	South Wall - Auditorium (under stage)	BP-15
3/6/2009	n/a		6	angle iron 20'	3/6/2009	South Wall - Auditorium (under stage)	BP-15
3/6/2009	n/a		2	aluminum C-channel w/holes 20'	3/6/2009	South Wall - Auditorium (under stage)	BP-15
3/6/2009	n/a		3	8' aluminum angles	3/6/2009	South Wall - Auditorium (under stage)	BP-15
3/6/2009	n/a		1	6' aluminum angles	3/6/2009	South Wall - Auditorium (under stage)	BP-15
3/6/2009	n/a		2	4' steel square tube w/3" base (1.5" square)	3/6/2009	South Wall - Auditorium (under stage)	BP-15
3/10/2009		N/A	3	Each, 10" dia Charlotte Pipe, 10' long, 10 No, Hubbed Coated Cast Iron Pipe	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15
3/10/2009		N/A	7	Each, 8" dia Charlotte Pipe, 10' long, 8 No, Hubbed Coated Cast Iron Pipe	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15
3/12/2009		N/A	80	Each, 3" connector, cast iron connector by Charlotte	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15
3/12/2009		N/A	2	Each, 10"x8" inlets, cast iron Y connectors	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15
3/12/2009		10SV 1/4 UPC	1	Each, 10" 90 degree elbow	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15
3/12/2009		ICHAR USA	1	Each, 10" 45 degree elbow	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15
3/12/2009		NH20	12	Each, 8"x8" inlets, cast iron, Y connectors	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15
3/13/2009		N/A	1	Each, 4" dia 20' long, hubbed coated cast iron pipe	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15
3/13/2009		N/A	9	Each, 6" dia, 10' long, hubbed, coated cast iron pipe	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15
3/13/2009		N/A	3	Each, 2" dia, 10' long, coated cast iron pipe	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15
3/13/2009		N/A	5	Each, 6" dia, 10' long, coated cast iron pipe	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15
3/13/2009		N/A	11	Each, 3" dia, 10' long, hubbed, coated, cast iron pipe	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15
3/13/2009		N/A	7	Each, 2" dia, 10' long, hubbed, coated, cast iron pipe	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15
3/13/2009		N/A	2	Each, 4" dia, 20' long, hubbed, coated, cast iron pipe	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15
3/13/2009		N/A	2	Each, 10" dia, 10' long, coated, cast iron pipe	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15
3/13/2009		N/A	3	Each, 6" dia, 20' long, hubbed, coated, cast iron pipe	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15
3/13/2009		N/A	72	Each, 6" dia, 10' long, coated, cast iron pipe	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15
3/13/2009		N/A	92	Each, 4" dia, 10' long, coated, cast iron pipe	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15
3/13/2009		N/A	32	Each, 8" dia, 10' long, coated, cast iron pipe	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15
3/13/2009		N/A	2	Each, 12" dia, 10' long, hubbed, coated, cast iron pipe	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15
3/13/2009		N/A	15	Each, 4" dia, 5' long, hubbed, coated, cast iron pipe	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15
3/13/2009		N/A	30	Each, 2-1/2" dia, cast iron, Y connectors	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15
3/13/2009		N/A	2	Pallets (approx 50 pieces/pallet), 2" to 8" dia, misc. cast iron fittings	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15
3/13/2009		N/A	20	Each, 6"x6" dia inlet cast iron Y connector	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15
3/13/2009		W-310-NHR	25	Wade 4"X8"/4	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15
3/4/2009		4960-ET-0	9	Kohler urinal	3/4/2009	West wall - Auditorium	BP-15
3/4/2009		2196-4-0	9	Kohler sinks	3/4/2009	West wall - Auditorium	BP-15
3/4/2009		2005-0	9	Kohler wall mounted sink	3/4/2009	West wall - Auditorium	BP-15
3/4/2009		4670-C-0	29	Kohler toilet seats	3/4/2009	West wall - Auditorium	BP-15
3/4/2009		4330-0	24	Kohler Kingston toilet bowl	3/4/2009	West wall - Auditorium	BP-15
3/4/2009			40	4" No hub couplings	3/4/2009	West wall - Auditorium	BP-15
3/4/2009		PW2150	18	McGuire Pro-Wrap Pre-Wrap 1.5 J Bend WV Cover - TLPC 2SUP.	3/4/2009	West wall - Auditorium	BP-15
3/4/2009			4	Hallsy Taylor Remote Chiller (Drinking Fountain)	3/4/2009	West wall - Auditorium	BP-15
3/4/2009		111	16	Sloan Flushometer	3/4/2009	West wall - Auditorium	BP-15
3/4/2009		186-1	2	Sloan Flushometer	3/4/2009	West wall - Auditorium	BP-15
3/4/2009			3	Lochinvar High Electric Water Heater	3/4/2009	West wall - Auditorium	BP-15
3/4/2009			20	12" quick tie gaskets	3/4/2009	West wall - Auditorium	BP-15
3/4/2009		ETF660	5	Sloan Electric Faucets	3/4/2009	West wall - Auditorium	BP-15
3/4/2009		22C151	8	Delta Faucets	3/4/2009	West wall - Auditorium	BP-15
3/4/2009			1	Elkay SS sink (missing clips replacement ordered)	3/4/2009	West wall - Auditorium	BP-15
3/4/2009			65	2" No hub couplings	3/4/2009	West wall - Auditorium	BP-15
3/4/2009		519-220ABF	1	Bradley wall mount eye was	3/4/2009	West wall - Auditorium	BP-15
3/4/2009		731587651550	4	Hallsy Taylor Aluminum Frame	3/4/2009	West wall - Auditorium	BP-15
3/4/2009		7434083683	4	Hallsy Taylor Drinking Fountain	3/4/2009	West wall - Auditorium	BP-15
3/4/2009		7434084883	2	Hallsy Taylor Drinking Fountain & Frame	3/4/2009	West wall - Auditorium	BP-15
3/4/2009			103	3" No hub couplings	3/4/2009	West wall - Auditorium	BP-15
3/4/2009		SCS400AC	19	Brass Craft Faucet Supply Kit	3/4/2009	West wall - Auditorium	BP-15
3/4/2009		EL-154	20	Control Transformers	3/4/2009	West wall - Auditorium	BP-15
3/4/2009		ST-12	1	Therm-x-trol thermal expansion tank	3/4/2009	West wall - Auditorium	BP-15



**Buley Library Project
Inventory Sheet**

ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/4/2009		ST-5	3	Therm-x-trol thermal expansion tank	3/4/2009	West wall - Auditorium	BP-15
3/4/2009		909	1	Backflow Preventer 3"	3/4/2009	West wall - Auditorium	BP-15
3/4/2009			8	Fire pump gaskets (used)	3/4/2009	West wall - Auditorium	BP-15
3/5/2009		CN-1680	60	No hub coupling 8"	3/5/2009	East wall auditorium	BP-15
3/5/2009		CN-1680	15	No hub coupling 6"	3/5/2009	East wall auditorium	BP-15
3/5/2009		CN-1680	144	No hub coupling 4"	3/5/2009	East wall auditorium	BP-15
3/10/2009		TSB-500	2	12" depth mop service basin - 36" x 36" x 12"	Existing	Basement Bay 5	BP-15
3/10/2009			27	pipe flange brackets for ceiling attachment	Existing	Basement Bay 9	BP-15
3/10/2009		ASTM-C564	3	Sewage pipe connectors 1' dia.	Existing	Basement Bay 9	BP-15
3/10/2009			4	CI 9" x 3' H pipes	Existing	Basement Bay 9	BP-15
3/10/2009			2	sewage pipe 3" connectors	Existing	Basement Bay 9	BP-15
3/10/2009			3	CI sewage pipes 10" dia x 10' length	Existing	Basement Bay 9	BP-15
3/10/2009			14	10' x 12" dia CI sewage bell end pipe	Existing	Outside mechanical room	BP-15
3/10/2009			2	12" x 4" CI reducers	Existing	Outside mechanical room	BP-15
3/10/2009			1	12" x 8" CI reducers	Existing	Outside mechanical room	BP-15
3/10/2009			1	90° angle CI pipe 12" dia.	Existing	Outside mechanical room	BP-15
3/10/2009			5	6" x 4" "Y" CI pipe	Existing	Outside mechanical room	BP-15
3/10/2009			1	6" x 4" sweep CI pipe	Existing	Outside mechanical room	BP-15
3/10/2009			1	12" x 12" CI "Y" pipe	Existing	Outside mechanical room	BP-15
3/10/2009			2	12" x 12" 45s CI pipe	Existing	Outside mechanical room	BP-15
3/10/2009			1	12" x 6" "Y" CI pipe	Existing	Outside mechanical room	BP-15
3/10/2009			1	4" 90° CI pipe	Existing	Outside mechanical room	BP-15
3/10/2009			1	12" x 12" x 12" triple "Y" CI pipe	Existing	Outside mechanical room	BP-15
3/10/2009			3	6" x 10' CI pipe with bell end	Existing	Outside mechanical room	BP-15
3/10/2009		N/A	18	Each, OPEX 6" Dia PVC 12364-C SDR-35 Perf Sewer Pipe, 125" Long	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15
3/10/2009		N/A	5	Each, 5" dia, 10' long PVC Pipes (in two dividable sections along the diameter)	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15
3/12/2009	3001	-	18	Pittsburg Soft Lite Insulated Air Diffuser 12" Vent	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3006	SRH616162401	5 Boxes, Qty 4	Metalaire, 5500S-6 16X16/24 01	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3006	SRH1121201	1 Box, Qty 1	Metalaire	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3006	SRH612122401	1 Box, Qty 2	Metalaire, 5500S-6 12X12/24 01	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3006	-	1 Box	Metalaire, V40045-1 10X06 01	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3006	SRH62222249	1 Box, Qty 4	Metalaire, 5500S-6 22X22/24 01	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3006	5500S6121224S301	2 Boxes, Qty 2	Metalaire, 5500S-6 22X22/24 S301	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3007	5500S-6S3	1 Box, Qty 2	Metalaire, Model 5500S-6S3, Ductsize 6X6, WHT Steel	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3007	5500S6S40606P01	1 Box	Metalaire, 5500S-6 06X06 24X24	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3007	-	1 Box, Qty 1	Metalaire, S65SC 9X9	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3007	SRH612122401	1 Box, Qty 1	Metalaire, 5500S-6 12X12/24 01	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3007	SRH612122401	1 Box, Qty 2	1-SRH-6 22X22, 1-SRH-1 8X8	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3007	SRH612122401	2 Boxes, Qty 4	Metalaire, 5500S-6 12X12/24 01	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3007	SRH612122401	2 Boxes, Qty 5	Metalaire, 5500S-6 12X12/24 01	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3007	-	1 Box, Qty 2	1-SRH-1 12X12, 1-SRH-1 8X8	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3007	5500S6S40606P01	-	Metalaire, 5500S-6 06X06 24X24	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3007	-	1 Box	Transition pieces, 10 ea 6X6/6, 8ea 12X12/10, 29ea 9X9/8	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3007	6610	1 Box	Air Grill, Model 6610, Style 12-6, Length 48, Slots 2, Inlet Size 2EB, Finish 20	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3008	6610	1 Box	Air Grill, Model 6610, Style 12-6, Length 48, Slots 2, Inlet Size 2EB, Finish 20	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3009	SRH1080801	1 Box, Qty 5	Metalaire, SRH-1 08X08-1	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3009	5500S-6S3	1 Box, Qty 1	Metalaire, Model 5500S-6S3, Ductsize 6X6, WHT Steel	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3009	-	1 Box	Transition 1 1/2" Deep, Size = STOCK, 12X12/10	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3009	SRH612122401	1 Box, Qty 4	5500S-6 12X12/24 S401	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3009	-	-	1-SRH-6 22X22, 1-SRH-1 8X8	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3009	5500S6121224S201	1 Box, Qty 2	5500S-6 12X12/24 S201	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3009	5500S6800606P01	1 Box, Qty 2	5500S-6 06X06 24X24	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3009	SRH1222201	1 Box, Qty 2	SRH-1 22X22 01	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3009	-	1 Box, Qty 3	SRH-1 22X22 01	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3010	-	1 Box	Transition 1 1/2" Deep, 12ea 12X12/10, 3ea 6X6/6, 5ea 18X18/14	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3010	-	1 Box	Transition 1 1/2" Deep, 8ea 9X9/8, 15ea 15X15/12	3/13/2009	1st Floor Bay 1	BP-15A



ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/13/2009	3010	-	1 Box	Transition 1 1/2" Deep, 47ea 9X9/8	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3010	-	1 Box	Transition 1 1/2" Deep, 32ea 12X12/10	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3011	5500S6S41212P01	1 Box	Metaire, 5500S-4 12X12 24x24	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3011	-	1 Box	9X9 S6 S3	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3011	-	1 Box	Metaire, 5500S-6S4, Ductsize = 15 X 15	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3011	5500S6S4D1515P01	4 Box	Metaire, 5500S-4 15X15 24x24	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3011	5500S6S4D1515P01	1 Box	Metaire, 5500S-4 15X15 24x24	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3011	5500S6S31515P01	1 Box	Metaire, 5500S-3 15X15 24x24	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3011	TAG-A	1 Box	TAG-A 2nd Floor S6S4 18X18	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3011	5500-6S4	1 Box	Metaire, Ductsize = 18X3, WHT Steel, "S6S4 18X18" (Handwritten)	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3011	5500-6S4	1 Box	Metaire, Ductsize = 18X18, "No Damper" (Handwritten)	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3011	-	1 Box	Transition pieces, 6 ea 6X6/6, 7ea 15X15/12	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3011	5500S6S41212P01	1 Box, Qty 2	Metaire, 5500S-6 S4 12X12 24X24	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3011	-	1 Box, Qty 2	Metaire, 5500S-6 S4 15X15	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3011	5500S6S4D1515P01	1 Box, Qty 2	Metaire, 5500S-6 S4 15X15 24X24	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3011	5500S6SC0909P01	1 Box, Qty 2	Metaire, 5500S-6 SC 09X09 24X24	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3011	-	1 Box, Qty 1	Metaire, 5500S-6 6S3D5 12X12	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3012	280421-33	3 Boxes, 3X2 pc	5500S-6 06X06/24 SC01	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3012	280041-6	2 Boxes, 2X2 pc	5500S-6 12X12/24 S301	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3012	280421-34	1 Box, 1X2 pc	5500S-6 12X12/24 S401	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3012	280421-37	1 Box, 1X2 pc	5500S-6 SC 12X12 24X24	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3012	280421-20	1 Box, 1X2 pc	5500S-6 12X12/24 S201	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3012	280421-5	1 Box, 1X2 pc	5500S-6 09X09/24 S301	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3012	280421-18	2 Boxes, 1X2 pc, 1X1 pc	5500S-6 09X09/24 SC01	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3012	280421-3	19 Boxes, 19X2 pc	5500S-6 09X09/24 S401	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3013	7-26-301	1 Box, CT 10	7" 26 ga 60" Galv. Pipe	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3013	5-26-301	1 Box, CT 10	5" 26 ga 60" Galv. Pipe	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3013	5500S6060624S201	1 Box, Qty 2	Metaire, 5500S-6 06X06/24 S201	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3013	5500S6090924S301	2 Boxes, Qty 2	Metaire, 5500S-6 09X09/24 S301	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3013	280421 V4004S-1	1 Pkg, Qty 1	10X6 Vent	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3013	5500S6090924S401	2 Boxes, Qty 2	Metaire, 5500S-6 09X09/24 S401	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3013	5500S6121224S201	1 Box, Qty 1	Metaire, 5500S-6 12X12/24 S201	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3013	5500S62222S401	3 Boxes, Qty 4	Metaire, SRH-6 22X22/24 01 SRH-6	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3013	5500S6151524S401	1 Box, Qty 2	Metaire, SRH-6 15X15/24 S401	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3013	5500S6151524S301	1 Box, Qty 1	Metaire, SRH-6 15X15/24 S301	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3013	SRH622222401	3 Boxes, Qty 4	Metaire, SRH-6 22X22/24 01	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3013	SRH616162401	1 Box, Qty 4	Metaire, SRH-6 16X16/24 01	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3013	SRH612122401	1 Box, Qty 2	Metaire, 5500S-6 12X12/24 01	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3013	5500S6121224S401	1 Box, Qty 2	Metaire, 5500S-6 12X12/24 S401	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3014	SRH1121201	1 Box, Qty 3	Metaire, SRH-1 12X12 01	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3014	5500S6151524S401	1 Box	Metaire, SRH-6 15X15/24 S401	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3014	5500S6121224S401	2 Boxes, Qty 2	Metaire, 5500S-6 12X12/24 S401	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3014	SRH622222401	3 Boxes, Qty 4	Metaire, SRH-6 22X22/24 01	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3014	5500S6121224S401	2 Boxes, Qty 2	Metaire, 5500S-6 12X12/24 S401	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3014	5500S6121224S401	1 Box, Qty 16	Metaire, 5500S-6 12X12/24 S401	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3014	248025	1 Box, Qty 13	Grille, SO #248025, Box # PFTB, Size = DFA, 24X24	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3014	5500S6S41212P01	1 Box, Qty 2	Metaire, 5500S-4 12X12 24x24	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3014	5500S6S40606P01	2 Boxes, Qty 2	Metaire, 5500S-6 06X06 24x24	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3014	SRH612122401	2 Boxes, Qty 4	Metaire, SRH-6 12X12/24 01	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3014	SRH622222401	2 Boxes, Qty 4	Metaire, SRH-6 12X12/24 01	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3014	5500S6121224S401	2 Boxes, Qty 2	Metaire, 5500S-6 12X12/24 S401	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3014	SRH608082401	1 Box, Qty 3	Metaire, 1-SRH-6 16X16 E (Handwritten)	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3014	SRH616162401	1 Box, Qty 4	Metaire, SRH-6 16X16/24 01	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3014	SRH622222401	2 Boxes, Qty 4	Metaire, SRH-6 22X22/24 01	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3014	SRH62222402	1 Box, Qty 2	Metaire, SRH-6 22X22/24 01	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3014	5500S6121224S401	3 Boxes, Qty 2	Metaire, 5500S-6 12X12/24 S401	3/13/2009	1st Floor Bay 1	BP-15A



**Buley Library Project
Inventory Sheet**

ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/16/2009	3014	SRH62222401	1 Box, Qty 4	Metalaire, SRH-6 22X22/24 01	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3015	5500S6S30909P01	2 Boxes, Qty 1	Metalaire, 5500S-6 S3 09X09 24X24	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3015	(Not Visible)	1 Box	Metalaire, 2-5653 6X6 (Handwritten)	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3015	N/A	1 Box	Ferguson C SCU Tag B - Ground Flor H1.0A 1. 6X6S6S2 (Handwritten)	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3015	N/A	1 Box, Qty 16	Transition 1 1/2" Deep, Size = STOCK, 12X12/10	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3015	5500S6S40606P01	2 Boxes, Qty 2	Metalaire, 5500S-6 S4 06X06 24X24	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3015	5500S6SC0909P01	2 Boxes, Qty 2	Metalaire, 5500S-6 SC 09X09 24X24	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3015	5500S6S41212P01	1 Box, Qty 2	Metalaire, 5500S-6 S4 12X12 24X24	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3016	6610	1 Box	Model: 6610, Style: 12-6, Length: 48, Slotsz, Inlet Size: 2EB, Finish 2Q, Qty:	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3016	6610	1 Box	Model: 6610, Style: 12-6, Length: 48, Slotsz, Inlet Size: 2EB, Finish 2Q, Qty:	3/13/2009	1st Floor Bay 1	BP-15A
3/13/2009	3016	6610	1 Box	Model: 6610, Style: 12-6, Length: 48, Slots 2, Inlet Size: 2EB, Finish 2Q, Qty:	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3017	5500S6090924S201	3 Boxes, Qty 2	Metalaire, 5500S-6 09X09/24 S201	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3017	5500S6121224S401	3 Boxes, Qty 2	Metalaire, 5500S-6 12X12/24 S401	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3017	5500S6090924S301	2 Boxes, Qty 1	Metalaire, 5500S-6 09X09/24 S301	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3017	5500S6090924SC01	1 Box, Qty 2	Metalaire, 5500S-6 09X09/24 SC01	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3017	5500S6060624SC01	3 Boxes, Qty 2	Metalaire, 5500S-6 06X06/24 SC01	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3017	5500S6090924S401	6 Boxes, Qty 2	Metalaire, 5500S-6 06X06/24 S201	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3017	SRH62222401	4 Boxes, Qty 4	Metalaire, SRH-6 22X22/24 01	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3017	SRH616162401	2 Boxes, Qty 4	Metalaire, SRH-6 16X16/24 01	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3018	SRH1161601	1 Box, Qty 4	Metalaire, SRH-1 16X16 01	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3018	5500S6121224S301	4 Boxes, Qty 2	Metalaire, 5500S-6 12X12/24 S301	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3018	SRH612122401	3 Boxes, Qty 4	Metalaire, 5500S-6 12X12/24 01	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3018	5500S6090924S401	18 Boxes, Qty 2	Metalaire, 5500S-6 09X09/24 S401	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3019	5500S6060624S201	1 Box, Qty 2	Metalaire, 5500S-6 06X06/24 S201	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3019	SRH1161601	1 Box, Qty 5	Metalaire, SRH-1 16X16/1	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3019	SRH1161601	1 Box, Qty 6	Metalaire, SRH-1 16X16/1	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3019	5500S6060624S201	1 Box	Metalaire, 5500S-6 06X06/24 S201	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3019	5500S6090924S201	7 Boxes, Qty 2	Metalaire, 5500S-6 09X09/24 S201	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3019	5500S6090924S301	2 Boxes, Qty 2	Metalaire, 5500S-6 09X09/24 S201	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3019	5500S6121224S401	1 Box, Qty 2	Metalaire, 5500S-6 12X12/24 S401	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3019	5500S6090924S401	6 Boxes, Qty 2	Metalaire, 5500S-6 09X09/24 S201	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3019	SRH62222401	4 Boxes, Qty 4	Metalaire, SRH-6 22X22/24 01	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3019	5500S6090924S301	1 Box, Qty 2	Metalaire, 5500S-6 09X09/24 S301	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3019	SRH616162401	1 Box, Qty 3	Metalaire, SRH-6 16X16/24 01	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3019	(Not Visible)	1 Box	1-STH6 12X12 T:E (Handwritten)	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3020	7002514	15	ATCO Rubber Products	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3020	6610	1 Box	SO# 280421, Item# 30B, Style:2-6 Slots:2, Inlet Size:WEB, Finish: 2Q; 1pc. 96	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3020	6610	1 Box	SO# 280421, Item# 30B, Style:2-6 Slots:2, Inlet Size:WEB, Finish: 2Q; 1pc. 96	3/13/2009	1st Floor Bay 1	BP-15A
3/16/2009	3020	6610	1 Box	SO# 280421, Item# 30B, Style:2-6 Slots:3, Inlet Size:WEB, Finish: 2Q; 2 sets c	3/13/2009	1st Floor Bay 1	BP-15A
3/5/2009	0044	N/A	25	1/4" petes plugs	3/5/2009	Southwest corner - Auditorium	BP-15A
3/5/2009	0049	N/A	15	3" rubber gasket	3/5/2009	Southwest corner - Auditorium	BP-15A
3/5/2009	0049	N/A	1	12" rubber gasket	3/5/2009	Southwest corner - Auditorium	BP-15A
3/5/2009	0050	N/A	6	3" iron elbow	3/5/2009	Southwest corner - Auditorium	BP-15A
3/5/2009	0050	N/A	6	3" iron coupling	3/5/2009	Southwest corner - Auditorium	BP-15A
3/5/2009	0051	N/A	6	3" iron elbow	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0051	N/A	6	3" iron coupling	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0052	N/A	6	3" iron elbow	3/5/2009	Southwest corner - Auditorium	BP-15A
3/5/2009	0052	N/A	6	3" iron coupling	3/5/2009	Southwest corner - Auditorium	BP-15A
3/5/2009	0053	N/A	3	3" iron coupling	3/5/2009	Southwest corner - Auditorium	BP-15A
3/5/2009	0053	N/A	20	1/2" iron end cap	3/5/2009	Southwest corner - Auditorium	BP-15A
3/5/2009	0053	N/A	1	branch butterfly valve	3/5/2009	Southwest corner - Auditorium	BP-15A
3/5/2009	0054	N/A	1	8" aluminum/bronze butterfly valve	3/5/2009	Southwest corner - Auditorium	BP-15A
3/5/2009	0055	N/A	1	8" aluminum/bronze butterfly valve	3/5/2009	Southwest corner - Auditorium	BP-15A
3/5/2009	0056	N/A	125	3/4" Dill electric waterway	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0056	N/A	50	1" Dill electric waterway	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0061		70	1/2" sch40 elbow 90°	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0080	KV009AE2HCB719M	2	Baldor 2 HP pump	3/6/2009	Mechanical Room	BP-15A



ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/5/2009	0081		1	8" flexible flanged connector	3/6/2009	Mechanical Room	BP-15A
3/5/2009	0081		2	Noll Victaulic 6" 45° elbow victaulic 6/168.3	3/6/2009	Mechanical Room	BP-15A
3/5/2009	0081		1	6" x 2" victaulic/threaded reducer No. 52 72T	3/6/2009	Mechanical Room	BP-15A
3/5/2009	0082 - 0083	2974M	2	Milvaco 6" 1255 200WOG IBBM check valve	3/6/2009	Mechanical Room	BP-15A
3/5/2009	0100	5VBM4	12	Weiss 5" Bimetal Thermometer	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0101	5VBM4	12	Weiss 5" Bimetal Thermometer	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0102	5VBM4	12	Weiss 5" Bimetal Thermometer	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0103	5VBM4	12	Weiss 5" Bimetal Thermometer	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0104	5VBM4	12	Weiss 5" Bimetal Thermometer	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0105	5VBM4	12	Weiss 5" Bimetal Thermometer	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0106	5VBM4	12	Weiss 5" Bimetal Thermometer	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0107	5VBM4	12	Weiss 5" Bimetal Thermometer	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0108	5VBM4	12	Weiss 5" Bimetal Thermometer	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0109		50	Water supply labels	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0110	5VBM4	12	Weiss 5" Bimetal Thermometer	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0111	5VBM4	12	Weiss 5" Bimetal Thermometer	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0112	5VBM4	12	Weiss 5" Bimetal Thermometer	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0113	5VBM4	1	Weiss 5" Bimetal Thermometer	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0113	HUG-1	20	Weiss Pressure Gauge 0-300	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0114	HUG-1	24	Weiss Pressure Gauge 0-301	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0128		2	Milwaukee 2-1/2" cast iron butterfly valve (1 incomplete)	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0128		2	Milwaukee 3" cast iron butterfly valve (1 is damaged)	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0128	TC-1	3	Bell & Gossett timer control kits	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0128	NBF-22	3	Bell & Gossett NRF/NBF/SSF circulator	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0128	AQS 3/4	3	Bell & Gossett Aquastat kit	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0128	9VU35160	4	Weiss 3-1/2" temperature stem	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0129		50	misc water signage	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0130		1	series 36 electric actuator	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0131	107559	2	Neptune pressure relief assembly	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0131		50	paint brush 2"	3/6/2009	West Wall - Auditorium	BP-15A
3/5/2009	0131	PSF-RTMTR	1	FlowMate 1-10 GBM .75"	3/6/2009	West Wall - Auditorium	BP-15A
3/5/2009	0131		6	3/4" brass flange	3/6/2009	West Wall - Auditorium	BP-15A
3/5/2009	0131		15	3/4" Brass T	3/6/2009	West Wall - Auditorium	BP-15A
3/5/2009	0131		2	1/2" vacuum relief valve	3/6/2009	West Wall - Auditorium	BP-15A
3/5/2009	0152		2	4" dial pressure gauge (600 PSI)	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0152		1	4" dial pressure gauge 1/4" NPT (200 PSI)	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0152		6	3" Garlock gasket	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0152		9	4" Garlock gasket	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0152		1	2" dial pressure gauge 100 PSI	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0152		4	Victaulic 2 1/2" coupling 73-75	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0152		10	Victaulic 3" x 2 1/2" reducer coupling 73 zero flex	3/5/2009	West Wall - Auditorium	BP-15A
3/5/2009	0153		3	Victaulic 3" x 2 1/2" reducer coupling	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0153		1	Victaulic 2" coupling 60, 3-005H	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0153		22	Victaulic 3" 45° elbow 3/88, 9 #11	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0154		25	Victaulic 2 1/2" 45° elbow	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0155		18	Victaulic 2 1/2" 45° elbow	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0155		1	Victaulic 3" x 2 1/2" reducer #51	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0155		2	Victaulic 2 1/2" x 2" reducer (40/5)	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0156		19	Victaulic 2 1/2" 90° elbows 2 1/2 / 73 #10	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0158 - 0162		1	Victaulic 570 reducer 1 1/2" x 2-51	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0158 - 0162		2	Victaulic 3" 606 Bronze coupling	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0158 - 0162		1	Victaulic 88.9/3" - 75 coupling	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0158 - 0162		20	Victaulic 2 2/3" / 73-75 coupling	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0158 - 0162		30	Victaulic 2 1/2" -73 zero flex coupling	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0158 - 0162		2	Victaulic 2 1/2" x 2 1/2" x 2 Tees No. 25	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0158 - 0162		2	Victaulic 73mm / 2 1/2" Tees No. 20	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0158 - 0162		1	Victaulic 3 x 3 x 2 Tee No. 25	3/5/2009	East Wall - Auditorium	BP-15A



**Buley Library Project
Inventory Sheet**

ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/5/2009	0158 - 0162		38	Victaulic 3" 88.9 90° elbows	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0158 - 0162		6	Victaulic 4" 114.3 90° elbows No. 10	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0158 - 0162		1	Victaulic 12" cap #8 2/9, No. 60	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0158 - 0162		22	Victaulic 4" 114.3 coupling zero flex	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0158 - 0162		2	Victaulic 6" 168.3 x 3 88.9 No. 50 reducer	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0158 - 0162		1	Victaulic 6 x 4 188, 3 x 114, 3 reducer no. 50	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0158 - 0162		3	Victaulic 45° elbow 4" 114.3 No. 11	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0158 - 0162		9	Victaulic 6" caps 168, 3 No. 60	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0158 - 0162		5	Victaulic 6" caps 168, 3 No. 60	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0158 - 0162		1	Victaulic 8" 63.3 6" central sprink	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0158 - 0162		3	Victaulic 8" 75 coupling	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0158 - 0162		8	Victaulic 8" x 8" x 6" Tees	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0158 - 0162	741	4	Victaulic 8" metal gaskets 8"	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0158 - 0162	741	6	Victaulic 3" metal gaskets	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0158 - 0162	741	3	Victaulic 2.5" metal gaskets	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0158 - 0162		19	Victaulic 6" metal gaskets	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0158 - 0162		17	4" 90° threaded elbow cast iron	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0158 - 0162		4	2 1/2" 90° threaded elbow cast iron	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0158 - 0162		2	6" Victaulic 90°elbow	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0158 - 0162		2	8" flange victaulic 5/741	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0158 - 0162		14	2-1/2" flange victaulic 2-1/2/741	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0158 - 0162		13	6" flange victaulic 6-741	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0158 - 0162		19	4" flange victaulic 4-741	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0158 - 0162		23	3" flange victaulic 3-741	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0158 - 0162		1	2-1/2" coupling victaulic 2 1/2-743 zero flex	3/5/2009	East Wall - Auditorium	BP-15A
3/5/2009	0163		28	Bx 162 V-belt torque flex 107'	3/6/2009	West Wall - Auditorium	BP-15A
3/5/2009	0164		1	Carlisle Super Vee-bannd RBP 120	3/6/2009	West Wall - Auditorium	BP-15A
3/5/2009	0165		2	Tubber gasket 8"	3/6/2009	West Wall - Auditorium	BP-15A
3/5/2009	0165		1	Victaulic adaptor galvanized 1" IPS x 2" CTS	3/6/2009	West Wall - Auditorium	BP-15A
3/5/2009	0165		1	cast iron cap 4"	3/6/2009	West Wall - Auditorium	BP-15A
3/5/2009	0165		1	threaded nipple galvanized steel 2"	3/6/2009	West Wall - Auditorium	BP-15A
3/5/2009	0165		40	Perfection Clear Flow 1/2" nipple threaded galvanized	3/6/2009	West Wall - Auditorium	BP-15A
3/5/2009	0165		3	Victaulic caps 8"/219, 1 no. 60	3/6/2009	West Wall - Auditorium	BP-15A
3/5/2009	0165		4	rolls 1" gasket material	3/6/2009	West Wall - Auditorium	BP-15A
3/5/2009	0180 - 0182		5	kits cased faced ladder and handrail fastener kit	3/6/2009	West Wall - Auditorium	BP-15A
3/5/2009	0180 - 0182		50	pounds misc galvanized nuts and bolts	3/6/2009	West Wall - Auditorium	BP-15A
3/5/2009	0180 - 0182		2	12" L 1/4" thick rubber gasket	3/6/2009	West Wall - Auditorium	BP-15A
3/5/2009	0180 - 0182		2	8" L 1/4" thick rubber gasket	3/6/2009	West Wall - Auditorium	BP-15A
3/5/2009	0180-0182		7	3" threaded victaulic	3/6/2009	West Wall - Auditorium	BP-15A
3/5/2009	0180-0182		1	victaulic 2-1/2" x 18" grooved nipple	3/6/2009	West Wall - Auditorium	BP-15A
3/5/2009	0180-0182		15	10" grooved nipple w/2 threadolet cast iron	3/6/2009	West Wall - Auditorium	BP-15A
3/9/2009	0200 - 0255	WCT310-IN2-C	1	Walchem cooling tower controller	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	0200 - 0255	WFM071-0G100	1	Walchem flowmeter .75"	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	0200 - 0255		25	IPEX 1/2" and 3/4" PVC elbows and fittings	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	0200 - 0255	1342BA08T	1	Jefferson Solenoid valve 1" NPT	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	0200 - 0255		1	Marely Cooling Tower liquid level control	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0256 - 0275	41HG0200	1	box Nefco 2" galvanized hinge type split ring - 50 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0256 - 0275	41HG0150	3	boxes Nefco 1-1/2" galvanized hinge type split ring - 50 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0256 - 0275	41HG0150	75	Nefco 1-1/2" galvanized hinge type split ring	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0256 - 0275	41HG0125	2	boxes Nefco 1-1/4" galvanized hinge type split ring - 50 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0256 - 0275	41HG0300	9	boxes Nefco 3" galvanized hinge type split ring - 25 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0256 - 0275	41HG0200	25	Nefco 2" galvanized hinge type split ring	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0256 - 0275	41HG0400	3	boxes Nefco 4" galvanized hinge type split ring - 25 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0256 - 0275	41HG0400	75	Nefco 4" galvanized hinge type split ring	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0256 - 0275	41HG0500	75	Nefco 5" galvanized hinge type split ring	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0256 - 0275	41HG0075	130	Nefco 3/4" Galvanized hinge type split ring	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0256 - 0275	41HG0050	1	box Nefco 1/2" galvanized hinge type split ring - 100 ct each	3/12/2009	Basement Bay 8	BP-15A



**Buley Library Project
Inventory Sheet**

ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/10/2009	0256 - 0275		16	2" galvanized riser clamps	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0256 - 0275		3	2-1/2" riser clamps	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0256 - 0275	Y105030	15	Tolco 3" galvanized riser clamps	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0256 - 0275	50G0400	32	Nefco 4" riser clamps	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0256 - 0275	50G0600	22	Nefco 6" galvanized riser clamps	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0256 - 0275	50G0800	9	Nefco 8" galvanized riser clamps	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0256 - 0275		2	10" galvanized riser clamps	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0256 - 0275		12	12" riser clamps	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0256 - 0275		35	1-1/4" riser clamps	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0256 - 0275	24039	3	United Abrasives Sait EZ-Chop Chopsaw disk - 1" Type 1-BF	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0256 - 0275		15	1-1/2" dampening support assembly w/spring	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0256 - 0275		3	2" dampening support assembly w/spring	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0256 - 0275	117413	4	Bell & Gossett 3/4" sweat circuit setter	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0256 - 0275	117401	1	Bell & Gossett 1" circuit setter	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0256 - 0275	117402	1	Bell & Gossett 1-1/4" circuit setter	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0256 - 0275	117404	2	Bell & Gossett 2" circuit setter	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0256 - 0275	117116	1	Bell & Gossett 2-1/2" circuit setter	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0256 - 0275	117117	2	Bell & Gossett 3" circuit setter	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0256 - 0275	TL35-015-42	3	Weiss 1/4" NPT LM pressure gauge	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0256 - 0275	5550-111-01	1	Metrix Vibration switch	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0256 - 0275		25	1" hex bolts	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0276 - 0299	CL223E	2	Milwaukee Valve 2-1/2" Iron butterfly Valves	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0276 - 0299	8687	2	Lever Handle Kit size 940	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0276 - 0299	ML224E	1	Milwaukee Valve 3" Iron Butterfly valve	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0276 - 0299		1	roll 1/2" metal strap	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0276 - 0299	307A	10	3-1/2" hex screws w/nuts and washers	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0276 - 0299	0026-3026-401	25	PFC 2-1/2" hex screws	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0276 - 0299	0334902145	8	Anvil blk stl CW nipple - assorted sizes	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0276 - 0299	VXBV204	2	Ipex 3/4" VX True Union Vall valve	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0276 - 0299	VXBV203	4	Ipex 1/2" VX True Union Vall valve	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0276 - 0299	BA150	1	Milwaukee Valve 3/4" ball valve	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0276 - 0299	10Z013	1	Asco Red Hat 3/4" solenoid valve	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0276 - 0299	W520-09	5	boxes CA arm assembly	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	0276 - 0299	C600C	1	box Mission metallic non-hub - 20 ct each	3/12/2009	Basement Bay 8	BP-15A
3/6/2009	0300 - 0302	165	1	Horizontal Unit Heater	3/6/2009	West Wall - Auditorium	BP-15A
3/6/2009	0305		7	black steel 1" CW nipple	3/6/2009	East Wall - Auditorium	BP-15A
3/6/2009	0305	117402	4	circuit setter P/S 1-1/4" ODS	3/6/2009	East Wall - Auditorium	BP-15A
3/6/2009	0305	117413	7	circuit setter 3/4" sweat	3/6/2009	East Wall - Auditorium	BP-15A
3/6/2009	0305	117401	13	circuit setter P/S 1" DS	3/6/2009	East Wall - Auditorium	BP-15A
3/6/2009	0305	WD100	2	aluminum frame 18" x 18"	3/6/2009	East Wall - Auditorium	BP-15A
3/6/2009	0305	NPTDA5C14	1	Cash Co. Inc. pump	3/6/2009	East Wall - Auditorium	BP-15A
3/6/2009	0306		5	misc duct work small pieces	3/6/2009	East Wall - Auditorium	BP-15A
3/6/2009	0306	TG-EL-WF-IZ	1	Preferred Instruments drag controller	3/6/2009	East Wall - Auditorium	BP-15A
3/6/2009	0306	DB-10	1	positive pressure switch	3/6/2009	East Wall - Auditorium	BP-15A
3/6/2009	0307	18/24	1	Horizontal Unit Heater	3/6/2009	West Wall - Auditorium	BP-15A
3/6/2009	0308 - 0312		1500	angle bracket steel 3"	3/6/2009	Basement Bay 2	BP-15A
3/6/2009	0308 - 0312	AH23A020	1	pop top actuator Erie	3/6/2009	Basement Bay 2	BP-15A
3/6/2009	0308 - 0312		1000	loop fasteners 1" steel	3/6/2009	Basement Bay 2	BP-15A
3/6/2009	0308 - 0312	DBBGA or PC3B	50	Ductmate corner duct pieces	3/6/2009	Basement Bay 2	BP-15A
3/6/2009	0308 - 0312	DC35	200	Ductmate corner duct pieces	3/6/2009	Basement Bay 2	BP-15A
3/6/2009	0308 - 0312	5454	3000	Protwist 1" screws	3/6/2009	Basement Bay 2	BP-15A
3/6/2009	0308 - 0312		1000	misc. fasteners	3/6/2009	Basement Bay 2	BP-15A
3/6/2009	0308 - 0312	62G0038	400	3/8" junior top beam clamp	3/6/2009	Basement Bay 2	BP-15A
3/6/2009	0308 - 0312	21LG10038	300	3/8" C clapr w/lock nut	3/6/2009	Basement Bay 2	BP-15A
3/6/2009	0308 - 0312		8	mechanical dampening supports - 10"	3/6/2009	Basement Bay 2	BP-15A
3/6/2009	0313		8	duct access panel 2' x 3'	3/6/2009	Basement Bay 2	BP-15A
3/6/2009	0313		5	duct access panel 1.5' x 2'	3/6/2009	Basement Bay 2	BP-15A



**Buley Library Project
Inventory Sheet**

ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/6/2009	0314	440	12	Elgen Butyl Gasket - 500 ft each	3/6/2009	Basement Bay 2	BP-15A
3/6/2009	0315	440	13	Elgen Butyl Gasket - 500 ft each	3/6/2009	Basement Bay 2	BP-15A
3/6/2009	0316		1	air condenser control unit	3/6/2009	Basement Bay 2	BP-15A
3/6/2009	0316		3500	hex washer head 10 x 3/1"	3/6/2009	Basement Bay 2	BP-15A
3/6/2009	0316	HH51BX005	11	Carrier heater small plastic covers	3/6/2009	Basement Bay 2	BP-15A
3/6/2009	0316	P902H	1	Powers pressure balancing valves - biltmore series 900	3/6/2009	Basement Bay 2	BP-15A
3/6/2009	0316		10	2" screw clamps	3/6/2009	Basement Bay 2	BP-15A
3/6/2009	0316		15	1/2" copper clamps	3/6/2009	Basement Bay 2	BP-15A
3/6/2009	0316		50	hex coupling 1-1/2" economy nuts 3/8x16x1/2X coarse thread	3/6/2009	Basement Bay 2	BP-15A
3/9/2009	0457 - 0460	4714-B	3	boxes Elkhart Baseboard Tee 3/4 x 1/8 3/4 - 25 ct each	3/10/2009	Basement Bay 7	BP-15A
3/9/2009	0457 - 0460		1	Weiss 3 psi Pressure gauge 1/2" MPT	3/10/2009	Basement Bay 7	BP-15A
3/5/2009	132		25	cast fittings misc. 2"	3/6/2009	West Wall - Auditorium	BP-15A
3/10/2009	2000 - 2002		1	steel square tray 3' x 3' x 1-1/2"	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2000 - 2002		30	assorted valves - Milwaukee Valve, 1/2" - 1-1/4" diam	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2000 - 2002		20	Assorted bolts and riser clamps	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2000 - 2002		29	threaded steel poles 10' x 5/8"	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2000 - 2002		3	threaded steel connectors 2" x 2"	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2000 - 2002		20	assorted bolts, elbos, nuts, brackets, small hangers	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2000 - 2002		7	4" clevis hangers	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2000 - 2002		1	2" clevis hanger	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2000 - 2002		150	assorted brackets, drop-ins, cable shields, all less than 2"	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2000 - 2002		2	spools 1/8" cable, 40 foot length each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2000 - 2002		10	2" steel elbow 90°	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2000 - 2002		1	3" steel elbow 45°	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2000 - 2002		1	box steel drop-ins 1/2" - 20 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2000 - 2002		4	steel circular flanges, 8" dia., 3/4" thick	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2000 - 2002		4	4" 90° steel pipe elbows	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2000 - 2002		1	4" 45° steel pipe elbow	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2000 - 2002		1	4" T steel pipe 8" x 6" x 4"	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2000 - 2002		100	assorted washers, bolts, drop-ins, all less than 3"	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2000 - 2002		10	rubber cog belts	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2000 - 2002		1	1-1/2" PVC P-Trap	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2000 - 2002		14	2" Dual Tite Neoprene pipe gaskets	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2000 - 2002		40	threaded steel poles 1' x 5/8"	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2000 - 2002		40	threaded steel poles 1' x 1/2"	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2000 - 2002		1	victaulic fitting 3" 90° elbow	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2000 - 2002		1	victaulic coupling 3"	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2000 - 2002		25	assorted plate steel pipe shields	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2000 - 2002		1	flange PCF 6" x 11"	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2003 - 2019	4010500EG	13	boxes Caddy 5" Clevis hanger - 25 ct each	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2003 - 2019	4010500EG	22	Caddy 5" Clevis hanger	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2003 - 2019	310G10075	90	Nefco Ferguson 3/4" EMLOK hanger	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2003 - 2019		1	box 4" riser clamps - 8 ct each	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2003 - 2019	310G10100	1	box Nefco Ferguson 1" EMLOCK hanger - 100 ct each	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2003 - 2019	310G10200	1	box Nefco Ferguson 2" EMLOCK hanger - 80 ct each	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2003 - 2019	50CT0300	1	box 3" riser clamp - 20 ct each	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2003 - 2019	50CT0200	1	box 2" copper riser clamps - 50 ct each	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2003 - 2019		1	box 1-1/2" copper riser clamps - 45 ct each	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2003 - 2019		1	box 1" copper riser clamps - 55 ct each	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2003 - 2019		1	box 3/4" copper riser clamps - 24 ct each	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2003 - 2019	060801	1	box 1/2" bell hangers - 24 ct each	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2003 - 2019	50CT0050	44	Nefco 1/2" riser clamps	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2003 - 2019		1	box 3/4" riser clamps - 20 ct each	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2003 - 2019		1	box 1/2" copper riser clamps - 25 ct each	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2003 - 2019		1	Brass Craft multi turn stop	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2003 - 2019		2	boxes alignment brackets - 45 ct each	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2003 - 2019	N36-M1	6	boxes Watts 3/4" vacuum relief valve - 6 ct each	3/12/2009	Basement Bay 8	BP-15A



**Buley Library Project
Inventory Sheet**

ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/9/2009	2003 - 2019	909AGF	1	Watts Air Gap	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2003 - 2019	909AGC	1	Watts air gap kit	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2003 - 2019	SS-112	1	Matco-Norca stainless steel strainer	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2003 - 2019	CLT150F-X20	3	rolls corrugated tubing - 10 ft each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2003 - 2019	05526	1	box Powers mush head spike 1/4 x 2" - 100 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2003 - 2019	05526	80	Powers mush head spike 1/4 x 2"	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2003 - 2019		2	boxes drive pins - 50 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2003 - 2019		4	10.5 fl oz. tubes duct sealant	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2003 - 2019		1	box junior top beam clamp - 30 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2003 - 2019		2	boxes 7/8" bam clamps - 15 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2003 - 2019		1	box 4/4" beam clamps - 20 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2003 - 2019		2	boxes 5/8" jr. top beam clamps - 25 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2003 - 2019		3	boxes 5/8" small mouth beam clamps - 50 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2003 - 2019		46	5/8" small mouth beam clamps	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2003 - 2019		3	boxes size 300 1/4 beam clamp - 100 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2003 - 2019		80	size 300 1/4 beam clamp	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2003 - 2019		2	boxes 5/8" junior top beam clamp - 50 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2003 - 2019		4	boxes 1/2" junior top beam clamp - 100 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2003 - 2019		48	1/2" junior beam clamps	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2003 - 2019		7	boxes 3/8" beam clamps - 100 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2003 - 2019		50	3/8" beam clamps	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2003 - 2019	06306	3	boxes Powers 3/8" steel drop in internal plug - 50 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2003 - 2019	06304	6	boxes Powers 1/4" steel drop in internal plug - 100 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2003 - 2019	06312	5	boxes Powers drop in plugs - 10 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2003 - 2019	06312	4	Powers drop in plugs	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2003 - 2019	02814	1	box Powers zamac nailing - 100 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2003 - 2019	02814	50	Powers Zamac nailing	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2003 - 2019	06132	1	box Powers steel drop in internal plug - 50 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2003 - 2019	06320	4	boxes Powers steel drop in internal plug - 25 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2003 - 2019	06308	2	boxes Powers steel drop in internal plug - 50 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2003 - 2019	06308	4	Powers steel drop in internal plug	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2003 - 2019	RL-58	16	boxes Redhead drop-in - 25 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2003 - 2019	06320	2	boxes Powers steel drop in - 125 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2003 - 2019	06320	100	internal plug	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2003 - 2019		1	box Hilti 3/8" drop in - 15 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2003 - 2019		800	3/8" steel nuts	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2020 - 2050	4010600 EG	20	boxes Caddy EG Clevis 6" hanger #401 - 10 ct each	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2020 - 2050	13602	11	metallic non-hub clam 8"	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2020 - 2050		14	6" hangers (sim to clevis, but with rubber grip)	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2020 - 2050	07542	2	boxes Powers 3/8" green bang it concrete inserts - 100 ct each	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2020 - 2050	07542	26	Powers 3/8" green bang it concrete inserts	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2020 - 2050	PSRS-3/8	100	Nefco 3/8"-16 spring nut	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2020 - 2050	PSRS-1/4-EG	100	Nefco 1/4"-20 spring nut	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2020 - 2050	A-100-5/8	80	Nefco 5/8"-11 spring nut	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2020 - 2050		80	Copper clamps 1-1/4" (see drawing)	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2020 - 2050	PSRS-1/2-EG	1	box Nefco 1/2"-13 spring nut - 100 ct each	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2020 - 2050	231G0075	80	two hole pipe strap galvanized 3/4"	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2020 - 2050	310CT0050	90	Emlock hanger 1/2" CT 3/8" rod	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2020 - 2050		120	1/2" zinc x 1" threaded bushing? (see drawing)	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2020 - 2050	41HCT0150	40	1-1/2" copper hinge type CT split ring	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2020 - 2050		9	angle bracket (see drawing)	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2020 - 2050	41HCT0200	15	2" copper hinge type CT split ring	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2020 - 2050	FP403	8	C 1" glaze plate	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2020 - 2050		5	galvanized plate with 4 holes 0 6" x 1-1/2" x 1/4" (see drawing)	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2020 - 2050		10	angle bracket (see drawing)	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2020 - 2050		50	1/2" copper hinge type CT split ring	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2020 - 2050		40	galvanized concrete screws hex head 1/4" x 3"	3/12/2009	Basement Bay 8	BP-15A



**Buley Library Project
Inventory Sheet**

ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/9/2009	2020 - 2050		60	square head 3/4" plugs	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2020 - 2050	ICBO ER-18B1	16	Wej-it wedge anchors 1/2 x 4/1/4	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2020 - 2050	CA-606PLT	23	angle bracket (see drawing)	3/12/2009	Basement Bay 8	BP-15A
3/9/2009	2020 - 2050		100	concrete screws hex head 3/8" x 1"	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2020 - 2050	33935	60	Oatey 1/2" PVC	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2020 - 2050		18	3/8" x 1-1/2" hex bolts galvanized	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2020 - 2050	ALA08040	40	1/2-13 x 1-1/4 x 5/8 AF hex rd coup/nut z/p	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2020 - 2050		18	hex rd coup/nut z/p 3/4"	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2020 - 2050		35	Hangermate self-tapping anchor 3/8"-16 rod	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2020 - 2050		30	Hangermate threaded rod anchor end drilled 2-1/4" shank length	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2020 - 2050		40	5/8" rod couplings	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2020 - 2050		8	hex bolts 5/8-11 2-3/4	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2020 - 2050		8	Independent pipie hex bolt w/heavy hex nuts 5/8-11 2-3/4	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2020 - 2050		100	hex bolt 5/8" x 2"	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2020 - 2050		8	3/4" rod coupling	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2020 - 2050		2	boxes hex coupling economy nuts coarse thread 3/8-16 x 1/2" x 1-1/8" - 50 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2020 - 2050		25	hex coupling economy nuts coarse thread 3/8-16 x 1/2" x 1-1/8"	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2020 - 2050		1	box coarse thread hex screws 3/4"-10 x 3-1/2" - 20 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2020 - 2050		40	3/4" x 7/8" rod couplings	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2020 - 2050		2000	assorted flat metal washers - 1/4" - 1" (example PFC 3/4" flat washer 00370-3200-421)	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2020 - 2050		1500	assorted bolts 1" - 4" length, 3/8" - 5/8" (example Global 3/8"-16x3" FFF06096)	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2020 - 2050		800	assorted misc. machine screws (example Nefco combo 5/8" rd BZL04080 mach sc zp 1/4-20x2-1/2)	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2020 - 2050		1100	assorted steel hex nuts 1/2"	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2020 - 2050		100	assorted steel hex nuts 3/8"	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2020 - 2050		500	PFC 5/8"-11 finished hex nut	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2020 - 2050		150	PFC 3/4" finished hex nut	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2020 - 2050	09340	2	boxes Powers 3/4" H/S drop-in - 50 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2020 - 2050	09350	1	box Powers 1/2" H/S drop-in - 50 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2020 - 2050	09220	1	box Powers 1/4" calk-in - 100 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2020 - 2050	04231	3	boxes Powers toggle bolts 1/4 x 3 - 50 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2020 - 2050	02814	1	box Powers mush head 1/4 x 1-1/4 - 100 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2020 - 2050	00370-3200-421	18	boxes PFC 7/8" flat washer - 25 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2020 - 2050		1000	flat washers 1/2"	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2020 - 2050		750	flat washers 3/4"	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2020 - 2050		120	galvanized hex nut 7/8"	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2020 - 2050		2000	flat washers 1/2" (bucket)	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2051 - 2087	H010600EG	23	boxes Caddy EG clevis hanger 6" - 10 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2051 - 2087	H010600EG	13	Caddy EG clevis hanger 6"	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2051 - 2087		1	copper tube - 1" x 3/8"	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2051 - 2087	5336030	1	box Cantex spacers 5x3" - 30 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2051 - 2087	5336024	2	boxes Cantex spacers 4x3" - 50 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2051 - 2087		6	3' hose stubs	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2051 - 2087		1	5.5' PBGS075ENCL14GADG	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2051 - 2087		1	7' PBGS075ENCL14GADG	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2051 - 2087		4	pounds duct seal	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2051 - 2087		1	box ear plugs - 20 pair	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2051 - 2087		1	box 45° elbow copper 1-1/2" - 18 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2051 - 2087		300	pipe sleepers 1' x 4" x 2" 1/8" steel sheet	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2051 - 2087		150	pipe sleepers 1' x 6" x 2" 1/8" steel sheet	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2051 - 2087		1	4" 90° steel elbow	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2051 - 2087		20	1-5/8" tube clamp	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2051 - 2087		1	gallon high temp cement	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2051 - 2087		5	boxes beam clamp 300-1/2 - 100 ct each	3/12/2009	Basement Bay 8	BP-15A



**Buley Library Project
Inventory Sheet**

ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/10/2009	2051 - 2087		90	beam clamp 300-1/2	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2088 - 2096		800	sheet metal pipe shields 1' x 4"	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2088 - 2096		1	1/2" copper pipe 4' long	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2088 - 2096		1	box non-hub metallic coupling size 142 - 10 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2088 - 2096		15	sheet metal pipe shields 2' x 6"	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2088 - 2096		20	sheet metal pipe shields 10" x 2"	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2088 - 2096		30	sheet metal pipe shields 10" x 2"	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2088 - 2096		10	1" copper 45° elbows	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2088 - 2096		1	steel pipe 2", 1-1/2' long	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2088 - 2096		5	sheet metal pipe shield 1-1/2' x 2'	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2088 - 2096		6	45° steel elbow 1-1/2"	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2088 - 2096		5	90° steel elbow 1-1/2"	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2088 - 2096	MX1140	2	Osco solenoid valve	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2088 - 2096		140	sheet metal pipe shields 4" x 1'	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2088 - 2096	F2885M	5	Milvaco 2-1/2 gate valve iron 200 WOG 8" x 8" x 1-1/2"	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2088 - 2096	F2885M	2	Milvaco 4 gate valve iron 230 WOG, 10" x 10" x 2'	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2088 - 2096	CL223E	1	Milwaukee Valve Iron butterfly Valve 3/200	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2088 - 2096		1	box steel pipe rins 2" connectors - 5 ct each	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2088 - 2096		1	4" vent cap	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2088 - 2096		1	4" end cap	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2088 - 2096		1	cast iron circular clamps 10"	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2088 - 2096	W370NHR	3	Wade connectors	3/12/2009	Basement Bay 8	BP-15A
3/10/2009	2088 - 2096	W1310FC	1	Wade connectors	3/12/2009	Basement Bay 8	BP-15A
3/12/2009	3001-3005	-	208	Pittsburg Soft Lite Insulated Air Diffuser 9" Vent	3/13/2009	1st Floor Bay 1	BP-15A
3/6/2009	no tag - lg box		5	25' Fabri-flex type 2 insulated (6" wide)	3/6/2009	Basement Bay 8	BP-15A
3/6/2009	no tag - lg box		4	25' Fabri-flex type 2 insulated (8" wide)	3/6/2009	Basement Bay 8	BP-15A
3/6/2009	no tag - lg box		2	25' Fabri-flex type 2 insulated (10" wide)	3/6/2009	Basement Bay 8	BP-15A
3/6/2009	no tag - lg box		5	25' Fabri-flex type 2 insulated (12" wide)	3/6/2009	Basement Bay 8	BP-15A
3/6/2009	no tag - lg box		4	boxes Rf200 04 LH HW-2 166A out aln f-ner 3 spd DG	3/6/2009	Basement Bay 8	BP-15A
3/6/2009	no tag - lg box	18/24	1	RH 18 Horizontal unit heater 115V60/ITE	3/6/2009	Basement Bay 8	BP-15A
3/6/2009	no tag - lg box	259578	1	Hilti FS-one - 5 gallon each	3/6/2009	Basement Bay 8	BP-15A
3/6/2009	no tag - lg box		1	25' Fabri-flex type 2 insulated (9" wide)	3/6/2009	Basement Bay 8	BP-15A
3/6/2009	no tag - lg box		2	4' x 4' roof air duct vent	3/6/2009	Basement Bay 8	BP-15A
3/6/2009	no tag - lg box		1.5	boxes sticky tape - 3/a6" x 5/8" x 25'	3/6/2009	Basement Bay 8	BP-15A
3/6/2009	no tag - lg box		10	boxes Elgen #440 butyl gasket 25' roll - 500 ft each	3/6/2009	Basement Bay 8	BP-15A
3/6/2009	no tag - lg box		3000	duct hangers 6'	3/6/2009	Basement Bay 8	BP-15A
3/6/2009	no tag - lg box		40	8" misc duct fittings	3/6/2009	Basement Bay 8	BP-15A
3/6/2009	no tag - lg box		3	boxes gasket tape 5/16" x 3/4"x 50' - 750 ft each	3/6/2009	Basement Bay 8	BP-15A
3/6/2009	no tag - lg box		4	fire proof insulation 25" x 46", 4" thick	3/6/2009	Basement Bay 8	BP-15A
3/6/2009	no tag - lg box		1	finned copper pip for ai duct - 4'	3/6/2009	Basement Bay 8	BP-15A
3/13/2009		N/A	6	Each, 8" dia, 20' long, steel pipe	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15A
3/11/2009		PRED108P26	1	10" to 8" reducer HVAC duct reducer 26 gauge	Existing	Basement Bay 3 and 4	BP-15A
3/11/2009			1	8" 26 gauge 90°elbow	Existing	Basement Bay 3 and 4	BP-15A
3/5/2009			1	Lochinvar 50 gal hot water heater	3/5/2009	East wall auditorium	BP-15A
3/5/2009		NXFB-250	8	Nexus 2" butterfly valve	3/5/2009	East wall auditorium	BP-15A
3/5/2009		JPL-0028	1	Lakos Separator & Filtration System	3/5/2009	East wall auditorium	BP-15A
3/5/2009		CB-6F	1	Bell & Gasset Circuit Setter	3/5/2009	East wall auditorium	BP-15A
3/5/2009			2	8' - .25" copper pipe	3/5/2009	S wall under stage in auditorium	BP-15A
3/5/2009			1	3' - .5" copper pipe	3/5/2009	S wall under stage in auditorium	BP-15A
3/5/2009			2	6' - .5" copper pipe	3/5/2009	S wall under stage in auditorium	BP-15A
3/5/2009			1	10' - .75" copper pipe	3/5/2009	S wall under stage in auditorium	BP-15A
3/5/2009			68'	1" copper pipe	3/5/2009	S wall under stage in auditorium	BP-15A
3/5/2009			1	10' - 1.5" copper pipe	3/5/2009	S wall under stage in auditorium	BP-15A
3/5/2009			52'	2" copper pipe	3/5/2009	S wall under stage in auditorium	BP-15A
3/5/2009			4	20' - .5" steel pipe	3/5/2009	S wall under stage in auditorium	BP-15A
3/5/2009			106	20' - 2" copper pipe	3/5/2009	S wall under stage in auditorium	BP-15A
3/5/2009			132	20' - 1.5" copper pipe	3/5/2009	S wall under stage in auditorium	BP-15A



ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/5/2009			17	20' - 1.25 copper pipe	3/5/2009	S wall under stage in auditorium	BP-15A
3/5/2009			12	20' - 1" copper pipe	3/5/2009	S wall under stage in auditorium	BP-15A
3/5/2009			42	20' - .75" copper pipe	3/5/2009	S wall under stage in auditorium	BP-15A
3/5/2009			6	20' - .5" copper pipe	3/5/2009	S wall under stage in auditorium	BP-15A
3/5/2009			192	5'- 10' - (.25"-.75") all thread	3/5/2009	S wall under stage in auditorium	BP-15A
3/9/2009	ST-5R		3	Each, Vibro Acoustics Noise Control Vents, 5" by 8" opening, 3' length	Existing	Basement East Wall	BP-15A
3/9/2009	5600		2	Each, Prefco fire Dampers, 15.5" height, 13-3/4" width, 16" length	Existing	Basement East Wall	BP-15A
3/9/2009	N/A		9	Each, 16" x 28" HVAC Damper with 17.5" round vent connection	Existing	Basement East Wall	BP-15A
3/9/2009	N/A		1	Each, 16.5" square transfer duct, 3' in length	Existing	Basement East Wall	BP-15A
3/9/2009	N/A		1	Each, 14" round duct elbow, 3' length	Existing	Basement East Wall	BP-15A
3/9/2009	507506, 507517, 507516		3	Each, 3' width, 10" height, 16" length fire dampers	Existing	Basement East Wall	BP-15A
3/9/2009	N/A		3	Each, 36" x 8" vent opening for AHU return	Existing	Basement East Wall	BP-15A
3/9/2009	N/A		5	Each, 6' duct joints and clips	Existing	Basement East Wall	BP-15A
3/9/2009	N/A		5	Each, 11" x 39" (in closed position) adjustable rectangular clips/connections for HVAC ducts	Existing	Basement East Wall	BP-15A
3/9/2009	N/A		1	Each, 8" round duct 46" length	Existing	Basement East Wall	BP-15A
3/9/2009	0085086, 00805059, 0085075, 0085060, 0085009, 0085053		6	Each, 8" 90 degree elbow, 24" length	Existing	Basement East Wall	BP-15A
3/9/2009	0025824		1	Each, 6" 90 degree elbow, 17" length	Existing	Basement East Wall	BP-15A
3/9/2009	Various		10	Each, 10" round duct collar	Existing	Basement East Wall	BP-15A
3/9/2009	Various		10	Each, 8" round duct collar	Existing	Basement East Wall	BP-15A
3/9/2009	N/A		3	Each, 8.5" x 11.25" opening, 39" length transfer ducts	Existing	Basement East Wall	BP-15A
3/9/2009	N/A		1	Pallet, Misc. HVAC collars, fittings, elbows	Existing	Basement East Wall	BP-15A
3/9/2009	N/A		5	Each, 17.5" round collar	Existing	Basement East Wall	BP-15A
3/9/2009	N/A		2	Each, 24" round collar	Existing	Basement East Wall	BP-15A
3/9/2009	N/A		6	Each, 8" round spiral collar duct, 10' section	Existing	Basement North Wall	BP-15A
3/9/2009	N/A		1	Each, 8" round spiral collar duct, 6' section	Existing	Basement North Wall	BP-15A
3/9/2009	N/A		2	Each, 24" round spiral collar duct, 10' section	Existing	Basement North Wall	BP-15A
3/9/2009	N/A		1	Each, 9" round spiral collar duct, 10' section	Existing	Basement North Wall	BP-15A
3/9/2009	N/A		6	Each, 1" galvanized pipes, 10' section	Existing	Basement North Wall	BP-15A
3/9/2009	N/A		4	Each, 2" galvanized pipes, 8' section	Existing	Basement North Wall	BP-15A
3/9/2009	N/A		12	Each, Misc. galvanized pipes 3' to 10' sections	Existing	Basement North Wall	BP-15A
3/9/2009	N/A		1	Each, 3", 90" pipe, 9' section	Existing	Basement North Wall	BP-15A
3/9/2009	N/A		1	Each, 2", 90" pipe, 9' section	Existing	Basement North Wall	BP-15A
3/9/2009	SSII		3	Boxes, Owens Corning Fiberglass pipe insulation	Existing	Basement Northeast Corner	BP-15A
3/9/2009	7-90		1	Box, Insulated PVC joint fitting covers by Manville	Existing	Basement Northeast Corner	BP-15A
3/10/2009			6	7" dia. x 8" H Cl pipes	Existing	Basement Bay 9	BP-15A
3/10/2009			60	2-1/2 x 73 - U No. 10 - Victaulic	Existing	Basement Bay 9	BP-15A
3/10/2009			84	2-1/2 x 73 flex zero pipe clamps	Existing	Basement Bay 9	BP-15A
3/10/2009			4	8 x 5 victaulic no. 50	Existing	Basement Bay 9	BP-15A
3/10/2009			10	6/168.3 victaulic no. 10	Existing	Basement Bay 9	BP-15A
3/10/2009			1	3/219.1 victaulic no. 20	Existing	Basement Bay 9	BP-15A
3/10/2009			10	Grinnell 4"x114.3MM (705)	Existing	Basement Bay 9	BP-15A
3/10/2009			4	clamps 3/4	Existing	Basement Bay 9	BP-15A
3/10/2009			28	zero 6-168.3 flex pipe clamps	Existing	Basement Bay 9	BP-15A
3/10/2009			1	273mm 10" victaulic no. 10	Existing	Basement Bay 9	BP-15A
3/10/2009			4	zero / 2-323.3 flex	Existing	Basement Bay 9	BP-15A
3/10/2009			16	8" / 219.1 no. 7 flex	Existing	Basement Bay 9	BP-15A
3/10/2009			6	Victaulic 8/219,1 no. 60	Existing	Basement Bay 9	BP-15A
3/10/2009			10	Victaulic 8"/5741 clamps - flange	Existing	Basement Bay 9	BP-15A
3/10/2009	EMT-125		20	plastic bushing 1-14" for Al/sheet metal	Existing	Basement Bay 9	BP-15A
3/10/2009	W02085		4	C-pipe 1/2" x 5/8"	Existing	Basement Bay 9	BP-15A
3/10/2009	S158558-001		6	1-1/2" clamp holders - pipe ceiling clamp	Existing	Basement Bay 9	BP-15A
3/10/2009			10	pipe hangers 1' 6" D x 11 W	Existing	Basement Bay 5	BP-15A
3/10/2009			2	1" dia. x 1' 6" H pipe Cl	Existing	Basement Bay 5	BP-15A
3/10/2009	4010600EG		25	6" pipe hanger	Existing	Basement Bay 5	BP-15A
3/10/2009			30	Cl "I" - 16" length	Existing	Basement Bay 5	BP-15A



**Buley Library Project
Inventory Sheet**

ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/10/2009			20	"T" 1/2" CI	Existing	Basement Bay 5	BP-15A
3/10/2009		PBG05075ENCL16GADG	4	6.5 ft long aluminum air vent (louvered)	Existing	Basement Bay 5	BP-15A
3/10/2009			20	pipe ceiling clamps (see drawing)	Existing	Basement Bay 5	BP-15A
3/10/2009			100	aluminum washers 1/2" dia.	Existing	Basement Bay 5	BP-15A
3/10/2009			2	rolls copper cable no. 3 - 30 ft each	Existing	Basement Bay 5	BP-15A
3/10/2009			33	springs 1/4" dia.	Existing	Basement Bay 5	BP-15A
3/10/2009			2	Mueller Steam Specialty WCB "T" 6.111/D27 CI	Existing	Basement Bay 5	BP-15A
3/10/2009		EIRCO-40112	12	1'6" x 1' aluminum pipe hangers	Existing	Basement Bay 9	BP-15A
3/10/2009		N/A	2	Boxes (4/box) plastic pipe spacers 9"x8"x1"	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15A
3/10/2009		N/A	1	Box (7/box), non-pop metal, 10" dia, plastic lined ??	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15A
3/10/2009		N/A	30	Each, 12" clevis hangers	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15A
3/10/2009		N/A	4	Each, 15" clevis hangers	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15A
3/10/2009		PBG507 5NCK	6	boxes (2/box) 16 GA DG 5.5' square duct	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15A
3/10/2009		N/A	1	Box (14/box) PBG 508 End Cap 3-1/2" Lefthand/Righthand Hydro air	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15A
3/10/2009		N/A	1	Box (4/box) PBG 5-1/2" end cap Hydro air	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15A
3/10/2009		N/A	2	Each, PBG 5-1/2" 90 degree steel elbow	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15A
3/10/2009		N/A	1	Box (2/box), PBG end cap 7 1/2"	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15A
3/10/2009		N/A	1	Box (10/box) PBG End Cap 5-1/2" x 7-1/2" Hydro air	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15A
3/10/2009		N/A	60	Each, Plastic Pipe Spacers 6"x4"	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15A
3/10/2009		BM-416823	1	Each, Fire damper for use in static system 92" x 50" Prefco Products, Inc.	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15A
3/10/2009		BM-416769	1	Each, Fire damper for use in static system 46" x 62" Prefco Products, Inc.	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-15A
3/11/2009		451589	4	electric actuator with spring return for HVAC	Existing	Basement Bay 3 and 4	BP-15A
3/11/2009		365544-11	1	3' x 5' louvers for mechanical room (5A)	Existing	Middle of basement, near Bay 10	BP-15A
3/11/2009		365544-10	3	3' x 5' louvers for HVAC room (5A)	Existing	Middle of basement, near Bay 10	BP-15A
3/11/2009		365544 L-4A	3	Louver 4A	Existing	Middle of basement, near Bay 10	BP-15A
3/11/2009		058523	4	Air handlers - ceiling hang air handler units	Existing	Basement Bay 3 and 4	BP-15A
3/11/2009		036379	1	ceiling hang air handling unit	Existing	Basement Bay 3 and 4	BP-15A
3/11/2009			1	air handling unit- unidentified	Existing	Basement Bay 3 and 4	BP-15A
3/11/2009		GB-121-3-X 5659479-001	3	roof fan - Greenheck exhaust	Existing	Basement Bay 3 and 4	BP-15A
3/11/2009		GB-180-15-X	3	Greenheck exhaust fans	Existing	Basement Bay 3 and 4	BP-15A
3/11/2009			50	misc fan betts 1/2" thick	Existing	Basement Bay 3 and 4	BP-15A
3/11/2009		SE1-16-428-A5-X	1	Greenheck fan	Existing	Basement Bay 3 and 4	BP-15A
3/11/2009		26449188	1	metalaire louvers 24" x 24"	Existing	Basement Bay 3 and 4	BP-15A
3/11/2009		26449161	2	metalaire louvers 12" x 12"	Existing	Basement Bay 3 and 4	BP-15A
3/11/2009			1	metalaire louvers 9" x 9"	Existing	Basement Bay 3 and 4	BP-15A
3/11/2009		264491122	2	metalaire louvers 22" x 22"	Existing	Basement Bay 3 and 4	BP-15A
3/11/2009			100	6" flex clamps	Existing	Basement Bay 3 and 4	BP-15A
3/11/2009		264491-96	12	metalaire louvers 9" x 9"	Existing	Basement Bay 3 and 4	BP-15A
3/11/2009			40	8" clamps (strips)	Existing	Basement Bay 3 and 4	BP-15A
3/11/2009			60	12" clamps	Existing	Basement Bay 3 and 4	BP-15A
3/11/2009			1	24" dia galvanized 90° elbow air duct	Existing	Basement, Bay 3 and 4	BP-15A
3/11/2009			10	4' indulated duct box (see drawing)	Existing	Basement, Bay 3 and 4	BP-15A
3/11/2009			1	snap lock pipe 5' x 8" dia - Southwork manufacture	Existing	Basement, Bay 3 and 4	BP-15A
3/11/2009			3	metalaire louvers 24" x 24"	Existing	Basement, Bay 3 and 4	BP-15A
3/11/2009		4WZ73	4	boxes Air handler insulation 48" x 90" x 10'	Existing	Basement, Bay 3 and 4	BP-15A
3/11/2009			3	boxes 10" x25' glass flexible class I duct 10" dia - Atco rubber products	Existing	Basement, Bay 3 and 4	BP-15A
3/11/2009			2	boxes 12" x 25' glass flexible duct - Class I	Existing	Basement Bay 3 and 4	BP-15A
3/11/2009		264491	4	35-1/4" air louvers 4" thick	Existing	Basement Bay 3 and 4	BP-15A
3/11/2009		WD100	3	18 x 18 HVAC duct tray	Existing	Basement Bay 3 and 4	BP-15A
3/12/2009		SDRWC	33	10" VAV Enviro-tec box SDRWC	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009		SDRWC	46	12" VAV Enviro-tec box SDRWC	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009			1	Fire Damper 12"x12"	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009			1	Fire Damper 16"x16"	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009		SDRWC	62	6" VAV Box	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009			45	10" x 60" 26GA 1 SP106026 Snaplock Pipe	3/14/2009	1st Floor Bay 4	BP-15A



**Buley Library Project
Inventory Sheet**

ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/12/2009		M1-3A-A/2	1	Galvanized duct insulated 2'x2'x4'	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009			1	Galvanized duct non-insulated 1'x1'x5'	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009			1	Galvanized duct non-insulated 9" x1.3'x5'	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009			2	Galvanized duct non-insulated 8" x1.83'x5'	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009			1	1.5'x1.5'x1.66' GI duct with louvers	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009			1	12" collar galvanized	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009		EL Box 089026	2	8" galvanized elbows 90 deg	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009		6133D	8	Galvanized - 10.5"x8" fire damper	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009			3	11.5"x14" galvanized fire damper	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009			2	24"x8" galvanized fire damper	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009			2	12"x12" duct galvanized	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009			1	18"x18"x12" duct galvanized	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009			1	12"x12"x18" galvanized duct	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009			18	36" (1"x1") angles	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009		ML4115B1008	2	16x16 two position direct coupled actuator	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009			1	28x36 galvanized fire damper	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009			1	24x22 galvanized duct	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009			2	6x8 galvanized fire damper	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009			1	24x24x48 hot galvanized duct	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009			1	35x27 galvanized insulated dampers - 1" flange	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009			1	59"x47" insulated galvanized duct	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009			1	10x12x60 galvanized riser duct	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009			1	27x28 insulated galvanized dampers	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009			1	14x28 galvanized dampers	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009			2	59x33 non-insulated galvanized duct	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009			2	12x12x5' insulated galvanized duct	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009			1	90' - 12x12 galvanized duct	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009		ST-2R9	1	36x48x84 insulated galvanized duct	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009			1	21x47 insulated galvanized duct	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009		ST-15B	1	40x51x84 noise transfer galvanized insulated duct	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009		ST-159	1	34x40x84 insulated noise transfer duct	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009		ST-2R	1	36x48x84 galvanized noise duct	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009		ST-251	1	36x34x84 galvanized noise duct	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009			6	collar 8x16 galvanized	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009			1	66x22 galvanized louver	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009			8	18x18 rectangular end cap	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009			4	18"x18"x5' galvanized non-insulated duct	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009			3	3'x2' galvanized louvers	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009			6	1'x1'x5' galvanized non-insulated duct	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009			2	10"x8"x5' galvanized duct non-insulated	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009			2	6"x5"x5' galvanized duct non-insulated	3/14/2009	1st Floor Bay 4	BP-15A
3/12/2009			1	12"x12"x6" galvanized duct non-insulated	3/14/2009	1st Floor Bay 4	BP-15A
3/5/2009	0115	AHU-2 Reheat	2	PO #8466 2" Ball Valve	3/5/2009	West Wall - Auditorium	BP-15B
3/5/2009	0115	AHU-1 Reheat	2	PO #8466 2" Ball Valve	3/5/2009	West Wall - Auditorium	BP-15B
3/5/2009	0115	UH-7	3	Nexus Valve Assembly PO #8231	3/5/2009	West Wall - Auditorium	BP-15B
3/5/2009	0116	FTR	14	Nexus Valve Assembly PO #8261	3/5/2009	West Wall - Auditorium	BP-15B
3/5/2009	0117	FTR	14	Nexus Valve Assembly PO #8261	3/5/2009	West Wall - Auditorium	BP-15B
3/5/2009	0118	FTR	14	Nexus Valve Assembly PO #8261	3/5/2009	West Wall - Auditorium	BP-15B
3/5/2009	0119	VAV-D	14	Nexus Valve Assembly PO #8231	3/5/2009	West Wall - Auditorium	BP-15B
3/5/2009	0120	VAV-C	17	Nexus Valve Assembly PO #8231	3/5/2009	West Wall - Auditorium	BP-15B
3/5/2009	0121	VAV-D	14	Nexus Valve Assembly PO #8231	3/5/2009	West Wall - Auditorium	BP-15B
3/5/2009	0122	VAV-A	19	Nexus Valve Assembly PO #8231	3/5/2009	West Wall - Auditorium	BP-15B
3/5/2009	0123	VAV-B	18	Nexus Valve Assembly PO #8231	3/5/2009	West Wall - Auditorium	BP-15B
3/5/2009	0124	VAV-A	17	Nexus Valve Assembly PO #8231	3/5/2009	West Wall - Auditorium	BP-15B
3/5/2009	0125	VAV-C	13	Nexus Valve Assembly PO #8231	3/5/2009	West Wall - Auditorium	BP-15B
3/5/2009	0125	5VBM4	2	Weiss 5" Bimetal Thermometer	3/5/2009	West Wall - Auditorium	BP-15B
3/5/2009	0126	FTR	6	Nexus Valve Assembly PO #8231	3/5/2009	West Wall - Auditorium	BP-15B



**Buley Library Project
Inventory Sheet**

ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/5/2009	0126	VAV-B	5	Nexus Valve Assembly PO #8231	3/5/2009	West Wall - Auditorium	BP-15B
3/5/2009	0126	FTR-201	1	Nexus Valve Assembly PO #8261	3/5/2009	West Wall - Auditorium	BP-15B
3/5/2009	0126	FTR-202	1	Nexus Valve Assembly PO #8261	3/5/2009	West Wall - Auditorium	BP-15B
3/5/2009	0127	UH-3	4	Nexus Valve Assembly PO #8231	3/5/2009	West Wall - Auditorium	BP-15B
3/5/2009	0127	CUH-4	1	Nexus Valve Assembly PO #8231	3/5/2009	West Wall - Auditorium	BP-15B
3/5/2009	0127	UH-4	1	Nexus Valve Assembly PO #8231	3/5/2009	West Wall - Auditorium	BP-15B
3/5/2009	0127	CUH-3	3	Nexus Valve Assembly PO #8231	3/5/2009	West Wall - Auditorium	BP-15B
3/5/2009	0127	UH-1	3	Nexus Valve Assembly PO #8231	3/5/2009	West Wall - Auditorium	BP-15B
3/5/2009	0127	FTR-100A-40	1	Nexus Valve Assembly PO #8261	3/5/2009	West Wall - Auditorium	BP-15B
3/5/2009	0127	FTR-400-176	1	Nexus Valve Assembly PO #8261	3/5/2009	West Wall - Auditorium	BP-15B
3/5/2009	0150	B212B+TR24-SR-T US	28	Belimo Non-spring return actuator 2-way valve assembly (600 PSI)	3/5/2009	West Wall - Auditorium	BP-15B
3/5/2009	0151	B211B+TFX24 US	5	Belimo actuator 2-way assembly CV 1.9 (600 PSI)	3/5/2009	West Wall - Auditorium	BP-15B
3/5/2009	0151	B210B+TFX24 US	4	Belimo actuator 2-way assembly (600 PSI)	3/5/2009	West Wall - Auditorium	BP-15B
3/5/2009	0151	B208B+TFX24 US	1	Belimo actuator 2-way assembly (600 PSI)	3/5/2009	West Wall - Auditorium	BP-15B
3/5/2009	0151	B212B+TFX24 US	1	Belimo actuator 2-way assembly (600 PSI)	3/5/2009	West Wall - Auditorium	BP-15B
3/5/2009	0151	B22B+TFX24 US	1	Belimo actuator 2-way assembly (600 PSI)	3/5/2009	West Wall - Auditorium	BP-15B
3/5/2009	0151	B214B+TFX24 US	1	Belimo actuator 2-way assembly (600 PSI)	3/5/2009	West Wall - Auditorium	BP-15B
3/5/2009	0157	B220+TFX24 US	8	Belimo Characterized Control Valves (CCV)	3/5/2009	West Wall - Auditorium	BP-15B
3/10/2009	0256 - 0275	SY3-24	5	Belimo 8" CF-8 Butterfly valve w/actuator	3/12/2009	Basement Bay 8	BP-15B
3/6/2009	0313	0631149	12	boxes Duct sensor assembly 4W, 4098-9756	3/6/2009	Basement Bay 2	BP-15B
3/7/2009	500	C-02710	480	Each, STT cable 18/3 white - 27"	3/7/2009	Center of Auditorium	BP-16
3/7/2009	500	C-02710	500	Each, 1/4" washers	3/7/2009	Center of Auditorium	BP-16
3/7/2009	501	M-00045	300	Each, STT cable 18/3 white - 26'	3/7/2009	Center of Auditorium	BP-16
3/7/2009	501	M-00045	150	Each, 2" plastic canopy white	3/7/2009	Center of Auditorium	BP-16
3/7/2009	502	A6VF142E2	6	Each, Vantage lighting, light fixture housing, no ballast	3/7/2009	Center of Auditorium	BP-16
3/7/2009	503	A6VF142E2	6	Each, Vantage lighting, light fixture housing	3/7/2009	Center of Auditorium	BP-16
3/7/2009	504	A6VF142E2	6	Each, Vantage lighting, light fixture housing	3/7/2009	Center of Auditorium	BP-16
3/7/2009	505	A6VF142E2	6	Each, Vantage lighting, light fixture housing	3/7/2009	Center of Auditorium	BP-16
3/7/2009	506	A6VF142E2	6	Each, Vantage lighting, light fixture housing	3/7/2009	Center of Auditorium	BP-16
3/7/2009	507	A6VF142E2	6	Each, Vantage lighting, light fixture housing	3/7/2009	Center of Auditorium	BP-16
3/7/2009	508	A6VF142E2	6	Each, Vantage lighting, light fixture housing	3/7/2009	Center of Auditorium	BP-16
3/7/2009	509	A6VF142E2	6	Each, Vantage lighting, light fixture housing	3/7/2009	Center of Auditorium	BP-16
3/7/2009	510	A6VF142E2	6	Each, Vantage lighting, light fixture housing	3/7/2009	Center of Auditorium	BP-16
3/7/2009	511	A6VF142E2	6	Each, Vantage lighting, light fixture housing	3/7/2009	Center of Auditorium	BP-16
3/7/2009	512	A6VF142E2	6	Each, Vantage lighting, light fixture housing	3/7/2009	Center of Auditorium	BP-16
3/7/2009	513	A6VF142E2	6	Each, Vantage lighting, light fixture housing	3/7/2009	Center of Auditorium	BP-16
3/7/2009	514	DECO DISK 0333	140	Each, 1/8" blue decco disk, 8-3/4" dia	3/7/2009	Center of Auditorium	BP-16
3/7/2009	514	N/A	2	Each light fixture housing	3/7/2009	Center of Auditorium	BP-16
3/7/2009	515	DECOD19E	230	Each, 1/8" blue decco disk, 8-3/4" dia	3/7/2009	Center of Auditorium	BP-16
3/7/2009	516	A6VF142E2	15	Boxes (6/box), Vantage lighting, light fixture housing	3/7/2009	Center of Auditorium	BP-16
3/9/2009	517	STN/SS-ASY 4-2-B	18	Boxes (15/box) Cooper 4' white A-symmetric reflector	3/6/2009	Center of Auditorium	BP-16
3/9/2009	518	BB-WM-2T8-1E-277-08CE1E	8	Each, cooper 8' light fixture (one was damaged)	3/6/2009	Center of Auditorium	BP-16
3/9/2009	519	BB-WM-2T8-1C-277-12 CCE-1E BB-WM-278-1E-277-12CCE-1E	78	Each, Cooper 12' light fixture	3/6/2009	Center of Auditorium	BP-16
3/9/2009	520	BB-WM-2T8-1C-277-04	7	Each, Cooper 4' light fixture	3/6/2009	Center of Auditorium	BP-16
3/9/2009	521	BB-WM-2T8-1E-277-4C-1E	2	Each, Cooper 4' light fixture	3/6/2009	Center of Auditorium	BP-16
3/9/2009	522	WS-332A-277V-EB81-U	46	Each, Cooper Lighting Fixture, 4' lamp, 4' surface wraparound	3/6/2009	Center of Auditorium	BP-16
3/9/2009	523	LCP-6-GR-1400 Series	1	Each, Lighting control & design (in blue box)	3/6/2009	Center of Auditorium	BP-16
3/9/2009	523	LCP-6-GR-1400 Series	1	Each, Lighting control & design (in blue box)	3/6/2009	Center of Auditorium	BP-16
3/9/2009	523	LCP-9-GR-1400 Series	1	Each, Lighting control & design (in blue box)	3/6/2009	Center of Auditorium	BP-16
3/9/2009	523	LCP-12-GR-1400 Series	1	Each, Lighting control & design (in blue box)	3/6/2009	Center of Auditorium	BP-16
3/9/2009	523	6001-1IWF	4	Each, 8" narrow beam reflector with white flange	3/6/2009	Center of Auditorium	BP-16
3/9/2009	523	6711LIWF	23	Each, Light housing with white flange	3/6/2009	Center of Auditorium	BP-16
3/9/2009	523	62511IWF	1	Each, White Flange Type	3/6/2009	Center of Auditorium	BP-16
3/9/2009	524	N/A	125	Each, Bar Hanger	3/6/2009	Center of Auditorium	BP-16
3/9/2009	524	MHW1-175-MT-EM-TR-MP	13	Each, 175W-MH-Mt glass Emergency TR	3/7/2009	Center of Auditorium	BP-16
3/9/2009	525	C6118E	20	Each, Cooper Lighting 18W BTTHOR 120-277V	3/7/2009	Center of Auditorium	BP-16



**Buley Library Project
Inventory Sheet**

ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/9/2009	525	HD-6	24	Each, Copper lighting 8" incadescent housing	3/7/2009	Center of Auditorium	BP-16
3/9/2009	526	N/A	9	Each, Advantage Lighting Light Trim - Misc.	3/7/2009	Center of Auditorium	BP-16
3/9/2009	527	BB-WM-2T8-1E-277-8CE-1E BB-WM-2t*-1C-277-08	95	Each, Cooper Lighting 12' Neo-ray	3/7/2009	Center of Auditorium	BP-16
3/9/2009	528	2EP-3GAX-3U15/5341-UN-EB81-4	30	Each, Cooper lighting 2x2 light fixture	3/7/2009	Center of Auditorium	BP-16
3/9/2009	529	N/A	272	Each, Cooper mounting hardware	3/7/2009	Center of Auditorium	BP-16
3/9/2009	529	2EP3GAX-3U1 5/85341-UNV-B81-U	12	Each, Cooper Lighting 2x2 light fixture	3/7/2009	Auditorium	BP-16
3/9/2009	530	2GCAFA-332A 125-UNV-EB81	18	Each, Cooper Lighting 2x4 light fixture	3/7/2009	Auditorium	BP-16
3/9/2009	530	30781011150653	400	Each, Cooper B-line independent suspension stud fastener 1/4" 25x5/8"	3/7/2009	Auditorium	BP-16
3/9/2009	531	CO# RAN050 722-23A	1	Each, VFRWC - Series B 3/4 hose by Emrio Tech	3/7/2009	Auditorium	BP-16
3/9/2009	600	2EP3GAX-332 9391-UNV-EB 81-U	106	Each, Cooper Lighting 2x4 light fixture	3/7/2009	Auditorium	BP-16
3/9/2009	600	RC919HBTC	15	Each, Recessed floor fixtures, wire mold electric system	3/7/2009	Auditorium	BP-16
3/9/2009	600	RC7AFFTGGY	16	Each, Recessed floor fixtures, wire mold electric system	3/7/2009	Auditorium	BP-16
3/9/2009	601	2EP39AX-332 5391-UNV-EB81-U	22	Each, Cooper Lighting 2x4 light fixture	3/7/2009	Auditorium	BP-16
3/9/2009	602	N/A	25	Each, Misc. lighting trim	3/7/2009	Center of Auditorium	BP-16
3/9/2009	602	N/A	3	Each, Advantage Lighting Light Trim - Misc.	3/7/2009	Center of Auditorium	BP-16
3/9/2009	602	F32T8/TL841	900	Each, Phillips 4' fluorescent lamps, 800 series	3/7/2009	Center of Auditorium	BP-16
3/9/2009	603	N/A	5	Each, Misc. lighting trim	3/7/2009	Center of Auditorium	BP-16
3/9/2009	603	F32T8/TL841	250	Each, Phillips 4' fluorescent lamps, 800 series	3/7/2009	Center of Auditorium	BP-16
3/9/2009	603	24241019F00000	14	Each, Type S, 4' fluorescent light fixture surface model - 2 tubes	3/7/2009	Center of Auditorium	BP-16
3/9/2009	603	YT2-232DR-UNV-EB81-WL-U	8	Each, LV1, Cooper lighting, 2 lamps, 4' raportite wet location strip	3/7/2009	Center of Auditorium	BP-16
3/9/2009	603	DECO-DISE	100	Each, 1/8" blue deco discs 8-3/4" dia	3/7/2009	Center of Auditorium	BP-16
3/9/2009	604	2073300974	2	Each, ACH550-VD-031A-4TF267 Electrical Control	3/7/2009	Auditorium	BP-16
3/9/2009	605	THHM-1-STR-BLK	1055	Feet, Ferguson electrical	3/7/2009	NE Corner, Near the Aud ramp	BP-16
3/9/2009	605	THHM-3-STR-BLK	505	Feet, Ferguson electrical	3/7/2009	NE Corner, Near the Aud ramp	BP-16
3/9/2009	605	N/A	700	Feet, Type T-90 Nylon or TWN75	3/7/2009	NE Corner, Near the Aud ramp	BP-16
3/9/2009	605	N/A	1200	Feet, Type No 2 - Standard Copper THHN	3/7/2009	NE Corner, Near the Aud ramp	BP-16
3/9/2009	605	N/A	100	Feet, Type THHN Standard Copper	3/7/2009	NE Corner, Near the Aud ramp	BP-16
3/9/2009	605	N/A	75	Feet, Type THHN # 8 Standard Copper	3/7/2009	NE Corner, Near the Aud ramp	BP-16
3/9/2009	605	N/A	1000	Feet, Type THHN # 6 Standard Copper	3/7/2009	NE Corner, Near the Aud ramp	BP-16
3/9/2009	605	N/A	500	Feet, Type THHN # 2 Standard Copper	3/7/2009	NE Corner, Near the Aud ramp	BP-16
3/9/2009	605	N/A	1500	Feet, Type THHN # 3 Standard Copper	3/7/2009	NE Corner, Near the Aud ramp	BP-16
3/9/2009	605	N/A	100	Feet, Misc. Wires	3/7/2009	NE Corner, Near the Aud ramp	BP-16
3/9/2009	606	1107-P-100-MH-277	1	Each, Vista Professional	3/7/2009	NE Corner, Near the Aud ramp	BP-16
3/9/2009	606	N/A	350	Each, 1/8" Blue Disc	3/7/2009	NE Corner, Near the Aud ramp	BP-16
3/9/2009	606	CC3WHSD	2	Each, switches conductor choice emergency light	3/7/2009	NE Corner, Near the Aud ramp	BP-16
3/9/2009	607	1107-P-100-MH-277	3	Each, Vista Professional	3/7/2009	NE Corner, Near the Aud ramp	BP-16
3/9/2009	607	N/A	100	Feet, Misc. Cooper Wire	3/7/2009	NE Corner, Near the Aud ramp	BP-16
3/9/2009	607	FB031/841	45	Each, Sylvania - Fluorescent 4100K Octron Curvvalume, Medium pin	3/7/2009	NE Corner, Near the Aud ramp	BP-16
3/9/2009	607	N/A	6	Electronic PT Lighting	3/7/2009	NE Corner, Near the Aud ramp	BP-16
3/9/2009	700	2EP3GAX-3U15-89341-11UNV-EB81-U	112	Each, Cooper lighting, 2x2 light fixture, Type B	3/7/2009	Basement Bay 1 and Bay 6	BP-16
3/9/2009	700	29CAFA-3U15-8a125-unv-eb81-u	62	Each, Cooper lighting, Type D, 2x2 light fixture	3/7/2009	Basement Bay 1 and Bay 6	BP-16
3/9/2009	700	50000512733	1	Each, GE transformer	3/7/2009	Basement Bay 10	BP-16
3/9/2009	700	50000512735	1	Each, GE transformer	3/7/2009	Basement Bay 10	BP-16
3/9/2009	700	CR1976	4	Each, Cable Relay Rack , 7'x19' wide black	3/7/2009	Basement Bay 10	BP-16
3/9/2009	701	2EP3GAX-3U15-89341-11UNV-EB81-U	16	Each, Cooper lighting, 2x2 light fixture, Type B	3/7/2009	Basement Bay 1 and Bay 6	BP-16
3/9/2009	701	2EB3GAX-3325391-UNV-EB81-U	64	Each, Type G, 2x4 light fixture	3/7/2009	Basement Bay 1 and Bay 6	BP-16
3/9/2009	701	400M36SQNS	16	Each, Assembly pts (4"x2"x2") item ID 670610411185 (plumbing) wade	3/7/2009	Basement Bay 1 and Bay 6	BP-16
3/9/2009	701	78351052830	4	Each, 52830 closure plates with knock outs	3/7/2009	Basement Bay 1 and Bay 6	BP-16
3/9/2009	701	50000512760	1	Each, GE transformer	3/7/2009	Basement Bay 10	BP-16



**Buley Library Project
Inventory Sheet**

ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/9/2009	701	50000512740	1	Each, GE transformer	3/7/2009	Basement Bay 10	BP-16
3/9/2009	702	2EP3GAX-3U15-89341-11UNV-EB81-U	88	Each, Type B 2x2 light fixture	3/7/2009	Basement Bay 10	BP-16
3/9/2009	703	2EP3GAX-3U15-89341-11UNV-EB81-U	44	Each, Cooper Lighting 2x2 Type B light Fixture	3/7/2009	Basement Bay 10	BP-16
3/9/2009	800	1706B60T00	30	Rolls (1000 ft/roll), 12-4- Type MC Steel Metal Clad Cable	3/7/2009	Basement Bay 10	BP-16
3/9/2009	800	1706B60T00	3	Rolls (500 ft/roll), 12-4- Type MC Steel Metal Clad Cable	3/7/2009	Auditorium near Ramp	BP-16
3/10/2009	3100	CX-SD, Mark EX	22+2	Boxes (6 per box) + 2 Each, Sure-Lites, Exit/Emergency Lighting	3/10/2009	1st Floor Bay 2	BP-16
3/10/2009	3100	MHC150/U/MP/3K Alto	10	Each, Phillips, Master Color, Ceramic Metal Halide Lamps	3/10/2009	1st Floor Bay 2	BP-16
3/10/2009	3100	38331-00	2	Boxes, Phillips, Alto PL-C, 180W/841/4P Compact Florescent Lamps	3/10/2009	1st Floor Bay 2	BP-16
3/10/2009	3100	815572	19	Each, Phillips, 100W Standard Frost Light Bulbs	3/10/2009	1st Floor Bay 2	BP-16
3/10/2009	3100	244772	6	Each, Master Color Ceramic Metal Halide, PAR30, Light Bulbs	3/10/2009	1st Floor Bay 2	BP-16
3/10/2009	3100	268763	11 + 9	Boxes (12/box) + 9 each, Philips Alto 42W/41/4P Compact Fluorescent Lamps	3/10/2009	1st Floor Bay 2	BP-16
3/10/2009	3100	97003-3	24	Each, Philips, 150 W, Frost Standard Incandescent Lamps	3/10/2009	1st Floor Bay 2	BP-16
3/10/2009	3100	924794736381	3	Boxes, Phillips, 100Q/CL/DC ESR Lamps	3/10/2009	1st Floor Bay 2	BP-16
3/10/2009	3100	232249	1	Box, Philips Master Color, CDM 70/PAR 30L/M/SP/3K Metal Halide Lamps	3/10/2009	1st Floor Bay 2	BP-16
3/10/2009	3100	367938	1	Box, Philips F17T8/TL841/Alto Fluorescent Lamps	3/10/2009	1st Floor Bay 2	BP-16
3/10/2009	3101	13534800, Mark M1	12	Each, Metalux Cooper Lighting, 2' x 4' Parabolic Troffer Fluorescent Drop Ceiling Fixtures	3/10/2009	1st Floor Bay 2	BP-16
3/10/2009	3105	246710004	55	Boxes, Philips alto II 800 Series F32T8/TL841 Fluorescent Lamps	3/10/2009	1st Floor Bay 2	BP-16
3/10/2009	3107	13553212, Mark H	10	Each, Metalux Cooper Lighting, 2' x 4' Parabolic Troffer Fluorescent Drop Ceiling Fixtures	3/10/2009	1st Floor Bay 2	BP-16
3/10/2009	3110	HD0000056, Mark C2	1	Box, Cooper Lighting, Incandescent Housing	3/10/2009	1st Floor Bay 2	BP-16
3/10/2009	3110	11553728, Mark U	3	Boxes, Cooper Lighting Halo Track Lighting Synchro, PAR 30 CMH Track Fixture	3/10/2009	1st Floor Bay 2	BP-16
3/10/2009	3110	MVR175/U	13	Each, GE Lighting, 175 Watts Light Bulbs	3/10/2009	1st Floor Bay 2	BP-16
3/10/2009	3110	26676-7, Mark K	12	Each, 150Q/CL/DC ETC 120V Halogen Lamps	3/10/2009	1st Floor Bay 2	BP-16
3/10/2009	3110	13554791, Mark Ball	6	Each, Metalux Cooper Lighting, 2' x 4' Parabolic Troffer Fluorescent Drop Ceiling Fixtures	3/10/2009	1st Floor Bay 2	BP-16
3/10/2009	3110	11737544, Mark K1	1	Box, INVUE Cooper Lighting, 175W MH CWA MT 3S GMEM	3/10/2009	1st Floor Bay 2	BP-16
3/10/2009	3110	11606967, Mark V	4	Boxes, Cooper Halo Track Lighting, Span, T5 Fluorescent Wall Wash Fixtures	3/10/2009	1st Floor Bay 2	BP-16
3/10/2009	3110	0590-L085, Mark W	2	Each, Cooper Lighting, 2 lamp, T8, 4" Strip, Electronic Ballast, Fluorescent Fixture	3/10/2009	1st Floor Bay 2	BP-16
3/10/2009	3110	1280764, Mark C2	4	Boxes, Cooper Lighting, 6" CFL, Multi-Split, 26-42W Compact Fluorescent	3/10/2009	1st Floor Bay 2	BP-16
3/10/2009	3110	13262255, Mark M	10	Each, Matalux Cooper Lighting, 2RDI-332RP-UNV-EB82-U	3/10/2009	1st Floor Bay 2	BP-16
3/5/2009	0048	N/A	1	1 1/2" bronze trap 150	3/5/2009	Southwest corner - Auditorium	BP-16
3/9/2009	0200 - 0255	18275	1	box GE lighting 120V incandescent lamps - 12 ct each	3/12/2009	Basement Bay 8	BP-16
3/6/2009	0305	FCW4300BK	3	FC lighting 775 W part 99025-CFI	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0306		1	panel box 6"	3/6/2009	East Wall - Auditorium	BP-16
3/6/2009	0306	8480R655	1	access cover	3/6/2009	East Wall - Auditorium	BP-16
3/6/2009	0306		10	Electric panel cover 5-1/2" x 7-1/2"	3/6/2009	East Wall - Auditorium	BP-16
3/6/2009	0316	515A	75	Caddy light fixture retainer clip	3/6/2009	Basement Bay 2	BP-16
3/6/2009	0401		1	Roll nylon fishing line - 1350 ft.	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0401	50DLOWZ/P	2	Boxes Nefco Split lock washer 1/2" - 50 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0401	BBA08	25	USS Hard Flat washer 1/2"	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0401	JKR05048	50	5/16-18 x 1 1/2 Bolt	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0401		1	Box Fender washer 1/2" x 1 1/2" - 50 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0401		1	Box 1/4" steel shims - 25 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0401	R63033484	30	1/2" x 1 1/2" stanless steel bolts	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0401		50	1/2" x 1 1/4" steel washers	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0401		30	1/2"-13 zinc locknuts	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0401		5	pounds Misc 1/2" galvanized nuts and bolts	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0401		1	pound anchor bolts 1/4" - 1/2"	3/6/2009	West Wall - Auditorium	BP-16



**Buley Library Project
Inventory Sheet**

ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/6/2009	0401		10	1/2" flat washers	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0401		40	1/4" x 1 1/2" galvanized square washers	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0401		2	3" Victaulic couplings 88.9/3" -75	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0401		1	Victaulic cap 3"/88.9 No. 60	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0401	BT37	2	Sylvania Metalarc metal halide lamp	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0402		7	Boxes 1/2" anchors - 50 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0402	09675	3	Boxes Powers Fasteners 1/2" machine bolt anchors - 25 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0402		2	Boxes Hex Bolts Gr. 2, 1/2-13 x 1 1/2" - 50 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0402		7	Pounds 1/2" flat washers	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0402		5	Boxes Flat washer 1/2" - 50 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0402		1	Box Flat washer 5/8" - 25 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0402		6	Boxes 1/2" Hex finish nuts - 50 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0402		1	Box hex bolt Gr. 2, 1/2-13 x 1" - 50 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0402		1	Box Flat washer 1/2" - 50 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0402		2	Boxes Red Head concrete anchors 1/2-13 - 50 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0402	06308	2	Boxes Powers Fasteners 1/2" steel drop-in - 50 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0402	09685	2	Boxes Powers Fasteners 5/8" Machine bolt anchors - 25 ct ea	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0402		1	Box Red Head Concrete anchor 1/4" x 1 3/8" - 100 ct ea	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0402	RL-58	2	Boxes Red Head Concrete anchors drop in bolt 5/8" - 11 - 25 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0402		1	Box 3/8" sheet metal screws - 200 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0403	5144012	20	Cantex 4" PVC End bell	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0403		5	2" PVC End bell	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0404	B2209ZN	6	Boxes B-Line clamps 3/4" - 100 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0405	B2209ZN	6	Boxes B-Line clamps 3/4" - 100 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0406	B2209ZN	6	Boxes B-Line clamps 3/4" - 100 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0407	665	12	Boxes Cooper Compression 2" coupling - 5 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0408	667	16	Boxes Crouse Hinds 3" Compression type coupling - 1 ct ea.	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0409	667	16	Boxes Crouse Hinds 3" Compression type coupling - 1 ct ea.	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0410	667	16	Boxes Crouse Hinds 3" Compression type coupling - 1 ct ea.	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0411	667	16	Boxes Crouse Hinds 3" Compression type coupling - 1 ct ea.	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0412	669	8	Boxes Crouse Hinds 4" Compression type coupling - 1 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0413	669	6	Boxes Crouse Hinds 4" Compression type coupling - 1 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0413	667	3	Boxes Crouse Hinds 3" Compression type coupling - 1 ct ea.	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0413	657	2	Boxes Crouse Hinds 3" Compression type coupling - 1 ct ea.	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0414	664	4	Boxes Crouse Hinds 1 1/2" Compression type coupling - 10 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0414	662	2	Boxes Crouse Hinds 1" compression type coupling - 25 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0414	652	2	Boxes Crouse Hinds 1" compression type coupling - 25 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0415	PS1300	2	Boxes Power Strut Universal Pipe Clamp 3/4" EG - 100 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0415	PS1300	1	Box Power Strut Universal Pipe Clamp 3/4" EG - 60 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0415	662	2	Boxes Crouse Hinds 1" compression type coupling - 25 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0416	PS1300	1	Box Power Strut Universal Pipe Clamp 1 1/4" ASEG - 100 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0416	SC-400	7	Boxes NEER Straight squeeze connector die-cast 4" - 1 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0417	LT200	12	Boxes Crouse Hinds Cooper Straight male connector w/o insulated bushing 2" - 1 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0417	SC-400	3	Boxes NEER Straight squeeze connector die-cast 4" - 1 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0418	LT20010	5	Boxes Crouse Hinds 90° male connector 2" w/o insulated throat bushing - 1 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0418	741	4	Boxes Cooper Crouse Hinds 90° clamp type connector 1 1/2" - 1 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0418	712	1	Box Cooper Crouse Hinds 1 1/2" squeeze type connector - 5 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0418	715	2	Boxes Cooper Crouse Hinds 3" squeeze type connector - 1 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0418	LT 50	1	Box Cooper Crouse Hinds 1/2" straight male connector - 20 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0418	LT 7590	3	Boxes Cooper 90° angle male connector 3/4" - 10 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0418	LT 5090	1	Box Cooper 90° angle male connector 1/2" - 20 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0418	LT15090	1	Box Cooper 90° angle male connector 1 1/2" - 2 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0419	LT100	4	Boxes Cooper Crouse Hinds 1" straight male connector - 5 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0419	LT10090	2	Boxes Cooper 90° angle male connector 1" - 10 ct each	3/6/2009	West Wall - Auditorium	BP-16



ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/6/2009	0419	LT75	1	Box Cooper 3/4" Straight male connector - 25 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0419	6615	1	Box Crouse Hinds 3/4" Crouse Hinds Compression type coupling - 25 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0419	667	1	Box Crouse Hinds 3" compression type coupling - 1 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0419	5334-T13	1	Box T&B Fittings 1" Liquid tight flex metal conduit connector straight insulated - 10 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0419	5354	1	box T&B Fittings 1" liquid tight flex metal conduit connector, 90° angle insulated - 5 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0419	5344	1	Box T&B Fittings 1" liquid tight flex metal conduit connector, 45° angle insulated - 5 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0419	5353	1	Box T&B Fittings 3/4" liquid tight flex metal conduit connector, 90° angle insulated - 10 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0420	EMT100	10	Boxes Arlington Industrial 1" Push-on non-metallic insulating bushing for Al/Steel - 100 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0420	EMT200C	1	Box Arlington Industrial 2" Push-on non-metallic pipe cap protector for Al/Steel - 50 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0420	EMT75	5	Boxes Arlington Industrial 3/4" push-on non-metallic insulating bushing - 100 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0421	70755	1	Box EGS 3/4" EMT Connector - 25 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0421	6535	1	Box Topaz 1" EMT Connector - 10 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0421	SLT29T	1	box Sepco 1" straight liquid tight connector steel ferrule w/sealing ring - 5 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0421	1021	2	Boxes Sepco 2" locknut EMT compression coupling concrete tight zinc die cast - 5 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0421	EMT150C	1	box Arlington Industrial 1 1/2" push-on non-metallic pipe cap - 100 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0421	NEER TC-613	4	Boxes EGS 1" compression type EMT coupling - 10 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0421	6625	1	Box Topaz 3/4" compression type EMT coupling - 25 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0421	NEER TC-612	4	Boxes EGS 3/4" compression type EMT coupling - 25 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0421	5320	1	Box T&B Fittings 1" EMT coupling -10 ct each	3/6/2009	West Wall - Auditorium	BP-16
3/6/2009	0422	6615	1	Box Crouse Hinds 3/4" EMT compression type coupling - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0422	657	15	Boxes Cooper 3" EMT Compression type connector -1 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0423	659	8	Boxes Crouse Hinds 4" EMT compression type box connector - 1 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0423	652	2	Boxes Crouse Hinds 1" EMT compression type connector - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0423	5323	1	Box T&B Fittings 1" EMT Connector Insulated - 10 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0423	8435	1	Box Armstrong Industrial 1" Cable connector NM sheathed cable - 20 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0423	L428	3	Boxes Armstrong Industrial 3" straight squeeze connector - 1 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0423	8620	1	Box Armstrong Industrial 3/4" SS EMT to 3/4" flex combination coupling zinc diecast - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0423	EMT75C	1	Box Armstrong Industrial 3/4" push-on non-metallic pipe cap - 100 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0424	L426	1	Box Armstrong Industrial 2" squeeze connectors for flex/BX, zinc diecast - 5 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0424	EMT400	1	Box Armstrong Industrial 4" push-on non-metallic insulating bushing for Al/Steel - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0424	EMT 300	1	Box Armstrong Industrial 3" push-on non-metallic insulating bushing for Al/Steel - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0424	EMT 200	1	Box Armstrong Industrial 2" push-on non-metallic insulating bushing for Al/Steel - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0424	EMT 100	1	Box Armstrong Industrial 1 1/4" push-on non-metallic insulating bushing for Al/Steel - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0424	SLT28T	1	Box Sepco 3/4" straight liquid tight connector w/ins. Throat steel ferrule sealing ring and locknut - 10 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0424	111R	1	Box Elkhart Products Co. 3x3x2 reducing tee - 1 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0424	NEER AC-90	1	Box EGS 3/8" zinc diecast 90° angle connector - 50 ct each	3/10/2009	Basement Bay 2	BP-16



ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/6/2009	0424	C23	1	Box Sepco 3/8" twin screw clamp connector zinc die cast for sheathed cable - 100 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0425	Z64-DC	1	Box Bridgeport Zinc EMT coupling 1 1/2" - 10 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0425	143S	1	Box Sepco EMT one-hold strap snapon type rigid to wooden structures 3/4" - 100 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0425	C28T	1	Box Sepco Straight squeeze connectors malleable iron zinc coated 3/4" - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0425	NEER EFC-100	1	Box EGS combination coupling 3/4" - 3/4" SS EMT to Flex metal conduit - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0425	NEER SC-100	1	box EGS straight squeeze connector 1" - 10 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0425	9075-W	1	box O-Z/Geonev EMT combination coupling 3/4" EMT to flex steel metal conduit	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0425	71505	3	boxes EGS EMT connector gland compression type 1 1/2" - 5 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0425	254-DC2	1	box Bridgeport EMT connectr compression type concrete tight 1-1/2" - 10 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0425	300-STL	7	boxes EMT connector compression type 3", 1 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0425	322	1	box Bridgeport plastic bushing 3/4" - 100 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0425	RD2	1	box Crouse Hinds single gang box 3/4" - 2 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0425	ST11	1	box Sepco plastic insulating bushings 3/4" - 100 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0425	ST12	2	boxes Sepco plastic insulating bushings 1" - 50 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0425	323	1	box Bridgeport plastic bushing 1" - 50 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0425	321	1	box Bridgeport plastic bushing 1/2" - 100 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0426	53336R	1	box T&B Fittings External bonding liquid tight flexmetal conduit fitting straight 3/4" - 15 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0426	SLT66-45T	1	box Sepco 45° connector 3" - 1 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0426	443	1	box Arlington Industries plastic insulating bushing 1-1/4" - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0426	655	1	box Cooper Crouse Hinds EMT compression type connector 2" - 5 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0426	810-DC2	1	box Bridgeport 90° angle connector 2" - 5 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0426	416I	1	box Bridgeport squeeze connector 2" - 2 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0426	804-DC2	1	box Bridgeport 90° angle connector 1/2" - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0426	EMT125	1	box Arlington Industries push-on non-metallic bushing 1-1/4" - 100 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0426	807-DC2	1	box Bridgeport 90° angle connector 1" - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/6/2009	0426	407	1	box Bridgeport squeeze connector 1/2" - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0427		20	5" end bells	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0428		4	5" rigid PVC female adapter	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0429		1	4" Sch 40 45° radius PVC elbow	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0429		3	4" Sch 40 22 1/2 - 30° PVC elbow	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0429		2	3" sch 40 90° rigid PVC elbow	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0430		26	3" PVC misc. conduit fitting (example - Carlon E942L)	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0430		1	4" PVC conduit fitting	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0430		20	conduit bend 90° sch 40 rigid PVC 1-1/2 & 2" mixed (example - Kraloy 278T)	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0431		5	pounds of misc. zinc coated bolts, nuts and washers 1/4" - 1/2" (example JKR08096, DND08)	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0431		1	pound misc. screws, washers and bolts (example Nefco B-108-022)	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0431		0.8	pound duct seal "IDEAL"	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0431		7	tubes Mobil Polyrex EM Grease (100 gr. Cartridge)	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0431	KK4A36U-4N	1	box Burndy Universal Terminal - 1 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0431	WPCAS100	1	box Pass & Seymour Legrand Weatherproof multiuse gasket black	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0431	E943E	1	box Carlon Lamson & Sessions non-metallic sch 40 male terminal adapter 3/4" - 125 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0431		1	box Carlon non-metallic sch 40 couplings - 40 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0432		25	gang toggle 302 stainless (example Mulberry 93071)	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0432		11	gang toggle 302 stainless (example Mulberry 93071) - screws INCOMPLETE	3/10/2009	Basement Bay 2	BP-16



ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/7/2009	0432	CR20	9	Pass & Seymour Legrand duplex receptacle 20A 125V	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0432	5362I	3	Pass & Seymour Legrand duplex receptacle 20A 125V	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0432	2094	10	Pass & Seymour GFCI Duplex Receptacle trip indicator light 20A 125V	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0432		2	Cover plate stainless 4" x 4"	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0432		2	Cover plate stainless 3" x 3"	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0432	PS20AC4	9	Pass & Seymour four-way switch	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0432	2094	6	Pass & Seymour GFCI Duplex Receptacle trip indicator light 20A 125V	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0432		4	4" sq. raised cover for GFCI duplex receptacle	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0432		16	4" sq. raised cover for GFCI duplex receptacle (example - Hubbell RACO 902)	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0432		18	4" sq. raised cover for GFCI, duplex, etc. (misc)	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0433	1202CF	2	boxes Ramset Fanstener angle clips - 100 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0433	CPR2	6	Cooper Crouse Hinds 3/4" compression type connector	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0433	511	1	box Cooper Crouse Hinds one hole clamp 3/4" - 50 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0433	512	1	box Cooper Crouse Hinds one hole clamp 1" - 50 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0433	CB2	4	boxes Cooper Crouse Hinds clampback spacer 3/4" - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0433	H1035	1	box bushing for threaded conduit 1 1/2" - 10 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0433	H1035	4	bushing for threaded conduit 1 1/2"	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0433	465	5	boxes Cooper set screw type coupling2" - 5 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0433	GL510	1	box Cooper lazy lug grounding bushing - set screw type 4" - 1 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0433		1	box conduit nipple galvanized 1/2" x CL (25 ct each)	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0433	708	3	boxes Sepco conduit locknuts (steel) 1" - 50 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0433	1692	1	box Bridgeport knockout seal 3/4" - 100 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0433	103	1	box Bridgeport conduit locknut 1" - 100 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0433	707	60	Sepco conduit locknuts 3/4"	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0433	NEER L-500-D	2	boxes EGS die cast locknuts 1 1/2" - 40 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0434		26	4" sq cover raise for duplex receptacle (example Hubbell Raco 1-907 universal no. 52-2D)	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0434	5133564	5	Cantex Access Type T PVC conduit 3/4"	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0434	1105	13	Bridgeport 4" conduit locknuts zinc coated steel	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0434	1104-DC	1	box Bridgeport conduit nipple diecast zinc 1" - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0434	1061	1	box Bridgeport reducing washer 1/2" - 3/4" - 250 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0434	410-DC2	2	boxes Bridgeport 1" squeeze connectors - 10 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0434	E989CN-CAR	1	box Carlon single gang cover - 12 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0434		19	Steel City CBA Galvanized steel adapter plate	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0434	421	11	Cooper Crouse Hinds set screw type combination coupling	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0434	821DC	1	Crouse Hinds 90° pull elbow 3/4" - 5 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0434	ST-8	1	Myers zinc 3" basic Hup - 2 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0434	711	1	box Sepco conduit locknuts 2" steel - 50 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0435 - 0438	CJ6	8	boxes Caddy Erico Colored jim cable support - 100 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0435 - 0438	CD3B	14	Caddy Erico conduit hanger 1-1/4"	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0435 - 0438	RB516	11	boxes Caddy Erico Outlet box mounting bracket 16" stud spacing - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0435 - 0438	RB516	1	box Caddy Erico outlet box mounting bracket 16" stud spacing - 15 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0435 - 0438	H6	10	boxes Caddy Erico quick mount box support - 50 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0435 - 0438	H4	4	boxes Caddy Erico quick mount box support - 100 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0435 - 0438	MEB1	3	boxes Caddy Erico mounting bracket for electrical box - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0435 - 0438		43	1 1/2" conduit PVC coupling	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0435 - 0438		2	boxes 1 1/2" conduit PVC couplings - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0435 - 0438		9	1-1/2" conduit PVC coupling female terminal adapter	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0435 - 0438	E943H	39	Carlon non-metallic sch 40 male terminal adapter 1-1/2"	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0435 - 0438	TA35	16	Scepter 2" PVC Terminal adapters	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0435 - 0438	1019	4	boxes Sepco EMT compression coupling concrete tight zinc diecast 1-1/4" - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0435 - 0438	7400S	2	boxes EGS EMT connector gland compression type 4" - 5 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0435 - 0438	6150S	1	box EGS EMT coupling gland compression type 1-1/2" - 25 ct each	3/10/2009	Basement Bay 2	BP-16



**Buley Library Project
Inventory Sheet**

ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/9/2009	0435 - 0438	NEER TC-620	5	EGS compression type EMT coupling 4"	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0435 - 0438	NEER TC-620	15	boxes EGS compression type EMT coupling - 6 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0435 - 0438	112STL	1	box 1 1/2" coupling compression type steel EMT steel nut & body concrete tight - 20 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0435 - 0438	7075S	1	box EGS EMT connector gland compression type zinc plated 3/4" - 250 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0435 - 0438	6689	3	boxes Topaz EMT rigid IMC couplings compression type steel 3" - 6 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0435 - 0438	NEER TC-612	5	boxes EGS compression type EMT coupling 3/4" - 250 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442	100STL	1	box Culus comp connecting 1" connector - 100 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442	C-106	4	boxes Kindorf 3/4" straps - 100 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442	7031	3	boxes Superstrut pip clamp steel - 100 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442	B2212 PAZN	2	boxes Cooper B-line pipe clamp 1 1/2" - 50 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442	B2213 PAZN	1	box Cooper B-line pipe clamp - 50 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442	B2213 ZN(2)	1	box Cooper B-line pipe clamp - 50 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442	PS1300	1	box Powerstrut ZEG pipe clamp - 30 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442	7023	1	box Superstrut straps - 50 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442		1	4" EMT metallic coupler, 1 ft long	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442		8	2" coupler	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442		1	metallic 90° coupler	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442		3	1" metallic flexible tube approx. 12' long - conduits (greenfield)	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442		1	1/2" metallic flexible tube approx 12' long - conduits (greenfield)	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442		1	Scaltite 1" plastic conduit, 12' length	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442		2	Scaltite 1/2" plastic conduit, 12' length	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442	5133824	1	box Cantex 3/4" 90° elbow - 15 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442	5140044	1	box Cantex 3/4" female adapters - 45 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442	E940E	1	box 3/4" non metallic sch 40 coupling - 100 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442	5140104	1	box Cantex terminal adapters - 125 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442	LR24719	1	box Milne - 300 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442	TWB-54	10	bags Bridgeport EMT bushings - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442	EMT 50	1	bag 1/2" insulated bushing - 40 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442		6	4" white bushing	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442	S60-DC2	4	boxes Bridgeport cable connectors - 250 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442	C270A	7	boxes Sepco straight squeeze connectors - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442	C270A	1	box Sepco straight squeeze connectors - 250 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442	C270A	1	box Sepco duplex single screw clamp - 250 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442	185-840	2	Venture lighting bulbs	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442	PLT 32W4	2	Phillips 4 pin bulbs	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442		2	boxes GE Roline 500 bulbs - 11 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442	500T3Q/CL	1	box Sylvania halogen bulbs - 16 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442	MHI75/U/M	1	Phillips metal halide	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442	F418	1	Sylvania lightbulb	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442	BC250T3Q/CL	2	Phillips halogen lamp	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442	18275	2	boxes GE lamps - 12 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442	F40CW/RS/EW/ALTO	1	box strip lamps - 13 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442	1017	6	boxes Sepco 3/4" EMT compression coupling - 250 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442	1017	1	box Sepco 3/4" EMT compression coupling - 100 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442	6615	1	box Cooper 3/4" compression coupling - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442	4T124	1	box Caddy Erico rod hanger - 100 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442	4T158	1	box Caddy Erico rod hanger clamp - 100 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442		3	boxes Caddy Erico BC Beam clamp - 100 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442	2600	1	box BC Beam clamp 25 EG - 100 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442	951	1	box Bridgeport insulator support - 12 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442	953	1	box Bridgeport insulator support - 11 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0439 - 0442	FBO 31/841	1	box Sylvania bulbs - 15 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	RL12	1	box Red head concrete anchors - 50 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	460-869924-01	1	box PVC conduit clamp - 80 ct each	3/10/2009	Basement Bay 2	BP-16



**Buley Library Project
Inventory Sheet**

ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/9/2009	0443 - 0445	B2017ZN (4RGD)	2	boxes B-line zinc plated conduit clamps - 40 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	1013	2	boxes Sepco EMT compression connector 1-1/4" - 100 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	1013	5	boxes Sepco compression connector 1-1/4" - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	TC-604	3	boxes Neer zinc diecast compression EMT connector 1-1/4" - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	TC-606	1	box Neer zinc diecast compression EMT connector 2" - 10 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	TC-606	8	Neer zinc diecast compression EMT connector 2"	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	812	1	box Bridgeport 90° angle connector 3" - 4 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	812-1	2	box Bridgeport 90° angle connector size 3 - 1 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	418-DC2	3	box Bridgeport squeeze connector 3" - 5 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	418-DC2	2	Bridgeport squeeze connector 3"	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	416-DC2	1	box Bridgeport squeeze connector 2" - 10 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	810-1	3	boxes Bridgeport 90° angle connector 2" - 1 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	408	1	box Bridgeport squeeze connector 3/4" - 5 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	C36T	1	box Bridgeport 90° angle connector 3/4" - 10 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	24-34	1	box Oz-Gedney straight squeeze connector 3/4" - 18 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	E943F	1	box Carlon non-metallic sch 40 male terminal adaptor 1" - 50 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	E943F	1	box Carlon non-metallic sch 40 male terminal adaptor 1" - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	FA10	1	box Kraloy 1" female adapter - 35 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445		1	box 1" PVC 90°, 45° - 40 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445		1	box 1-1/4" female adapter - 15 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	E940G	1	box Carlon nonmetallic sch 40 coupling 1-1/4" - 30 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445		1	box Kraloy 1-1/4" terminal adapter - 10 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	E940F	1	box Carlon non metallic sch 40 coupling 1" - 40 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	UA9AG	1	box Carlon non metallic sch 40 90° elbow - 12 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	304B2	1	box Caddy cable and pipe protection - 80 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	6MATA	3	box Caddy acoustical T bar clip - 100 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	4H58	1	box Caddy flange clamps - 80 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	BC812M	1	box Caddy beam clamp - 80 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	812M	1	box Caddy combination conduit clip - 128 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	812M24SM	1	box Caddy combination conduit hanger - 70 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	812M24	1	box Caddy combination conduit hanger - 100 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	812M24	1	box Caddy combination conduit hanger - 60 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	16M	1	box Caddy conduit clip - 90 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	16M24	1	box Caddy combination conduit hanger - 90 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	CD2B	1	box Caddy conduit hanger w/bolt attached - 50 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	KX	4	boxes Caddy KXKON clip - 100 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	449	4	boxes Caddy snap clamps for flexible - 100 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	449	80	Caddy snap clamps for flexible	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	PCS2	1	box Caddy conduit clip EMT 1/2" and 3/4" - 80 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	PCS1	5	boxes Caddy MC & AC cable support - 100 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	EC3114 Z34	1	box Caddy electrical drop wire - 80 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	EC311	1	box Caddy electrical drop wire - 60 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0443 - 0445	EC311	1	box Caddy electrical drop wire - 90 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0446		1	roll 8AWMTW or THHN or THWN - 5000 ft (INCOMPLETE)	3/10/2009	North Wall - Auditorium	BP-16
3/9/2009	0446		1	roll corrugated tubing - 100 ft (INCOMPLETE)	3/10/2009	North Wall - Auditorium	BP-16
3/9/2009	0446		1	roll 4AWG THWN-2 - 5000 ft (INCOMPLETE)	3/10/2009	North Wall - Auditorium	BP-16
3/9/2009	0446	12527005005	2	rolls American Insulated Wire Corp THHN 10AWG - 500 ft each	3/10/2009	North Wall - Auditorium	BP-16
3/9/2009	0446	106100406450	2	rolls Encore Wire 10AWG THHN strand yellow - 500 ft each	3/10/2009	North Wall - Auditorium	BP-16
3/9/2009	0446	12523005005	2	rolls American Insulated Wire Corp 10AWG THHN stranded green - 500 ft each	3/10/2009	North Wall - Auditorium	BP-16
3/9/2009	0446	106101801440	1	roll Encore wire 8AWG Black 500SP Strand copper THHN - 152.4m	3/10/2009	North Wall - Auditorium	BP-16
3/9/2009	0446		1	roll 6AWG type THHN 600V Type T90 Nylon - 1000 ft	3/10/2009	North Wall - Auditorium	BP-16
3/9/2009	0446	616425	1	roll Nexus 12 str blue THHN/THWN-2 MTW - 2500 ft	3/10/2009	North Wall - Auditorium	BP-16
3/9/2009	0446		1	roll 12AWG stranded copper THHN or THWN red strand - 2500 ft	3/10/2009	North Wall - Auditorium	BP-16
3/9/2009	0446	E148891-J	2	rolls Colonial Wire & Cable - 2500 ft each	3/10/2009	North Wall - Auditorium	BP-16



**Buley Library Project
Inventory Sheet**

ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/9/2009	0446		2	rolls 12-19/CU/THHN THHN-THWN MTW-M WM green VW-1 rated - 2500 ft each	3/10/2009	North Wall - Auditorium	BP-16
3/9/2009	0446	616409	2	rolls Nexus 12 strand wht, THHN/THWN-2/MTW - 2500 ft each	3/10/2009	North Wall - Auditorium	BP-16
3/9/2009	0447	1824	3	Hubbell 1" compression coupling unthreaded for rigid and IMC steel conduit	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0447		1	box Hubbell 1" compression coupling unthreaded for rigid and IMC steel conduit - 5 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0447	5320	2	boxes T&B Fittings 1" EMT steel couplings - 10 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0447	5323	1	box T&B Fittings 1" EMT insulated connectors - 10 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0447	TK-113	2	boxes T&B Fittings Steel City - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0447	6655	1	box Topaz EMT steel compression coupling 1-1/2" - 20 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0447	2904	1	box Hubbell 1" compression connector for Steel EMT - 18 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0447	6605	1	box Crouse Hinds Compression coupling for EMT 1/2" - 50 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0447	MCS100	20	Caddy support bracket #12/14 AC/MC cable	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0447	MCS100	1	box Caddy support bracket #12/14 AC/MC cable - 50 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0447	TSGB16	2	boxes Caddy screw gun box bracket - 50 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0447	TSGB16	16	Caddy screw gun box bracket	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0447	SGB16A	18	Caddy screw gun bracket 16" stub spacing	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0447	SGB16A	4	boxes Caddy screw gun bracket 16" stub spacing - 50 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0447	078006	1	box Kraloy 2" coupling - 30 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0447	078003	40	Kraloy 1" coupling	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0447	512	1	box Caddy snap-on support for electrical box - 50 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0447	1823	2	boxes Hubbell 3/4" compression coupling unthreaded for rigid IMC steel conduit - 10 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0447	TC113A	1	box T&B Fittings St1" compression connector for EMT - 14 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0447	PS-619-1/2-E6	3	boxes Nefco square washers 9/16 - 1/2" - 100 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0447	AA8030	1	roll Alcan S1-AWG cable (incomplete)	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0447		1	roll greenfield	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	RE325	1	box Killark 1" -3/4" steel reducer - 50 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	5262	3	boxes T&B Fittings 1/2" sealing ring - 50 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	5303	2	boxes T&B fittings - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	SR101	1	box Steel City 1/2" neoprene sealing O ring - 50 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	SR102	1	box Steel City 3/4" neoprene sealing O ring - 50 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452		18	1" sealing ring	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452		18	plastic 1/2" single gang extension ring	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	893	3	boxes Hubbell ceiling box cover - 50 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452		1	box adapter plate - 30 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	E9811EN	1	box Carlon non metallic molded box w/mounting 3/4" Type FDC - 12 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452		11	Carlon non metallic molded box w/mounting 3/4" Type FDC	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	NS 664	2	boxes Carlon circuit safe enclosure w/screw fastened cover 6x6x4 - 1 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452		3	1-1/2" pipe strap f/EMT steel galvanized	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	921-S	1	box Bridgeport one hole pipe strap f/EMT 3/4" - 30 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452		1	box EGS NEER 1 hole plated click on strap 1/2" - 50 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	902-S	1	box Bridgeport one hole pipe strap 3/4" - 20 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452		3	boxes EGS NEER 1 hole plated stamped steel click on strap 1" - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	922-S	3	boxes Bridgeport pipe strap one hole f/EMT 1" - 50 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	1455	4	boxes Sepco one hole strap snap on type 1-1/4" - 50 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	1455	1	box Sepco EMT one hole strap snap on type 1-1/4" - 100 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	925-S	1	box Bridgeport pipe strap one hole f/EMT 2" - 50 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	2139S	1	box Sepco two hole strap snap on type for rigid conduit 3" - 20 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	910-S	1	box Bridgeport pipe strap one hole f/EMT 4" - 10 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	21485	4	boxes Sepco two hole strap snap on type 4" - 10 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	21485	3	Sepco two hole strap snap on type 4"	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	2110	1	box Bridgeport conduit hanger 3/4" - 100 ct each	3/10/2009	Basement Bay 2	BP-16



ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/7/2009	0448 - 0452	CD2B	1	box Caddy conduit hanger for EMT or rigid 1" - 100 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452		8	3" one hole straps steel galvanized	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452		20	2" conduit hanger	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452		24	1-1/2" conduit hanger	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452		6	3" conduit hanger	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	CD9B	1	Caddy 4" conduit hanger	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	CD8B	9	Caddy 3-1/2" conduit hanger	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	773	5	boxes Hubbell mud ring 4"x4" raised 3/4" - 50 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	773	1	box Hubbell mud ring 4"x4" raised 3/4" - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452		47	4" square mud rings raised 5/8"	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	52C15	1	box Steel City 4" square device ring raised 1" - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	775	2	boxes Hubbell mud ring 4"x4" raised 1-1/4" - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	775	12	Hubbell mud ring 4"x4" raised 1-1/4"	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	785	4	boxes Hubbell mud ring 4"x4" raised 1-1/2" - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	785	7	Hubbell mud ring 4"x4" raised 1-1/2"	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	786	2	boxes Hubbell mud ring 4"x4" raised 2" - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	786	18	Hubbell mud ring 4"x4" raised 2"	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	52C18518-25	1	box Steel City 4" square device ring - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	779	2	boxes Hubbell Mud ring 4" x 4" raised 3/4" - 50 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	779	30	Hubbell Mud ring 4" x 4" raised 3/4"	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	781	2	boxes Hubbell Mud ring 4"x4", raised 1-1/4" - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	795	4	boxes Hubbell Mud ring 4"x4", raised 1-1/2" - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	795	14	Hubbell Mud ring 4"x4", raised 1-1/2"	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	796	2	boxes Hubbell Mud ring 4"x4", raised 2" - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	838	3	boxes Hubbell Mud ring 4"x4", raised 3/4" - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	838	19	Hubbell Mud ring 4"x4", raised 3/4"	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452		2	4" mud ring, raised 1"	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	842	11	boxes Hubbell Mud ring 4-11/16"x4-11/16", raised 1-1/4" - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452		13	Hubbell Mud ring 4-11/16"x4-11/16", raised 1-1/4"	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	818	20	Hubbell Mud ring 4-11/16"x4-11/16", raised 5/8"	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	898	2	boxes Hubbell Mud ring 4-11/16"x4-11/16", raised 1-1/2" - 20 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	899	2	boxes Hubbell Mud ring 4-11/16"x4-11/16", raised 2" - 20 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	72C512	2	boxes Steel City Galvanized tile wall - 4-11/16"sq. 2" high - 20 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	72C512	4	Steel City Galvanized tile wall - 4-11/16"sq. 2" high	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	820	3	boxes Hubbell Mud ring 4-11/16" x 4-11/16" raised 1-1/4" - 25 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	885	1	box Hubbell 4-11/16" square cover - 20 ct each	3/10/2009	Basement Bay 2	BP-16
3/7/2009	0448 - 0452	11376	2	boxes Mulberry 1-" 16" tile cover 2" raised - 20 ct each	3/10/2009	Basement Bay 2	BP-16
3/9/2009	0453 - 0456	5385-0	17	Bell Outdoor Deep Single Gang Box	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	5320-0	8	Bell Outdoor Single Gang Box	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	5406-0	12	Bell Outdoor Box Extension	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	5101-0	10	Bell Outdoor Single Gang Device Cover	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	TP472	4	boxes Cooper Outlet Box Cover - 50 ct each	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	TP568	3	boxes Cooper 4-11/16" Square cover - 25 ct each	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	ST19	15	Sepeco 4" plastic insulating bushings	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	328	35	Bridgeport 3" plastic bushing	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	325	50	Bridgeport 1-1/2" plastic bushing	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	ST15	40	Sepeco 2" Plastic Insulating bushing	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16



ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/9/2009	0453 - 0456		12	2" conduit locknuts	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	IBC-300LS20AC	7	OZ Gedney 3" set screw insulated grounding bushing	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	IBC-200LS20AC	17	OZ Gedney 2" set screw insulated grounding bushing	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456		6	3" sealing lock nuts	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456		25	4" conduit lock nuts	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	GLS3	35	Crouse Hinds 1" threadless bond bushing	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	C23C	80	Sepco 1/2" metal bushing	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	1203	50	Hubbell 3/4" sealing locknut	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	1204	50	Hubbell 1" sealing locknut	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456		50	1-1/2" locknuts	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	101-S	1	box Bridgeport 1/2" conduit locknuts - 100 ct each	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	145	1	box Bridgeport 1-1/2" sealing locknut - 25 ct each	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	108	1	box Bridgeport 3" conduit locknut - 35 ct each	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456		25	3" conduit locknut	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456		35	reducing bushings - various sizes 1/2" to 2" (example CR15)	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456		20	1" plastic coated metal coupling	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	1112C	1	Sepco 2" set screw connector	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456		2	Sepco 1" set screw connector	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456		10	Hoffman Type 4 hole seal	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	722	1	box Hubbell 4" round ceiling box cover - 50 ct each	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	890	1	box Hubbell 4-1/2" concrete ring ceiling box cover -25 ct each	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	892	1	box Hubbell Flat blank 4-1/2" ceiling box cover - 25 ct each	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	2920NM	5	T&B 1/2" NPT	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456		20	Crouse Hinds lugs for bushings - various sizes	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	LT43-E-NEW	12	Carlton 3/4" non-metallic straight fitting	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456		40	3/4" long metal nuts	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456		25	90° non-metallic fitting	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	SCC-75	9	Appleton 3/4" steel bolt-on coupling	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16



ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/9/2009	0453 - 0456		1	1-1/2" steel bolt-on coupling	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	1353	5	combo coupling 3/4 RG	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	30290	40	1/2" plug	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	30292	15	3/4" plug	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456		15	3/4" pipe plug	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	E98SSCN-CAR	6	Carlton switch cover	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	E980GDRN-CAR	1		3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456		5	misc. lugs	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456		7	3-1/2" metal plate w/raised round hole	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456		2	3-1/2" metal plate w/outlet hole	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456		6	3" metal plate w/rect hole	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	111	1	Sloan Flushometer bypass diaphragm (INCOMPLETE)	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	5173-0	48	Bell Outdoor Single Gang Blank Cover	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	709	15	Hubbell Low Voltage partition	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	708	2	boxes Hubbell Low Voltage partition - 25 ct each	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	707RAC	20	Hubbell Low Voltage partition	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	706	40	Hubbell Low Voltage partition	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	187	11	Hubbell Extension Ring 4x4x1-1/2"	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	187	1	box Hubbell Extension Ring 4x4x1-1/2" - 25 ct each	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	192	16	Hubbell Square Box 4x4x1-1/2"	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	192	2	boxes Hubbell Square Box 4x4x1-1/2" - 50 ct each	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	232	4	boxes Hubbell Square Box 4x4x2-1/8" - 25 ct each	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	232	18	Hubbell Square Box 4x4x2-1/8"	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	233	19	Hubbell Square Box 4x4x2-1/8"	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456		9	Gray bar Handy boxes and covers	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	52151X	2	boxes Thomas & Betts Galvanized Steel outlet boxes - 50 ct each	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	52151X	39	Thomas & Betts Galvanized Steel outlet boxes	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	213	3	boxes Hubbell Square Box 4x4x1-1/2" - 50 ct each	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16



**Buley Library Project
Inventory Sheet**

ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/9/2009	0453 - 0456	TP422	43	Crouse Hinds 4" square extension ring	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	130	1	box Hubbell ceiling box ectagon extension ring - 50 ct each	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0453 - 0456	203	1	box Hubbell square box 4x4x1-1/2" - 50 ct each	3/10/2009	Basement Bay 2 (0453) and Bay 7 (0454-0456)	BP-16
3/9/2009	0457 - 0460	250	5	boxes Hubbell square box extension ring 4-11/16x4-11/16x1-1/2" - 25 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	262	16	Hubbell square box extension ring 4-11/16"x4-11/16"x2-1/8"	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	258	5	boxes Hubbell square box 4-11/16"x4-11/16"x2-1/8" - 25 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	246	1	box Hubbell square box 4-11/16"x4-11/16"x1-1/2" - 25 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	247	20	Hubbell square box 4-11/16"x4-11/16"x1-1/2"	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	TP563	22	Crouse Hinds 4-11/16" square outlet box	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	TP558	2	boxes Crouse Hinds 4-11/16" square box - 25 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	00338762	2	boxes Hilti X-EMTC ZF22P8TH 3/4" - 100 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	00335120	25	Hilti X-EMTC ZF22P8TH 3/8"	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	078006	20	Kraloy 2" PVC coupling	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	00335120	7	boxes Hilti X-EMTC ZF22P8TH 3/8" - 100 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	TGN3321	1	GE General Duty 30 amp Safety Switch	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	THN3361	1	GE Heavy Duty 30 amp Safety Switch	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	3033600140	2	boxes Wheatland Galvanized coupling - 12 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460		15	2" rigid coupling	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460		11	1-1/4" rigid coupling	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460		30	1" rigid coupling	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460		50	1/2" rigid coupling	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460		19	3/4" rigid coupling	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	0316	28	Shamrock 1" rigid galvanized coupling	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	B1-B	7	bags Buchanan B Cap connectors - 500 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	73B	175	Ideal Wire nut wire connector	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	B2-B	2	bags Buchanan B Cap wire connectors - 500 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	TC-503	1	EGS Neer 1" die cast set screw EMT connector - 20 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	SC125	2	boxes AFC Fittings 1-1/4" EMT Set Screw Connector - 10 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	C34	6	Sepco 3" straight squeeze connector	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	5400S	3	EGS 4" EMT couplings	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	4400S	1	box EGS 4" EMT coupling set screw type - 5 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	642S	2	boxes Topaz EMT coupling set screw type 3/4" - 250 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	644S	3	boxes Topaz EMT coupling set screw type 1-1/4" - 25 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	644S	4	Topaz EMT coupling set screw type 1-1/4"	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460		250	1" lock nuts	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460		12	red plastic bushing	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460		25	various 1-1/2" nust and bolts	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460		25	3/4" bonding bushings	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	13CS	1	box Sepco conduit hanger 1-1/4" - 100 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460		50	unistrut nut	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460		20	round washers	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460		12	1-1/2" threaded reducer	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	703	20	Superstrut EMT IMC rigid	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460		250	Carlton non-metallic flat washers - 3-4" - 1-1/2"	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460		25	1/2" connector	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	72B	75	Ideal Wire nut wire connector	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	JB664	1	Kraloy 6x6x4 JB	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460		30	sealing lock nuts - 1"	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	SCC-100	7	EGS 1" steel colt-on coupling	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460		30	1/2" chase nippers	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460		75	1-18" rod coupling nuts	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	HC0616	1	box Hex cap screws 3/8" x 1" - 100 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	FWC0524	75	fender washers 5/16" - 1-1/2"	3/10/2009	Basement Bay 7	BP-16



**Buley Library Project
Inventory Sheet**

ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/9/2009	0457 - 0460	A102-037	25	split lock washers 1/2" medium collar	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	A110-025	1	box fender washer zinc 3/8" x 1-1/4" - 100 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	A108-166	25	hex bolts 3/8-16x1	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	A100-001	1	hex finished nut 1/4-20 - 100 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	LWC16	2	boxes Colony 5/16" split lock washer - 100 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	FHN05	2	boxes Colony 5/16" finished hex nuts - 100 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460		4	hex bolts 1/4"-20 x 3/4"	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460		100	fender washer 1"	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460		3	2" grounding bushings	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460		10	unistrut nut	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460		15	metal & plastic switchplates/outlet covers	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460		10	Siemens breakers 20 amp	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460		12	3/4" and 1" running threads	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	F88-GUC	2	Hoffman Wireway gutter fitting	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	CPHV17A	1	GE Switch/breaker	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	CPHV17C	1	GE Switch/breaker	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	1492-100Y	2	Allen Bradley wire torque	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	TGC2	2	Equipment ground kit	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	5790B	1	Wire Mold Stl Armored Cable conn. Galvanized	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460	E30640	1	3/4" LB Condulet	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460		1	Crouse Hinds 1-1/2" LB Condulet	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0457 - 0460		25	Misc conduit fittings	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465	259	7	boxes Hubbell square box - 25 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465	259	14	Hubbel square box	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465		1	box 4" octagon box extension - 80 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465	167	1	box Hubbell ceiling box - 50 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465	153	1	box Hubbell ceiling box - 20 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465	146	1	box Hubbell ceiling box - 15 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465		1	container IDEAL aguagel lubricant - 19 liter each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465	695	1	box Hubbell switch box - 7 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465	GW135G	1	box Steel City Masonry Box - 18 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465	CXWOW	1	box Steel City 3" x 2" switch box	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465	965	1	box Hubbell Masonry box - 1 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465	4422	3	Shamrock 3" x 8" galvanized nipple	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465	4560	2	box Shamrock 4" galvanized nipple - 10 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465	4224	1	box Shamrock 2" galvanized nipple - 14 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465		9	2" x 4" galvanized nipple	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465		2	2" x 6" plastic coated nipple	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465		1	2" x 1' galvanized nipple	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465		1	4" galvanized nipple	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465	4422	1	box Shamrock 3" x 8" galvanized nipple - 5 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465		1	4" x 2' galvanized nipple	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465		2	3" x 1' galvanized nipple	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465		6	Unistrut section 8' x 1-1/2 x 1-1/2 steel conduit	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465		4	Unistrut section 8' x 1-1/2 x 1-1/2 steel conduit	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465		13	1-1/2" x 6" nipple	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465		2	1" galvanized nipple	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465	3955	1	box Shamrock 1" galvanized nipple - 25 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465	3975	1	box Shamrock 1" galvanized nipple - 24 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465	3XAS	1	box Conduit pipe product - 25 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465		3	90° rigid conduit elbows 2" metallic	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465		2	90° rigid conduit elbows 1-1/2" metallic	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465		1	box 90° rigid conduit elbows 1-1/4" metallic - 10 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465		1	box 90° rigid conduit elbows 1" metallic - 24 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465	HH-8549	11	Robroy 3/4 x 10-3/4" elbow	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465	E9811EN	1	box Carlon non metallic molded box - 6 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465	E9811EN	1	box Carlon 3/4" molded box - 12 ct each	3/10/2009	Basement Bay 7	BP-16



**Buley Library Project
Inventory Sheet**

ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/9/2009	0461 - 0465		6	steel angle brackets 1-1/2'	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465		6	steel angle brackets 2'	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465		1	box steel brackets - 12 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465		1	box 2 x 3 unistrut L brackets - 7 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465		1	box L x S unistrut straight brackets - 10 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465		1	box 4" unistrut T brackets - 12 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465		1	box 4" unistrut L brackets - 12 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465		1	box unistrut L brackets 4" x 1" - 20 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465		2	access door 1-1/2" x 1/2"	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465		6	unistrut flange brackets 6"	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465		1	box Commercial products on hole clamp 5" - 10 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465		1	box 4" L brackets - 2 ct each	3/10/2009	Basement Bay 7	BP-16
3/9/2009	0461 - 0465		1	box Circular flange 4" - 5 ct each	3/10/2009	Basement Bay 7	BP-16
3/10/2009	0800	25-DTC-4	72	Telepower Pole - 11" wiremold (1 carpet/tile gripperpad, 1 ent end plate, 2 trimplates, 1 pole mounting bracket)		Basement Bay 10	BP-16
3/10/2009	0800	11578531	2	Cooper lighting		Basement Bay 10	BP-16
3/10/2009	0800	06771976N	16	boxes SSD sensor base - 18 ct each		Basement Bay 10	BP-16
3/10/2009	0800	4098-9714	11	smoke detector ULC		Basement Bay 10	BP-16
3/10/2009	0800	0626612	17	boxes 4903 True Alert speakers 9305 s/v assy red 15 cd and 75 cd - 8 ct each		Basement Bay 10	BP-16
3/10/2009	0800	074244	10	boxes photo sensor SSD - 30 ct each		Basement Bay 10	BP-16
3/10/2009	0800	4100-9611	3	intercom system audio control system		Basement Bay 10	BP-16
3/10/2009	0800	GV070MPMT SB8	17	Ballast Assembly - 70 watts min 90°C supply conductors		Basement Bay 10	BP-16
3/10/2009	0800		1	Red 14 AWG THHN wire spool (1/2 spool only)		Middle of auditorium	BP-16
3/10/2009	0800		1	spool Red 14 AWG THHN wire spool		Middle of auditorium	BP-16
3/10/2009	0800		2	spool Black 14 AWG THHN wire spool		Middle of auditorium	BP-16
3/10/2009	0800	3570109	1	spool Brown 10 AWG stranded 2500 LF		Middle of auditorium	BP-16
3/10/2009	0800	G898	2	spools orange 12 AWG THHN wire spool		Middle of auditorium	BP-16
3/10/2009	0800		1	spool yellow 12 AWG THHN wire spool		Middle of auditorium	BP-16
3/10/2009	0800		2	spools blue 12 AWG THHN wire spool		Middle of auditorium	BP-16
3/10/2009	0800		1	spool Blue 12 AWG stranded wire spool		Middle of auditorium	BP-16
3/11/2009	0800		25	3-1/2" x 9" Trimpes bowl black		Basement Bay 10	BP-16
3/11/2009	0800	TC4ATCGY	25	flush pole through assembly		Basement Bay 10	BP-16
3/11/2009	0800	1287	3	boxes suspension system bar ad" (male and female) vantage lighting hanger set - 125 ct each		Basement Bay 10	BP-16
3/11/2009	0800	1200	22	Sylvania HID lamps - 70W		Basement Bay 10	BP-16
3/11/2009	0800	24195243	1	electric panel 1' x 3'		Basement Bay 10	BP-16
3/11/2009	0800	4100-9611 PID#	1	command center		Basement Bay 10	BP-16
3/11/2009	0800		80	floor box covers		Basement Bay 10	BP-16
3/11/2009	0800	LA5063070AM	2	Halo Architectural track		Basement Bay 10	BP-16
3/11/2009	0800	GV85B	16	Outdoor pedestal glass lights		Basement Bay 6	BP-16
3/11/2009	0800	0630763	1	Addr Pull stay Assembly		Basement Bay 6	BP-16
3/11/2009	0800		2	Audio system - intercom system		Basement Bay 10	BP-16
3/11/2009	0800		5	Cabling for Simplex audio/intercom/fire system		Basement Bay 10	BP-16
3/11/2009	0800	742-879	3	2 bay box glass door - beige		Basement Bay 10	BP-16
3/11/2009	0800	1704BG0T01	54	rolls MC Tuff Metal clad cable 12-4 blue - 1000 ft each		Auditorium near ramp	BP-16
3/11/2009	0800	E194201	2	rolls THHN or THWN stranded copper - yellow -2500 ft each		Auditorium near ramp	BP-16
3/11/2009	0800		3 1/2	rolls No 14 THHN or THWN red - 500 ft each		Auditorium near ramp	BP-16
3/11/2009	0800		1	roll No 14 THHN or THWN red - 250 ft each		Auditorium near ramp	BP-16
3/11/2009	0800		3	rolls AWG stranded copper THHN brown 12 AWG - 2500 ft each		Auditorium near ramp	BP-16
3/11/2009	0800		3	rolls 12 AWG THHN black - 2500 ft each		Auditorium near ramp	BP-16
3/11/2009	0800	85115	1	roll 12 AWG stranded gray - 2500 ft each		Middle of auditorium	BP-16
3/11/2009	0800	6-19STR	1	6-19 STR black machine tool wire - 500 ft each		Middle of auditorium	BP-16
3/10/2009	2051 - 2087		6	10' copper ground rods	3/12/2009	Basement Bay 8	BP-16
3/10/2009	3102, 3103, 3104	X1-7293	99	Boxes (15/box), Sylvania Octron Curvalume Fluorescent Rapid & Instant Start Medium B1PIN Lamps	3/10/2009	1st Floor Bay 2	BP-16



**Buley Library Project
Inventory Sheet**

ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/10/2009	3106, 3107, 3108, 3109, 3111	13555059, Mark G	71	Each, Metalux Cooper Lighting, 2' x 4' Parabolic Troffer Fluorescent Drop Ceiling Fixtures	3/10/2009	1st Floor Bay 2	BP-16
3/10/2009	3107, 3110	13554790, Mark B	6	Each, Metalux Cooper Lighting, 2' x 4' Parabolic Troffer Fluorescent Drop Ceiling Fixtures	3/10/2009	1st Floor Bay 2	BP-16
3/6/2009	A001	M-2DR	4	Wire multi flex service fitting	3/6/2009	East Wall - Auditorium	BP-16
3/6/2009	A001	3832075	2	Metalux 2, T8 Lamp 4 ft strip light	3/6/2009	East Wall - Auditorium	BP-16
3/6/2009	A001	3883705	3	Metalux light fixture 4' SS-232-UNV_EB81-4B	3/6/2009	East Wall - Auditorium	BP-16
3/6/2009	A001	plt-bc	3	Nelson heat tracing system	3/6/2009	East Wall - Auditorium	BP-16
3/6/2009	A001		2	lighting cap	3/6/2009	East Wall - Auditorium	BP-16
3/6/2009	A001	9995C2	4	Hand-out auto selector switch kit series B	3/6/2009	East Wall - Auditorium	BP-16
3/6/2009	A001	CR101X3	9	Locking attachment enclosure for CR101H+Y	3/6/2009	East Wall - Auditorium	BP-16
3/6/2009	A001	TVRM52	1	GE Digital test kit	3/6/2009	East Wall - Auditorium	BP-16
3/6/2009	A001	0617952	10	supervised IAM	3/6/2009	East Wall - Auditorium	BP-16
3/6/2009	A001	ASE12X12X6NK	1	Hoffman SCR-CUR pull box	3/6/2009	East Wall - Auditorium	BP-16
3/6/2009	A001	KLU-800	3	Cooper Bussman limitron fuse	3/6/2009	East Wall - Auditorium	BP-16
3/6/2009	A001	742-659	1	T/A power supply - domestic	3/6/2009	East Wall - Auditorium	BP-16
3/6/2009	A001		900	zinc plated machine screw 6/32 1.5-2"	3/6/2009	East Wall - Auditorium	BP-16
3/6/2009	A001	LT8JT	1	spool Nelson parallel heat tracing - 340 ft	3/6/2009	East Wall - Auditorium	BP-16
3/6/2009	A001		5	pounds zinc washers 3/8"	3/6/2009	East Wall - Auditorium	BP-16
3/6/2009	A001		4	Rayntite single gang device cover	3/6/2009	East Wall - Auditorium	BP-16
3/6/2009	A001	120V ESR	2	Philips Tungsten halogen lamp 100Q/CL/DC	3/6/2009	East Wall - Auditorium	BP-16
3/6/2009	A001		8	Burndy wire range 2 #6 STR-300 KCML AL/CC	3/6/2009	East Wall - Auditorium	BP-16
3/6/2009	A001	0626598	1	4904-9350 V/O assembly red 15 CD	3/6/2009	East Wall - Auditorium	BP-16
3/6/2009	A001	TH4X325	2	Nelson heat tracing system	3/6/2009	East Wall - Auditorium	BP-16
3/6/2009	A001	0626612	3	True Alert red 75 DC S/V assembly	3/6/2009	East Wall - Auditorium	BP-16
3/6/2009	A001	0677197CN	27	SSD sensor base	3/6/2009	East Wall - Auditorium	BP-16
3/6/2009	A001	0743258	5	True Alert non-addressable multi candela notification 4906-9151M-CS/V wall N-A red	3/6/2009	East Wall - Auditorium	BP-16
3/6/2009	A001	018180	1	can Harvey's P-6 PVC cement for pipes and fittings - 32 fl. Oz.	3/6/2009	East Wall - Auditorium	BP-16
3/6/2009	A001		1	quart PVC solvent cement medium body	3/6/2009	East Wall - Auditorium	BP-16
3/6/2009	A001	7210413	1	quart Cantex clear fast dry cement	3/6/2009	East Wall - Auditorium	BP-16
3/6/2009	A001	Q1060	10	Hubbell 4 ort office white	3/6/2009	East Wall - Auditorium	BP-16
3/6/2009	A001		27	wire RC4 poke-thru series	3/6/2009	East Wall - Auditorium	BP-16
3/6/2009	A001	SS106	4	RC7 ff poke-thru series tek tone transformer	3/6/2009	East Wall - Auditorium	BP-16
3/6/2009	A001		7	Philips PL-T 42 watt 4 pin bulbs	3/6/2009	East Wall - Auditorium	BP-16
3/10/2009		H32624	4	A Series II panelboard Interior Type HV-45	Existing	Basement Bay 9	BP-16
3/9/2009		N/A	3	Boxes, ABB Fluorescent light bulbs	Existing	Basement Northeast Corner	BP-16
3/10/2009			15	cable connector 3/8"	Existing	Basement Bay 5	BP-16
3/10/2009		AB64B	4	series panelboard type 1 enclosure	Existing	Basement - near Bay 9, close to wall	BP-16
3/10/2009		AB55B	1	A Series II panelboard Box NEMA 1 type HVE15	Existing	Basement - near Bay 9, close to wall	BP-16
3/10/2009		AB49B	14	A Series II panelboard Box NEMA 1 LV15	Existing	Basement - near Bay 9, close to wall	BP-16
3/10/2009			6	4-1/2" bent pipe Al electrical 8' length	Existing	Basement - near Bay 9, close to wall	BP-16
3/10/2009			2	8' x length x 3-1/2" al straight electrical pipe	Existing	Basement - near Bay 9, close to wall	BP-16
3/10/2009		AF498D	15	panel doors for A Series II panelboard - 49"	Existing	Basement - near Bay 9, close to wall	BP-16
3/10/2009		AF558D	1	panel doors for A Series II panelboard - 55"	Existing	Basement - near Bay 9, close to wall	BP-16
3/10/2009		AF648D	3	64" panel doors for A Series panelboards	Existing	Basement Bay 9	BP-16
3/10/2009		AF768D	2	76" panel doors for A Series panelboards	Existing	Basement Bay 9	BP-16
3/10/2009		AQF3422ABX-AXTI	9	A Series II panelboard E-16	Existing	Basement Bay 9	BP-16
3/10/2009		ADF341DB	6	A Series II panelboard C-19	Existing	Basement Bay 9	BP-16
3/10/2009		A52EA42	2	Each, 4" dia Centex rigid, 20' long, PVC Conduit, Schedule 40	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-16
3/11/2009		B100-1025TL	4	Geist Manufacturing Inc., 10 outlet rackmount, box, 5ct/ each		1st floor Bay 3	BP-16
3/11/2009		VC76	8	Hubbell, Vert. cable organizer 7' rack, 1pc		1st floor Bay 3	BP-16
3/11/2009		6110 FTK 64WL	14	Nextspeed Category 6, 6110 Cross connect series CCE3		1st floor Bay 3	BP-16
3/11/2009			2	Tappan Wire & Cable Inc. P18CCSRG 6X4 White CMP/CL2P/CATVP 18/1C, Roll, 1000ft/ each		1st floor Bay 3	BP-16
3/11/2009			1	Ladder cable tray 6ft X 1ft X 15" hght		1st floor Bay 3	BP-16



ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/11/2009			40	Miscellaneous gang plates. Example: Infine plate 1 gang 4 port. Hubbell 1FP140W		1st floor Bay 3	BP-16
3/11/2009		110BLK100FTK5	1 box, 90% full	Hubbell, speedgain Category 5e 110 cross connect series series 100 pair field termination kit, 5 pair, 110 connecting blocks		1st floor Bay 3	BP-16
3/11/2009		SF1310	60	Hubbell, Snapping fitting office white.		1st floor Bay 3	BP-16
3/11/2009		FSPSCD6	2	Hubbell, 12 port 5 pack SC Duplex adapter panel, boxes		1st floor Bay 3	BP-16
3/11/2009		FP4BBK	8	Standard furn box plate 4 port black with label fields, each		1st floor Bay 3	BP-16
3/11/2009		0563-32-444 20 -PC	24	25100-110-M110PC breaker or junction box, box		1st floor Bay 3	BP-16
3/11/2009		FDC-2M	5	Hubbell Killark, duraloy Size 3/4 Ductile iron deep flush switch fitting, each		1st floor Bay 3	BP-16
3/11/2009		C27 form 7	2	Cooper Crouse Hinds, Condulet Size 3/4", box, 10 ct/each		1st floor Bay 3	BP-16
3/11/2009		DS185	2	Cooper Crouse Hinds Cover, each		1st floor Bay 3	BP-16
3/11/2009		FS2	21	Cooper Crouse Hinds, Single gang box, box, 5ct/box		1st floor Bay 3	BP-16
3/11/2009		FD2	13	Crouse hinds, Size 3/4", each		1st floor Bay 3	BP-16
3/11/2009		T50R2C2UL	25	Hellerman Tyton, Tie-wraps 8", bag, 110ct/bag		1st floor Bay 3	BP-16
3/11/2009		SI-4754	2	Senior Industries, distribution ring, bag, 25ct/bag		1st floor Bay 3	BP-16
3/11/2009			1 roll, 10" tall, 12" diam, 10%	Colonial, 14 AWG E1488973 MTW or THHN or THWN		1st floor Bay 3	BP-16
3/11/2009			3	Crouse hinds, Usat 1/2 FS1 3/4 FS2, each		1st floor Bay 3	BP-16
3/11/2009		FDS	1	Appleton, Unilet Type 3/4"		1st floor Bay 3	BP-16
3/11/2009			4	Unilets single gang (switch plate), each		1st floor Bay 3	BP-16
3/11/2009			9	Appleton, FS-FD Unilet, single gang device cover, vertical duplex, each		1st floor Bay 3	BP-16
3/11/2009		21	3	Crouse Hinds, 3/4" 127 condulet, pc		1st floor Bay 3	BP-16
3/11/2009			6	Bracket support 13" long 2" L section		1st floor Bay 3	BP-16
3/11/2009			12	Cover plate w/ gasket and screws PVC, pcs		1st floor Bay 3	BP-16
3/11/2009		B1-B	300	Buchanan, BCAP Connectors, pcs		1st floor Bay 3	BP-16
3/11/2009			300	Misc. machine screws, washers. Example: 10/32 x 1 1/4"		1st floor Bay 3	BP-16
3/11/2009			2	Square box 4" x 4" x 2"		1st floor Bay 3	BP-16
3/11/2009		06-4E00-4512-12	2	P-W Industries Inc., Aluminum Ladder 45 Deg 1ft wide (cable tray)		1st floor Bay 3	BP-16
3/11/2009		06-4E00-9012-12	2	P-W Industries Inc., Aluminum Ladder 90 Deg 1ft wide (cable tray)		1st floor Bay 3	BP-16
3/11/2009		64	235	Caddy Erico, Cable cats hanger 4", pcs		1st floor Bay 3	BP-16
3/11/2009		HXJ6GY25	12	Hubbell, Xcellerator, pack, 25ct/pack		1st floor Bay 3	BP-16
3/11/2009		32	1	Caddy Erico, Cable hanger, box, 60ct/box		1st floor Bay 3	BP-16
3/11/2009		HXJ6GN25	8	Hubbell, Xcellerator, pack, 25ct/pack		1st floor Bay 3	BP-16
3/11/2009		HC119MS3N	26	Hubbell, Next frame cable holder		1st floor Bay 3	BP-16
3/11/2009		P6484	15	Hubbell, 48 port patch panel, pcs		1st floor Bay 3	BP-16
3/11/2009		SFFX	1	Hubbell, Snap in connector, box, 25ct/box		1st floor Bay 3	BP-16
3/11/2009		P630S1G	2	Hubbell, SS Plate, box, 25ct/each		1st floor Bay 3	BP-16
3/11/2009		FCR3500PR6R	3	Hubbell, Premise Wiring 2u Fiber optic rack mount enclosure, box		1st floor Bay 3	BP-16
3/11/2009		FSPSC6	15	Hubbell, 3 rack adapter panel installed with 6sc simplex adapters, box		1st floor Bay 3	BP-16
3/11/2009		6110 FTK 64WL	4	Hubbell, Next speed Category 6 6110 Cross connect series 64 pair field termination kit CCE 3, box		1st floor Bay 3	BP-16
3/11/2009		6110 FTK 64WL	1	Hubbell, Next speed Category 6 6110 Cross connect series 64 pair field termination kit CCE 3, box, 50% full		1st floor Bay 3	BP-16
3/11/2009		HC119MS3N	15	Next frame horizontal cbl mtg pnl 1.75"Hx19"Wx3.5"D (communication circuit accessory), box		1st floor Bay 3	BP-16
3/11/2009		VT2-4DR-U	5	Metalux, 4' vaporite replacement lens, box, 1ct/box		1st floor Bay 3	BP-16
3/11/2009			1	Assorted nuts bolts screws cable hangers small items plating fittings, box, 300ct/each		1st floor Bay 3	BP-16
3/11/2009		FT40DL/835/RS	3	Sylvania, 40w bulbs		1st floor Bay 3	BP-16
3/11/2009		RDMS3/816x1	1	Colony, round head slot bolts 1" x 3/8", box, 80ct/box		1st floor Bay 3	BP-16
3/11/2009		RDCOMS14201	1	Colony, round head screws 1/4" x 1", box, 20ct/box		1st floor Bay 3	BP-16
3/11/2009			1	1/2" Flat washer Steel, box, 30pc/each		1st floor Bay 3	BP-16
3/11/2009		SNS11AS	102	Thomas & Betts LRC, Snap n seal connectors, pcs		1st floor Bay 3	BP-16
3/11/2009		FR5950 Type RK1	1	Dickopp, Lens CLR 5-55 3-9/16, box, 40ct/box		1st floor Bay 3	BP-16
3/11/2009		WRA3EE SL171-A2	1	Venture lighting, Halide lamp, box, 40ct/box		1st floor Bay 3	BP-16
3/11/2009		KV8400	1	HBKV Company, Steel U Section strips 2' x 1 1/2", box, 25 pair/box		1st floor Bay 3	BP-16
3/11/2009		302743-00 BKT	1	FIXT. NTG, Steel 2'x1 1/2" strips, tube, 24ct/tube		1st floor Bay 3	BP-16
3/11/2009		PL-L	9	Philips, 24W 35 4 pin bulbs, box, 7pc/box		1st floor Bay 3	BP-16



**Buley Library Project
Inventory Sheet**

ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/11/2009			4	Fisher Rierxe Sunrise technologies, Electro switch corp 04 Blue plastic round 3pin 2"x2"x2, pi		1st floor Bay 3	BP-16
3/11/2009			1	Lithonia, Upper visor only for KFL architectural floodlight, box, 1pc/box		1st floor Bay 3	BP-16
3/11/2009			1	The Austin Co, Plate/cover only Type 3x12 10"x10" Steel plate 8 drilled holes, pc		1st floor Bay 3	BP-16
3/11/2009		FT55DL/835	14	Sylvania,Dulux L 55W bulbs, pcs		1st floor Bay 3	BP-16
3/11/2009			50	Mason, 3" folding hook 2 bolts steel, pc		1st floor Bay 3	BP-16
3/11/2009		D10S36	3	Sylvania, Fluorescent strip, pcs		1st floor Bay 3	BP-16
3/11/2009			1	30lb roll of wire ties - 400 ties		1st floor Bay 3	BP-16
3/11/2009		ZBP-BLED-S-R-BA	68	Exit sing faces High Lites, pcs		1st floor Bay 3	BP-16
3/11/2009		ZBP-BLED-S-R-BA	1	Exit sing faces High Lites, box, 80pc/box		1st floor Bay 3	BP-16
3/11/2009		23200229	4	Chatsworth Products Inc., box, 4pc/box		1st floor Bay 3	BP-16
3/11/2009			1	1/8 Steel cable, spool, 200ft/spool		1st floor Bay 3	BP-16
3/11/2009			8	1"x3"x3" wall boxes, pcs		1st floor Bay 3	BP-16
3/11/2009			40	Clamps 1" - 2", pcs		1st floor Bay 3	BP-16
3/11/2009			20	Circular seel connectors 3/4", pcs		1st floor Bay 3	BP-16
3/11/2009			1	Ferrule 1/8", box, 20pcs/box		1st floor Bay 3	BP-16
3/11/2009			1	Extruded polycarbonate sheet 1 1/2'x1'		1st floor Bay 3	BP-16
3/11/2009			1	Colony, Steel Cable 1/16 7x7 GAC IMP, spool, 500ft/spool		1st floor Bay 3	BP-16
3/11/2009		7000427	1	Campbell Cooper, 1/8" Cable Zinc Coated 7x7 construction, reel, 500ft/reel		1st floor Bay 3	BP-16
3/11/2009			60	Assorted bolts and washers, pcs		1st floor Bay 3	BP-16
3/11/2009		181050/CAT64	35	Caddy Erico, Cable Cat 5 Hanger 4"		1st floor Bay 3	BP-16
3/11/2009			40	Flat steel plates 3"x4"x1/8", pcs		1st floor Bay 3	BP-16
3/11/2009			80	1/4" nuts, pcs		1st floor Bay 3	BP-16
3/11/2009			80	1/4" bolts, pcs		1st floor Bay 3	BP-16
3/11/2009		09340	1	Powers, 16mm drop ins, box, 10pc/box		1st floor Bay 3	BP-16
3/11/2009			15	Bolts 1 1/2", pcs		1st floor Bay 3	BP-16
3/11/2009			30	Flat washers 1/2", pcs		1st floor Bay 3	BP-16
3/11/2009			30	Flat steel plates painted 1"x2", pcs		1st floor Bay 3	BP-16
3/11/2009			4	Painted steel trays 1"x4"x1'		1st floor Bay 3	BP-16
3/11/2009			1	3 SAC Security access control module, box, 1pc/box		1st floor Bay 3	BP-16
3/11/2009		27193-11	6	SPX Canada, Res surface box-1		1st floor Bay 3	BP-16
3/11/2009			5	SIGA-SB Peftor base		1st floor Bay 3	BP-16
3/11/2009			2	Phone wire extension 20', pc		1st floor Bay 3	BP-16
3/11/2009		V4050	3	Wiremold, Raceway, pcs		1st floor Bay 3	BP-16
3/11/2009			1	3 Modcom modem communicator, pc		1st floor Bay 3	BP-16
3/11/2009		Artima	2	Edison Price Lighting, Artima Max Lamp 100W 1x5", pcs		1st floor Bay 3	BP-16
3/11/2009		QMR 565B714G38	1	General Electric, QMR Switch MW100 1 1/2"x2", pc		1st floor Bay 3	BP-16
3/11/2009			3	Neon light box 3"x2"x1", pcs		1st floor Bay 3	BP-16
3/11/2009			1	Light fitting -circular - steel 1.5 x 1.5, pc		1st floor Bay 3	BP-16
3/11/2009			20	Steel brackets 1"x6", pcs		1st floor Bay 3	BP-16
3/11/2009		SCNNCP18210R	700	3' wire, feet		1st floor Bay 3	BP-16
3/11/2009			120	Coleman, Cable E100316 14AWG RG 11/U Type CL 2P/CATVP, feet		1st floor Bay 3	BP-16
3/11/2009			1	2" Liquidtight conduit Type LFMC, pc, 25 feet/pc		1st floor Bay 3	BP-16
3/11/2009			1	1" Liquidtight conduit, pc, 25 feet/pc		1st floor Bay 3	BP-16
3/11/2009		5210-12-00	2	3" flexible steel conduit, pc, 25 feet/pc		1st floor Bay 3	BP-16
3/11/2009			1	2" Flexible steel conduit, pc, 25 feet/pc		1st floor Bay 3	BP-16
3/11/2009			2	2" Liquidtight conduit, pc, 25 feet/pc		1st floor Bay 3	BP-16
3/11/2009			25	Wall plates metallic 3"x5", pcs		1st floor Bay 3	BP-16
3/12/2009		IFP110W	1	Hubbell, 1 gang 1 port ifinestation plate, box, 25ct/box		1st floor Bay 3	BP-16
3/12/2009		FCR350SP54R	1	Hubbell, Rack mount enclosure, pc		1st floor Bay 3	BP-16
3/12/2009		MCCCW519	1	Hubbell, Center weighted shelf, pc		1st floor Bay 3	BP-16
3/12/2009		45-200-41	12	Corning, cable systems unicom, box, 25ct/box		1st floor Bay 3	BP-16
3/12/2009		VC76	5	Hubbell, Vertical cable organizer for 7" rack, box		1st floor Bay 3	BP-16
3/12/2009		HXJ625	9	Hubbell, Xcellerator Cat.6 universal wired, pack, 25ct/each		1st floor Bay 3	BP-16
3/12/2009		BRDN080-1034TL	3	Geist Manufacturing Inc., Power distribution unit 30A 125V, pc		1st floor Bay 3	BP-16
3/12/2009		700427	1	Cooper, 1/8" cable Zinc coated, roll, 500ft/roll		1st floor Bay 3	BP-16
3/12/2009			1 Roll ~ 8%	Mohawk, 6LAM (TM) Ctg 4 PR 24 AWG(UL) C(UL) CMP ETL Verified to TIA.	3/14/2009	1st Floor Bay 3	BP-16
3/12/2009			1 Roll ~ 8%	Mohawk, 6LAM (TM) Ctg 4 PR 24 AWG(UL) C(UL) CMP ETL Verified to TIA.	3/14/2009	1st Floor Bay 3	BP-16



ADDENDUM #1 INVENTORY UPDATE

Date	Tag No.	Serial/Part No.	Quantity	Description	Stored Date	Stored Location	Bid Package
3/12/2009			1 Roll ~ 8%	Mohawk, 6LAM (TM) Ctg 4 PR 24 AWG(UL) C(UL) CMP ETL Verified to TIA.	3/14/2009	1st Floor Bay 3	BP-16
3/12/2009			1 Roll ~ 15%	Mohawk, 6LAM (TM) Ctg 4 PR 24 AWG(UL) C(UL) CMP ETL Verified to TIA.	3/14/2009	1st Floor Bay 3	BP-16
3/12/2009			1 Roll ~ 10%	Mohawk, 6LAM (TM) Ctg 4 PR 24 AWG(UL) C(UL) CMP ETL Verified to TIA.	3/14/2009	1st Floor Bay 3	BP-16
3/12/2009			1 Roll ~ 10%	Mohawk, 6LAM (TM) Ctg 4 PR 24 AWG(UL) C(UL) CMP ETL Verified to TIA.	3/14/2009	1st Floor Bay 3	BP-16
3/12/2009			1 Roll ~ 8%	Mohawk, 6LAM (TM) Ctg 4 PR 24 AWG(UL) C(UL) CMP ETL Verified to TIA.	3/14/2009	1st Floor Bay 3	BP-16
3/12/2009			1 Roll ~ 50'	Cerro wire vinyl lon - A 12AWG (VL) MTW green cable	3/14/2009	1st Floor Bay 3	BP-16
3/12/2009			1 Roll ~ 1000'	Colonial E1488973 14AWG Red Cable	3/14/2009	1st Floor Bay 3	BP-16
3/12/2009			1 Roll ~ 15%	Mohawk E 153612 Megalan™ 4PR 24AWG (UL) cat 5e 686' (green) 17.75D	3/14/2009	1st Floor Bay 3	BP-16
3/12/2009			1 Roll ~ 95%	White Calde 1000' Beld fail Flamarrest shielded cable 18AWG Zconductor	3/14/2009	1st Floor Bay 3	BP-16
3/12/2009			1 Roll ~ 10%	Comon Scope 1/18 AWG copper/steel communications cable	3/14/2009	1st Floor Bay 3	BP-16
3/12/2009			1 Roll ~ 20%	General Cable optical cable 24 F single mode MIA-DWB series	3/14/2009	1st Floor Bay 3	BP-16
3/12/2009			21 Rolls	Mohawk 3000' P/N M58281 4 PR B-24.1 (blue)	3/14/2009	1st Floor Bay 3	BP-16
3/12/2009			5 rolls	Lappan AWG 18/1C white 1000'	3/14/2009	1st Floor Bay 3	BP-16
3/12/2009			1 Roll ~ 90%	Nexans -C Ultrex-VN600V shielded black cable	3/14/2009	1st Floor Bay 3	BP-16
3/12/2009			1 Roll ~ 70%	17.75"x12" 5848' Belden 600V Type TC	3/14/2009	1st Floor Bay 3	BP-16
3/12/2009			1 Roll ~ 90%	Belden 3C16 600V Type TC	3/14/2009	1st Floor Bay 3	BP-16
3/12/2009			1 Roll ~ 70%	Belden 3C16 600V Type TC 23.75Dx12.875H	3/14/2009	1st Floor Bay 3	BP-16
3/12/2009			1 Roll ~ 150'	Mohawk 200 PR 24AWG Cat 3 M56129 1680'	3/14/2009	1st Floor Bay 3	BP-16
3/12/2009			1 Roll ~ 500'	4'x2.5' Type OFNP Fiberoptic cable 300 series grade 2	3/14/2009	1st Floor Bay 3	BP-16
3/12/2009			~800'	General Cable optical cable 48F62.5-125 MIA-DWB series	3/14/2009	1st Floor Bay 3	BP-16
3/13/2009	852AG12		90	Each, 3/4" dia, 10' long, schedule 40, PVC conduit	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-16
3/13/2009	E35309		12	Each, 2" dia, 10' long, schedule 40, PVC conduit	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-16
3/13/2009	N/A		25	Each, 4" dia, 10' long, hubbed, schedule 40, PVC conduit	3/10 - 3/13/09	Pipe Yard outside Old Library	BP-16

EXHIBIT "B"

Attachment to **Subcontract/Purchase Order No. 1312021-xxx** dated **mm dd, year**, by and between **[insert full legal name of subcontractor/seller]** and **SKANSKA USA BUILDING INC.** for **[insert description of trade work/goods and services]** at **Southern Connecticut State University, Buley Library, New Haven, CT.**

DRAWINGS & SKETCHES, SPECIFICATIONS, ADDENDA and OTHER DOCUMENTS

The Contract Documents include the following documents:

Drawings & Sketches

Number	Title	Date
G-1	DRAWING LIST, SYMBOLS & ABBREVIATIONS	11/30/2012
G-2	CODE DATA GROUND FLOOR PLAN	11/30/2012
G-3	CODE DATA FIRST & SECOND FLOOR PLANS	11/30/2012
G-4	CODE DATA THIRD, FOURTH, & PENTHOUSE FLOOR PLANS	11/30/2012
1 OF 2	TOPOGRAPHIC SURVEY	11/30/2012
2 OF 2	TOPOGRAPHIC SURVEY	11/30/2012
SPH-100	SITE PHASING AND STAGING PLAN	11/30/2012
ES-100	EROSION AND SEDIMENTATION CONTROL PLAN	11/30/2012
L-100	SITE DEMOLITION PLAN	11/30/2012
L-101	SITE LAYOUT PLAN	11/30/2012
L-102	SITE GRADING PLAN	11/30/2012
L-103	SITE DRAINAGE PLAN	11/30/2012
L-104	SITE PLANTING PLAN	11/30/2012
L-105	SITE SCORING PLAN	11/30/2012
L-106	SITE DETAILS	11/30/2012
AD-100	GROUND FLOOR DEMOLITION PLAN	11/30/2012
AD-101	FIRST FLOOR DEMOLITION PLAN	11/30/2012
AD-102	SECOND FLOOR DEMOLITION PLAN	11/30/2012
AD-103	THIRD FLOOR DEMOPLITION PLAN	11/30/2012
AD-104	FOURTH FLOOR DEMOLITION PLAN	11/30/2012
AD-104.1	FOURTH FLOOR ADDITION DEMOLITION PLAN	11/30/2012
A-100	GROUND FLOOR PLAN	11/30/2012
A-101	FIRST FLOOR PLAN	11/30/2012
A-102	SECOND FLOOR PLAN	11/30/2012
A-102A	SECOND FLOOR PLAN (UNIT PRICE)	11/30/2012
A-103	THIRD FLOOR PLAN	11/30/2012
A-103A	THIRD FLOOR PLAN (UNIT PRICE)	11/30/2012
A-104	FOURTH FLOOR PLAN	11/30/2012
A-104A	FOURTH FLOOR PLAN (UNIT PRICE)	11/30/2012
A-104.1	FOURTH FLOOR ADDITION PLAN	11/30/2012
A-105	PENTHOUSE AND ROOF FLOOR PLAN	11/30/2012
A-106	ROOF PLAN	11/30/2012
A-200	GROUND FLOOR REFLECTED CEILING PLAN	11/30/2012

EXHIBIT "B"

Attachment to **Subcontract/Purchase Order No. 1312021-xxx** dated **mm dd, year**, by and between **[insert full legal name of subcontractor/seller]** and **SKANSKA USA BUILDING INC.** for **[insert description of trade work/goods and services]** at **Southern Connecticut State University, Buley Library, New Haven, CT.**

A-201	FIRST FLOOR REFLECTED CEILING PLAN	11/30/2012
A-202	SECOND FLOOR REFLECTED CEILING PLAN	11/30/2012
A-203	THIRD FLOOR REFLECTED CEILING PLAN	11/30/2012
A-204	FOURTH FLOOR REFLECTED CEILING PLAN	11/30/2012
A-204.1	FOURTH FLOOR ADDITION REFLECTED CEILING PLAN	11/30/2012
A-205	CEILING DETAILS & SCHEDULES	11/30/2012
A-300	ENLARGED INTERIOR PLAN DETAILS	11/30/2012
A-301	ENLARGED PLANS AND DETAILS	11/30/2012
A-302	ENLARGED INTERIOR PLAN DETAILS	11/30/2012
A-303	ENLARGED INTERIOR PLAN DETAILS	11/30/2012
A-320	ENLARGED PLANS AND DETAILS	11/30/2012
A-321	ENLARGED PLANS AND DETAILS	11/30/2012
A-400	SOUTH ELEVATIONS	11/30/2012
A-401	EAST AND WEST ELEVATIONS	11/30/2012
A-500	BUILDING SECTIONS A & B	11/30/2012
A-501	BUILDING SECTIONS C & D	11/30/2012
A-510	WALL SECTIONS A-F	11/30/2012
A-511	WALL SECTIONS A-D	11/30/2012
A-512	WALL SECTIONS A-G	11/30/2012
A-513	WALL SECTION ENLARGED DETAILS	11/30/2012
A-514	WALL SECTION ENLARGED DETAILS	11/30/2012
A-515	WALL SECTION ENLARGED DETAILS	11/30/2012
A-516	ROOF DETAILS	11/30/2012
A-550	FIRST FLOOR PLAN DETAILS	11/30/2012
A-551	SECOND, THIRD, & FOURTH FLOOR PLAN DETAILS	11/30/2012
A-600	INTERIOR ELEVATIONS	11/30/2012
A-601	INTERIOR ELEVATIONS	11/30/2012
A-602	INTERIOR ELEVATIONS	11/30/2012
A-603	INTERIOR ELEVATIONS	11/30/2012
A-604	INTERIOR ELEVATIONS	11/30/2012
A-605	INTERIOR ELEVATIONS	11/30/2012
A-650	MILLWORK DETAILS	11/30/2012
A-651	MILLWORK DETAILS	11/30/2012
A-652	MILLWORK DETAILS	11/30/2012
A-653	MILLWORK DETAILS	11/30/2012
A-654	MILLWORK DETAILS	11/30/2012
A-656	MILLWORK DETAILS	11/30/2012
A-659	MILLWORK DETAILS	11/30/2012
A-661	MILLWORK DETAILS	11/30/2012
A-662	MILLWORK DETAILS	11/30/2012

EXHIBIT "B"

Attachment to **Subcontract/Purchase Order No. 1312021-xxx** dated **mm dd, year**, by and between **[insert full legal name of subcontractor/seller]** and **SKANSKA USA BUILDING INC.** for **[insert description of trade work/goods and services]** at **Southern Connecticut State University, Buley Library, New Haven, CT.**

A-663	MILLWORK DETAILS	11/30/2012
A-664	MILLWORK DETAILS	11/30/2012
A-665	MILLWORK DETAILS	11/30/2012
A-666	MILLWORK DETAILS	11/30/2012
A-667	MILLWORK DETAILS	11/30/2012
A-668	MILLWORK DETAILS	11/30/2012
A-700	STAIR DETAILS	11/30/2012
A-701	STAIR DETAILS	11/30/2012
A-702	STAIR DETAILS	11/30/2012
A-800	DOOR SCHEDULE	11/30/2012
A-801	DOOR TYPES AND DETAILS	11/30/2012
A-805	STOREFRONT TYPES AND DETAILS	11/30/2012
A-806	STOREFRONT DETAILS	11/30/2012
A-810	WINDOWS AND CURTAINWALLS	11/30/2012
A-811	WINDOWS AND CURTAINWALLS	11/30/2012
A-812	CURTAIN WALLS AND STOREFRONTS	11/30/2012
A-813	PRECAST STOREFRONTS	11/30/2012
A-815	LOUVER ELEVATIONS	11/30/2012
A-820	PARTITION TYPES	11/30/2012
A-900A	GROUND FLOOR-FLOOR FINISH PLAN	11/30/2012
A-900B	GROUND FLOOR-WALL FINISH PLAN	11/30/2012
A-901A	FIRST FLOOR-FLOOR FINISH PLAN	11/30/2012
A-901B	FIRST FLOOR-WALL FINISH PLAN	11/30/2012
A-902A	SECOND FLOOR-FLOOR FINISH PLAN	11/30/2012
A-902B	SECOND FLOOR-WALL FINISH PLAN	11/30/2012
A-903A	THIRD FLOOR-FLOOR FINISH PLAN	11/30/2012
A-903B	THIRD FLOOR-WALL FINISH PLAN	11/30/2012
A-904A	FOURTH FLOOR-FLOOR FINISH PLAN	11/30/2012
A-904B	FOURTH FLOOR-WALL FINISH PLAN	11/30/2012
A-904.1A	FOURTH FLOOR ADDITION-FLOOR FINISH PLAN	11/30/2012
A-904.1B	FOURTH FLOOR ADDITION-WALL FINISH PLAN	11/30/2012
A-950	SIGNAGE SCHEDULE & DETAILS	11/30/2012
A-951	SIGNAGE DETAILS	11/30/2012
F-100	GROUND FLOOR FURNITURE PLAN	11/30/2012
F-101	FIRST FLOOR FURNITURE PLAN	11/30/2012
F-102	SECOND FLOOR FURNITURE PLAN	11/30/2012
F-103	THIRD FLOOR FURNITURE PLAN	11/30/2012
F-104	FOURTH FLOOR FURNITURE PLAN	11/30/2012
F-104.1	FOURTH FLOOR ADDITION FURNITURE PLAN	11/30/2012
SD-101	STRUCTURAL DEMOLITION PLANS	11/30/2012

EXHIBIT “B”

Attachment to **Subcontract/Purchase Order No. 1312021-xxx** dated **mm dd, year**, by and between **[insert full legal name of subcontractor/seller]** and **SKANSKA USA BUILDING INC.** for **[insert description of trade work/goods and services]** at **Southern Connecticut State University, Buley Library, New Haven, CT.**

S-101	FOUNDATION PLAN	11/30/2012
S-102	FIRST FLOOR FRAMING PLAN	11/30/2012
S-103	SECOND FLOOR AND LOW ROOF FRAMING PLAN	11/30/2012
S-104	THIRD FLOOR FRAMING PLAN	11/30/2012
S-105	FOURTH FLOOR FRAMING PLAN	11/30/2012
S-106	ROOF AND PENTHOUSE FLOOR FRAMING PLAN	11/30/2012
S-107	PENTHOUSE ROOF FRAMING PLAN	11/30/2012
S-201	ENLARGED PLANS AND SECTIONS	11/30/2012
S-202	ENLARGED PLANS AND SECTIONS	11/30/2012
S-203	ENLARGED PLANS AND SECTIONS	11/30/2012
S-204	FIRST FLOOR PART PLAN & SECTIONS	
S-301	FRAMING SECTIONS AND DETAILS	11/30/2012
S-302	FRAMING SECTIONS AND DETAILS	11/30/2012
S-303	FRAMING SECTIONS AND DETAILS	11/30/2012
S-304	FRAMING SECTIONS AND DETAILS	11/30/2012
S-305	FRAMING SECTIONS AND DETAILS	11/30/2012
S-306	FRAMING SECTIONS AND DETAILS	11/30/2012
S-307	FRAMING SECTIONS AND DETAILS	11/30/2012
S-308	FRAMING SECTIONS AND DETAILS	11/30/2012
S-309	FRAMING SECTIONS AND DETAILS	11/30/2012
S-310	FRAMING SECTIONS AND DETAILS	11/30/2012
S-311	FRAMING SECTIONS AND DETAILS	11/30/2012
S-312	FRAMING SECTIONS AND DETAILS	11/30/2012
S-401	LATERAL FRAMES	11/30/2012
S-402	LATERAL FRAMES	11/30/2012
S-501	COLUMN SCHEDULE	11/30/2012
S-601	GENERAL NOTES AND TYPICAL DETAILS	11/30/2012
FP-001	GENERAL NOTES AND LEGEND	11/30/2012
FPD-100	GROUND FLOOR DEMOLITION PLAN	11/30/2012
FP-100	GROUND FLOOR PLAN	11/30/2012
FP-101	FIRST FLOOR PLAN	11/30/2012
FP-102	SECOND FLOOR PLAN	11/30/2012
FP-103	THIRD FLOOR PLAN	11/30/2012
FP-104	FOURTH FLOOR PLAN	11/30/2012
FP-105	PENTHOUSE/ROOF FIRE PROTECTION	11/30/2012
FP-106	FOURTH FLOOR ADDITION PLAN	11/30/2012
FP-201	DETAILS-FIRE PROTECTION	11/30/2012
FP-301	SCHEDULE & RISERS	11/30/2012
P-001	GENERAL NOTES	11/30/2012
PD-100	GROUND FLOOR DEMOLITION PLAN	11/30/2012

EXHIBIT "B"

Attachment to **Subcontract/Purchase Order No. 1312021-xxx** dated **mm dd, year**, by and between **[insert full legal name of subcontractor/seller]** and **SKANSKA USA BUILDING INC.** for **[insert description of trade work/goods and services]** at **Southern Connecticut State University, Buley Library, New Haven, CT.**

PD-101	FIRST FLOOR DEMOLITION PLAN	11/30/2012
PD-104	FOURTH FLOOR DEMOLITION PLAN	11/30/2012
PD-105	PENTHOUSE/ROOF DEMOLITION PLAN	11/30/2012
P-100	GROUND FLOOR PLAN - PLUMBING	11/30/2012
P-101	FIRST FLOOR PLAN - PLUMBING	11/30/2012
P-102	SECOND FLOOR PLAN - PLUMBING	11/30/2012
P-103	THIRD FLOOR PLAN - PLUMBING	11/30/2012
P-104	FOURTH FLOOR PLAN - PLUMBING	11/30/2012
P-105	PENTHOUSE/ROOF FLOOR PLAN - PLUMBING	11/30/2012
P-200	PARTIAL PLANS - PLUMBING	11/30/2012
P-201	PARTIAL PLANS - PLUMBING	11/30/2012
P-301	DETAILS - PLUMBING	11/30/2012
P-302	DETAILS - PLUMBING	11/30/2012
P-401	SCHEDULES - PLUMBING	11/30/2012
P-402	SCHEDULES - PLUMBING	11/30/2012
P-501	STORM RISER DIAGRAM PLUMBING	
P-502	SANITARY, WASTE & VENT RISER DIAGRAM	
M-001	GENERAL NOTES - MECHANICAL	11/30/2012
MD-100	DEMOLITION GROUND FLOOR - MECHANICAL	11/30/2012
MD-101	DEMOLITION SECOND, THIRD AND FOURTH FLOOR PLANS	11/30/2012
M-100	GROUND FLOOR PLAN - MECHANICAL	11/30/2012
M-101	FIRST FLOOR PLAN - MECHANICAL	11/30/2012
M-102	SECOND FLOOR PLAN - MECHANICAL	11/30/2012
M-103	THIRD FLOOR PLAN - MECHANICAL	11/30/2012
M-104	FOURTH FLOOR PLAN - MECHANICAL	11/30/2012
M-105	PENTHOUSE & ROOF PLAN - MECHANICAL	11/30/2012
M-106	FOURTH FLOOR ADDITION PLAN - MECHANICAL	11/30/2012
M-200	PARTIAL PLANS - MECHANICAL	11/30/2012
M-201	PENTHOUSE PARTIAL PLAN - MECHANICAL	11/30/2012
M-202	PENTHOUSE SECTIONS - MECHANICAL	11/30/2012
M-300	SCHEDULES - MECHANICAL	11/30/2012
M-301	SCHEDULES - MECHANICAL	11/30/2012
M-302	SCHEDULES - MECHANICAL	11/30/2012
M-303	SCHEDULES - MECHANICAL	11/30/2012
M-400	FLOW & CONTROL - MECHANICAL	11/30/2012
M-401	FLOW & CONTROL - MECHANICAL	11/30/2012
M-402	FLOW & CONTROL - MECHANICAL	11/30/2012
M-500	DETAILS - MECHANICAL	11/30/2012
M-501	DETAILS - MECHANICAL	11/30/2012
M-502	DETAILS - MECHANICAL	11/30/2012

EXHIBIT "B"

Attachment to **Subcontract/Purchase Order No. 1312021-xxx** dated **mm dd, year**, by and between **[insert full legal name of subcontractor/seller]** and **SKANSKA USA BUILDING INC.** for **[insert description of trade work/goods and services]** at **Southern Connecticut State University, Buley Library, New Haven, CT.**

M-503	DETAILS - MECHANICAL	11/30/2012
E-001	GENERAL NOTES - ELECTRICAL	11/30/2012
E-002	SITE PLAN - ELECTRICAL	11/30/2012
E-003	SITE PLAN - ELECTRICAL	11/30/2012
ED-100	GROUND FLOOR DEMOLITION PLAN - ELECTRICAL	11/30/2012
ED-104	FOURTH FLOOR DEMOLITION PLAN - ELECTRICAL	11/30/2012
E-100	GROUND FLOOR PLAN	11/30/2012
E-101	FIRST FLOOR PLAN	11/30/2012
E-102	SECOND FLOOR PLAN	11/30/2012
E-103	THIRD FLOOR PLAN	11/30/2012
E-104	FOURTH FLOOR PLAN	11/30/2012
E-105	PENTHOUSE FLOOR PLAN	11/30/2012
E-106	FOURTH FLOOR ADDITION PLAN	11/30/2012
E-200	GROUND FLOOR PLAN LIGHTING	11/30/2012
E-201	FIRST FLOOR PLAN LIGHTING	11/30/2012
E-202	SECOND FLOOR PLAN LIGHTING	11/30/2012
E-203	THIRD FLOOR PLAN LIGHTING	11/30/2012
E-204	FOURTH FLOOR PLAN LIGHTING	11/30/2012
E-205	PENTHOUSE FLOOR PLAN LIGHTING	11/30/2012
E-206	FOURTH FLOOR ADDITION PLAN LIGHTING	11/30/2012
E-300	RISER DIAGRAM - ELECTRICAL	11/30/2012
E-301	FIRE ALARM RISER - ELECTRICAL	11/30/2012
E-400	PANEL SCHEDULES - ELECTRICAL	11/30/2012
E-401	PANEL SCHEDULES - ELECTRICAL	11/30/2012
E-402	PANEL SCHEDULES - ELECTRICAL	11/30/2012
E-403	PANEL SCHEDULES - ELECTRICAL	11/30/2012
E-500	DETAILS - ELECTRICAL	11/30/2012
T-001	TELECOM. SYMBOLS & LEGENDS	11/30/2012
T-100	TELECOM. GROUND FLOOR PLA	11/30/2012
T-101	TELECOM. FIRST FLOOR PLAN	11/30/2012
T-102	TELECOM. SECOND FLOOR PLAN	11/30/2012
T-103	TELECOM. THIRD FLOOR PLAN	11/30/2012
T-104	TELECOM. FOURTH FLOOR PLAN	11/30/2012
T-104.1	TELECOM. FOURTH FLOOR ADDITION PLAN	11/30/2012
T-105	TELECOM PENTHOUSE PLAN	11/30/2012
T-201	TELECOM. DATA ROOM LAYOUT	11/30/2012
T-202	TELECOM. RACK ELEVATIONS	11/30/2012
T-203	TELECOM. RACK ELEVATIONS	11/30/2012
T-501	TELECOM. DETAIL DRAWINGS	11/30/2012
T-502	TELECOM A/V DETAILS	11/30/2012

EXHIBIT "B"

Attachment to **Subcontract/Purchase Order No. 1312021-xxx** dated **mm dd, year**, by and between **[insert full legal name of subcontractor/seller]** and **SKANSKA USA BUILDING INC.** for **[insert description of trade work/goods and services]** at **Southern Connecticut State University, Buley Library, New Haven, CT.**

SEC-001	SECURITY SYMBIOLS & LEGENDS	11/30/2012
SEC-100	SECURITY GROUND FLOOR PLAN	11/30/2012
SEC-101	SECURITY FIRST FLOOR PLAN	11/30/2012
SEC-102	SECURITY SECOND FLOOR PLAN	11/30/2012
SEC-103	SECURITY THIRD FLOOR PLAN	11/30/2012
SEC-104	SECURITY FOURTH FLOOR PLAN	11/30/2012
SEC-104.1	SECURITY FOURTH FLOOR ADDITION PLAN	11/30/2012

Drawings & Sketches

Spec Section	Title	Date
00 01 01	Project Title Page	11/30/2012
00 01 07	Seals Page	11/30/2012
00 01 10	Table of Contents	11/30/2012
00 01 15	List of Drawing Sheets - CMR	11/30/2012
00 11 16	Invitation to Bid	11/30/2012
00 21 19	Notice to Bidders	11/30/2012
00 30 00	Available Information	11/30/2012
00 31 19	Existing Condition Information	11/30/2012
00 31 21	Survey Information	11/30/2012
00 31 24	Environmental Assessment Information	11/30/2012
00 31 25	Existing Material Information	11/30/2012
00 31 26.23	Existing Hazardous Material Information	11/30/2012
00 31 32 13	Subsurface Geotechnical Report	11/30/2012
00 31 33.11	Elevator Agreement	11/30/2012
00 40 14	Certificate (of Authority) (Required to be Submitted with Bid Proposal Form)	11/30/2012
00 40 15	Department of Administrative Services (DAS) Pre-qualification Forms	11/30/2012
00 41 00	Bid Proposal Form (Major & Minor Capital Projects Greater Than \$500,000)	11/30/2012
00 43 16	Standard Bid Bond Form (Required to be Submitted with Bid Proposal Form)	11/30/2012
00 43 24	Special Unit Prices (Not Used)	11/30/2012
00 45 14	General Contractor Bidder's Qualification Statement	11/30/2012
00 45 15	Objective Criteria for Evaluating Qualifications of Bidders	11/30/2012
00 45 17	Named Subcontractor Bidder's Qualification Statement	11/30/2012
00 52 03	Contract	11/30/2012
00 52 73	Subcontract Agreement Form	11/30/2012
00 62 16	Certificate of Insurance	11/30/2012
00 62 16.1	Asbestos Attachment to Acord Form	11/30/2012
00 72 23	General Conditions of the Contract for Construction For CMR	11/30/2012
00 72 23.1	Supplementary Conditions	11/30/2012
00 73 27	Set Aside Contractor Schedule	11/30/2012
00 73 38	Commission on Human Rights & Opportunities (CHRO) Contract Compliance Regulations	11/30/2012

EXHIBIT “B”

Attachment to **Subcontract/Purchase Order No. 1312021-xxx** dated **mm dd, year**, by and between **[insert full legal name of subcontractor/seller]** and **SKANSKA USA BUILDING INC.** for **[insert description of trade work/goods and services]** at **Southern Connecticut State University, Buley Library, New Haven, CT.**

00-73-44	Prevailing Wage Rates/Contractor’s Wage Certification/Payroll Certification	11/30/2012
00-73-53	Affidavit For Certification Of Subcontractors As Minority Business Enterprises (MBE)	11/30/2012
00-73-63	Security Requirements	11/30/2012
00-92-00	Amendments (No. 1 A, 2) (Major & Minor Capital Projects Greater Than \$500,000)	11/30/2012
00-92-10	Additional Forms To be Submitted After Bond Commission Funding Approval	11/30/2012
00-92-20	Executive Orders	11/30/2012
01-11-00	Summary of Work – CMR	11/30/2012
01-20-00	Contract Considerations – CMR	11/30/2012
01-23-13	Supplemental Bids	11/30/2012
01-25-00	Substitution Procedures – CMR	11/30/2012
01-26-00	Contract Modification Procedures – CMR	11/30/2012
01-29-76	Progress Payment Procedures – CMR	11/30/2012
01-31-00	Project Management and Coordination – CMR	11/30/2012
01-31-19	Project Meetings – CMR	11/30/2012
01-32-16.13	CPM Schedules – CMR	11/30/2012
01-32-33	Photographic Documentation – CMR	11/30/2012
01-33-00	Submittal Procedures – CMR	11/30/2012
01-35-16	Alteration Project Procedures – CMR	11/30/2012
01-35-26	Government Safety Requirements – CMR	11/30/2012
01-42-20	Reference Standards – CMR	11/30/2012
01-45-00	Quality Control – CMR	11/30/2012
01-45-23.13	Testing for Indoor Air Quality, Baseline Indoor Air Quality, and Materials – CMR	11/30/2012
01-50-00	Temporary Facilities & Controls – CMR	11/30/2012
01-57-30	Indoor Environmental Control - CMR	11/30/2012
01-57-40	Construction Indoor Air Quality Management Plan – CMR	11/30/2012
01-60-00	Product Requirements – CMR	11/30/2012
01-63-00	Mock-Ups	11/30/2012
01-71-23	Field Engineering – CMR	11/30/2012
01-73-29	Cutting and Patching – CMR	11/30/2012
01-74-19	Construction Waste Management & Disposal – CMR	11/30/2012
01-75-00	Starting & Adjusting – CMR	11/30/2012
01-77-00	Closeout Procedures- CMR	11/30/2012
01-78-23	Operation & Maintenance Data – CMR	11/30/2012
01-78-30	Warranties & Bonds – CMR	11/30/2012
01-81-13	Sustainable Design Requirements – CMR (Not Required)	11/30/2012
01-91-00	Commissioning – CMR	11/30/2012
02-41-19	Selective Demolition	11/30/2012
02-83-00	Lead Remediation	11/30/2012
03-10-00	Concrete Formwork	11/30/2012
03-20-00	Concrete Reinforcement	11/30/2012

EXHIBIT "B"

Attachment to **Subcontract/Purchase Order No. 1312021-xxx** dated **mm dd, year**, by and between **[insert full legal name of subcontractor/seller]** and **SKANSKA USA BUILDING INC.** for **[insert description of trade work/goods and services]** at **Southern Connecticut State University, Buley Library, New Haven, CT.**

03 30 00	Cast-In-Place Concrete	11/30/2012
03 41 23	Concrete Steps	11/30/2012
03 45 00	Architectural Precast Concrete	11/30/2012
04 20 00	Unit Masonry	11/30/2012
05 12 00	Structural Steel	11/30/2012
05 21 00	Steel Joists	11/30/2012
05 31 10	Steel Deck	11/30/2012
05 50 00	Miscellaneous Metals	11/30/2012
05 51 33	Inclined Metal Ladders and Platforms	11/30/2012
05 71 00	Ornamental Metal Stairs	11/30/2012
05 73 00	Ornamental Metal Railings	11/30/2012
06 20 00	Carpentry	11/30/2012
06 40 23	Architectural Woodwork	11/30/2012
06 61 16	Solid Surfacing Fabrications	11/30/2012
07 13 00	Air and Vapor Barrier System	11/30/2012
07 21 00	Thermal Insulation	11/30/2012
07 42 00	Laminated Metal Wall Panels	11/30/2012
07 42 13	Insulated Metal Wall Panels	11/30/2012
07 53 23	EPDM Membrane Roofing	11/30/2012
07 62 00	Sheet Metal Flashing and Trim	11/30/2012
07 81 00	Applied Fireproofing	11/30/2012
07 84 00	Firestopping	11/30/2012
07 90 00	Joint Protection	11/30/2012
07 95 00	Expansion Control	11/30/2012
08 11 13	Steel Doors and Frames	11/30/2012
08 31 13	Access Doors	11/30/2012
08 33 00	Overhead Coiling Doors	11/30/2012
08 33 26	Overhead Coiling Grilles	11/30/2012
08 41 23	Glazed Fire-Rated Door and Framing Systems	11/30/2012
08 44 13	Aluminum Curtain Wall System	11/30/2012
08 44 29	Glass Canopy	11/30/2012
08 51 13	Aluminum Windows	11/30/2012
08 71 00	Finish Hardware	11/30/2012
08 71 13	Automatic Door Operators	11/30/2012
08 80 00	Glass and Glazing	11/30/2012
09 21 16	Gypsum Board Assemblies	11/30/2012
09 30 13	Ceramic Tiling	11/30/2012
09 51 13	Acoustical Panel Ceilings	11/30/2012
09 51 33	Metal Acoustical Ceilings	11/30/2012
09 65 13	Resilient Base and Accessories	11/30/2012
09 65 43	Linoleum Flooring	11/30/2012
09 66 23	Thin Sets Epoxy Terrazzo	11/30/2012
09 68 16	Carpet(Glue Down)	11/30/2012
09 91 00	Painting and Finishing	11/30/2012
10 11 23	Tackable Wall Surface	11/30/2012
10 14 00	Signage	11/30/2012
10 20 00	Louvers and Vents	11/30/2012
10 21 13	Toilet Partitions	11/30/2012

EXHIBIT “B”

Attachment to **Subcontract/Purchase Order No. 1312021-xxx** dated **mm dd, year**, by and between **[insert full legal name of subcontractor/seller]** and **SKANSKA USA BUILDING INC.** for **[insert description of trade work/goods and services]** at **Southern Connecticut State University, Buley Library, New Haven, CT.**

10 22 26	Operable Partitions	11/30/2012
10 28 13	Toilet Accessories	11/30/2012
10 75 16	Flagpole	11/30/2012
11 13 00	Loading Dock Equipment	11/30/2012
11 50 01	Library Specialties	11/30/2012
11 52 13	Motorized Projection Screens	11/30/2012
12 24 13	Window Shades	11/30/2012
12 48 13	Floor Mats and Frames	11/30/2012
12 48 23	Floor Grids and Frames	11/30/2012
12 93 13	Bicycle Racks	11/30/2012
14 22 00	Electric Traction Modernization	11/30/2012
21 05 00	Common Work Results for Fire Suppression	11/30/2012
21 05 48	Vibration and Seismic Controls for Fire-Suppression Piping & Equipment	11/30/2012
21 08 00	Commissioning of Sprinkler Systems	11/30/2012
21 10 00	Water-Based Fire-Suppression Systems	11/30/2012
22 05 00	Common Work Results for Plumbing	11/30/2012
22 05 13	Common Motor Requirements for Plumbing Equipment	11/30/2012
22 05 16	Expansion Fittings and Loops for Plumbing Piping	11/30/2012
22 05 17	Sleeves and Sleeve Seals for Plumbing Piping	11/30/2012
22 05 18	Escutcheons for Plumbing Piping	11/30/2012
22 05 19	Meters and Gages for Plumbing Piping	11/30/2012
22 05 20	Protective Cover System for Plumbing Piping	11/30/2012
22 05 23	General-Duty Valves for Plumbing Piping	11/30/2012
22 05 29	Hangers and Supports for Plumbing Piping and Equipment	11/30/2012
22 05 33	Heat Tracing for Plumbing Piping	11/30/2012
22 05 48	Vibration and Seismic Controls for Plumbing Piping and Equipment	11/30/2012
22 05 53	Identification for Plumbing Piping and Equipment	11/30/2012
22 07 19	Plumbing Piping Insulation	11/30/2012
22 08 00	Commissioning for Plumbing Systems	11/30/2012
22 11 16	Domestic Water Piping	11/30/2012
22 11 19	Domestic Water Piping Specialties	11/30/2012
22 11 23	Domestic Water Pumps	11/30/2012
22 13 16	Sanitary Waste and Vent Piping	11/30/2012
22 13 19	Sanitary Waste Piping Specialties	11/30/2012
22 14 13	Storm Drainage Piping	11/30/2012
22 14 23	Storm Drainage Piping Specialties	11/30/2012
22 33 00	Electric, Domestic-Water Heaters	11/30/2012
22 42 13.13	Commercial Water Closets	11/30/2012
22 42 13.16	Commercial Urinals	11/30/2012
22 42 16.13	Commercial Lavatories	11/30/2012
22 42 16.16	Commercial Sinks	11/30/2012
22 45 00	Emergency Plumbing Fixtures	11/30/2012
22 47 16	Pressure Water Coolers	11/30/2012
23 00 00	General Provisions	11/30/2012
23 01 30.51	HVAC Air-Distribution System Cleaning	11/30/2012
23 05 13	Common Motor Requirements for HVAC Equipment	11/30/2012
23 05 16	Expansion Fittings and Loops for HVAC Piping	11/30/2012
23 05 17	Sleeves and Sleeve Seals for HVAC Piping	11/30/2012

EXHIBIT “B”

Attachment to **Subcontract/Purchase Order No. 1312021-xxx** dated **mm dd, year**, by and between **[insert full legal name of subcontractor/seller]** and **SKANSKA USA BUILDING INC.** for **[insert description of trade work/goods and services]** at **Southern Connecticut State University, Buley Library, New Haven, CT.**

23 05 18	Escutcheons for HVAC Piping	11/30/2012
23 05 19	Meters and Gages for HVAC Piping	11/30/2012
23 05 23	General-Duty Valves for HVAC Piping	11/30/2012
23 05 29	Hangers and Supports for HVAC Piping and Equipment	11/30/2012
23 05 33	Heat Tracing for HVAC Piping	11/30/2012
23 05 48	Vibration and Seismic Controls for HVAC Piping and Equipment	11/30/2012
23 05 53	Identification for HVAC Piping and Equipment	11/30/2012
23 05 93	Testing, Adjusting, and Balancing for HVAC	11/30/2012
23 07 00	HVAC Insulation	11/30/2012
23 08 00	Commissioning of HVAC	11/30/2012
23 09 00	Instrumentation and Control for HVAC	11/30/2012
23 09 93	Sequence of Operations for HVAC Controls	11/30/2012
23 21 13	Hydronic Piping	11/30/2012
23 21 23	Hydronic Pumps	11/30/2012
23 22 13	Steam and Condensate Heating Piping	11/30/2012
23 23 00	Refrigerant Piping	11/30/2012
23 25 00	HVAC Water Treatment	11/30/2012
23 29 13	Enclosed Controllers	11/30/2012
23 31 13	Metal Ducts	11/30/2012
23 33 00	Air Duct Accessories	11/30/2012
23 34 23	HVAC Power Ventilators	11/30/2012
23 34 33	Air Curtains	11/30/2012
23 36 00	Air Terminal Units	11/30/2012
23 37 13	Diffusers, Registers, and Grilles	11/30/2012
23 37 23	HVAC Gravity Ventilators	11/30/2012
23 51 00	Breechings, Chimneys, and Stacks	11/30/2012
23 64 16	Centrifugal Water Chillers	11/30/2012
23 81 26	Split-System Air-Conditioners	11/30/2012
23 82 13	Valance Heating and Cooling Units	11/30/2012
23 82 16	Air Coils	11/30/2012
23 82 19	Fan Coil Units	11/30/2012
23 82 33	Convectors	11/30/2012
23 82 39	Unit Heaters	11/30/2012
26 01 00	General Electrical Requirements	11/30/2012
26 05 00	Common Work Results for Electrical	11/30/2012
26 05 19	Low-Voltage Electrical Power Conductors and Cables	11/30/2012
26 05 26	Grounding and Bonding for Electrical Systems	11/30/2012
26 05 29	Hangers and Supports for Electrical Systems	11/30/2012
26 05 33	Raceway and Boxes for Electrical Systems	11/30/2012
26 05 48	Vibration and Seismic Controls for Electrical Systems	11/30/2012
26 05 53	Identification for Electrical Systems	11/30/2012
26 05 73	Overcurrent Protective Device Coordination Study	11/30/2012
26 08 00	Commissioning of Electrical Systems	11/30/2012
26 22 00	Low-Voltage Transformers	11/30/2012
26 24 16	Panelboards	11/30/2012
26 27 26	Wiring Devices	11/30/2012
26 28 16	Enclosed Switches and Circuit Breakers	11/30/2012
26 41 13	Lightning Protection for Structures	11/30/2012

EXHIBIT "B"

Attachment to **Subcontract/Purchase Order No. 1312021-xxx** dated **mm dd, year**, by and between **[insert full legal name of subcontractor/seller]** and **SKANSKA USA BUILDING INC.** for **[insert description of trade work/goods and services]** at **Southern Connecticut State University, Buley Library, New Haven, CT.**

26 51 00	Interior Lighting	11/30/2012
26 56 00	Exterior Lighting	11/30/2012
27 01 00	Operation & Maintenance of Communication Systems	11/30/2012
27 05 00	Common Methods for Communication Work	11/30/2012
27 05 26	Grounding and Bonding	11/30/2012
27 05 28	Pathways for Communications Systems	11/30/2012
27 05 44	Sleeves and Sleeve Seals for Communications Pathways and Cabling	11/30/2012
27 05 53	Identification for Communications Systems	11/30/2012
27 08 00	Communications Systems Commissioning	11/30/2012
27 11 00	Communications Equipment Room Fittings	11/30/2012
27 13 00	Communications Backbone Cabling	11/30/2012
27 15 00	Communications Horizontal Cabling	11/30/2012
27 41 16	Audio Visual Systems	11/30/2012
28 13 00	Access Control	11/30/2012
28 16 00	Intrusion Detection	11/30/2012
28 23 00	Video Surveillance	11/30/2012
28 31 11	Digital, Addressable Fire-Alarm System	11/30/2012
31 00 00	Sitework Instructions	11/30/2012
31 11 00	Clearing of Site	11/30/2012
31 14 13	Topsoiling	11/30/2012
31 23 13	Site Earthwork	11/30/2012
31 23 23.33	Flowable Fill	11/30/2012
31 23 33	Trenching	11/30/2012
31 25 00	Siltation Control	11/30/2012
32 01 90.33	Tree Protection	11/30/2012
32 11 26.19	Bituminous Concrete Road Pavement	11/30/2012
32 13 13.01	Concrete Pavement	11/30/2012
32 14 13.17	Precast Concrete Pavers on Concrete Base	11/30/2012
32 16 13.26	Precast Concrete Curb	11/30/2012
32 16 40	Granite Curbing	11/30/2012
32 17 23.13	Painted Pavement Markings	11/30/2012
32 92 19	Seeding	11/30/2012
32 93 00	Trees, Plants and Ground Cover	11/30/2012
33 05 26	Warning Markings	11/30/2012
33 40 00	Storm Drainage	11/30/2012