Page 1 of 1

ADDENDUM NO.: 2

DATE OF CMR ADDENDUM: 01.22.2013

Notice of Construction Manager-at-Risk (CMR) Addendum on behalf of the **CT Department of Construction Services (CT DCS)**

Project Name:	Southern Connecticut State University Buley Library Renovation
Project Location:	New Haven, CT
Project Description:	Core & Shell & Fit-Out
Project Construction Budget:	20.7 Million
CT DCS Project Number:	BI-RS-225B CMR

The Construction Manager-at-Risk (CMR) is issuing a Notice of CMR Addendum for this State of CT Department of Construction Services (CT DCS) Project. Specific Addendum Information is available as noted below. If you have any questions, please contact the CMR as noted below.

CMR Information:

	Skanska USA Building Inc.
Address:	545 Long Wharf Drive, 6 th Floor
Contact Name:	Kate Westrin
Contact Phone Number:	203-859-7708
Contact Email Address:	Kate.westrin@skanska.com

Addendum Information is available as follows:

CMR Website and/or FTP Site:	https://partners.myskanska.com/usa/clients/scsu/Buley/SitePages/Home.aspx
Printing Company:	Service Point USA - 203-624-0079

 □ DCS Project Manager Copies:

□ DCS Process Management (peter.babey@ct.gov)

□ DCS Process Management (<u>randy.daigle@ct.gov</u>)



January 22nd, 2013

ADDENDUM NO. 2

BID DUE DATE: Friday, February 8th, 2013 by 11AM

TIME: Reference Bid Receipt and Opening Schedule in Division 0

PROJECT: SCSU Buley Library Renovations

Project No. BI-RS-225B CMR

SUBMITTED TO: Michael J. Adanti Student Center

Southern Connecticut State University

501 Crescent Street

New Haven, Connecticut 06515

C/O: Skanska USA Building Inc.

Attention: Kate Westrin

I. GENERAL ITEMS:

1. Please note the following bid dates have changed:

- A. Follow-up Site Visit on Monday January 28th, 2013 from 8AM-11AM.
 - i. BP-05A (Reference RFI #60)
 - ii. BP-07B (Reference RFI #77)
 - iii. BP-09C (Reference RFI #124)
 - Other trades are welcome to review existing conditions related to their scope of work
- 2. Please note the Pre-Bid Agenda and Sign-in Sheet are available on the project website for review, under 'Bid Docs': https://partners.myskanska.com/usa/clients/scsu/Buley/SitePages/Home.aspx
- 3. State of Connecticut DPW/DCS Change Order Proposal Workbook Form 735 is attached for reference. Per the revised Bid Proposal Form, subcontractors shall be responsible to complete this form with any proposed change order proposals. Skanska will provide an electronic copy of this document to successful bidders for use during the project.
- 4. Please note Bid Packages 13A, 13B and 15B are required to provide bid bonds and payment and performance bonds in accordance with the contract documents.
- 5. BP-15A is advised to review M-001 "Mechanical General Notes" in preparation of their bid.
- 6. Please incorporate the attached revised Table of Contents into Division 0. This document reflects:
 - A. REVISED 00 21 13 Instructions to Bidders
 - B. REVISED 00 31 13 Project Schedule
 - C. REVISED 00 41 00 Bid Proposal Form
- 7. Please incorporate the revised 00 21 13 Instructions to Bidders into Division 0. This document reflects:
 - A. REVISED Section 4.3.5 omitting bid attachment requirement for 'Small Contractor & Minority Business Enterprise Goals and/or Good Faith Effort Contractor Attachment Illa (Section 00 43 39.2)'
- 8. Please incorporate the revised 00 31 13 Project Schedule into Division 0. This document reflects:
 - A. REVISED Schedule 'BL05' data date 15-January-13 issued
- 9. Please incorporate the revised 00 41 00 Bid Proposal Form- Addendum #2 into Division 0. This document reflects:
 - A. REVISED Part 1, Note 3
 - B. REVISED Section 5 ADDENDA

Addendum #2 Page 1 of 5

- C. REVISED Section 7 SUPPLEMENTAL BIDS
- D. REVISED Part 11 "CHANGE ORDERS/ALLOWABLE MARKUPS"

II. SCOPE CLARIFICATIONS/CHANGES:

BP-02 SITEWORK

- 1. OMIT Item #41- No stone ballast strip
- 2. MODIFY Item #48 to read- "This Subcontractor shall furnish and install all site furnishings included but not limited to bike racks and flagpoles. This Subcontractor shall install waste receptacles and benches furnished by the Owner. Note: Electrical ground lighting for glag pole will be completed by BP-16"
- 3. ADD Item #95- "This Subcontractor shall furnish and install temporary covered walkway as identified on the Site Logistics Plan"

BP-02A LANDSCAPING

1. OMIT Item #8- No gravel drip strips.

BP-02C SITE CONCRETE

1. MODIFY Item #6 to add the following statement- "...Also reference architectural details 13/L106, 12/A321 and 13/A321"

BP-03 CONCRETE

- 1. MODIFY Item #4 to add reference to structural drawings.
- 2. MODIFY Item #6 to add reference to structural drawings.
- 3. MODIFY Item #21 as follows- "...Scope of Work includes drilling, dowels, <u>new and existing foundation wall interface steel angles</u>, epoxy, fillers, grout, caulking, etc. As shown or required for a complete installation."
- 4. MODIFY Item #25 to add the following statement- "...This Subcontractor is responsible for coordination with BP-04 and the precast manufacturer/supplier as required for a complete installation."
- 5. MODIFY Item #54:"...will perform measurements within seventy-two (72) hours..."
- 6. ADD Item #82- "This Subcontractor is responsible for furnishing and installing all concrete for ornamental metal stairs. Pour stops shall be provided by BP-05A."

BP-04 MASONRY / PRECAST

- 1. MODIFY Item #7 to add the following statement- "...This Subcontractor is responsible for coordination with BP-03 and the precast manufacturer/supplier as required for a complete installation."
- 2. MODIFY Item #38 to add the following statement- "...This Subcontractor shall provide a professional caulker in accordance with the specifications for caulking within the masonry Scope of Work."
- 3. MODIFY Item #55 to add the following statement- "...This Subcontractor shall enlist the services of a Professional Engineer to provide engineered support for scaffolding and material loading at all locations not on a structural beam."

BP-05 STRUCTURAL STEEL

- 1. MODIFY Item #13 as follows- "This Subcontractor is responsible for furnishing and installing all diagonal braces, galvanized vertical support angles and galvanized precast lintel horizontal support angles and coordinate materials and supports with precast manufacturer. Refer to detail B/S-202 for an example of this condition."
- 2. MODIFY Item #16- "This Subcontractor is responsible..."
- 3. MODIFY Item #29 Adding the following statement- "...Details of corrections along with notes to be submitted for review by Engineer of Record for review prior to any corrections being performed."
- 4. MODIFY Item #34 as follows- "...required for head and jamb attachment of curtainwall/storefront / folding partitions / entrance systems..."
- 5. ADD Item #63- "Use and support of mechanical lifting devices, etc. On new and/or existing concrete slabs on grade and existing and/or new framed floor slabs are the responsibility of the

Addendum #2 Page 2 of 5

- subcontractor. Any repairs to damaged new and/or existing concrete slabs or framing is the responsibility of same contractor. Repairs to be submitted for review prior to any repair work."
- 5. ADD Item #64 "This Subcontractor is responsible for patching metal deck at all concrete infill locations, all upper floors. Reference structural plans and architectural demolition plans."

BP-05A MISCELLANEOUS METALS

- 1. MODIFY Item #5 as follows- "This Subcontractor is responsible for furnishing and installing all ornamental metal stairs <u>and associated pour stops</u>. Scope of Work includes all shop drawings, engineering, shop finishing, field measuring, samples, and field coordination with other trades, hardwood treads and wood handrails. <u>BP-03 will be responsible for providing concrete pan infill."</u>
- 2. MODIFY Item #10 as follows- "...A-302 for additional information. This Subcontractor is responsible for coordination with the owner's stained glass supplier/installer and BP-08 for a complete installation. This Subcontractor shall include a site visit to stained glass supplier's facility in Needham, MA prior to submission of shop drawings. Note: All stained glass will be furnished and installed by the owner's stained glass supplier/installer, with shims and wood trim coordinated and installed by BP-08 Subcontractor."

BP-07 ROOFING

1. MODIFY Item #4 as follows- "This Subcontractor will be responsible for furnishing and installing all concealed spray-on fireproofing, exposed fire-resistive coatings (intumescent paint), and sealers."

BP-08 CURTAINWALL / STOREFRONT / METAL PANELING & FIRE RATED GLASS ASSEMBLIES

- 1. MODIFY Item #5 to read- "This Subcontractor shall furnish and install all shims and wood trim required for a complete installation of stained glass windows. This Subcontractor is responsible for coordination with owner's stained glass supplier/installer and coordination with steel framing supports for stained glass furnished and installed by BP-05A. Coordination shall include a site visit to stained glass supplier's facility in Needham, MA prior to submission of shop drawings in order to field measure stained glass units to be installed. Refer to drawing A-302 for additional information."
- 2. MODIFY Item #12 as follows- "...Note: Fire rated assemblies specified in section 08 41 23 are limited to the following areas: <u>Stair A next to RM208 and Stair B next to RM493A."</u>
- 3. MODIFY Item #23 as follows- "This Subcontractor shall be responsible for engineering the windows, curtainwall, sunshade and eyebrow systems..."
- 4. MODIFY Item #40 as follows- "...providing all handicap push buttons and steel posts for and mounting of push buttons for each location."
- 5. MODIFY Item #66 as follows- "This Subcontractor shall provide a metal panel material allowance to be used for re-fabricating metal panels to be used at the discretion of Skanska. This Subcontractor shall assume 5% of total metal panel square footage."
- 6. MODIFY Item #80 Adding the following statement "...This Subcontractor shall enlist the services of a Professional Engineer to provide engineered support for scaffolding and material loading at all locations not on a structural beam""

BP-09 GYPSUM BOARD ASSEMBLIES

- 1. ADD within 'SCOPE OF WORK/SUPPLY:' Spec. Section 05 50 00 Miscellaneous Metals (As it Pertains to this Scope of Work)
- 2. Modify Item #7 as follows- "This Subcontractor will be responsible for modifying temporary first floor "floor protection" described in item #6 for installation of first floor framing. Modifications include cutting membrane as required to install metal stud framing then re-sealing membrane as required for a water tight seal."
- 3. ADD Item #95- "This Subcontractor is responsible for furnishing and installing all blocking required for toilet accessories. This Subcontractor shall coordinate with BP-10 Subcontractor. BP-10 shall provide all toilet accessories to this contractor for installation."
- 4. ADD Item #96- "This subcontractor is responsible for demolition and rework of ceilings required for HVAC ductwork tie in to existing system in ground floor corridor 001L, Elevators 098C/D lobbies, ground floor rooms 002, 003, 004, 005 and first floor corridor 100H. Reference mechanical drawings."

Addendum #2 Page 3 of 5

BP-09A ACOUSTICAL CEILINGS

1. ADD Item #25- "This subcontractor is responsible for demolition and rework of ceilings required for HVAC ductwork tie in to existing system in ground floor corridor 001L, Elevators 098C/D lobbies, ground floor rooms 002, 003, 004, 005 and first floor corridor 100H. Reference mechanical drawings."

BP-09D POURED TERRAZZO

1. OMIT Item #10- This Subcontractor is responsible for furnishing and installing all epoxy terrazzo stair treads at ornamental metal stairs. (Epoxy terrazzo stair treads omitted from project)

BP-13B FIRE ALARM

1. ADD Item #34- "This subcontractor shall assume that all wiring is plenum rated regardless of whether or not it is shown on the contract documents."

BP-15 PLUMBING

- 1. MODIFY Item #9, Add the following statement- "...This Subcontractor shall assume that all piping and accessories are plenum rated regardless of whether or not it is shown on the contract documents."
- 2. MODIFY Item #46 Add the following statement- "...Discharge piping shall be 2" threaded galvanized steel pipe discharged to site storm system."

BP-15A HVAC

- 1. ADD Item #103- "This subcontractor shall provide condensate drain piping from all air handlers to local floor drains in the associated mechanical rooms they reside per the mechanical schedules on M-300."
- 2. ADD Item #104- "This subcontractor shall be responsible for the removal and proper disposal of the existing chiller CH-2 located in mechanical room 205. Removal includes rigging and removal through the existing areaway."
- 3. ADD Item #105- "This subcontractor shall be responsible for the modification or addition to the refrigerant detection system, and shall provide refrigerant detection for both the existing chiller CH-1 and the new chiller CH-2 installation."
- 4. ADD Item #106- "This subcontractor shall assume that all wiring is plenum rated regardless of whether or not it is shown on the contract documents."

BP-15B HVAC INSTRUMENTATION AND CONTROLS

- 5. MODIFY Item #9 Add the following statement- "...All cabling to be plenum rated regardless of whether or not it is shown on the contract documents."
- 6. MODIFY Item #26 Add the following statement- "...This subcontractor shall provide lighting controls interface to the existing blue box systems and newly installed lighting control systems. Modify the blue boxes as required to facilitate control interface."
- 7. MODIFY Item #27 Add the following statement- "...This subcontractor shall provide exterior clock controls."

BP-16 ELECTRICAL

- 8. MODIFY Item #77 adding the following statement- "...This subcontractor shall include furnish and installation of four (4) temporary emergency lights at the ground level. Emergency lighting shall be wired back to the nearest emergency panel."
- 9. OMIT item #58- "This Subcontractor is responsible for furnishing and installing a complete fully operational Audio Visual System..."
- 10. ADD Item #97- "All wiring and cabling to be plenum rated whether or not it is shown on the contract documents."
- 11. ADD Item #98- "This subcontractor shall be responsible for making safe existing electrical room panels and providing temporary electrical room signage at the ground level prior to the start of construction activities."

III. SUBCONTRACTOR RFIs:

Subcontractor RFI's #1-159 are attached and incorporated into the Bid Documents.

Addendum #2 Page 4 of 5

IV. DRAWINGS AND SPECIFICATION CLARIFICATIONS/CHANGES:

- 1. AD-101 Omit Note- "Demo. Conc. Slab For Future Mechanical Shaft, See Structural Drawings" North of Elevator 098B. All other demo notes on AD-101 remain in the demolition plans, including demo of existing walls North of Elevator 098B. Mechanical shaft requires concrete cutting at floors 2, 3, and 4 only, as shown on structural drawings.
- 2. A-800 MODIFIED as follows- Door Schedule: Penthouse Floor Mechanical Room Door 501.1
 - a. Door A, Frame M3/A815
 - b. Jamb 6/A814
 - c. Head 1/A815
 - d. Sill 4/A320
- 3. A-812 MODIFIED as follows- Details 1, D1, D2, D3, D4 should be reference to drawing sheet A812, not A810.
- 4. ED-100 MODIFIED. Added note #11 clarifying loop splice.
- 5. A-102, A-103 and A-104 MODIFIED Core & Shell drawing note #12 revised to read: "E.C. shall install self-contained two lamp heads emergency lighting fixtures by McPhilben or approved equal, connected to the local normal power panels, for illumination levels of at least 2 ft.cd. at the floor level. The fixtures shall be spaced at approximately 40' on the perimeter and two fixtures at the stairwell doors, a total of approximately 12 units/floor."
- 6. Incorporate SCSU Buley Library Sketch Log with associated sketches issued via Addendum #2 as follows:
 - a. B-SKL-01 Added Site Plan Detail
 - b. B-SKA-01 Plaster Ceiling
 - c. B-SKA-02 Light Fixture
 - d. B-SKP-01 Sump Pump Clarifications
 - e. B-SKP-02 Sump Pump Clarifications
 - f. B-SKP-03 Fixture Schedule Revisions
 - g. B-SKP-04 Water Heater Schedule Revisions
 - h. B-SKM-01 AHU-5 Condensate Piping
 - i. B-SKM-02 AHU-1 Condensate Piping
 - j. B-SKM-03 AHU-3 Condensate Piping
 - k. B-SKM-04 Cooling Tower Overflow Drainl. B-SKM-05 Cooling Tower Schedule Revisions
 - m. B-SKE-01 Added GFI Outlet Near Reloc. Condensing Units Basement
 - n. B-SKE-02 Added Circuit to Room 214
 - o. B-SKE-03 Exist. Distribution Panel HD-4NEH-2 Sect. Revisions
 - p. B-SKE-04 Added Circuit to Cooling Tower 2
 - g. B-SKE-05 Lighting Fixture Schedule Revisions
 - r. B-SKE-06 Lighting Fixture Schedule Revisions
 - s. B-SKE-07 Demolition/Installation of Oil Filled Transformer
 - t. B-SKE-08 Demolition/Installation of Oil Filled Transformer

Bidders shall acknowledge receipt of Addendum 2 under 'Addenda' on page 2 of the bid form.

Sincerely, Skanska USA Building, Inc.

Kate Westrin, LEED® AP Project Manager

cc: Service Point USA at 85 Willow St., Bldg. 12. New Haven, CT

Skanska Share Site: https://partners.myskanska.com/usa/clients/scsu/Buley/SitePages/Home.aspx



Change Order Proposal Workbook Subcontractor



State of Cor	nnectic	ut							Departn	nent of Public Works
							Change C	rder Propos	al Number:	
To:	Gen	eral Contractor]	-		1/0/00
		contractor						Projec	ct Number:	.,,,,,
		Contractor				1		Proje	ct Number.	
Propo							Project Name			
Chai	nge:						and Location:			
Quantity	Unit		Propos	ed Ma	terial and/o	r Equipment		Unit Cost	Item Cost	
									-	
									-	
									-	
									-	
									-	
									-	
									-	
									-	
									-	
									-	
									-	
									-	
									-	
									-	
									-	
									-	
	ı	Jse Continuation W	orksheet M	-E for Ac	Iditional Materi	al(s) and/or Equipn	nent		-	
							Total Ma	aterial(s) and/or E	quipment Cost	-
Labo	r Cla	assification	No. of Workers	Total Hours	Prevailing Labor Rate	Taxes on Labor	Worker's Compensation	Hourly Cash Benefits	Labor Cost	
									-	
									-	
									-	
									-	
									-	
		Use Co	ontinuation \	Workshe	et LC for Addi	tional Labor Classif	ications		-	
									otal Labor Cost	-
								Total Material a	nd Labor Cost	\$ -
		_								
Subcon					000.00 20%		\$15,001.00 to \$2			
Overhe	ad ar	nd Profit	\$5,001.00) to \$15,	000.00 17%		\$25,000.00 an			
							l otal Subc	contractor's Overh		
								Total Subcontr	actor's Charge	\$ -
	Total Secondary Subcontractor's Cost									
	6% Subontractor's Mark-up on Secondary Subcontractor Cost -								-	
						Te	otal Proposed S	Subcontracto	or's Charge	\$ -
ATTEST:	The a	bove named subco	ntractor her	eby certi	fies to the bes	t of his/her knowled	dge and belief that th	e foregoing Char	nge Order Prop	osal Workbook is
	corre	ct				1				
	Ву:								i i	



DOCUMENT 00 01 10 - TABLE OF CONTENTS

VOLUME 1 OF 1

<u>Division 0 - PROCUREMENT AND CONTRACTING REQUIREMENTS</u>

00 11 16	Invitation to Bid
00 11 17	Subcontractor Acknowledgement of Bidding (Mandatory)
00 21 13	Instructions to Bidders ADDENDUM #2
00 24 13	Scopes of Work (Ref. Sec. 00 7000 Exhibit 'A' General Requirements)
00 31 13	Project Schedule / Construction Schedule Narrative ADDENDUM #2
00 31 19	Site Logistics Plan
00 31 19.1	SL-01 Campus Map
00 31 19.2	SL-02 Reserved
00 31 25	Existing Materials (Inventory Sheets for Existing Stored Materials) ADDENDUM #1
00 31 25.1	RCx Deficiency Issues Log & Proposed Energy Conservation Measures to Investigate
00 31 26.26	Existing Lead Information
00 41 00	Bid Proposal Form (Required at time of bid) ADDENDUM #2
00 43 13	AIA 310 Bid Bond Form (Required at time of bid)
00 43 28	SCSU Tax Exempt Certificate
00 43 39.1	CHRO Affirmative Action Plan
00 43 39.2	CHRO Attachment IIIA (Required at time of bid) ADDENDUM #1: Attachment not
	required
00 43 43	Certified Payroll & Contractors Wage Rate Certification Form (Required at time of bid)
00 45 13	Subcontractor Qualification Form (Required at time of bid)
00 45 19	Non-Collusive Affidavit (Required at time of bid)
00 45 19.1	State of Connecticut Guide to the Code of Ethics & OPM Ethics Form 6 (Required at time of bid)
00 61 13	Consent of Surety Form (Required at time of bid)
00 63 13	Request for Information (RFI) Form
00 63 57	Proposed Change Form
00 70 00	Skanska Sample Subcontractor Agreement (Exhibits A thru Y):
	Exhibit A Scope of Work (Ref. Sec. 00 2413 for Specific Requirements)
	Exhibit B Drawings Sketches Specifications & Other Documents ADDENDUM #1
	Exhibit C Alternates Unit Price & Labor Rates
	Exhibit D Project Schedule & Milestones
	Exhibit E Standard Subcontract Terms & Conditions
	Exhibit F Skanska Code of Conduct
	Exhibit G Skanska Insurance Requirements
	Exhibit H Interim Estimate for Payment, Waiver & Release
	Exhibit I Interim & Unconditional Waiver & Release of Liens & Claims
	Exhibit J Subcontractor Standard Subcontractor EH&S Requirements
	Exhibit K Skanska Standard Change Order
	Exhibit N Supplemental Terms & Conditions for use in the State of CT

TABLE OF CONTENTS ADDENDUM #2 1 of 2



Exhibit O Payment and Performance Bonds

Exhibit Q Skanska Standard Environmental Insurance Requirements

Exhibit U Subcontractor Identification

Exhibit V Guarantee to Owner

Exhibit X Site Requirements and Logistics

Exhibit Y Terms & Conditions for Subcontractor Design Responsibility

00 70 01 Standard Form of Agreement Between Owner and CMR

00 73 19 Skanska Safety & Health Management Program

00 73 43 Prevailing Wage Rates



INSTRUCTIONS TO BIDDERS

Table of Articles

- 1. Definitions
- 2. Bidder's Representations
- 3. Contract Documents
- 4. Bidding Procedures
- 5. Consideration of Bids
- 6. Post-Bid Information
- 7. Performance Bond and Payment Bond
- 8. Payroll
- 9. Labor Standards EEO
- 10. Non-Resident Bidders
- 11. Commission on Human Rights and Opportunities
- 12. LEED Certification Not Applicable to this project
- 13. Project Site Logistics
- 14. Construction Work Hours
- 15. Parking
- 16. Safety
- 17. Housekeeping
- 18. Insurance
- 19. Existing Materials (Inventory of Existing Stored Materials)



1. **DEFINITIONS**

- 1.1 Bid Documents shall be referred to as Contract Documents herein.
- 1.2 Contract Documents include; (1) 100% Construction Documents, Project Manual Volumes 1 & 2 dated November 30th, 2012; (2) Bid Set, Drawing Volumes 1 & 2 dated 11-30-2012; and (3) Division 0 Volume 1 dated December 21st, 2012.
- 1.3 Addenda are written or graphic instruments issued by the Construction Manager prior to the opening of bids, which modify or interpret the Contract Documents by additions, deletions, clarifications or corrections.
- 1.4 A Bid is a complete and properly executed proposal to do the Work for the sums stipulated therein, submitted in accordance with the Contract Documents.
- 1.5 A Unit Price is an amount stated in the Bid as a price per unit of measurement for materials, equipment or services or a portion of the Work as described in the Contract Documents. Subcontractors will be responsible accepting only those units pricing which are identified in Section 012000 1.5 Unit Price Schedules.
- 1.6 A Supplemental Bid is an amount stated in the Bid for materials, equipment and labor to complete the interior fit-out of an additional floor for each of the bid packages.
- 1.7 A Bidder is a person or entity who submits a Bid and who meets the requirements set forth in the Contract Documents.
- 1.8 A Sub-Subcontractor is a person or entity who submits a bid to a Bidder for materials, equipment or labor for a portion of the Work.

2. BIDDER'S REPRESENTATIONS

The Bidder by making a Bid represents that:

- 2.1 The Bidder has read and understands the Contract Documents, to the extent that such documentation relates to the Work for which the Bid is submitted, and for other portions of the Project, if any, being bid concurrently or presently under construction.
- 2.2 The Bid is made in compliance with the Contract Documents.
- 2.3 The Bidder has visited the site, become familiar with local conditions under which the Work is to be performed and has correlated the Bidder's personal observations with the requirements of the proposed Contract Documents.
- 2.4 The Bid is based upon the materials, equipment and systems required by the Contract Documents without exception.
- 2.5 A pre-bid meeting and walk through will be held on January 3, 2013 at 10 a.m. The pre-bid will be mandatory for all bidders. The pre-bid meeting will take place at the *Michael J. Adanti Student Center* located on the Southern CT State University Campus. Refer to Section 00 31 19.1 for a copy of the Campus Map. An optional walkthrough will be held at the construction site immediately following the pre-bid. Any subcontractor who fails to attend the pre-bid will



not be permitted to submit a proposal for the project. Bids received from a contractor who did not attend the meeting will be returned unopened within (7) days of the bid opening.

3. CONTRACT DOCUMENTS

3.1 COPIES

- 3.1.1 Contract Documents can be obtained on Wednesday, December 26th, 2012 at the following locations:
 - A. Bid Documents can be viewed from an online plan room prior to placing an order. The documents can be accessed using the following information:

Website: https://partners.myskanska.com/usa/clients/scsu/Buley/SitePages/Home.aspx

- B. Service Point USA at 85 Willow St., Bldg. 12. New Haven, CT 06511 Tel: 203-624-0079, Fax: 203-624-8533 for a non-refundable fee for approximately \$50 for a CD of all bid documents or \$450 for a complete hard copy (plus any taxes & delivery fees) to be paid by the bidder. Checks shall be made payable to Service Point USA. Bidders must call Service Point and order documents prior to pick-up (1 day in advance).
 - Bidders will be held accountable for the requirements of all documents made available and will not be relieved of responsibilities for requirements indicated in any bid documents not purchased or viewed.
- 3.1.2 Contract Documents will not be issued directly to Sub-bidders unless specifically offered in the Advertisement or Invitation to Bid, or in supplementary instructions to bidders.
- 3.1.3 Bidders shall use complete sets of Contract Documents in preparing Bids. Neither the Owner, Skanska, nor the Architect assumes responsibility for errors or misinterpretations resulting from the use of incomplete sets of Contract Documents.

3.2 INTERPRETATION OR CORRECTION OF CONTRACT DOCUMENTS

- 3.2.1 The Bidder shall carefully study and compare the Contract Documents with each other, and with other work being bid concurrently or presently under construction to the extent that it relates to the Work for which the Bid is submitted, shall examine the site and local conditions, and shall at once report to Skanska errors, inconsistencies or ambiguities discovered.
- 3.2.2 Bidders requiring clarification or interpretation of the Contract Documents shall make a written request within the time frame as noted in the Invitation to Bid.
- 3.2.3 Interpretations, corrections and changes of the Contract Documents will be made by Addendum. Interpretations corrections and changes of the Contract Documents made in any other manner will not be binding, and Bidders shall not rely upon them.

3.3 SUBSTITUTIONS

3.3.1 The materials, products and equipment described in the Contract Documents establish a standard of required function, dimension, appearance and quality to be met by the bidder for the Project.



3.3.2 **Substitutions** shall not be considered by the Architect after the project has bid. Each bidder shall utilize the specified manufacturers or equal where indicated in the Contract Documents. If a subcontractor wishes to submit a substitution for consideration during the bid phase of the project, substitution procedures outlined in Section 012500 of the project specifications must be followed or the substitution will not be considered.

3.4 ADDENDA

- 3.4.1 Notification of addenda will be transmitted to all bidders that have returned the Acknowledgement to Bid form to Skanska. In addition, notification of all addenda will also be posted on the DAS website.
- 3.4.2 Copies of Addenda will be made available for inspection wherever Contract Documents are on file.
- 3.4.3 Addenda will be issued no later than two (2) days prior to the date for receipt of Bids except Addendum withdrawing the request for Bids or one which includes postponement of the date for receipt of Bids.
- 3.4.4 Each Bidder shall ascertain prior to submitting a Bid that the Bidder has receive all Addenda issued, and the Bidder shall acknowledge their receipt in the Bid. It is not the responsibility of the Construction Manager to verify with each Bidder that it has received all Addenda issued.
- 3.4.5 No oral interpretation will be made to any Bidders as to the meaning of the Contract Documents or any part thereof. All questions must be directed in writing to Skanska USA Building Inc, Attention Ms. Kate Westrin, Skanska USA, Fax 866-435-9009 using the Request for Information Form Section 00 63 13 within the Contract Documents. Questions received verbally will not be answered. No questions will be accepted after Friday January 11th, 2013. All answers will be published by written addendum. Extensions of deadlines may only be revised via written addendum. It is the responsibility of all bidders to verify that they are current with all addenda issued with the printer prior to bid submission. Oral interpretation may not be relied upon.

4. BIDDING PROCEDURES

4.1 PREPARATION OF BIDS

- 4.1.1 Upon receipt of Contract documents the bidder shall review the Contract Documents to verify that all documents listed on the Table of Contents have been received. If any documents are missing, contact Ms. Kate Westrin, Skanska USA, Fax 866-435-9009
 - 4.1.1.1 Upon review of the Contract Documents the bidder will fill out, sign and return the Acknowledgement of Bid form by either faxing the form to 866-435-9009 or email to kate.westrin@skanska.com. Acknowledgement of Bid Form shall be sent no later than December 28th, 2012. Acknowledgement of Bid Form is mandatory.
- 4.1.2 Bids shall be submitted on the Bid Proposal Form furnished specifically for each bid package in this Project. Two (2) original Bid Proposal Forms shall be submitted with one



- (1) original Bid Bond for each bid package. Each proposal must also include the items listed at the end of the Bid Proposal Form.
- 4.1.3 All blanks on the bid form shall be legibly executed in a non-erasable medium. Submission of an incomplete Bid Proposal Form may be grounds for the rejection of the bid proposal by Skanska.
- 4.1.4 All requested **Supplemental Bids** shall be bid. If no change in the Bid is required, enter "Zero." No Supplemental Bid will be considered unless Supplemental Bids are specifically requested, and only those requested on the Bid Proposal Form will be considered.
- 4.1.5 Sums shall be expressed in both words and figures. In case of discrepancy, the amount written in words shall govern.
- 4.1.6 Each copy of the Bid shall state the legal name of the Bidder and the nature of legal form of the Bidder. The Bidder shall provide evidence of legal authority to perform within the jurisdiction of the Work. Each copy shall be signed by the person or persons legally authorized to bind the Bidder to a contract. A Bid by a corporation shall further give the state of incorporation and have the corporate seal affixed. A Bid submitted by an agent shall have a current power of attorney attached certifying the agent's authority to bind the Bidder.

4.2 BID SECURITY

- 4.2.1 Bidders shall note that Bid Securities are required for select bid packages. For those bid packages that require a bid security, each bid shall be accompanied by a bid security payable to Skanska USA Building Inc. in the amount of ten (10%) percent of the bid proposal and shall be written on AIA Document A310 Bid Bond and the attorney-in-fact who executes the bond on behalf of the surety shall affix to the bond a certified and current copy of the power of attorney. The bid bond must be issued by a Surety Company listed on the Current US Department of Treasury's Federal Register and be licensed to underwrite bonds in the State of Connecticut and have a rating of A- or better. *In lieu of a Bid Bond, the bidder has the option of submitting a certified check in the amount of 10% of the bid value or a letter of credit in the amount equal to 10% of the bid amount.*
- 4.2.2 Skanska will have the right to retain the bid security of Bidders to whom an award is being considered until either (a) the Contract has been executed and bonds, if required, have been furnished, or (b) the specified time has elapsed so that Bids may be withdrawn or (c) all Bids have been rejected.

4.3 SUBMISSION OF BIDS

- 4.3.1 All copies of the Bid, the bid security, if any, and any other documents required to be submitted with the Bid shall be enclosed in a sealed opaque envelope. The envelope shall be addressed to the party receiving the Bids, and shall be identified with the Project name, the Bidder's name and address and applicable bid package for which the Bid is submitted. *NOTE: Refer to item 4.3.5 of this section for all required attachments.*
- 4.3.2 Bids shall be deposited at the designated location prior to the time and date for receipt of Bids (Reference Invitation to Bid for location, date and time). Bids received after the time and date for receipt of Bids will be returned unopened.



- 4.3.3 The Bidder shall assume full responsibility for timely delivery at the location designated for receipt of Bids.
- 4.3.4 Oral, telephonic, telegraphic, facsimile or other electronically transmitted bids will not be considered.
- 4.3.5 A Bidder's proposal shall be considered nonresponsive if all proposal form attachments are not submitted at the time of bid. There are a total of nine (9) attachments required to be submitted including the proposal form. The required attachments are as follows and are located within Division 0 Bidding Requirements & Contractor Forms in the sections identified below.

	Proposal Form (Section 00 41 00)
	Skanska Qualification Form (Section 00 45 13)
	DAS Prequalification Certificate (If Bid is in excess of \$500,000) (Provided by Subcontractor)
	Bid Bond (Section 00 43 13)
	Consent of Surety (Section 00 61 13)
	Non-Collusion Affidavit (Section 00 45 19)
	State of Connecticut OPM Ethics Form 6 (Section 00 45 19.1)
	Contractors Wage Certification Form (Section 00 43 43)
\boxtimes	Reauirement Omitted via Addendum

4.4 MODIFICATION OR WITHDRAWAL OF BID

- 4.4.1 A Bid may not be modified, withdrawn, or cancelled by the Bidder for a period of ninety (90) days following the date designated for the receipt and opening of bids, and each Bidder so agrees in submitting a Bid.
- 4.4.2 Prior to the time and date designated for receipt of Bids, a Bid submitted may be modified or withdrawn by notice to the party receiving Bids at the place designated for receipt of Bids. Such notice shall be in writing over the signature of the Bidder. Written confirmation over the signature of the Bidder shall be received, and date- and time-stamped by the receiving party on or before the date and time set for receipt of Bids. A change shall be so worded as not to reveal the amount of the original Bid.
- 4.4.3 Withdrawn Bids may be resubmitted up to the date and time designated for the receipt of Bids provided that they are then fully in conformance with these Instructions to Bidders.

5. CONSIDERATION OF BIDS

5.1 OPENING OF BIDS

5.1.1 As stipulated in the Invitation to Bid, Bids received on Time will be opened by Skanska at the *Michael J. Adanti Student Center* located on the Southern CT State University Campus. Within seven (7) business days after award of subcontracts accepted bid results will be available for viewing by written request at Skanska's New Haven office. Requests should be sent to the attention of Ms. Kate Westrin, Skanska USA, Fax 866-435-9009

5.2 REJECTION OF BIDS



5.2.1 Skanska reserves the right to reject any or all bids including without limitation the right to reject any or all nonconforming, non-responsive, unbalanced, or conditional bids and to reject the bid of any bidder if Skanska determines that the bid is not responsive or the bidder is unqualified and or not responsible (which includes financial stability) or fails to meet any other pertinent standard or criteria established by Skanska. *Skanska reserves the right to waive minor irregularities which it considers in the best interest of the project.*

5.3 ACCEPTANCE OF BID (AWARD)

- 5.3.1 Skanska will have the right to award the Contract to any Bidder, and not necessarily the low bidder, and to waive informalities and irregularities in any Bid received if it is determined to be in the best interest of the Owner.
- 5.3.2 Skanska has the right to accept Supplemental Bids. Supplemental Bids will be taken in order as identified in the Bid Proposal Form.
- 5.3.3 The award of subcontracts for a specific bid package will be based on the lowest qualified and responsible base bid plus those Supplemental Bids selected. The selection of supplemental bids will be determined after the bid opening and is contingent on the available project funds.
- 5.3.4 The award of supplemental bids will be taken in order as they appear in section 6 of the Subcontractor Proposal Form. If project funds do not allow for a supplemental bid to be taken in its entirety, the owner reserves the right to add portions of the supplemental bid.

6. POST-BID INFORMATION

6.1 SUB-CONTRACTORS

- 6.1.1 Prior to the execution of the Contract, Skanska will notify the Bidder in writing if after due investigation, has reasonable objection to a person or entity proposed by the Bidder. If Skanska has reasonable objection to a proposed person or entity, the Bidder may, at the Bidder's option, (1) withdraw the Bid or (2) submit an acceptable substitute person with no adjustment in Base Bid price. In the event of either withdrawal or disqualification, bid security will not be forfeited. Reasonable objection may include but is not limited to review of qualifications on similar type projects, financial stability and past safety performance.
- 6.1.2 Persons and entities proposed by the Bidder and to whom Skanska has made no reasonable objection must be used on the Work for which they were proposed and shall not be changed except with the written consent of the Construction Manager.

6.2 SUPERINTENDENCE AND WORKERS

- 6.2.1 The Bidder will be required to establish to the satisfaction of Skanska the reliability and responsibility of the persons or entities proposed to furnish and perform the Work described in the Contract Documents.
- 6.2.2 The employment of a competent superintendent, foreman, and experienced mechanics will be required. The bidder shall furnish the qualifications of the superintendent, foreman, or any other individual delegated with important functions connected with the project to Skanska for approval.



- 6.2.3 Whenever Skanska informs the bidder or his/her representative in charge that any person on the work is incompetent, disorderly, working contrary to the specifications and/or the instructions of Skanska, or that Skanska knows that the person has been incompetent or disorderly on this or any previous work, or is objectionable, that person shall thereupon be immediately dismissed from the job and shall not be given employment on any work connected with the Contract.
- 6.2.4 All employees performing work on this project must receive OSHA 10-hr prior to starting work onsite. This includes but is not limited to; Project Managers, Superintendents, Safety Managers, Project Engineers, General Foremen, Foremen, Craftsmen, Apprentices and Laborers. All costs associated with providing this training will be the sole responsibility of this bidder. Training related information can be found at the following website: clicksafety.com.
- 6.2.5 The successful bidder shall have one (1) OSHA 30 hr trained employee on site at all times who has been certified within the past three years.

7. PERFORMANCE BOND AND PAYMENT BOND

- 7.1 Both the Performance Bond and the Labor and Material Payment Bond shall be in the amount of one-hundred percent (100%) of the Contract price payable to Skanska USA Building. (Determine value of subcontracts that may be exempt from providing P&P Bond)
- 7.2 Within seven (7) days after the receipt of the Contract Form, the successful bidder shall furnish both a Performance Bond and a Labor and Material Payment Bond. Failure to comply with this requirement will result in termination of contract
- 7.3 Bond forms shall be in accordance with those found in Exhibit "O" of the Subcontract.
- 7.4 Both Bonds must be issued by a Surety Company licensed to underwrite bonds in the State of Connecticut and have ab AM Best Rating of A- or better.
- 7.5 The cost shall be included in the Bid and is shown as a separate line item in the Proposal Form.

8. PAYROLL (PAYMENT OF WAGES)

8.1. Pursuant to General Statutes, Section 31-53, of the State of Connecticut, the following provision is hereby made part of these Contract Documents:

"The wages paid on an hourly basis to any mechanic, laborer or worker employed upon the work herein contracted to be done and the amount of payment or contribution paid or payable on behalf of each such employee to any employee welfare fund, as defined in Section 31-53 of the General Statutes, shall be at a rate equal to the rate (of wages) customary or prevailing for the same work in the same trade or occupation in the town in which such public works are being constructed. Any bidder who is not obligated by agreement to make payment or contribution on behalf of such employees to any such employee welfare fund shall pay to each employee as part of his wages the amount of payment or contribution for his classification on each pay day."

8.2 Attached is a copy of the minimum wage rate schedule issued by the State of Connecticut Labor Department. Said wage rate schedules shall be posted at the project site.



- 8.3 This bidder is cautioned that wage rates are continually changing. This bidder shall include all labor increases that occur during the duration of this project.
- 8.4 Periodic checks will be made by Skanska and or the Department of Labor to ensure that wages are being paid according to wage rate schedules for this particular job. Reference Exhibit A for additional information.

9. LABOR STANDARDS - EEO

9.1 All bidders employed on this project are required to implement an Equal Opportunity Program within their organization. Proper steps should be taken to establish a workforce which reflects non-discrimination in hiring practices due to race, color, creed, sex or national origin. All Federal and State Legislation on Equal Employment Opportunities will be adhered to in the carrying out of the contract.

10. NON-RESIDENT BIDDERS

- 10.1 The State of Connecticut requires non-resident bidders (contractors) to furnish 2 separate bonds with the State:
 - Connecticut General Statute 12-430(7) requires non-resident contractors to file a bond with the Commissioner of Revenue Services for Sales and Use taxes. This bond is for 5% of the contract amount.
 - Connecticut Public Act No. 80-250 Section 31-225 requires non-resident contractors to file a bond with the Administrator of the CT Department of Labor for Unemployment Compensation contributions if CT labor is to be used. This bond is for 3% of the contract amount.
- 10.2 A rider to the original bond or an additional bond must be filed for all amendments to the contract amount.
- 10.3 A non-resident contractor is defined as a contractor without a permanent place of business in the State of Connecticut.

11. CHRO - COMMISSION on HUMAN RIGHTS and OPPORTUNITUES

- 11.1 Bid solicitation for this project will be broken into two groups; Non-Set Aside Bid Packages and Set Aside Bid Packages.
- 11.2 Non-Set Bid Packages are open to only those bidders who have been prequalified by DAS Certified if Bid is in excess of \$500,000 (Reference Section 11.4 for additional information).
 - In addition to Skanska and DAS requirements, specific Non Set-Aside bidders are required to award twenty-five (25%) percent or more of the value of this Subcontract to DAS certified SBE's. These bidders shall also award fifteen (10%) percent or more to DAS certified M/WBE's. The Invitation to Bid names those specific Non Set-Aside bidders that must meet this requirement.
- 11.3 Set Aside Packages are only open to those bidders who have been (1) pre-approved by the State of Connecticut as an SBE, M/WBE, and (2) DAS Prequalified if Bid is in excess of \$500,000 (Reference Section 11.4 for additional information).



SBE Set Aside Packages are required to award five (5%) percent or more of the value of this Subcontract to DAS certified M/WBE's. The Invitation to Bid names those specific SBE Set Aside bidders that must meet this requirement.

11.4 The DAS Contractor Prequalification Program (C.G.S §4a-100) requires all bidders to prequalify before they can bid on a contract or perform work pursuant to a contract for the construction, reconstruction, alteration, remodeling, repair or demolition of any public building or any other public work by the state or a municipality, estimated to cost more than \$500,000 and which is funded in whole or in part with state funds, except a public highway or bridge project or any other construction project administered by the Department of Transportation. DAS prequalification is required for all work in excess of \$500,000 regardless of tier.

Any bid in excess of \$500,000 shall be accompanied by a copy of the bidder's prequalification certificate.

A prospective bidder whose bid does not exceed \$500,000 is not required to be pre-qualified by the State of Connecticut Department of Administrative Services for the classification of work that they are bidding.

11.5 The successful bidder shall participate and comply with all contract compliance regulations concerning contract compliance and approval of contract compliance programs by the Commission Human Rights and Opportunities (CHRO) Sections 46a-68j – 21 through 43 inclusive. Each subcontractor will be required to develop and implement a CHRO Affirmative Action Plan for the project. Refer to section 00 43 39.1and 00 43 39.2 of Division 0 "Instructions to Bidders" for additional information concerning the development and implementation of the CHRO plan.

12. LEED CERTIFICATION

12.1. Not applicable to the project. However, subcontractors will be required to meet all project specifications and requirements that make reference to LEED.

13. PROJECT SITE LOGISTICS

- 13.1. 00 31 19 Skanska Site Logistics Plan
- 13.2. 00 31 19.1 General Campus Map (Identifies Pre-Bid, Bid Opening and Subcontractor Parking Areas)
- 13.3. Reserved

14. CONSTRUCTION WORK HOURS

- 14.1. Normal work hours for construction are from 7:00 AM to 3:30 PM.
- 14.2. All subcontractors shall be responsible for the Project Schedule (Reference Section 003113). Subcontractors shall also be responsible for the schedule requirements set forth within their Specific Scope of Work (Reference Section 002413) and General Scope of Work (Section 0070 00).

15. PARKING

15.1. Onsite parking is limited due to space restrictions. Each subcontractor will be allowed one company vehicle onsite. All other vehicles will be required to park in Parking Lot 9. A shuttle bus service will be provided to transport workers from the parking lot to a drop off location



near the project site. Refer to section 00 31 19 for a copy of the campus map that identifies the parking and drop off location.

16. SAFETY

- 16.1 All subcontractors will be required to comply with Skanska USA Building Environmental Health and Safety (EHS) Policy. Reference Division 0 for Safety Policy
- 16.2. Subcontractor to provide EMR for the past 3 years at the time of bid. Please attach a letter from your insurance carrier verifying the EMR rate. Provide written explanation for EMR ratings over 1.00. The same is to be provided for sub-tier subcontractors.
- 16.3. All employees will be required to attend and participate in the Skanska Stretch & Flex Program. Skanska will conduct the Stretch & Flex Program at the beginning of every workday (7:00 am). The program will run for the duration of approximately fifteen minutes. The Subcontractor agrees that it has accounted for the same in the Subcontract Price set forth herein.

17. HOUSEKEEPING

17.1. Housekeeping is paramount. Subcontractors shall provide continuous cleanup of debris generated by its operations type. All subcontractors will be required to follow the "No material shall be allowed to hit the floor" policy.


18. INSURANCE

18.1 Before commencing the Work, the Subcontractor shall procure and maintain, at its own expense, until final acceptance of the Work and throughout the term of the warranty of the Work, at least the insurance as specified in Exhibit G of the Subcontract, included in the Contract Documents. The cost of all required insurance shall be included in the subcontractor's proposal.

19. EXISTING MATERIALS (Inventory Sheets for Existing Stored Materials)

- 19.1 Bidder has reviewed the Existing Inventory Materials list included in section 00 31 25 and has included those materials assigned to your specific bid package for use on this project. Bidder is responsible for the transportation of inventory materials from storage facilities to your shop for fabrication or to the project site for installation. Any unused materials assigned to your bid package will be the responsibility of this subcontractor to remove from storage and legally dispose of at no additional cost to the project unless specifically identified to be turned over to the owner at the completion of the project.
- 19.2. Refer to Section 00 31 25 for the different storage locations for existing materials.

END OF INSTRUCTIONS TO BIDDERS



	SKANSKA					
Activity ID	Activity Name		Original S Duration	Start		2012 2013 2014 2015 J J A S O N D J F M A M J J A S O N D J F M A M J J A S O N D J F M A M J J A S O N D
BID-1000	SKANSKA TO DEVELOP DIVISION () SPECS	40	23-Jul-12 A	03-Oct-12 A	SKANSKA TO DEVELOP DIVISION 0 SPECS
BID-1020	SKANSKA TO DEVELOP BID PACKA	AGES	50 2	23-Jul-12 A	03-Oct-12 A	SKANSKA TO DEVELOP BID PACKAGES
BID-1010	SKANSKA TO ISSUE DIVISION 0 TO	D DCS FOR APPROVAL	10 (04-Oct-12 A	04-Oct-12 A	SKANSKA TO ISSUE DIVISION 0 TO DCS FOR APPROVAL
BID-1040	SKANSKA TO FINALIZE DIV 0 & BID	PACKAGES	14 (03-Dec-12 A	20-Dec-12 A	SKANSKA TO FINALIZE DIV 0 & BID PACKAGES
BIDDING PHASE						
BIDPH-1000	SKANSKA TO ISSUE INVITATION TO) BID	1 2	21-Dec-12 A	21-Dec-12 A	I SKANSKA TO ISSUE INVITATION TO BID
BIDPH-1010	BID DOCUMENTS AVAILABLE TO B	IDDERS	6	24-Dec-12 A	02-Jan-13 A	■ BID DOCUMENTS AVAILABLE TO BIDDERS
BIDPH-1020	SKANSKA PRE BID MEETING		1 (03-Jan-13 A	03-Jan-13 A	SKANSKA PRE BID MEETING
BIDPH-1040	BID RFI SUBMISSION PERIOD		10 (03-Jan-13 A	16-Jan-13	■ BID RFI SUBMISSION PERIOD
BIDPH-1030	BID PERIOD		15 (03-Jan-13 A	23-Jan-13	BID PERIOD
BIDPH-1050	SKANSKA TO SUBMIT RFI'S TO OA	K	3	17-Jan-13	21-Jan-13	I SKANSKA TO SUBMIT RFI'S TO OAK
BIDPH-1060	OAK TO PROVIDE RFI RESPONSE	S	5 2	22-Jan-13	28-Jan-13	■ OAK TO PROVIDE RFI RESPONSES
BIDPH-1070	SKANSKA TO ISSUE ADDENDA TO	BIDDERS (RFI'S)	2 2	29-Jan-13	30-Jan-13	I SKANSKA TO ISSUE ADDENDA TO BIDDERS (RFI'S)
BIDPH-1080	REVISED BID DATE		7 :	31-Jan-13	08-Feb-13	■ REVISED BID DATE
GMP DEVELOPI	MENT / SUBMISSION PHASE					
GMP-1000	REVIEW SUBCONTRACTOR BID R	ESULTS	1	11-Feb-13	11-Feb-13	I REVIEW SUBCONTRACTOR BID RESULTS
GMP-1010	SUBCONTRACTOR SCOPE REVIE	WS	15	12-Feb-13	04-Mar-13	SUBCONTRACTOR SCOPE REVIEWS
GMP-1020	AWARD / RECOMMENDATIONS		1 (05-Mar-13	05-Mar-13	I AWARD / RECOMMENDATIONS
GMP-1030	PREPARE GMP		10 (05-Mar-13	19-Mar-13	■ PREPARE GMP
Remaining Level of Actual Work	Effort			LEY LIBRARY R		
Remaining Work Critical Remaining V Milestone	Work	PRELIMINARY CONSTRUCTION SCHEDU BL05 PAGE 2 OF 32 DATA DATE = 15-Jan-				SKANSKA

	SKANSKA								
Activity ID	Activity Name	Original Start Duration	Finish	2012 J J A S O N D J	2013 F M A M J J A S	ONDJFMA	2014 \ M J J A S O N D		015 JASON
GMP-1040	SUBMIT GMP TO DCS	1 19-N	Mar-13 19-Mar-	J J A S O N D J	I SUBMIT GMF	TO DCS			
GMP-1050	GMP REVISIONS (IF REQUIRED)	1 20-N	1ar-13 20-Mar-	13	ı GMP REVISI	ONS (IF REQU	JIRED)		
GMP-1060	FINAL GMP SUBMISSION	1 21-N	1ar-13 21-Mar-	13	I FINAL GMP S	SUBMISSION			
GMP-1070	GMP APPROVAL / EXECUTION	15 22-N	11-Apr-1	3	■ GMP APPR	OVAL / EXECU	TION		
GMP-1080	SUBCONTRACTOR NOTICE TO PROCEED	1 12-A	pr-13 12-Apr-1	3	I SUBCONTI	RACTOR NOTI	CE TO PROCEED		
SUBMITTAL PHAS	SE CONTRACTOR OF THE CONTRACTO								
SITE SUBMITTAL	S								++
SITESUB-1000	SUBMIT UTILITY PIPING AND UNDERGROUND S	STRUCTURES 20 15-A	pr-13 10-May-	13	SUBMIT (UTILITY PIPING	AND UNDERGRO	OUND STRUC	TURES
SITESUB-1010	MISC SITE SUBMITTALS	20 15-A	pr-13 10-May-	13	□ MISC SIT	E SUBMITTALS	8		
APPROVE SITE S	BUBMITTALS								
APP-1000	APPROVE UTILITY PIPING AND UNDERGROUNI	D STRUCTURES 15 22-A	pr-13 10-May-	13	□ APPROV	E UTILITY PIPII	NG AND UNDERG	ROUND STR	₹UCTURE\$
APP-1010	APPROVE MISC SITE SUBMITTALS	15 22-A	pr-13 10-May-	13	□ APPROV	E MISC SITE S	UBMITTALS		
FAB & DELIVER	SITE MATERIALS								
FAB-1000	FAB & START TO DELIVER PIPING & STRUCTUR	ES 10 13-N	1ay-13 24-May-	13	□ FAB & S	TART TO DELIV	VER PIPING & STI	RUCTURES	
FAB-1010	FAB & START TO DELIVER MISC SITE MATERIAL	S 10 13-N	1ay-13 24-May-	13	□ FAB & S	TART TO DELIV	VER MISC SITE M	ATERIALS	
CONCRETE SUB	MITALS								
CONSUB-1000	SUBMIT REBAR SHOP DRAWINGS	10 15-A	pr-13 26-Apr-1	3	□ SUBMIT R	EBAR SHOP D	RAWINGS		
CONSUB-1010	SUBMIT CONCRETE DESIGN MIXES	10 15-A	pr-13 26-Apr-1	3	□ SUBMIT C	ONCRETE DE	SIGN MIXES	-;;;;;;	
		RI II EV I	IBRARY RENOVATION	S					
Remaining Level of Actual Work	Remaining Level of Effort Actual Work								
Remaining Work Critical Remaining W	Vork		Y CONSTRUCTION SC DF 32 DATA DATE = 19			2	SKAN!	5KA	
◆ Milestone									

	SKANSKA			
Activity ID	Activity Name	Original Start Duration	Finish	2012 2013 2014 2015 3 3 3 3 4 5 5 6 7 7 7 7 7 7 7 7 7
CONSUB-1020	MISC CONCRETE SUBMITTALS	10 15-Apr-13	26-Apr-13	□ MISC CONCRETE SUBMITTALS
APPROVE CONCR	ETE SUBMITALS			
APP-1020	APPROVE REBAR SHOP DRAWINGS	15 22-Apr-13	10-May-13	□ APPROVE REBAR SHOP DRAWINGS
APP-1030	APPROVE CONCRETE DESIGN MIXES	15 22-Apr-13	10-May-13	□ APPROVE CONCRETE DESIGN MIXES
APP-1040	APPROVE MISC CONCRETE SUBMITTALS	15 22-Apr-13	10-May-13	□ APPROVE MISC CONCRETE SUBMITTALS
FAB & DELIVER CO	ONCRETE MATERIALS			
FAB-1030	FAB & START TO DELIVER CONCRETE	5 13-May-13	17-May-13	I FAB & START TO DELIVER CONCRETE
FAB-1040	FAB & START TO DELIVER MISC CONCRETE MATERIAL	5 13-May-13	17-May-13	I FAB & START TO DELIVER MISC CONCRETE MATERIAL
FAB-1020	FAB AND START TO DELIVER REBAR	7 13-May-13	21-May-13	□ FAB AND START TO DELIVER REBAR
STRUCTURAL STE	EL SUBMITTALS			
STEELSUB-1030	FIELD MEASURE EXISTING STEEL AT COLUMN LINES X-9 AND X-4	5 15-Apr-13	19-Apr-13	☐ FIELD MEASURE EXISTING STEEL AT COLUMN LINES X-9 AND X-4
STEELSUB-1000	STRUCTURAL STEEL SUBMITTALS	20 15-Apr-13	10-May-13	□ STRUCTURAL STEEL SUBMITTALS
STEELSUB-1010	METAL DECKING SUBMITTALS	20 15-Apr-13	10-May-13	☐ METAL DECKING SUBMITTALS
STEELSUB-1020	MISC STEEL SUBMITTALS	10 29-Apr-13	10-May-13	□ MISC STEEL SUBMITTALS
APPROVE STRUC	TURAL STEEL SUBMITTALS			
APP-1050	APPROVE STRUCTURAL STEEL SUBMITTALS	15 22-Apr-13	10-May-13	□ APPROVE STRUCTURAL STEEL SUBMITTALS
APP-1060	APPROVE METAL DECKING SUBMITTALS	15 22-Apr-13	10-May-13	□ APPROVE METAL DECKING SUBMITTALS
APP-1070	APPROVE MISC STEEL SUBMITTALS	15 06-May-13	24-May-13	■ APPROVE MISC STEEL SUBMITTALS
	.	,	·	
Remaining Level of Eff	ort	BULEY LIBRARY I	RENOVATIONS	
Actual Work Remaining Work		PRELIMINARY CONST	RUCTION SCHED	SKANSKA
Critical Remaining Wor	rk	BL05 PAGE 4 OF 32 DA	ATA DATE = 15-Jan	
◆ Milestone				

	SKANSKA				
Activity ID	Activity Name	Original Start Duration	Finish	2012	2013 2014 2015 M A M J J A S O N D J F M A M J J A S O N D J F M A M J J A S O N D
FAB & DELIVER S	STRUCTURAL STEEL MATERIALS				
FAB-1050	FAB & START TO DELIVER STRUCTURAL STEEL	20 13-May-13	10-Jun-13		FAB & START TO DELIVER STRUCTURAL STEEL
FAB-1060	FAB & START TO DELIVER METAL DECKING	20 13-May-13	10-Jun-13	-	FAB & START TO DELIVER METAL DECKING
MASONRY SUBM	IITTALS				
MACHE 4000	OMIL & BRIOK OURMITTAL O	00 45 4 40	40.14		□ CMU & BRICK SUBMITTALS
MASUB-1000	CMU & BRICK SUBMITTALS	20 15-Apr-13	10-May-13		LIVIU & BRICK SUBIVITIALS
MASUB-1010	MISC MASONRY SUBMITTALS	10 29-Apr-13	10-May-13		□ MISC MASONRY SUBMITTALS
APPROVE MASO	DNRY SUBMITTALS				
APP-1080	APPROVE CMU & BRICK SUBMITTALS	15 22-Apr-13	10-May-13		□ APPROVE CMU & BRICK SUBMITTALS
		· ·			
APP-1090	APPROVE MISC MASONRY SUBMITTALS	15 06-May-13	24-May-13		□ APPROVE MISC MASONRY SUBMITTALS
FAB & DELIVER I	MASONRY MATERIALS				
				1	
FAB-1080	FAB & START TO DELIVER CMU / BRICK	20 13-May-13	10-Jun-13		☐ FAB & START TO DELIVER CMU / BRICK
		20 10 May 10	10 0011 10		
METAL PANEL S	UBMITTALS				
MPSUB-1000	METAL PANEL SUBMITTALS	20 15-Apr-13	10-May-13		■ METAL PANEL SUBMITTALS
MPSUB-1010	MISC METAL PANEL SUBMITTALS	10 29-Apr-13	10-May-13	1	□ MISC METAL PANEL SUBMITTALS
APPROVE META	L PANEL SUBMITTALS				
APP-1100	APPROVE METAL PANEL SUBMITTALS	15 22-Apr-13	10-May-13		APPROVE METAL PANEL SUBMITTALS
		, ,			
Remaining Level of I	Effort	BULEY LIBRARY F	RENOVATIONS		
Actual Work		PRELIMINARY CONST	RUCTION SCHED	JLE	CVANCVA
Remaining Work Critical Remaining W	Vork	BL05 PAGE 5 OF 32 DA	TA DATE = 15-Jan	-13	SKANSKA
◆ Milestone					

	SKANSKA		_	
Activity ID	Activity Name	Original Start Duration	Finish	2012 2013 2014 2015
APP-1110	APPROVE MISC METAL PANEL SUBMITTALS	15 06-May-13	24-May-13	JJASONDJEMAMJJASONDJEMAMJJASONDJEMAMJJASOND APPROVE MISC METAL PANEL SUBMITTALS
FAB & DELIVER M	IETAL PANEL SUBMITTALS			
FAB-1100	FAB & DELIVER METAL PANELS	40 13-May-13	09-Jul-13	FAB & DELIVER METAL PANELS
CURTAIN WALL AN	ND WINDOW SUBMITTALS			
CWSUB-1000	CURTAIN WALL & WINDOW SUBMITTALS	20 15-Apr-13	10-May-13	CURTAIN WALL& WINDOW SUBMITTALS
CWSUB-1010	MISC CURTAIN WALL SUBMITTALS	10 29-Apr-13	10-May-13	□ MISC CURTAIN WALL SUBMITTALS
APPROVE CURTA	IN WALL AND WINDOW SUBMITTALS			
APP-1120	APPROVE CURTAIN WALL & WINDOW SUBMITTALS	15 22-Apr-13	10-May-13	□ APPROVE CURTAIN WALL & WINDOW SUBMITTALS
APP-1130	APPROVE MISC CURTAIN WALL SUBMITTALS	15 06-May-13	24-May-13	□ APPROVE MISC CURTAIN WALL SUBMITTALS
FAB & DELIVER C	URTAIN WALL MATERIALS			
FAB-1120	FAB & DELIVER CURTAIN WALLS	60 13-May-13	02-Aug-13	FAB & DELIVER CURTAIN WALLS
MECHANICAL SUE	BMITTALS			
MECHSUB-1000	MECHANICAL EQUIPMENT SUBMITTALS	20 15-Apr-13	10-May-13	☐ MECHANICAL EQUIPMENT SUBMITTALS
MECHSUB-1010	GENERAL MECHANICAL SUBMITTALS	10 29-Apr-13	10-May-13	□ GENERAL MECHANICAL SUBMITTALS
APPROVE MECHA	ANICAL SUBMITTALS			
APP-1140	APPROVE MECHANICAL EQUIPMENT SUBMITTALS	15 22-Apr-13	10-May-13	□ APPROVE MECHANICAL EQUIPMENT SUBMITTALS
Remaining Level of Ef	ffort	BULEY LIBRARY F	RENOVATIONS	
Actual Work Remaining Work		PRELIMINARY CONSTI	RUCTION SCHEDI	SKANSKA
Critical Remaining Wo	ork	BL05 PAGE 6 OF 32 DA	TA DATE = 15-Jan	
Williostorio				

	SKANSKA					
Activity ID	Activity Name	Origina Duration		Finish	2012	2013 2014 2015 D LEMAM J LASOND LEMAM J LASOND LEMAM J LASONI
APP-1150	APPROVE GENERAL MECHANICAL SUBMITTALS	15	06-May-13	24-May-13		JFMAMJJASONDJFMAMJJASONDJFMAMJJASONI APPROVE GENERAL MECHANICAL SUBMITTALS
FAB & DELIVER M	MECHANICAL MATERIALS					
FAB-1140	FAB & DELIVER MECHANICAL EQUIPMENT	80	13-May-13	30-Aug-13		FAB & DELIVER MECHANICAL EQUIPMENT
FAB-1150	FAB & DELIVER MISC MECHANICAL MATERIALS	20	28-May-13	24-Jun-13		FAB & DELIVER MISC MECHANICAL MATERIALS
ELECTRICAL SUE	BMITTALS					
ELECSUB-1000	ELECTRICAL EQUIPMENT SUBMITTALS	20	15-Apr-13	10-May-13		= ELECTRICAL EQUIPMENT SUBMITTALS
ELECSUB-1010	ELECTRICAL LIGHTING FIXTURE SUBMITTALS	20	15-Apr-13	10-May-13		ELECTRICAL LIGHTING FIXTURE SUBMITTALS
ELECSUB-1020	GENERAL ELECTRICAL SUBMITTALS	10	29-Apr-13	10-May-13		☐ GENERAL ELECTRICAL SUBMITTALS
APPROVE ELECT	RICAL SUBMITTALS	,				
APP-1160	APPROVE ELECTRICAL EQUIPMENT SUBMITTALS	15	13-May-13	03-Jun-13		☐ APPROVE ELECTRICAL EQUIPMENT SUBMITTALS
APP-1170	APPROVE ELECTRICAL LIGHTING FIXTURE SUBMIT	TALS 15	13-May-13	03-Jun-13		☐ APPROVE ELECTRICAL LIGHTING FIXTURE SUBMITTALS
APP-1180	APPROVE GENERAL ELECTRICAL SUBMITTALS	15	13-May-13	03-Jun-13		☐ APPROVE GENERAL ELECTRICAL SUBMITTALS
FAB & DELIVER E	LECTRICAL MATERIALS					
FAB-1180	FAB & DELIVER GENERAL ELECTRIC MATERIALS	20	04-Jun-13	01-Jul-13		FAB & DELIVER GENERAL ELECTRIC MATERIALS
FAB-1170	FAB & DELIVER LIGHT FIXTURES	60	04-Jun-13	23-Aug-13		FAB & DELIVER LIGHT FIXTURES
FAB-1160	FAB & DELIVER ELECTRICAL EQUIPMENT	80	04-Jun-13	23-Sep-13		FAB & DELIVER ELECTRICAL EQUIPMENT
PLUMBING SUBM	IITTALS	,				
Remaining Level of E	ffort	E	BULEY LIBRARY F	RENOVATIONS		
Actual Work Remaining Work		PREL	IMINARY CONST	RUCTION SCHED	ULE	SKANSKA
Critical Remaining We ♦ Milestone	ork	BL05 P	AGE 7 OF 32 DA	TA DATE = 15-Jar	n-13	

	SKANSKA			
Activity ID	Activity Name	Original Start Duration	Finish	2012 2013 2014 2015
PLMGSUB-1000	PLUMBING EQUIPMENT SUBMITTALS	20 15-A	Apr-13 10-May-13	JJASONDJEMAMJJASONDJEMAMJJASONDJEMAMJJASOND — PLUMBING EQUIPMENT SUBMITIALS
PLMGSUB-1010	PLUMBING FIXTURE SUBMITTAL	20 15- <i>A</i>	Apr-13 10-May-13	
PLMGSUB-1020	GENERAL PLUMBING SUBMITTALS	10 29-A	Apr-13 10-May-13	☐ GENERAL PLUMBING SUBMITTALS
APPROVE PLUME	BING SUBMITTALS			
APP-1190	APPROVE PLUMBING EQUIPMENT SUBMITTALS	15 22- <i>A</i>	Apr-13 10-May-13	□ APPROVE PLUMBING EQUIPMENT SUBMITTALS
APP-1200	APPROVE PLUMBING FIXTURE SUBMITTAL	15 22- <i>A</i>	Apr-13 10-May-13	□ APPROVE PLUMBING FIXTURE SUBMITTAL
APP-1210	APPROVE GENERAL PLUMBING SUBMITTALS	15 06-N	May-13 24-May-13	■ APPROVE GENERAL PLUMBING SUBMITTALS
FAB & DELIVER P	LUMBING MATERIALS			
FAB-1190	FAB & DELIVER PLUMBING EQUIPMENT	40 13-N	May-13 09-Jul-13	FAB & DELIVER PLUMBING EQUIPMENT
FAB-1200	FAB & DELIVER PLUMBING FIXTURES	40 13-1	May-13 09-Jul-13	FAB & DELIVER PLUMBING FIXTURES
FAB-1210	FAB & DELIVER GENERAL PLUMBING MATERIALS	20 28-1	May-13 24-Jun-13	☐ FAB & DELIVER GENERAL PLUMBING MATERIALS
MILLWORK SUBM	IITTALS			
MILLSUB-1000	MILLWORK SUBMITTALS	10 15- <i>A</i>	Apr-13 26-Apr-13	□ MILLWORK SUBMITTALS
MILLSUB-1010	MISC MILLWORK SUBMITTALS	10 22- <i>A</i>	Apr-13 03-May-13	II MISC MILLWORK SUBMITTALS
APPROVE MILLW	ORK SUBMITTALS			
APP-1220	APPROVE MILLWORK SUBMITTALS	15 29- <i>A</i>	Apr-13 17-May-13	□ APPROVE MILLWORK SUBMITTALS
APP-1230	APPROVE MISC MILLWORK SUBMITTALS	15 06-N	May-13 24-May-13	■ APPROVE MISC MILLWORK SUBMITTALS
FAB & DELIVER M	IILLWORK MATERIALS			
Remaining Level of Ef	ffort	BULEY	LIBRARY RENOVATIONS	
Actual Work		PRELIMINAF	RY CONSTRUCTION SCHED	
Remaining Work Critical Remaining Wo	ork	BL05 PAGE 8	OF 32 DATA DATE = 15-Ja	SKANSKA
◆ Milestone				

	SKANSKA			
Activity ID	Activity Name	Original Start Duration	Finish	2012 2013 2014 2015 J J A S O N D J F M A M J J A S O N D D D D D D D D D D D D D D D D D D
FAB-1220	FAB & DELIVER MILLWORK	40 28-May-13	23-Jul-13	FAB & DELIVER MILLWORK
ACCOUSTIC CEIL	LING SUBMITTALS			
ACCCUD 1000		10 15 Am 10	00 Apr 10	□ SUBMIT ACCOUSTIC CEILING MATERIALS
ACCSUB-1000	SUBMIT ACCOUSTIC CEILING MATERIALS	10 15-Apr-13	26-Apr-13	E GODIVITI ADOGOCITO CETENINA MALETIALO
APPROVE ACCO	USTIC CEILINGS SUBMITTALS			
APP-1240	APPROVE ACCOUSTIC CEILING MATERIALS	15 29-Apr-13	17-May-13	□ APPROVE ACCOUSTIC CEILING MATERIALS
FAB & DELIVER A	ACCOUSTIC CEILING MATERIALS			
FAB-1230	FAB & DELIVER ACCOUSTIC CEILING MATERIALS	30 20-May-13	01-Jul-13	FAB & DELIVER ACCOUSTIC CEILING MATERIALS
FLOORING SUBM	MITTALS			
FLRSUB-1000	SUBMIT FLOORING MATERIALS	10 15-Apr-13	26-Apr-13	□ SUBMIT FLOORING MATERIALS
FLRSUB-1010	SUBMIT MISC FLOORING MATERIALS	10 22-Apr-13	03-May-13	I SUBMIT MISC FLOORING MATERIALS
APPROVE FLOO	RING SUBMITTALS			
APP-1250	APPROVE FLOORING MATERIALS	15 29-Apr-13	17-May-13	☐ APPROVE FLOORING MATERIALS
APP-1260	APPROVE MISC FLOORING MATERIALS	15 06-May-13	24-May-13	■ APPROVE MISC FLOORING MATERIALS
FAB & DELIVER I	FLOORING MATERIALS			
FAB-1240	FAB & DELIVER FLOORING MATERIALS	40 28-May-13	23-Jul-13	FAB & DELIVER FLOORING MATERIALS
Remaining Level of I	Effort	BULEY LIBRARY F		
Actual Work Remaining Work Critical Remaining W	Vork	PRELIMINARY CONSTI		SKANSKA
◆ Milestone				

	SKANSKA																	
Activity ID	Activity Name		Original Duration	Start	Finish	2012 J J A	SOND	JFM)13 J A S	ONDJ	F M A M	2014 J J A S	sloluli	D J F I		2015 J J A S	SOND
CONSTRUCTION	PHASE																9 9 7 7 1 9	
MOBILIZE																		
MOB-170	CONSTRUCTION TIMEFRAME BEG	BINS	1	12-Apr-13	12-Apr-13				I CON	NSTRU(CHONT	MEFRAM	E BEGII	NS				
MOB-130	NOTIFY CBYD		3	12-Apr-13	16-Apr-13				I NO	TIFY CE	3YD							
MOB-100	MOBILIZE ON SITE		10	12-Apr-13	25-Apr-13	1			■ MO	BILIZE	ON SITE							
MOB-110	INSTALL CONSTRUCTION FENCIN	G	10	12-Apr-13	25-Apr-13	-			■ INS	TALL C	ONSTRI	JCTION F	ENCINO	3				
MOB-120	INSTALL EROSION CONTROLS			12-Apr-13	25-Apr-13				INIS	ΤΔΙΙ Ε	BOSION	CONTRO	N S					
				•	•									a				
MOB-150	INSTALL TREE PROTECTION IF RE	EQUIRED	2	19-Apr-13	22-Apr-13				I INS	IALL I	REE PRO	OTECTIO	N IF RE	QUIRE	D			
MOB-140	ESTABLISH TRUCK WASH STATIO	NS	5	19-Apr-13	25-Apr-13				I ES	TABLIS	H TRUCI	(WASH S	TATION	18				
MOB-160	PROTECT EXIST MEP EQUIP IN B.	ASEMENT AS REQUIRED	10	19-Apr-13	02-May-13				■ PR	ROTECT	TEXIST	MEP EQU	IP IN B	ASEME	NTAS	REQU	IRED	
FOUNDATIONS																		
												·						
										EN401/F	- FVIOTI		/ EVO 4\	/h	OD 45	NIEVA/ 14		
FOUN-150	REMOVE EXISTING SLAB / EXCAVA FOOTINGS	ATE FOR 15 NEW ISOLATED	10	03-May-13	16-May-13							NG SLAB					SOLATE	D FOO
FOUN-300	FORM / REBAR POUR NEW INTER	IOR FOOTINGS	10	17-May-13	31-May-13				□ F	FORM /	REBAR	POUR NE	W INTE	RIOR	FOOT	INGS		
FOUN-310	CONSTRUCT NEW FOUNDATIONS	S AT COLUMN LINE X12	15	03-Jun-13	21-Jun-13				•	CONS	TRUCT	NEW FOL	INDATIO	ONS AT	COLL	JMN LI	NE X12	
INTERIOR DEMO	LITION																	
DEMO-150	RE-CONFIGURE EXISTING WATER	R LINE	5	03-May-13	09-May-13				ı RE	-CONF	FIGURE	EXISTING	WATER	RLINE				
DEMO-140	REMOVE EXISTING CMU SHAFT / MECHANICAL SHAFT	CUT FLOORS FOR NEW	10	03-May-13	16-May-13				□ R	EMOVE	EXISTI	NG CMU S	SHAFT /	CUTF	LOOR	SFOR	NEW	/IECHAN
DEMO-130	SAWCUT / REMOVE EXISTING SLA		25	03-May-13	07-Jun-13					SAWC	JT / REM	OVE EXIS	STING S	SLABS	AS RE	QUIRE	D FOR	NEW O
DEMO-100	OPENINGS (SHORE EXISTING SL DEMO EXISTING PLUMBING AS RE		25	10-May-13	14-Jun-13	-				DEMO	EXISTIN	G PLUME	ING AS	REQL	JIRED	ALL FLO	OORS	
]			<u> </u>		<u> </u>	<u>: </u>	<u> </u>	<u> </u>	<u> </u>	<u> </u>	<u> </u>	<u> </u>	<u> </u>	<u> </u>
	F(f)		RI	ULEY LIBRARY R	RENOVATIONS					<u> </u>								
Remaining Level of Actual Work	EIIOT					JLE										7.5		
Remaining Work Critical Remaining	Mark	F	PRELIMINARY CONSTRUCTION SCHEDULE BL05 PAGE 10 OF 32 DATA DATE = 15-Jan-13									5	KA	N:	5 K	A		
Milestone	AA OLK				2 = 10 0ui	•												

	SKANSKA				
Activity ID	Activity Name	Original Start Duration	Finish	2012 J J A S O N D J F M A	2013 2014 2015 M J J A S O N D J F M A M J J A S O N D J F M A M J J A S O N D
DEMO-110	DEMO EXISTING MECHANICAL AS REQUIRED ALL FLOORS	25 10-May-13	14-Jun-13		DEMO EXISTING MECHANICAL AS REQUIRED ALL FLOORS
DEMO-120	DEMO EXISTING ELECTRICAL AS REQUIRED ALL FLOORS	25 10-May-13	14-Jun-13		DEMO EXISTING ELECTRICAL AS REQUIRED ALL FLOORS
DEMO-160	REMOVE LEAD PAINT FROM EXISTING STAIR STRINGERS AS REQUIRED	5 10-Jun-13	14-Jun-13		■ REMOVE LEAD PAINT FROM EXISTING STAIR STRINGERS AS RE
STRUCTURE					
STR-530	FIELD MEASURE EXISTING STEEL AS REQUIRED	5 10-May-13	16-May-13		■ FIELD MEASURE EXISTING STEEL AS REQUIRED
STR-460	LAYOUT AND MARK EXISTING STEEL FRAMING FOR NEW STEEL CONNECTIONS	15 10-May-13	31-May-13		☐ LAYOUT AND MARK EXISTING STEEL FRAMING FOR NEW STEEL
STR-470	REMOVE EXISTING LEAD PAINT AT NEW STEEL CONNECTION LOCATIONS	30 14-May-13	25-Jun-13		REMOVE EXISTING LEAD PAINT AT NEW STEEL CONNECTION L
STR-480	ERECT NEW STRUCTURAL STEEL BETWEEN COLUMN LINES A-F, 2-9	10 21-May-13	04-Jun-13	7	□ ERECT NEW STRUCTURAL STEEL BETWEEN COLUMN LINES A-F
STR-490	ERECT NEW STEEL DECKING BETWEEN COLUMN LINES A-F, 2-9	10 29-May-13	11-Jun-13		□ ERECT NEW STEEL DECKING BETWEEN COLUMN LINES A-F, 2-9
STR-500	PLACE CONCRETE AT METAL DECKS BETWEEN COLUMN LINES A-F, 2-9	10 05-Jun-13	18-Jun-13		□ PLACE CONCRETE AT METAL DECKS BETWEEN COLUMN LINES
STR-410	STRUCTURAL STEEL INFILLS (FLR'S 1,2,3,4,PH)	25 10-Jun-13	15-Jul-13		STRUCTURAL STEEL INFILLS (FLR'S 1,2,3,4,PH)
STR-420	INSTALL METAL DECKING (FLR'S 1,2,3,4 .PH)	25 14-Jun-13	19-Jul-13		INSTALL METAL DECKING (FLR'S 1,2,3,4 .PH)
STR-450	INSTALL METAL DECK / CONCRETE @ PERIMETER INFILL	25 17-Jun-13	22-Jul-13		install metal deck/congrete@perimeter infill
STR-430	PLACE CONCRETE AT METAL DECKS	25 21-Jun-13	26-Jul-13		PLACE CONCRETE AT METAL DECKS
STR-510	INSTALL ALL REQUIRED TEMPORARY STORM DRAINAGE PIPING	10 28-Jun-13	12-Jul-13		■ INSTALLALL REQUIRED TEMPORARY STORM DRAINAGE PIPIN
STR-520	SPRAY FIREPROOFING AT PERIMETER STEEL AS RERQUIRED	10 28-Jun-13	12-Jul-13		SPRAY FIREPROOFING AT PERIMETER STEEL AS RERQUIRED
STR-440	SPRAY FIREPROOFING AT INTERIOR STEEL AS REQUIRED	15 15-Jul-13	31-Jul-13		SPRAY FIREPROOFING AT INTERIOR STEEL AS REQUIRED
GROUND LEVEL	EXTERIOR VENEER				
GLEXTV-460	ERECT CMU BACKUP WALLS	15 08-Jul-13	26-Jul-13		■ ERECT CMU BACKUP WALLS
GLEXTV-510	INSTALL EXTERIOR WATERPROOFING/ INSULATION	15 15-Jul-13	31-Jul-13	-	■ INSTALL EXTERIOR WATERPROOFING/INSULATION
				_[
Remaining Level of	Effort	BULEY LIBRARY	RENOVATIONS		
Actual Work		PRELIMINARY CONS	TRUCTION SCHED	ULE	
Remaining Work Critical Remaining V	Work	BL05 PAGE 11 OF 32 D			SKANSKA
◆ Milestone					

	SKANSKA					
Activity ID	Activity Name	Original Duration	Start	Finish	2012	2013 2014 2015 F M A M J J A S O N D J F M A M J J A S O N D J F M A M J J A S O N D
GLEXTV-470	ERECT MASONRY / PRECAST VENEER	12	25-Jul-13	07-Aug-13		■ ERECT MASONRY / PRECAST VENEER
GLEXTV-490	ERECT CURTAIN WALLS	20	08-Aug-13	05-Sep-13		ERECT CURTAIN WALLS
GLEXTV-560	INSTALL PUNCH WINDOWS	5	29-Aug-13	05-Sep-13		1 INSTALL PUNCH WINDOWS
SOUTH ELEVATION	ON EXTERIOR VENEER (LVLS 2-ROOF)					
SEXTV-1000	ERECT CMU BACKUP WALLS	15	27-Jul-13	14-Aug-13		□ ERECT CMU BACKUP WALLS
SEXTV-1010	INSTALL EXTERIOR WATERPROOFING/ INSULATION	15	01-Aug-13	21-Aug-13		☐ INSTALL EXTERIOR WATERPROOFING/ INSULATION
SEXTV-1020	ERECT MASONRY / PRECAST VENEER	12	13-Aug-13	28-Aug-13		■ ERECT MASONRY / PRECAST VENEER
EXTV-530	INSTALL METAL PANELS	20	29-Aug-13	26-Sep-13		□ INSTALL METAL PANELS
SEXTV-1030	ERECT CURTAIN WALLS / SUNSCREENS	20	06-Sep-13	03-Oct-13		ERECT CURTAIN WALLS / SUNSCREENS
SEXTV-1040	INSTALL PUNCH WINDOWS	5	27-Sep-13	03-Oct-13		I INSTALL PUNCH WINDOWS
WEST ELEVATIO	ON EXTERIOR VENEER (LVLS 2-ROOF)					
WEXTV-1000	ERECT CMU BACKUP WALLS	17	15-Aug-13	09-Sep-13		■ ERECT CMU BACKUP WALLS
WEXTV-1010	INSTALL EXTERIOR WATERPROOFING/ INSULATION	17	22-Aug-13	16-Sep-13		☐ INSTALL EXTERIOR WATERPROOFING/ INSULATION
WEXTV-1020	ERECT MASONRY / PRECAST VENEER	15	03-Sep-13	23-Sep-13		■ ERECT MASONRY / PRECAST VENEER
WEXTV-1030	INSTALL METAL PANELS	20	24-Sep-13	22-Oct-13		☐ INSTALL METAL PANELS
WEXTV-1040	ERECT CURTAIN WALLS	20	04-Oct-13	01-Nov-13		ERECT CURTAIN WALLS
WEXTV-1050	INSTALL PUNCH WINDOWS	5	28-Oct-13	01-Nov-13		i INSTALL PUNCH WINDOWS
EAST ELEVATION	N EXTERIOR VENEER (LVLS 2-ROOF)					
EEXTV-1000	ERECT CMU BACKUP WALLS	17	10-Sep-13	02-Oct-13		■ ERECT CMU BACKUP WALLS
					_[
Remaining Level of	Effort	В	BULEY LIBRARY F	RENOVATIONS		
Actual Work	Liiott	PRFI	IMINARY CONST	RUCTION SCHED	UI F	
Remaining Work						SKANSKA
Critical Remaining V ♦ Milestone	Nork	BLUS PA	1GE 12 UF 32 D	ATA DATE = 15-Ja	11-13	
_	Nork	BLUD PA	NUL 12 UF 32 DI		n-1 3	

	SKANSKA							
ctivity ID	Activity Name	Original Start Duration	Finish	2012 J J A S O N D J F	2013 M A M J J A S O N D	2014 J F M A M J J A S O I	2015	
EEXTV-1010	INSTALL EXTERIOR WATERPROOFING/ INSULA	TION 17 17-Sep-13	09-Oct-13		□ INS1	ALLEXTERIOR WATER	PROOFING/INSULATION	
EEXTV-1020	ERECT MASONRY / PRECAST VENEER	15 26-Sep-13	17-Oct-13		□ ERE	CT MASONRY / PRECA	STVENEER	
EEXTV-1030	INSTALL METAL PANELS	20 18-Oct-13	14-Nov-13		□ IN	STALL METAL PANELS		
EEXTV-1040	ERECT CURTAIN WALLS	20 04-Nov-13	03-Dec-13			ERECT CURTAIN WALL	5	
EEXTV-1050	INSTALL PUNCH WINDOWS	5 25-Nov-13	03-Dec-13		<u> </u>	INSTALL PUNCH WINDO	ws	
ROOFING								
EXTV-690	INSTALL ROOFING AT LOW ROOF AREAS	15 04-Nov-13	22-Nov-13		= 11	NSTALL ROOFING AT LO	WROOFAREAS	
EXTV-660	INSTALL MAIN ROOFING (HIGH ROOF AREA)	20 11-Nov-13	10-Dec-13		-	INSTALL MAIN ROOFIN	G (HIGH ROOF AREA)	
EXTV-680	BUILDING TIGHT	0	10-Dec-13		•	BUILDING TIGHT		
EXTV-670	COMPLETE ROOFING AT BUILDING PERIMETER	10 11-Dec-13	24-Dec-13			COMPLETE ROOFING	AT BUILDING PERIMETER	
MECHANICAL P	PENTHOUSE							
MPH-140	REMOVE EXISTING MECHANICAL EQUIPMENT	5 22-Nov-13	02-Dec-13	-	.	REMOVE EXISTING ME	CHANICAL EQUIPMENT	
MPH-150	FORM AND POUR NEW EQUIPMENT PADS	3 03-Dec-13	05-Dec-13		•	FORM AND POUR NEW	EQUIPMENT PADS	
MPH-160	CURE TIME FOR EQUIPMENT PADS	3 06-Dec-13	10-Dec-13	-	0	CURE TIME FOR EQUIP	MENT PADS	
MPH-100	INSTALL MECHANICAL EQUIPMENT	10 11-Dec-13	24-Dec-13			INSTALL MECHANICAL	EQUIPMENT	
MPH-110	INSTALL ELECTRICAL EQUIPMENT	10 26-Dec-13	09-Jan-14	-		□ INSTALLELECTRICA	EQUIPMENT	
MPH-120	MECHANICAL / ELECTRICAL ROUGH IN	70 10-Jan-14	21-Apr-14	1		MECHANICAL	/ ELECTRICAL ROUGH IN	
MPH-130	EQUIPMENT START UP / TESTING	30 22-Apr-14	03-Jun-14	-		EQUIPMEN	T START UP/TESTING	
COOLING TOWE	ERS							
Remaining Level of	of Effort	BULEY LIBRARY F	RENOVATIONS					
Actual Work		PRELIMINARY CONST	RUCTION SCHEDI	ULE				
Remaining Work				SKANSKA				
Critical Remaining		BL05 PAGE 13 OF 32 DA	ATA DATE 45 1-	n 10				

	SKANSKA				<u> </u>
ivity ID	Activity Name	Original Start Duration	Finish	JJASONDJEM	2013 2014 2015 A M J J A S O N D J F M A M J J A S O N D J F M A M J J A S O N
CT-1000	INSTALL SUPPORT / DUNNAGE STEEL FOR COOLING TOWER	5 28-Oct-13	01-Nov-13		I INSTALL SUPPORT / DUNNAGE STEEL FOR COOLING
CT-1010	INSTALL COOLING TOWER # 2	5 15-Jan-14	21-Jan-14		I INSTALL COOLING TOWER # 2
CT-1020	INSTALL PIPING FOR COOLING TOWER # 2	30 22-Jan-14	05-Mar-14		INSTALL PIPING FOR COOLING TOWER # 2
CT-1030	INSTALL ELECTRICAL CONDUIT / WIRING & CONNECTIONS FOR COOLING TOWER # 2	15 20-Feb-14	13-Mar-14	-	install electrical conduit/wiring &
CT-1080	INSTALLALL REQUIRED CONTROL WIRING	10 27-Feb-14	13-Mar-14	+	☐ INSTALLALL REQUIRED CONTROL WIRING
CT-1040	INSTALL HEAT TRACING FOR COOLING TOWER PIPING	5 06-Mar-14	13-Mar-14	-	□ INSTALL HEAT TRACING FOR COOLING TO
CT-1050	INSTALL INSULATION ON ALL COOLING TOWER PIPING	10 14-Mar-14	27-Mar-14	-	☐ INSTALL INSULATION ON ALL COOLING TO
CT-1060	REFURBISH COOLING TOWER # 1 AS REQUIRED	30 14-Mar-14	24-Apr-14	-	REFURBISH COOLING TOWER # 1 AS RE
CT-1070	START UP COOLING TOWERS, (CO-ORDINATE WITH PENTHOUSE AND GROUND FLOOR EQUIPMENT)	20 06-May-14	03-Jun-14		START UP COOLING TOWERS, (CO-C
ELEVATORS					
ELEV-1530	USE EXISTING ELEVATOR / PATCH FIREPROOFING AT EXISTING STEEL IN SHAFTS	10 25-Nov-13	10-Dec-13		□ USE EXISTING ELEVATOR / PATCH FIREPROOFING
ELEV-1520	UPGRADE / RESTORE ELEVATORS AS REQUIRED	50 11-Dec-13	21-Feb-14		UPGRADE / RESTORE ELEVATORS AS REQU
ELEV-1500	TEST / INSPECT ELEVATORS	5 24-Feb-14	28-Feb-14		ı TEST/INSPECT ELEVATORS
ELEV-1510	ELEVATORS COMPLETE (CO-ORD WITH FIRE ALARM INSPECTIONS)	0	07-Mar-14		◆ ELEVATORS COMPLETE (CO-ORD WITH FI
INTERIOR CONS	·				
GROUND FLOOR					
ICGF-4350	SAWCUT AND REMOVE SLAB AS REQUIRED FOR NEW UNDERSLAB UTILITIES	5 05-Jun-13	11-Jun-13		■ SAWCUT AND REMOVE SLAB AS REQUIRED FOR NEW UNDEF
ICGF-4360	EXCAVATE FOR NEW UNDERSLAB UTILITIES	3 12-Jun-13	14-Jun-13	1	I EXCAVATE FOR NEW UNDERSLAB UTILITIES
ICGF-4370	INSTALL UNDERSLAB UTILITIES	5 17-Jun-13	21-Jun-13	 	I INSTALL UNDERSLAB UTILITIES
ICGF-4380	TEST AND INSPECT UNDERSLAB UTILITIES	2 24-Jun-13	25-Jun-13	7	I TEST AND INSPECT UNDERSLAB UTILITIES
ICGF-4390	BACKFILL UNDERSLAB UTILITIES	3 26-Jun-13			I BACKFILL UNDERSLAB UTILITIES
			ı		
Remaining Level of	f Effort	BULEY LIBRARY F	RENOVATIONS		
Actual Work		PRELIMINARY CONST	RUCTION SCHEDI	ULE	CIZARICIZA
Remaining Work Critical Remaining		BL05 PAGE 14 OF 32 DA			SKANSKA
	Work	DLUD PAGE 14 UF 32 DA	AIA DAIE = 15-Jai	(I-10	

		SKANSKA				
Act	vity ID	Activity Name	Original Start Duration	Finish	2012	2013 2014 2015 1 A M J J A S O N D J F M A M J J A S O N D J F M A M J J A S O N D
	ICGF-4400	PLACE CONCRETE AT UTILITY TRENCHES	2 01-Jul-13	02-Jul-13		PLACE CONCRETE AT UTILITY TRENCHES
ı	ICGF-4410	PATCH SPRAY ON FIREPROOFING AS REQUIRED	5 03-Jul-13	10-Jul-13	-	■ PATCH SPRAY ON FIREPROOFING AS REQUIRED
۱	ICGF-4330	OVERHEAD ELECTRICAL ROUGH-IN	30 11-Jul-13	19-Aug-13		OVERHEAD ELECTRICAL ROUGH:IN
ı	ICGF-4340	OVERHEAD SPRINKLER ROUGH-IN	30 11-Jul-13	19-Aug-13		OVERHEAD SPRINKLER ROUGH-IN
	ICGF-1420	OVERHEAD MECHANICAL ROUGH-IN	30 11-Jul-13	19-Aug-13		OVERHEAD MECHANICAL ROUGH-IN
ı	ICGF-1440	INSTALL HM DOOR FRAMES	20 30-Jul-13	26-Aug-13		INSTALL HM DOOR FRAMES
I	ICGF-1450	INSTALL METAL STUDS / INCLUDES MECHANICAL SHAFTS	20 30-Jul-13	26-Aug-13		INSTALL METAL STUDS / INCLUDES MECHANICAL SHAFTS
ı	ICGF-1460	ELEC ROUGH IN AT METAL STUDS	20 06-Aug-13	03-Sep-13		ELEC ROUGH IN AT METAL STUDS
I	ICGF-1430	INSTALL DUCT RISERS IN NEW MECHANICAL SHAFT	5 13-Aug-13	19-Aug-13		I INSTALL DUCT RISERS IN NEW MECHANICAL SHAFT
ı	ICGF-1470	PIPE INSULATION AT WALLS AND CEILINGS	10 20-Aug-13	03-Sep-13]	☐ PIPE INSULATION AT WALLS AND CEILINGS
I	ICGF-1480	INSTALL FIRESTOPPING	3 06-Sep-13	10-Sep-13		I INSTALL FIRESTOPPING
II	ICGF-1750	TEST ALL ABOVE CEILING PIPING	3 06-Sep-13	10-Sep-13		I TESTALL ABOVE CEILING PIPING
	ICGF-1490	MECH / ELEC ROUGH IN INSPECTIONS	1 11-Sep-13	11-Sep-13		MECH/ELEC ROUGH IN INSPECTIONS
ı	ICGF-1500	BUILDING INSPECTOR INSPECTION	1 12-Sep-13	12-Sep-13		I BUILDING INSPECTOR INSPECTION
ı	ICGF-1510	INSTALL DRYWALL / INCLUDES DUCT SHAFTS	20 11-Dec-13	09-Jan-14		INSTALL DRYWALL / INCLUDES DUCT SHAFTS
II	ICGF-1520	TAPE AND FINISH DRYWALL	20 17-Dec-13	15-Jan-14		TAPE AND FINISH DRYWALL
ı	ICGF-1530	PRIME PAINT	15 02-Jan-14	22-Jan-14		□ PRIME PAINT
	ICGF-1550	INSTALL CERAMIC TILE AT BATHROOMS	7 16-Jan-14	24-Jan-14		□ INSTALL CERAMIC TILE AT BATHROOMS
	ICGF-1540	INSTALL MECH / SPRINKLER CEILING DROPS	10 16-Jan-14	29-Jan-14		☐ INSTALL MECH / SPRINKLER CEILING DROPS
	ICGF-1560	INSTALLACT / TEC CEILING GRID	15 23-Jan-14	13-Feb-14		installact/tec ceiling grid
	ICGF-1570	INSTALL LIGHT FIXTURES	10 05-Feb-14	19-Feb-14		□ INSTALL LIGHT FIXTURES
	ICGF-1580	INSTALL SPRINKLER HEADS	7 11-Feb-14	19-Feb-14		I INSTALL SPRINKLER HEADS
		ı	BULEY LIBRARY F	DENOVATIONS		
-	Remaining Level of Actual Work	Effort				
	Remaining Work Critical Remaining \(\)	Vork	PRELIMINARY CONST BL05 PAGE 15 OF 32 DA			SKANSKA
-	Critical remaining (

Milestone

	SKANSKA								
Activity ID	Activity Name		Original Duration	Start	Finish	2012	2013 EIMIAIMI II II AISIOINID		
ICGF-1610	INSTALL PLUMBING FIXTURES		5	12-Feb-14	18-Feb-14	3 3 A 3 O N D 3	F M A M 3 3 A 3 O N D	I INSTALL PLUMBING	D J F M A M J J A S O N D G FIXTURES
ICGF-1590	INSTALL ELECT RECEPTACLES AND	SWITCHES	5	13-Feb-14	19-Feb-14			I INSTALL ELECT RE	CEPTACLES AND SWITCHES
ICGF-1600	INSTALL HVAC GRILLES		5	13-Feb-14	19-Feb-14			I INSTALL HVAC GRI	LLES
ICGF-1620	INSTALL TEL/DATA JACKS		3	17-Feb-14	19-Feb-14			I INSTALL TEL/DATA	JACKS
ICGF-1630	INSTALL THERMOSTATS		3	17-Feb-14	19-Feb-14			I INSTALL THERMOS	TATS
ICGF-1640	INSTALL ACT / TEC CEILING TILES /	PANELS	10	20-Feb-14	05-Mar-14			□ INSTALLACT / TEC	CEILING TILES / PANELS
ICGF-1650	HANG DOORS		5	05-Mar-14	12-Mar-14			I HANG DOORS	
ICGF-1660	FINISH PAINT		7	13-Mar-14	21-Mar-14			□ FINISH PAINT	
ICGF-1680	INSTALL DOOR HARDWARE		5	24-Mar-14	28-Mar-14			t INSTALL DOOR I	HARDWARE
ICGF-1670	INSTALL FINISH MILLWORK		15	24-Mar-14	11-Apr-14			□ INSTALL FINISH	MILLWORK
ICGF-1690	INSTALL CARPET / FLOORING		9	08-Apr-14	18-Apr-14			□ INSTALL CARPI	ET / FLOORING
ICGF-1700	INSTALL ELEC COVER PLATES		3	09-Apr-14	11-Apr-14			I INSTALLELEC	COVER PLATES
ICGF-1710	MECH / ELEC FINAL INSPECTIONS		1	14-Apr-14	14-Apr-14			I MECH / ELEC F	INALINSPECTIONS
ICGF-1720	BUILDING INSPECTOR FINAL INSPE	ECTION	1	15-Apr-14	15-Apr-14			I BUILDING INSF	ECTOR FINAL INSPECTION
ICGF-1730	FINAL CLEANING		5	21-Apr-14	25-Apr-14			■ FINAL CLEANI	NG
ICGF-1740	GROUND FLOOR COMPLETE		0		25-Apr-14			◆ GROUND FLO	OR COMPLETE
GROUND FLOOR M	IECHANICAL ROOM								
GFMR-1000	DISCONNECT AND REMOVE EXIST	NG CHILLER # 2	10	06-Aug-13	19-Aug-13		□ DISCON	NECTAND REMOVE EX	ISTING CHILLER # 2
GFMR-1010	MODIFY EXISTING AND FORM / PO	UR NEW PAD FOR CHILLER	3	20-Aug-13	22-Aug-13		ı MODIFY	EXISTING AND FORM	POUR NEW PAD FOR CHILL
GFMR-1020	CURING TIME FOR NEW CONCRET	E PAD	3	23-Aug-13	27-Aug-13		ı CURINO	TIME FOR NEW CONC	RETE PAD
GFMR-1030	INSTALL NEW CHILLER # 2		10	03-Sep-13	16-Sep-13		□ INSTA	LL NEW CHILLER #2	
GFMR-1040	INSTALL NEW PIPING AND CONNEC	CTIONS TO CHILLER # 2	30	17-Sep-13	29-Oct-13		ins	TALL NEW PIPING AND	CONNECTIONS TO CHILLER
	1	'			·				
Remaining Level of	Effort		BU	JLEY LIBRARY F	RENOVATIONS				
Remaining Work	Critical Remaining Work				RUCTION SCHED ATA DATE = 15-Ja			SKAN	SKA

	SKANSKA						
Activity ID	Activity Name	Original Start Duration	Finish	2012 J J A S O N D J F M	2013	2014 E M A M A S O N	2015 D J F M A M J J A S O N D
GFMR-1050	INSTALL NEW ELECTRICAL CONNECTIONS TO CHILLER # 2	15 16-Oct-13	05-Nov-13			ALL NEW ELECTRICAL	CONNECTIONS TO CHILLE
GFMR-1080	INSTALLALL REQUIRED CONTROL WIRING FOR CHILLER # 2	10 23-Oct-13	05-Nov-13	-	□ INST	ALLALL REQUIRED CO	NTROL WIRING FOR CHILL
GFMR-1060	INSTALL NEW PIPE INSULATION AT CHILLER # 2	5 06-Nov-13	12-Nov-13	-	INS	TALL NEW PIPE INSULA	TION AT CHILLER # 2
GFMR-1070	START UP / TEST CHILLER # 2 (CO-ORD WITH PENTHOUSE EQUIPMENT & COOLING TOWERS)	20 06-May-14	03-Jun-14			START UP /	FEST CHILLER # 2 (CO-ORD
FIRST FLOOR							
IC1F-4350	OVERHEAD ELECTRICAL ROUGH-IN	30 20-Aug-13	01-Oct-13		OVERH	IEAD ELECTRICAL RO	UGH-IN
IC1F-4360	OVERHEAD SPRINKLER ROUGH-IN	30 20-Aug-13	01-Oct-13			IEAD SPRINKLER ROU	GH-IN
IC1F-1000	OVERHEAD MECHANICAL ROUGH-IN	30 20-Aug-13	01-Oct-13		OVERH	IEAD MECHANICAL RO	UGH-IN
IC1F-1020	INSTALL HM DOOR FRAMES	20 11-Sep-13	08-Oct-13		□ INSTA	LHM DOOR FRAMES	
IC1F-1030	INSTALL METAL STUDS / INCLUDES MECHANICAL SHAFTS	20 11-Sep-13	08-Oct-13		□ INSTA	LMETAL STUDS / INC	UDES MECHANICAL SHAFT
IC1F-1050	ELEC ROUGH IN AT METAL STUDS	20 18-Sep-13	16-Oct-13	-	= ELEC	ROUGH IN AT METAL S	TUDS
IC1F-1010	INSTALL DUCT RISERS IN NEW MECHANICAL SHAFT	5 25-Sep-13	01-Oct-13	-	ı INSTAL	L DUCT RISERS IN NE	W MECHANICAL SHAFT
IC1F-1060	PIPE INSULATION AT WALLS AND CEILINGS	10 02-Oct-13	16-Oct-13	-	□ P(PE I	NSULATION AT WALLS	AND CEILINGS
IC1F-1070	INSTALL FIRESTOPPING	3 21-Oct-13	23-Oct-13		I INSTA	ILL FIRESTOPPING	
IC1F-1130	TEST ALL ABOVE CEILING PIPING	3 21-Oct-13	23-Oct-13		ı TEST	ALLABOVE CEILING P	PING
IC1F-1110	MECH / ELEC ROUGH IN INSPECTIONS	1 24-Oct-13	24-Oct-13		ı MECI	I / ELEC ROUGH IN IN	SPECTIONS
IC1F-1120	BUILDING INSPECTOR INSPECTION	1 25-Oct-13	25-Oct-13		ı BUİLI	ING INSPECTOR INSP	ECTION
IC1F-1140	INSTALL DRYWALL / INCLUDES MECH SHAFTS	20 08-Jan-14	04-Feb-14		-	NSTALL DRYWALL /	NCLUDES MECH SHAFTS
IC1F-1150	TAPE AND FINISH DRYWALL	20 15-Jan-14	12-Feb-14	 		TAPE AND FINISH D	RYWALL
IC1F-1160	PRIME PAINT	15 29-Jan-14	19-Feb-14	-		■ PRIME PAINT	
IC1F-1180	INSTALL CERAMIC TILE AT BATHROOMS	7 12-Feb-14	20-Feb-14			□ INSTALL CERAMIC	TILE AT BATHROOMS
IC1F-1080	INSTALL MECH / SPRINKLER CEILING DROPS	10 12-Feb-14	25-Feb-14			□ INSTALL MECH / SF	RINKLER CEILING DROPS
_		BULEY LIBRARY	RENOVATIONS				
Remaining Level Actual Work	of Effort	PRELIMINARY CONST		NIII F			
Remaining Work Critical Remaining Milestone		BL05 PAGE 17 OF 32 D				SKAN	5KA

		SKANSKA					
Acti	vity ID	Activity Name	Original Start Duration	Finish	2012	2013 4 A M 1 1 A S O N D	2014 2015 J F M A M J J A S O N D J F M A M J J A S O N D
	IC1F-1100	INSTALL AND TEST WIRING TO VAV'S	5 14-Feb-14	20-Feb-14			INSTALL AND TEST WIRING TO VAV'S
	IC1F-1090	INSTALLACT / TEC CEILING GRID	15 19-Feb-14	12-Mar-14			□ INSTALLACT / TEC CEILING GRID
	IC1F-1250	INSTALL LIGHT FIXTURES	10 05-Mar-14	19-Mar-14	-		□ INSTALL LIGHT FIXTURES
	IC1F-1280	INSTALL SPRINKLER HEADS	7 11-Mar-14	19-Mar-14	-		□ INSTALL SPRINKLER HEADS
Ш	IC1F-1190	INSTALL PLUMBING FIXTURES	5 13-Mar-14	19-Mar-14	-		I INSTALL PLUMBING FIXTURES
	IC1F-1200	INSTALL ELECT RECEPTACLES AND SWITCHES	5 13-Mar-14	19-Mar-14	-		I INSTALL ELECT RECEPTACLES AND SWITCH
	IC1F-1270	INSTALL HVAC GRILLES	5 13-Mar-14	19-Mar-14	+		I INSTALL HVAC GRILLES
	IC1F-1260	INSTALL TEL/DATA JACKS	3 17-Mar-14	19-Mar-14	\dashv		I INSTALL TEL/DATA JACKS
	IC1F-1300	INSTALL THERMOSTATS	3 17-Mar-14	19-Mar-14	\dashv		I INSTALL THERMOSTATS
Ш	IC1F-1320	INSTALL ACT / TEC CEILING TILES / PANELS	10 20-Mar-14	02-Apr-14	\dashv		☐ INSTALLACT / TEC CEILING TILES / PANELS
	IC1F-1210	HANG DOORS	5 03-Apr-14	09-Apr-14	\dashv		I HANG DOORS
Ш	IC1F-1220	FINISH PAINT	7 10-Apr-14	18-Apr-14			□ FINISH PAINT
Ш	IC1F-1310	INSTALL DOOR HARDWARE	5 21-Apr-14	25-Apr-14	\dashv		I INSTALL DOOR HARDWARE
Ш	IC1F-1230	INSTALL FINISH MILLWORK	15 21-Apr-14	09-May-14	\dashv		□ INSTALL FINISH MILLWORK
Ш	IC1F-1290	INSTALL TERRAZZO FLOORING (USE MULTIPLE CREWS)	35 21-Apr-14	09-Jun-14	\dashv		INSTALL TERRAZZO FLOORING (USE I
	IC1F-1340	INSTALL CARPET / FLOORING	9 06-May-14	16-May-14	-		□ INSTALL CARPET / FLOORING
	IC1F-1240	INSTALL ELEC COVER PLATES	3 07-May-14	09-May-14			I INSTALLELEC COVER PLATES
	IC1F-1370	MECH / ELEC FINAL INSPECTIONS	1 12-May-14	12-May-14	-		I MECH / ELEC FINAL INSPECTIONS
	IC1F-1390	BUILDING INSPECTOR FINAL INSPECTION	1 13-May-14	13-May-14	-		I BUILDING INSPECTOR FINAL INSPECTIO
	IC1F-1360	FINAL CLEANING	5 19-May-14	23-May-14			I FINAL CLEANING
	IC1F-1400	FIRST FLOOR COMPLETE (DOES NOT INCLUDE TERRAZZO	0	23-May-14	-		◆ FIRST FLOOR COMPLETE (DOES NOT IN
	SECOND FLOOR (FLOORING) CORE & SHELL ONLY)					
	Remaining Level of	of Effort	BULEY LIBRARY	/ RENOVATIONS			
-	Actual Work		PRELIMINARY CONS	STRUCTION SCHEE	DULE		CIZANICIZA
	Remaining Work	Wards	BL05 PAGE 18 OF 32				SKANSKA
-	Critical Remaining	Work	DLUD FAGE 10 OF 32	DVIV DVIE = 19-79	#II-13		

Milestone

	SKANSKA							
ctivity ID	Activity Name	Original Start Duration	Finish	2012	2013			2015
ICCS-2000	INSTALL MECHANICAL RISERS WITH CONNECTIONS FOR FUTURE FITOUT	5 02-Oct-13	08-Oct-13	JJAJOND		ONDJFMAMJJASO NSTALL MECHANICAL RIS	SERS WITH CO	NNECTIONS FO
ICCS-2010	INSTALL ELECTRICAL RISERS WITH CONNECTIONS FOR FUTURE FITOUT	5 02-Oct-13	08-Oct-13			INSTALLELECTRICALRIS	ERS WITH CON	INECTIONS FOR
ICCS-2050	INSTALL SPRINKLER RISERS WITH CONNECTIONS FOR FUTURE FITOUT	5 02-Oct-13	08-Oct-13			INSTALL SPRINKLER RISI	RS WITH CON	NECTIONS FOF
ICCS-2020	INSTALL PLUMBING ROUGH IN AT REST ROOMS	5 09-Oct-13	16-Oct-13			INSTALL PLUMBING ROU	GH IN AT REST	ROOMS
ICCS-2080	INSTALL SPRINKLER PIPING WITH UPRIGHT SPRINKLER HEADS (GENERAL FLOOR AREA)	5 09-Oct-13	16-Oct-13			I INSTALL SPRINKLER PIPI	NG WITH UPRI	GHT SPRINKLEI
ICCS-2230	TEST ALL ABOVE CEILING PIPING	3 11-Oct-13	16-Oct-13			I TESTALLABOVE CEILING	PIPING	
ICCS-2030	INSTALL STEEL STUDS	3 16-Oct-13	18-Oct-13			I INSTALL STEEL STUDS		
ICCS-2040	IN STUD ROUGH IN	3 17-Oct-13	21-Oct-13			I IN STUD ROUGH IN		
ICCS-2110	INSTALL CODE REQUIRED FIRESTOPPING	3 17-Oct-13	21-Oct-13			I INSTALL CODE REQUIRE	D FIRESTOPPI	NG
ICCS-2190	INSULATE EXTERIOR WALL FRAMING	3 21-Oct-13	23-Oct-13			I INSULATE EXTERIOR WA	LL FRAMING	
ICCS-2060	INSTALL DRYWALL AT RESTROOMS / ELECT & DATA ROOMS	3 06-Feb-14	11-Feb-14			I INSTALL DRYWA	LAT RESTRO	OMS / ELECT & D
ICCS-2070	TAPE AND FINISH DRWALL	3 12-Feb-14	14-Feb-14			I TAPE AND FINISI	I DRWALL	
ICCS-2090	INSTALL CODE REQUIRED LIGHTING (GENERAL FLOOR AREA	5 12-Feb-14	18-Feb-14			I INSTALL CODE F	EQUIRED LIGH	ITING (GENERA
ICCS-2120	PAINT ELECTRIC AND DATA ROOMS AND STAIRWELLS	3 17-Feb-14	19-Feb-14			I PAINT ELECTRIC	AND DATA RO	OMS AND STAIF
ICCS-2130	INSTALL CERAMIC TILE AT RESTROOMS	3 17-Feb-14	19-Feb-14			I INSTALL CERAM	IC TILE AT RES	TROOMS
ICCS-2100	INSTALL CODE REQUIRED FIRE ALARM SYSTEM (GENERAL FLOOR AREA)	5 17-Feb-14	21-Feb-14			ı INSTALL CODE F	REQUIRED FIRI	E ALARM SYSTE
ICCS-2140	INSTALL CEILING GRID AT RESTROOMS	2 20-Feb-14	21-Feb-14			I INSTALL CEILING	GRID AT RES	TROOMS
ICCS-2150	MECHANICAL DROPS AT CEILING GRID	2 21-Feb-14	24-Feb-14			I MECHANICAL D	ROPS AT CEILII	NG GRID
ICCS-2160	INSTALL LIGHT FIXTURES / GRILLES / DIFFUSERS AT CEILING GRID	2 24-Feb-14	25-Feb-14			ı installlight i	IXTURES / GR	ILLES / DIFFUSE
ICCS-2170	INSTALL CEILING TILE	2 25-Feb-14	26-Feb-14			i install ceiling	STILE	++
ICCS-2180	INSTALL PLUMBING FIXTURES	2 26-Feb-14	27-Feb-14			I INSTALL PLUMB	ING FIXTURES	
ICCS-2200	INSTALL TOILET PARTITIONS	1 28-Feb-14	28-Feb-14			I INSTALL TOILET	PARTITIONS	
				_[<u> </u>		<u> </u>	<u> </u>
Remaining Level	of Effort	BULEY LIBRARY	RENOVATIONS					

Remaining Level of Effort
Actual Work
Remaining Work
Critical Remaining Work

Milestone

PRELIMINARY CONSTRUCTION SCHEDULE

BL05 PAGE 19 OF 32 DATA DATE = 15-Jan-13



	SKANSKA				
Activity ID	Activity Name	Original Start Duration	Finish	2012	2013 2014 2015 FMAMJJASONDJFMAMJJASONDJFMAMJJASOND
ICCS-2210	INSTALL TOILET ACCESSORIES	1 03-Mar-14	03-Mar-14	JJASONDJF	FMAMJJASONDJFMAMJJASONDJFMAMJJASOND
ICCS-2220	SECOND FLOOR CORE AND SHELL COMPLETE	1 04-Mar-14	04-Mar-14	-	I SECOND FLOOR CORE AND SHELL COMPLET
THIRD FLOOR (C	ORE & SHELL ONLY)				-
			1.0.0		
ICCS-3000	INSTALL MECHANICAL RISERS WITH CONNECTIONS FOR FUTURE FITOUT	5 09-Oct-13	16-Oct-13		INSTALL MECHANICAL RISERS WITH CONNECTIONS FO
ICCS-3010	INSTALL ELECTRICAL RISERS WITH CONNECTIONS FOR FUTURE FITOUT	5 09-Oct-13	16-Oct-13		I INSTALL ELECTRICAL RISERS WITH CONNECTIONS FO
ICCS-3020	INSTALL SPRINKLER RISERS WITH CONNECTIONS FOR FUTURE FITOUT	5 09-Oct-13	16-Oct-13		INSTALL SPRINKLER RISERS WITH CONNECTIONS FOR
ICCS-3040	INSTALL SPRINKLER PIPING WITH UPRIGHT SPRINKLER HEADS (GENERAL FLOOR AREA)	5 17-Oct-13	23-Oct-13		INSTALL SPRINKLER PIPING WITH UPRIGHT SPRINKLE
ICCS-3030	INSTALL PLUMBING ROUGH IN AT REST ROOMS	5 17-Oct-13	23-Oct-13		□ INSTALL PLUMBING ROUGH IN AT REST ROOMS
ICCS-3070	INSTALL STEEL STUDS	3 23-Oct-13	25-Oct-13		I INSTALL STEEL STUDS
ICCS-3090	INSTALL CODE REQUIRED FIRESTOPPING	3 24-Oct-13	28-Oct-13		INSTALL CODE REQUIRED FIRESTOPPING
ICCS-3080	IN STUD ROUGH IN	3 24-Oct-13	28-Oct-13	7	I IN STUD ROUGH IN
ICCS-3230	TEST ALL ABOVE CEILING PIPING	3 24-Oct-13	28-Oct-13		I TEST ALLABOVE CEILING PIPING
ICCS-3110	INSULATE EXTERIOR WALL FRAMING	3 28-Oct-13	30-Oct-13		I INSULATE EXTERIOR WALL FRAMING
ICCS-3100	INSTALL DRYWALL AT RESTROOMS / ELECT & DATA ROOMS	3 13-Feb-14	17-Feb-14		■ INSTALL DRYWALL AT RESTROOMS / ELECT & I
ICCS-3120	TAPE AND FINISH DRWALL	3 18-Feb-14	20-Feb-14		I TAPE AND FINISH DRWALL
ICCS-3050	INSTALL CODE REQUIRED LIGHTING (GENERAL FLOOR AREA	5 18-Feb-14	24-Feb-14		I INSTALL CODE REQUIRED LIGHTING (GENER
ICCS-3130	PAINT ELECTRIC AND DATA ROOMS AND STAIRWELLS	3 21-Feb-14	25-Feb-14		PAINT ELECTRIC AND DATA ROOMS AND STAIL
ICCS-3140	INSTALL CERAMIC TILE AT RESTROOMS	3 21-Feb-14	25-Feb-14	 	■ INSTALL CERAMIC TILE AT RESTROOMS
ICCS-3060	INSTALL CODE REQUIRED FIRE ALARM SYSTEM (GENERAL FLOOR AREA)	5 21-Feb-14	27-Feb-14	-	IL INSTALL CODE REQUIRED FIRE ALARM SYSTE
ICCS-3150	INSTALL CEILING GRID AT RESTROOMS	2 26-Feb-14	27-Feb-14		I INSTALL CEILING GRID AT RESTROOMS
ICCS-3160	MECHANICAL DROPS AT CEILING GRID	2 27-Feb-14	28-Feb-14		I MECHANICAL DROPS AT CEILING GRID
ICCS-3170	INSTALL LIGHT FIXTURES / GRILLES / DIFFUSERS AT CEILING GRID	2 28-Feb-14	03-Mar-14		≬ INSTALL LIGHT FIXTURES / GRILLES / DIFFUSI
Remaining Level of	of Effort	BULEY LIBRARY	RENOVATIONS		
Actual Work		PRELIMINARY CONST	RUCTION SCHED	ULE	CIZANICIZA
Remaining Work		BL05_PAGE 20 OF 32_D	ATA DATE - 15- la	n-13	SKANSKA

BL05 PAGE 20 OF 32 DATA DATE = 15-Jan-13

Critical Remaining Work

Milestone



	SKANSKA							
Activity ID	Activity Name	Original Start Duration	Finish	2012	2013	2014		2015
ICCS-3180	INSTALL CEILING TILE	2 03-Mar-14	04-Mar-14	JJASONDJFM	MAMJJJASON	DJFMAMJJJASON INSTALL CEILING		I J J A S O N D
1003-3180	INSTALL CEILING TILE	2 03-IVIAI - 14	04-Mar-14			I WOMED CLIENCE	,	
ICCS-3190	INSTALL PLUMBING FIXTURES	2 04-Mar-14	05-Mar-14	7		I INSTALL PLUMBIN	G FIXTURES	3
ICCS-3200	INSTALL TOILET PARTITIONS	1 06-Mar-14	06-Mar-14			I INSTALL TOILET F	ARTITIONS	
ICCS-3210	INSTALL TOILET ACCESSORIES	1 07-Mar-14	07-Mar-14			I INSTALL TOILET A	CCESSORIE	S
ICCS-3220	THIRD FLOOR CORE AND SHELL COMPLETE	1 11-Mar-14	11-Mar-14			i THIRD FLOOR Co	RE AND SH	ELL COMPLETE
FOURTH FLOOR (CORE & SHELL ONLY)							
ICCS-4000	INSTALL MECHANICAL RISERS WITH CONNECTIONS FOR FUTURE FITOUT	5 17-Oct-13	23-Oct-13		a IN	STALL MECHANICAL RIS	RS WITH CO	ONNECTIONS FO
ICCS-4010	INSTALL ELECTRICAL RISERS WITH CONNECTIONS FOR FUTURE FITOUT	5 17-Oct-13	23-Oct-13		o IN	STALL ELECTRICAL RISE	RS WITH CO	NNECTIONS FO
ICCS-4020	INSTALL SPRINKLER RISERS WITH CONNECTIONS FOR FUTURE FITOUT	5 17-Oct-13	23-Oct-13		o IN	STALL SPRINKLER RISE	RS WITH CO	NNECTIONS FO
ICCS-4040	INSTALL SPRINKLER PIPING WITH UPRIGHT SPRINKLER HEADS (GENERAL FLOOR AREA)	5 24-Oct-13	30-Oct-13	7	D IN	ISTALL SPRINKLER PIPIN	G WITH UPP	IGHT SPRINKLE
ICCS-4030	INSTALL PLUMBING ROUGH IN AT REST ROOMS	5 24-Oct-13	30-Oct-13		ū IN	ISTALL PLUMBING ROUG	H IN AT RES	T ROOMS
ICCS-4070	INSTALL STEEL STUDS	3 30-Oct-13	01-Nov-13		1 17	ISTALL STEEL STUDS		
ICCS-4080	IN STUD ROUGH IN	3 31-Oct-13	04-Nov-13		0 17	I STUD ROUGH IN		
ICCS-4090	INSTALL CODE REQUIRED FIRESTOPPING	3 31-Oct-13	04-Nov-13		10 0	ISTALL CODE REQUIRED	FIRESTOPF	'ING
ICCS-4230	TEST ALLABOVE CEILING PIPING	3 31-Oct-13	04-Nov-13		ů Ť	ESTALLABOVE CEILING	PIPING	
ICCS-4110	INSULATE EXTERIOR WALL FRAMING	3 04-Nov-13	06-Nov-13			ISULATE EXTERIOR WAI	L FRAMING	
ICCS-4100	INSTALL DRYWALL AT RESTROOMS / ELECT & DATA ROOMS	3 18-Feb-14	20-Feb-14	1		ı İNSTALL DRYWALI	AT RESTRO	OMS / ELECT & I
ICCS-4120	TAPE AND FINISH DRWALL	3 21-Feb-14	25-Feb-14	7		I TAPE AND FINISH	DRWALL	
ICCS-4050	INSTALL CODE REQUIRED LIGHTING (GENERAL FLOOR AREA	5 21-Feb-14	27-Feb-14	7		I INSTALL CODE RE	QUIRED LIG	HTING (GENER
ICCS-4130	PAINT ELECTRIC AND DATA ROOMS AND STAIRWELLS	3 26-Feb-14	28-Feb-14			I PAINT ELECTRIC	ND DATA RC	OMS AND STAIF
ICCS-4140	INSTALL CERAMIC TILE AT RESTROOMS	3 26-Feb-14	28-Feb-14	1		I INSTALL CERAMIC	TILE AT RES	3TROOMS
ICCS-4060	INSTALL CODE REQUIRED FIRE ALARM SYSTEM (GENERAL FLOOR AREA)	5 26-Feb-14	04-Mar-14			1 INSTALL CODE R	QUIRED FIF	RE ALARM SYSTE
	T	BULEY LIBRARY	RENOVATIONS					
Remaining Level of	f Effort							
Actual Work Remaining Work Critical Remaining	Work	PRELIMINARY CONST BL05 PAGE 21 OF 32 D				SKAN	SKA	
♦ Milestone								

		SKANSKA				
Activit	ty ID	Activity Name	Original Start Duration	Finish	2012	2013 2014 2015 MIAIM ILLIAISIONID LIEMAIM ILLIAISIONID
	ICCS-4150	INSTALL CEILING GRID AT RESTROOMS	2 03-Mar-14	04-Mar-14		M A M J J A S O N D J F M A M J J A S O N D J F M A M J J A S O N D I INSTALL CEILING GRID AT RESTROOMS
	ICCS-4160	MECHANICAL DROPS AT CEILING GRID	2 04-Mar-14	05-Mar-14	-	I MECHANICAL DROPS AT CEILING GRID
	ICCS-4170	INSTALL LIGHT FIXTURES / GRILLES / DIFFUSERS AT CEILING GRID	2 05-Mar-14	06-Mar-14		I INSTALL LIGHT FIXTURES / GRILLES / DIFFUS
	ICCS-4180	INSTALL CEILING TILE	2 06-Mar-14	07-Mar-14		I INSTALL CEILING TILE
	ICCS-4190	INSTALL PLUMBING FIXTURES	2 07-Mar-14	11-Mar-14		I INSTALL PLUMBING FIXTURES
	ICCS-4200	INSTALL TOILET PARTITIONS	1 12-Mar-14	12-Mar-14		I INSTALL TOILET PARTITIONS
	ICCS-4210	INSTALL TOILET ACCESSORIES	1 13-Mar-14	13-Mar-14		I INSTALL TOILET ACCESSORIES
	ICCS-4220	FOURTH FLOOR CORE AND SHELL COMPLETE	1 14-Mar-14	14-Mar-14		I FOURTH FLOOR CORE AND SHELL COMPLET
	FOURTH FLOOR AD	DITION (CORE AND SHELL ONLY)				
	ICCS4A-4000	INSTALL MECHANICAL RISERS WITH CONNECTIONS FOR FUTURE FITOUT	5 24-Oct-13	30-Oct-13		I INSTALL MECHANICAL RISERS WITH CONNECTIONS F
	ICCS4A-4010	INSTALL ELECTRICAL RISERS WITH CONNECTIONS FOR FUTURE FITOUT	5 24-Oct-13	30-Oct-13		I INSTALL ELECTRICAL RISERS WITH CONNECTIONS FO
	ICCS4A-4020	INSTALL SPRINKLER RISERS WITH CONNECTIONS FOR FUTURE FITOUT	5 24-Oct-13	30-Oct-13		I INSTALL SPRINKLER RISERS WITH CONNECTIONS FO
	ICCS4A-4030	INSTALL PLUMBING ROUGH IN AT REST ROOMS	5 31-Oct-13	06-Nov-13		I INSTALL PLUMBING ROUGH IN AT REST ROOMS
	ICCS4A-4040	INSTALL SPRINKLER PIPING WITH UPRIGHT SPRINKLER HEADS (GENERAL FLOOR AREA)	5 31-Oct-13	06-Nov-13		I INSTALL SPRINKLER PIPING WITH UPRIGHT SPRINKLI
	ICCS4A-4070	INSTALL STEEL STUDS	3 06-Nov-13	08-Nov-13		I INSTALL STEEL STUDS
	ICCS4A-4080	IN STUD ROUGH IN	3 07-Nov-13	11-Nov-13		ı in stud rough in
	ICCS4A-4090	INSTALL CODE REQUIRED FIRESTOPPING	3 07-Nov-13	11-Nov-13		I INSTALL CODE REQUIRED FIRESTOPPING
	ICCS4A-4230	TEST ALL ABOVE CEILING PIPING	3 07-Nov-13	11-Nov-13		I TEST ALL ABOVE CEILING PIPING
	ICCS4A-4110	INSULATE EXTERIOR WALL FRAMING	3 11-Nov-13	13-Nov-13		I INSULATE EXTERIOR WALL FRAMING
	ICCS4A-4100	INSTALL DRYWALL AT RESTROOMS / ELECT & DATA ROOMS	3 21-Feb-14	25-Feb-14		I INSTALL DRYWALL AT RESTROOMS / ELECT &
	ICCS4A-4120	TAPE AND FINISH DRWALL	3 26-Feb-14	28-Feb-14		i TAPE AND FINISH DRWALL
	ICCS4A-4050	INSTALL CODE REQUIRED LIGHTING (GENERAL FLOOR AREA)	5 26-Feb-14	04-Mar-14		□ INSTALL CODE REQUIRED LIGHTING (GENEF
	Remaining Level of I	Effort	BULEY LIBRARY F	RENOVATIONS		
	Actual Work Remaining Work		PRELIMINARY CONST	RUCTION SCHEE	DULE	SKANSKA
	Critical Remaining W	Vork	BL05 PAGE 22 OF 32 D	ATA DATE = 15-Ja	an-13	

Milestone

	SKANSKA							
Activity ID	Activity Name	Original Start Duration	Finish	2012	2013 J F M A M J J A S	2014		2015
ICCS4A-4130	PAINT ELECTRIC AND DATA ROOMS AND STAIRWELLS	3 03-Mar-14	05-Mar-14	JJASOND	J F M A M J J A		ECTRIC AND I	MAMJJASOND DATA ROOMS AND STAI
ICCS4A-4140	INSTALL CERAMIC TILE AT RESTROOMS	3 03-Mar-14	05-Mar-14			I INSTALL	CERAMIC TILE	AT RESTROOMS
ICCS4A-4060	INSTALL CODE REQUIRED FIRE ALARM SYSTEM (GENERAL FLOOR AREA)	5 03-Mar-14	07-Mar-14			1 INSTALL	CODE REQUIF	RED FIRE ALARM SYSTI
ICCS4A-4150	INSTALL CEILING GRID AT RESTROOMS	2 06-Mar-14	07-Mar-14			ı İNSTALL	CEILING GRID	AT RESTROOMS
ICCS4A-4160	MECHANICAL DROPS AT CEILING GRID	2 07-Mar-14	11-Mar-14			ı MECHAI	VICAL DROPS /	AT CEILING GRID
ICCS4A-4170	INSTALL LIGHT FIXTURES / GRILLES / DIFFUSERS AT CEILING GRID	2 11-Mar-14	12-Mar-14			I INSTALL	LIGHT FIXTUP	ES/GRILLES/DIFFUS
ICCS4A-4180	INSTALL CEILING TILE	2 12-Mar-14	13-Mar-14	 		I INSTALL	CEILING TILE	
ICCS4A-4190	INSTALL PLUMBING FIXTURES	2 13-Mar-14	14-Mar-14			ı instali	PLUMBING FIX	KTURES
ICCS4A-4200	INSTALL TOILET PARTITIONS	1 17-Mar-14	17-Mar-14			ı İNSTALI	L TOILET PARTI	TIONS
ICCS4A-4210	INSTALL TOILET ACCESSORIES	1 18-Mar-14	18-Mar-14			ı INSTAL	LTOILETACCE	SSORIES
ICCS4A-4220	FOURTH FLOOR ADDITION CORE AND SHELL COMPLETE	1 19-Mar-14	19-Mar-14			ı FOURT	H FLOOR ADDI	TION CORE AND SHELL
SECOND FLOOR (COMPLETE FITOUT)							
IC2F-4370	OVERHEAD ELECTRICAL ROUGH-IN	20 02-Oct-13	30-Oct-13			OVERHEAD ELEC	TRICAL ROUG	H-IN
IC2F-4380	OVERHEAD SPRINKLER ROUGH-IN	20 02-Oct-13	30-Oct-13			OVERHEAD SPRI	NKLER ROUGH	H-IN
IC2F-1800	OVERHEAD MECHANICAL ROUGH-IN	20 02-Oct-13	30-Oct-13			OVERHEAD MEC	HANICAL ROUC	AH-IN
IC2F-1820	INSTALL HM DOOR FRAMES	15 17-Oct-13	06-Nov-13			■ INSTALL HM DOC	R FRAMES	
IC2F-1830	INSTALL METAL STUDS / INCLUDES MECHANICAL SHAFTS	15 17-Oct-13	06-Nov-13			INSTALL METALS	TUDS/INCLUI	DES MECHANICAL SHA
IC2F-1840	ELEC ROUGH IN AT METAL STUDS	18 21-Oct-13	13-Nov-13			ELEC ROUGH IN	AT METAL STU	DS
IC2F-4390	INSTALL DUCT RISERS IN NEW MECHANICAL SHAFT	5 24-Oct-13	30-Oct-13			I INSTALL DUCT RI	SERS IN NEW I	MECHANICAL SHAFT
IC2F-1850	PIPE INSULATION AT WALLS AND CEILINGS	7 05-Nov-13	13-Nov-13			PIPE INSULATIO	NAT WALLS AN	ID CEILINGS
IC2F-1860	INSTALL FIRESTOPPING	3 18-Nov-13	20-Nov-13			I INSTALL FIREST	OPPING	
IC2F-2140	TEST ALL ABOVE CEILING PIPING	3 18-Nov-13	20-Nov-13			I TESTALLABOV	CEILING PIPI	NG
Remaining Level of	f Effort	BULEY LIBRARY	RENOVATIONS					
Actual Work Remaining Work Critical Remaining Milestone		PRELIMINARY CONST				SK	ANS	KA

	SKANSKA						
Activity ID	Activity Name	Original Start Duration	Finish	2012			
IC2F-1870	MECH / ELEC ROUGH IN INSPECTIONS	1 21-Nov-13	21-Nov-13	JJASON		DJFMAMJJASONI MECH/ELEC ROUGHIN I	NSPECTIONS STATES OF THE NEXT
						BUILDING INSPECTOR INS	PROTION
IC2F-1880	BUILDING INSPECTOR INSPECTION	1 22-Nov-13	22-Nov-13				SPECITION
IC2F-1890	INSTALL DRYWALL / INCLUDES MECHANICAL SHAFTS	15 05-Feb-14	26-Feb-14			■ INSTALL DRYWALL	/INCLUDES MECHANICALS
IC2F-1900	TAPE AND FINISH DRYWALL	15 13-Feb-14	05-Mar-14			☐ TAPE AND FINISH [DRYWALL
		10.07.5.1.14			<u> </u>	□ PRIME PAINT	
IC2F-1910	PRIME PAINT	10 27-Feb-14	13-Mar-14				
IC2F-1930	INSTALL CERAMIC TILE AT BATHROOMS	7 05-Mar-14	14-Mar-14			□ INSTALL CERAMIC	TILE AT BATHROOMS
IC2F-1920	INSTALL MECH / SPRINKLER CEILING DROPS	7 12-Mar-14	20-Mar-14			□ INSTALL MECH / S	PRINKLER CEILING DROP
IC2F-2130	INSTALL AND TEST WIRING TO VAV'S	5 14-Mar-14	20-Mar-14			□ INSTALL AND TES	T WIRING TO VAV'S
1026-2130	INSTALLAND TEST WINING TO VAV S	5 14-IVIAI-14	20-Mai-14				
IC2F-1940	INSTALLACT / TEC CEILING GRID	10 19-Mar-14	01-Apr-14			□ INSTALLACT / TE	C CEILING GRID
IC2F-1950	INSTALL LIGHT FIXTURES	7 31-Mar-14	08-Apr-14			□ INSTALLLIGHT F	IXTURES
IC2F-1960	INSTALL SPRINKLER HEADS	7 31-Mar-14	08-Apr-14			□ INSTALL SPRINK	LER HEADS
			•				
IC2F-1970	INSTALL ELECT RECEPTACLES AND SWITCHES	5 02-Apr-14	08-Apr-14			1 INSTALLELECT	RECEPTACLES AND SWITC
IC2F-1980	INSTALL HVAC GRILLES	5 02-Apr-14	08-Apr-14			□ INSTALL HVAC G	RILLES
IC2F-1990	INSTALL PLUMBING FIXTURES	5 02-Apr-14	08-Apr-14			ı INSTALL PLUMBI	NG FIXTURES
		· ·	•				-A 14 OZO
IC2F-2000	INSTALL TEL/DATA JACKS	3 04-Apr-14	08-Apr-14			■ INSTALL TEL/DAT	AJACKS
IC2F-2010	INSTALL THERMOSTATS	3 04-Apr-14	08-Apr-14			I INSTALL THERM	OSTATS
IC2F-2020	INSTALL ACT / TEC CEILING TILES / PANELS	10 09-Apr-14	22-Apr-14			□ INSTALL ACT / T	EC CEILING TILES / PANEL
1005 0000	HANG BOORS	· ·	•			I HANG DOORS	
IC2F-2030	HANG DOORS	5 23-Apr-14	29-Apr-14				
IC2F-2040	FINISH PAINT	7 30-Apr-14	08-May-14			□ FINISH PAINT	
IC2F-2060	INSTALL DOOR HARDWARE	5 09-May-14	15-May-14			I INSTALL DOO	R HARDWARE
IC2F-2050	INSTALL FINISH MILLWORK	14 09-May-14	29-May-14			□ INSTALL FINI	SH MILLWORK
			•				
IC2F-2070	INSTALL CARPET / FLOORING	12 20-May-14	05-Jun-14			INSTALL CAF	RPET / FLOORING
		J			<u> </u>	<u>, , , , , , , , , , , , , , , , , , , </u>	
Remaining Level	Lof Effort	BULEY LIBRARY	RENOVATIONS				
Actual Work	TOT ENOTE	PRELIMINARY CONST				CIZANI	

Actual Work
Remaining Work
Critical Remaining Work

Milestone

PRELIMINARY CONSTRUCTION SCHEDULE

BL05 PAGE 24 OF 32 DATA DATE = 15-Jan-13



	SKANSKA						
Activity ID	Activity Name	Original Start Duration	Finish	2012			2015 J F M A M J J A S O N D
IC2F-2080	INSTALL ELEC COVER PLATES	3 27-May-14	29-May-14	3 3 A 3 O N D 3		I INSTALL ELEC	COVER PLATES
IC2F-2090	MECH / ELEC FINAL INSPECTIONS	1 30-May-14	30-May-14	-		I MECH / ELEC	FINAL INSPECTIONS
IC2F-2100	BUILDING INSPECTOR FINAL INSPECTION	1 02-Jun-14	02-Jun-14			I BUILDING INS	PECTOR FINAL INSPECTION
IC2F-2110	FINAL CLEANING	5 03-Jun-14	09-Jun-14	-		□ FINAL CLEAN	NG
IC2F-2120	SECOND FLOOR COMPLETE	0	09-Jun-14			◆ SECOND FLC	OR COMPLETE
THIRD FLOOR (COMPLETE FITOUT)						
IC3F-4390	OVERHEAD ELECTRICAL ROUGH-IN	20 31-Oct-13	27-Nov-13		□ OV	ERHEAD ELECTRICAL R	OUGH-IN
IC3F-4400	OVERHEAD SPRINKLER ROUGH-IN	20 31-Oct-13	27-Nov-13	1	□ OV	ERHEAD SPRINKLER RO	DUGH-IN
IC3F-2200	OVERHEAD MECHANICAL ROUGH-IN	20 31-Oct-13	27-Nov-13		□ ov	ERHEAD MECHANICAL F	ROUGH-IN
IC3F-2220	INSTALL HM DOOR FRAMES	15 14-Nov-13	06-Dec-13		□ I N	STALL HM DOOR FRAME	S
IC3F-2230	INSTALL METAL STUDS / INCLUDES MECHANICAL SHAFTS	15 14-Nov-13	06-Dec-13	1	□ I N	STALL METAL STUDS / IN	CLUDES MECHANICAL SH
IC3F-2240	ELEC ROUGH IN AT METAL STUDS	18 18-Nov-13	13-Dec-13		E1	EC ROUGH IN AT METAL	STUDS
IC3F-4410	INSTALL DUCT RISERS IN NEW MECHANICAL SHAFT	5 21-Nov-13	27-Nov-13		o ins	STALL DUCT RISERS IN N	EW MECHANICAL SHAFT
IC3F-2250	PIPE INSULATION AT WALLS AND CEILINGS	7 05-Dec-13	13-Dec-13	1	□ P	PE INSULATION AT WAL	S AND CEILINGS
IC3F-2260	INSTALL FIRESTOPPING	3 18-Dec-13	20-Dec-13		1 11	NSTALL FIRESTOPPING	
IC3F-2540	TEST ALLABOVE CEILING PIPING	3 18-Dec-13	20-Dec-13	1	1 T	ESTALLABOVE CEILING	PIPING
IC3F-2270	MECH / ELEC ROUGH IN INSPECTIONS	1 23-Dec-13	23-Dec-13	1	1 N	MECH / ELEC ROUGH IN	INSPECTIONS
IC3F-2280	BUILDING INSPECTOR INSPECTION	1 24-Dec-13	24-Dec-13		THE STATE OF THE S	BUILDING INSPECTOR IN	SPECTION
IC3F-2290	INSTALL DRYWALL / INCLUDES MECHANICAL SHAFTS	15 27-Feb-14	20-Mar-14			■ INSTALL DRYWALL	/ INCLUDES MECHANICAL
IC3F-2300	TAPE AND FINISH DRYWALL	15 06-Mar-14	27-Mar-14	1		☐ TAPE AND FINISH [PRYWALL
IC3F-2310	PRIME PAINT	10 21-Mar-14	03-Apr-14	1		□ PRIME PAINT	
IC3F-2330	INSTALL CERAMIC TILE AT BATHROOMS	7 28-Mar-14	07-Apr-14			1 INSTALL CERAMIC	TILE AT BATHROOMS
		BULEY LIBRARY I	RENOVATIONS				
Remaining Leve Actual Work	el of Etfort	PRELIMINARY CONST		UI F		@174 316	
Remaining Worl Critical Remainin Milestone		BL05 PAGE 25 OF 32 D				SKANS	KA

	SKANSKA							
Activity ID	Activity Name	Original Start Duration	Finish	2012 J J A S O N D J F	2013 FMAMJJASON	2014 2015 D J F M A M J J A S O N D J F M A M J J A S O N D		
IC3F-2320	INSTALL MECH / SPRINKLER CEILING DROPS	7 02-Apr-14	10-Apr-14			INSTALLMECH / SPRINKLER CEILING DROI		
IC3F-2530	INSTALL AND TEST WIRING TO VAV'S	5 04-Apr-14	10-Apr-14			I INSTALLAND TEST WIRING TO VAV'S		
IC3F-2340	INSTALL ACT / TEC CEILING GRID	10 09-Apr-14	22-Apr-14	7		□ INSTALL ACT / TEC CEILING GRID		
IC3F-2350	INSTALL LIGHT FIXTURES	7 21-Apr-14	29-Apr-14	7		I INSTALL LIGHT FIXTURES		
IC3F-2360	INSTALL SPRINKLER HEADS	7 21-Apr-14	29-Apr-14	7		I INSTALL SPRINKLER HEADS		
IC3F-2370	INSTALL ELECT RECEPTACLES AND SWITCHES	5 23-Apr-14	29-Apr-14	+		I INSTALL ELECT RECEPTACLES AND SWIT		
IC3F-2380	INSTALL HVAC GRILLES	5 23-Apr-14	29-Apr-14	-		I INSTALL HVAC GRILLES		
IC3F-2390	INSTALL PLUMBING FIXTURES	5 23-Apr-14	29-Apr-14	-		I INSTALL PLUMBING FIXTURES		
IC3F-2400	INSTALL TEL/DATA JACKS	3 25-Apr-14	29-Apr-14	-		I INSTALL TEL/DATA JACKS		
IC3F-2410	INSTALL THERMOSTATS	3 25-Apr-14	29-Apr-14	-		I INSTALL THERMOSTATS		
IC3F-2420	INSTALLACT / TEC CEILING TILES / PANELS	10 30-Apr-14	13-May-14			☐ INSTALLACT / TEC CEILING TILES / PANE		
IC3F-2430	HANG DOORS	5 14-May-14	20-May-14			□ HANG DOORS		
IC3F-2440	FINISH PAINT	7 21-May-14	30-May-14			I FINISH PAINT		
IC3F-2460	INSTALL DOOR HARDWARE	5 02-Jun-14	06-Jun-14			1 INSTALL DOOR HARDWARE		
IC3F-2450	INSTALL FINISH MILLWORK	14 02-Jun-14	19-Jun-14			□ INSTALL FINISH MILLWORK		
IC3F-2470	INSTALL CARPET / FLOORING	12 11-Jun-14	26-Jun-14	1		□ INSTALL CARPET / FLOORING		
IC3F-2480	INSTALL ELEC COVER PLATES	3 17-Jun-14	19-Jun-14			I INSTALL ELEC COVER PLATES		
IC3F-2490	MECH / ELEC FINAL INSPECTIONS	1 20-Jun-14	20-Jun-14			I MECH / ELEC FINAL INSPECTIONS		
IC3F-2500	BUILDING INSPECTOR FINAL INSPECTION	1 23-Jun-14	23-Jun-14			I BUILDING INSPECTOR FINAL INSPECT		
IC3F-2510	FINAL CLEANING	5 24-Jun-14	30-Jun-14			I FINAL CLEANING		
IC3F-2520	THIRD FLOOR COMPLETE	0	30-Jun-14			♦ THIRD FLOOR COMPLETE		
FOURTH FLOOR (COMPLETE FITOUT)							
	T	BULEY LIBRARY	/ DENOVATIONS					
Remaining Level o	f Effort							
Remaining Work		PRELIMINARY CONS	TRUCTION SCHED	ULE	SKANSKA			
Critical Remaining	Work	BL05 PAGE 26 OF 32	DATA DATE = 15-Ja	n-13				
◆ ◆ Milestone								

	SKANSKA					
tivity ID	Activity Name	Original Start Duration	Finish	2012	2013	2014 2015
IC4F-4410	OVERHEAD ELECTRICAL ROUGH-IN	20 02-Dec-13	30-Dec-13	J J A S O N D J F M	AMJJASC	OVERHEAD ELECTRICAL ROUGH-IN
IC4F-2700	OVERHEAD MECHANICAL ROUGH-IN	20 02-Dec-13	30-Dec-13	+		OVERHEAD MECHANICAL ROUGH-IN
IC4F-4420	OVERHEAD SPRINKLER ROUGH-IN	20 02-Dec-13	30-Dec-13	+		OVERHEAD SPRINKLER ROUGH-IN
IC4F-2720	INSTALL HM DOOR FRAMES	15 16-Dec-13	07-Jan-14			☐ INSTALLHM DOOR FRAMES
IC4F-2730	INSTALL METAL STUDS / INCLUDES MECHANICAL SHAFTS	15 16-Dec-13	07-Jan-14	-		☐ INSTALLMETAL STUDS / INCLUDES MECHANICAI
IC4F-2740	ELEC ROUGH IN AT METAL STUDS	18 18-Dec-13	14-Jan-14	-		□ ELEC ROUGH IN AT METAL STUDS
IC4F-4430	INSTALL DUCT RISERS IN NEW MECHANICAL SHAFT	5 23-Dec-13	30-Dec-13			I INSTALL DUCT RISERS IN NEW MECHANICAL SHA
IC4F-2750	PIPE INSULATION AT WALLS AND CEILINGS	7 06-Jan-14	14-Jan-14	-		□ PIPE INSULATION AT WALLS AND CEILINGS
IC4F-2760	INSTALL FIRESTOPPING	3 17-Jan-14	21-Jan-14			ı İNSTALL FIRESTOPPING
IC4F-3040	TEST ALL ABOVE CEILING PIPING	3 17-Jan-14	21-Jan-14	-		I TEST ALLABOVE CEILING PIPING
IC4F-2770	MECH / ELEC ROUGH IN INSPECTIONS	1 22-Jan-14	22-Jan-14	-		I MECH / ELEC ROUGH IN INSPECTIONS
IC4F-2780	BUILDING INSPECTOR INSPECTION	1 23-Jan-14	23-Jan-14	-		I BUILDING INSPECTOR INSPECTION
IC4F-2790	INSTALL DRYWALL / INCLUDES MECHANICAL SHAFTS	15 21-Mar-14	10-Apr-14	-		■ INSTALL DRYWALL / INCLUDES MECHANIC
IC4F-2800	TAPE AND FINISH DRYWALL	15 28-Mar-14	17-Apr-14			☐ TAPE AND FINISH DRYWALL
IC4F-2810	PRIME PAINT	10 11-Apr-14	24-Apr-14			□ PRIME PAINT
IC4F-2830	INSTALL CERAMIC TILE AT BATHROOMS	7 18-Apr-14	28-Apr-14			□ INSTALL CERAMIC TILE AT BATHROOMS
IC4F-2820	INSTALL MECH / SPRINKLER CEILING DROPS	7 23-Apr-14	01-May-14			I INSTALL MECH / SPRINKLER CEILING DE
IC4F-3030	INSTALLAND TEST WIRING TO VAV'S	5 25-Apr-14	01-May-14			I INSTALLAND TEST WIRING TO VAV'S
IC4F-2840	INSTALLACT / TEC CEILING GRID	10 30-Apr-14	13-May-14	+		□ INSTALLACT / TEC CEILING GRID
IC4F-2850	INSTALL LIGHT FIXTURES	7 12-May-14	20-May-14	1		□ INSTALL LIGHT FIXTURES
IC4F-2860	INSTALL SPRINKLER HEADS	7 12-May-14	20-May-14			□ INSTALL SPRINKLER HEADS
IC4F-2870	INSTALL ELECT RECEPTACLES AND SWITCHES	5 14-May-14	20-May-14			□ INSTALL ELECT RECEPTACLES AND SM
	·	,	-			
Remaining Level Actual Work	of Effort	BULEY LIBRARY	RENOVATIONS			

Actual Work

Remaining Work

Critical Remaining Work

Milestone

PRELIMINARY CONSTRUCTION SCHEDULE

BL05 PAGE 27 OF 32 DATA DATE = 15-Jan-13



		SKANSKA										
Act	vity ID	Activity Name		Original Duration	Start	Finish	2012 .II A S O N D	JEM	2013 I. II. I		2014 N D J F M A M J J A S O N D J	2015
	IC4F-2880	INSTALL HVAC GRILLES		5	14-May-14	20-May-14		<u> </u>	NIMI O O	1110101	□ INSTALL HVAC G	RILLES
П	IC4F-2890	INSTALL PLUMBING FIXTURES		5	14-May-14	20-May-14					□ INSTALL PLUMB	NG FIXTURES
П	IC4F-2900	INSTALL TEL/DATA JACKS		3	16-May-14	20-May-14					I INSTALL TEL/DA	TAJACKS
П	IC4F-2910	INSTALL THERMOSTATS		3	16-May-14	20-May-14					I INSTALL THERM	OSTATS
ı	IC4F-2920	INSTALL ACT / TEC CEILING TILES / F	PANELS	10	21-May-14	04-Jun-14					□ INSTALLACT / 1	EC CEILING TILES / PAI
ı	IC4F-2930	HANG DOORS		5	05-Jun-14	11-Jun-14					I HANG DOORS	
ı	IC4F-2940	FINISH PAINT		7	12-Jun-14	20-Jun-14					□ FINISH PAINT	
	IC4F-2960	INSTALL DOOR HARDWARE		5	23-Jun-14	27-Jun-14					□ INSTALL DOO	R HARDWARE
ı	IC4F-2950	INSTALL FINISH MILLWORK		14	23-Jun-14	11-Jul-14					□ INSTALL FINI	SH MILLWORK
ı	IC4F-2970	INSTALL CARPET / FLOORING		12	02-Jul-14	18-Jul-14					☐ INSTALL CA	RPET / FLOORING
ı	IC4F-2980	INSTALL ELEC COVER PLATES		3	09-Jul-14	11-Jul-14					I INSTALLELE	C COVER PLATES
	IC4F-2990	MECH / ELEC FINAL INSPECTIONS		1	14-Jul-14	14-Jul-14					I MECH/ELE	C FINAL INSPECTIONS
	IC4F-3000	BUILDING INSPECTOR FINAL INSPE	CTION	1	15-Jul-14	15-Jul-14					I BUILDING IN	ISPECTOR FINAL INSPE
П	IC4F-3010	FINAL CLEANING		5	15-Jul-14	21-Jul-14					☐ FINAL CLEA	NING
ı	IC4F-3020	FOURTH FLOOR COMPLETE		0		21-Jul-14					◆ FOURTH FL	OOR COMPLETE
	FOURTH FLOOR A	DDITION (COMPLETE FITOUT)										
	IC4FA-4000	OVERHEAD MECHANICAL ROUGH-II	N	15	31-Dec-13	21-Jan-14					□ OVERHEAD MECHANICA	LROUGH-IN
	IC4FA-4430	OVERHEAD ELECTRICAL ROUGH-IN	V	15	31-Dec-13	21-Jan-14					OVERHEAD ELECTRICAL	ROUGH-IN
	IC4FA-4440	OVERHEAD SPRINKLER ROUGH-IN		15	31-Dec-13	21-Jan-14					☐ OVERHEAD SPRINKLER	ROUGH-IN
	IC4FA-4450	INSTALL DUCT RISERS IN NEW MEC	HANICAL SHAFT	5	15-Jan-14	21-Jan-14					I INSTALL DUCT RISERS II	NEW MECHANICAL SE
	IC4FA-4020	INSTALL HM DOOR FRAMES		10	15-Jan-14	28-Jan-14					☐ INSTALL HM DOOR FRAI	VIES
	IC4FA-4030	INSTALL METAL STUDS / INCLUDES	MECHANICAL SHAFTS	10	15-Jan-14	28-Jan-14					■ INSTALL METAL STUDS /	INCLUDES MECHANICA
			,	J.		1		, , , ,		. , , ,		
•	Remaining Level of	f Effort		BU	JLEY LIBRARY R	ENOVATIONS						
	Actual Work			PRELIM	MINARY CONSTE	RUCTION SCHED	ULE				CVANC	I/A
	Remaining Work Critical Remaining	Work	E	BL05 PAG	GE 28 OF 32 DA	ATA DATE = 15-Ja	n-13				SKANS	KA
•	Milestone	TO CONTROL OF THE CON										
	¥ 111110010110											

: 10	SKANSKA		le	
vity ID	Activity Name	Original Start Duration	Finish	2012 2013 2014 2015 J J A S O N D J F M A M J J A S O N D J F M A M J J A S O N D J F M A M J J A S O N I
IC4FA-4040	ELEC ROUGH IN AT METAL STUDS	10 22-Jan-14	04-Feb-14	□ ELEC ROUGH IN AT METAL STUDS
IC4FA-4050	PIPE INSULATION AT WALLS AND CEILINGS	5 29-Jan-14	04-Feb-14	n PIPE INSULATION AT WALLS AND CEILINGS
IC4FA-4060	INSTALL FIRESTOPPING	3 07-Feb-14	12-Feb-14	1 INSTALL FIRESTOPPING
IC4FA-4330	TEST ALL ABOVE CEILING PIPING	3 07-Feb-14	12-Feb-14	I TEST ALLABOVE CEILING PIPING
IC4FA-4070	MECH / ELEC ROUGH IN INSPECTIONS	1 13-Feb-14	13-Feb-14	I MECH/ELEC ROUGH IN INSPECTIONS
IC4FA-4080	BUILDING INSPECTOR INSPECTION	1 14-Feb-14	14-Feb-14	I BUILDING INSPECTOR INSPECTION
IC4FA-4090	INSTALL DRYWALL / INCLUDES MECHANICAL SHAFTS	10 09-Apr-14	22-Apr-14	■ INSTALL DRYWALL / INCLUDES MECHANI
IC4FA-4100	TAPE AND FINISH DRYWALL	10 16-Apr-14	29-Apr-14	■ TAPE AND FINISH DRYWALL
IC4FA-4110	PRIME PAINT	7 28-Apr-14	06-May-14	■ PRIME PAINT
IC4FA-4130	INSTALL CERAMIC TILE AT BATHROOMS	7 30-Apr-14	08-May-14	☐ INSTALL CERAMIC TILE AT BATHROOMS
IC4FA-4120	INSTALL MECH / SPRINKLER CEILING DROPS	7 05-May-14	13-May-14	■ INSTALL MECH / SPRINKLER CEILING D
IC4FA-4190	INSTALL AND TEST WIRING TO VAV'S	5 07-May-14	13-May-14	□ INSTALLAND TEST WIRING TO VAV'S
IC4FA-4140	INSTALL ACT / TEC CEILING GRID	10 12-May-14	23-May-14	■ INSTALLACT / TEC CEILING GRID
IC4FA-4150	INSTALL LIGHT FIXTURES	7 22-May-14	02-Jun-14	■ INSTALL LIGHT FIXTURES
IC4FA-4160	INSTALL SPRINKLER HEADS	7 22-May-14	02-Jun-14	■ INSTALL SPRINKLER HEADS
IC4FA-4170	INSTALL ELECT RECEPTACLES AND SWITCHES	3 29-May-14	02-Jun-14	I INSTALL ELEGT RECEPTACLES AND S
IC4FA-4180	INSTALL HVAC GRILLES	3 29-May-14	02-Jun-14	I INSTALL HVAC GRILLES
IC4FA-4200	INSTALL TEL/DATA JACKS	3 29-May-14	02-Jun-14	I INSTALL TEL/DATA JACKS
IC4FA-4210	INSTALL THERMOSTATS	3 29-May-14	02-Jun-14	I INSTALL THERMOSTATS
IC4FA-4220	INSTALLACT / TEC CEILING TILES / PANELS	10 03-Jun-14	16-Jun-14	■ INSTALLACT / TEC CEILING TILES / PA
IC4FA-4230	HANG DOORS	3 17-Jun-14	19-Jun-14	I HANG DOORS
IC4FA-4240	FINISH PAINT	5 20-Jun-14	26-Jun-14	■ FINISH PAINT

Actual Work
Remaining Work
Critical Remaining Work

Milestone

PRELIMINARY CONSTRUCTION SCHEDULE

BL05 PAGE 29 OF 32 DATA DATE = 15-Jan-13



: ID	SKANSKA	Order of Oct.	T:=:-1:	10010	2017
ivity ID	Activity Name	Original Start Duration	Finish		013 2014 2015 J A S O N D J F M A M J J A S O N D J F M A M J J A S O N
IC4FA-4260	INSTALL DOOR HARDWARE	5 27-Jun-14	03-Jul-14		I INSTALL DOOR HARDWARE
IC4FA-4250	INSTALL FINISH MILLWORK	10 27-Jun-14	11-Jul-14		■ INSTALL FINISH MILLWORK
IC4FA-4270	INSTALL CARPET / FLOORING	10 07-Jul-14	18-Jul-14		■ INSTALL CARPET / FLOORING
IC4FA-4280	INSTALL ELEC COVER PLATES	3 09-Jul-14	11-Jul-14	-	I INSTALLELEC COVER PLATES
IC4FA-4290	MECH / ELEC FINAL INSPECTIONS	1 14-Jul-14	14-Jul-14	-	I MECH / ELEC FINAL INSPECTIONS
IC4FA-4300	BUILDING INSPECTOR FINAL INSPECTION	1 15-Jul-14	15-Jul-14	-	I BUILDING INSPECTOR FINAL INSF
IC4FA-4310	FINAL CLEANING	5 17-Jul-14	23-Jul-14	-	■ FINAL CLEANING
IC4FA-4320	FOURTH FLOOR ADDITION COMPLETE	0	23-Jul-14		◆ FOURTH FLOOR ADDITION COM
SITEWORK					
SI-160	SITE DEMO AS REQUIRED	10 01-May-13	14-May-13	□ SI	TE DEMO AS REQUIRED
SI-100	INSTALL ALL UTILITIES AS REQUIRED	25 15-May-13	19-Jun-13	-	INSTALL ALL UTILITIES AS REQUIRED
SI-110	FINE GRADE SITE	10 20-Jun-13	03-Jul-13		I FINE GRADE SITE
SI-170	INSTALL SITE LIGHTING	10 05-Jul-13	18-Jul-13		□ INSTALL SITE LIGHTING
SI-120	CONSTRUCT ALL WALKS/ RAMPS/STAIRS AS REQUIRED	35 03-Mar-14*	21-Apr-14	-	CONSTRUCT ALL WALKS/ RAMPS/STAJF
SI-140	INSTALL ALL PAVEMENT AS REQUIRED	10 15-Apr-14	28-Apr-14	-	□ INSTALLALL PAVEMENT AS REQUIRED
SI-130	INSTALLALL REQUIRED CONCRETE PAVERS	35 22-Apr-14	10-Jun-14	-	INSTALLALL REQUIRED CONCRETE
SI-150	INSTALLALL REQUIRED LANDSCAPING	25 06-May-14	10-Jun-14	 	INSTALLALL REQUIRED LANDSCAP
SI-180	SITEWORK COMPLETE	1 10-Jun-14	10-Jun-14	-	I SITEWORK COMPLETE
LOCAL AND ST	TATE INSPECTIONS (BASE BID ONLY)				
LSI-710	ELECTRICAL FINAL INSPECTION	1 27-May-14	27-May-14		I ELECTRICAL FINAL INSPECTION
Remaining Level	of Effort	BULEY LIBRARY F	RENOVATIONS		
Actual Work		PRELIMINARY CONST	RUCTION SCHED	ULE	CLANCIA
Remaining Work Critical Remaining		BL05 PAGE 30 OF 32 D	ATA DATE = 15-Ja	n-13	SKANSKA
Milestone	y work			-	

	SKANSKA						
Activity ID	Activity Name	Original Start Duration	Finish	2012 J J A S O N D J F M A	2013 M. J. J. A. S. O. N. D. J	2014 F	2015 F M A M J J A S O N D
LSI-720	PLUMBING FINAL INSPECTION	1 27-May-14	27-May-14			PLUMBING FINA	LINSPECTION
LSI-730	MECHANICAL FINAL INSPECTION	1 27-May-14	27-May-14			ı MECHANICAL F	NAL INSPECTION
LSI-740	FIRE ALARM FINAL INSPECTION	2 28-May-14	29-May-14			I FIRE ALARM FIN	AL INSPECTION
LSI-760	WEATHER DAYS	10 30-May-14	12-Jun-14			□ WEATHER DAY	S
LSI-750	ISSUE C OF O / SUBSTANTIAL COM	PLETION 0	12-Jun-14			◆ ISSUE C OF O	SUBSTANTIAL COMPLE
LOCAL AND S	TATE INSPECTIONS (BASE BID PLUS S	SECOND FLOOR)					
LSI-800	ELECTRICAL FINAL INSPECTION	1 10-Jun-14	10-Jun-14			I ELECTRICAL F	NAL INSPECTION
LSI-810	PLUMBING FINAL INSPECTION	1 10-Jun-14	10-Jun-14			I PLUMBING FIN	ALINSPECTION
LSI-820	MECHANICAL FINAL INSPECTION	1 10-Jun-14	10-Jun-14	7		ı MECHANICAL F	INAL INSPECTION
LSI-830	FIRE ALARM FINAL INSPECTION	2 11-Jun-14	12-Jun-14			I FIRE ALARM FI	NAL INSPECTION
LSI-840	WEATHER DAYS	10 13-Jun-14	26-Jun-14			□ WEATHER DA	YS
LSI-850	ISSUE C OF O / SUBSTANTIAL COM	PLETION 0	26-Jun-14			♦ ISSUE C OF C	/SUBSTANTIAL COMPL
LOCAL AND S	TATE INSPECTION (BASE BID + FLOOF	IS 2 & 3)					
LSI-900	ELECTRICAL FINAL INSPECTION	1 01-Jul-14	01-Jul-14			ELECTRICAL	FINAL INSPECTION
LSI-910	PLUMBING FINAL INSPECTION	1 01-Jul-14	01-Jul-14			i PLUMBING FI	NALINSPECTION
LSI-920	MECHANICAL FINAL INSPECTION	1 01-Jul-14	01-Jul-14			I MECHANICAL	FINAL INSPECTION
LSI-930	FIRE ALARM FINAL INSPECTION	2 02-Jul-14	03-Jul-14			I FIREALARM	INAL INSPECTION
LSI-940	WEATHER DAYS	10 07-Jul-14	18-Jul-14			□ WEATHER D	AYS
LSI-950	ISSUE C OF O / SUBSTANTIAL COM	PLETION 0	18-Jul-14			◆ ISSUE C OF	O/SUBSTANTIAL COMP
LOCAL AND S	TATE INSPECTIONS (BASE BID + FLOO	PRS 2, 3, & 4)					
				,	·		
Remaining Leve	el of Effort	BULEY LIBRAR	/ RENOVATIONS				
Actual Work Remaining Wor		PRELIMINARY CONS	STRUCTION SCHED	ULE		CVANC	VA
Critical Remaining		BL05 PAGE 31 OF 32	DATA DATE = 15-Ja	n-13		SKANS	IVA
◆ Milestone	-						

ctivity ID	SKANSKA Activity Name	Original Start	Finish	2012 2013	2014 2015
CIVILY ID	Activity Name	Duration	FINISH		2014 2015 A S O N D J F M A M J J A S O N D J F M A M J J A S O N
LSI-1000	ELECTRICAL FINAL INSPECTION	1 22-Jul-14	22-Jul-14		I ELECTRICAL FINAL INSPECTION
LSI-1010	PLUMBING FINAL INSPECTION	1 22-Jul-14	22-Jul-14	1	I PLUMBING FINAL INSPECTION
LSI-1020	MECHANICAL FINAL INSPECTION	1 22-Jul-14	22-Jul-14		I MECHANICAL FINAL INSPECTION
LSI-1030	FIRE ALARM FINAL INSPECTION	2 23-Jul-14	24-Jul-14	-	I FIRE ALARM FINAL INSPECTION
LSI-1040	WEATHER DAYS	10 25-Jul-14	07-Aug-14	-	□ WEATHER DAYS
LSI-1050	ISSUE C OF O / SUBSTANTIAL COMPLETION	0	07-Aug-14	1	◆ ISSUE C OF O / SUBSTANTIAL C
LOCAL AND S	TATE INSPECTIONS (BASE BID + FLOORS 2,3,4,& 4A)				
LSI-1100	ELECTRICAL FINAL INSPECTION	1 24-Jul-14	24-Jul-14		I ELECTRICAL FINAL INSPECTION
LSI-1110	PLUMBING FINAL INSPECTION	1 24-Jul-14	24-Jul-14	1	I PLUMBING FINAL INSPECTION
LSI-1120	MECHANICAL FINAL INSPECTION	1 24-Jul-14	24-Jul-14		ı MECHANICAL FINAL INSPECTIOI
LSI-1130	FIRE ALARM FINAL INSPECTION	2 25-Jul-14	28-Jul-14		■ FIRE ALARM FINAL INSPECTION
LSI-1140	WEATHER DAYS	10 29-Jul-14	11-Aug-14		■ WEATHER DAYS
LSI-1150	ISSUE C OF O / SUBSTANTIAL COMPLETION	0	11-Aug-14		◆ ISSUE C OF O / SUBSTANTIAL O
POST SUBSTA	ANTIAL COMPLETION				
SC-100	SCSU FF&E	30 12-Aug-14	23-Sep-14		SCSU FF&E
SC-130	PROJECT CLOSEOUT	90 12-Aug-14	18-Dec-14		PROJECT CLOSEOUT
SC-110	SCHOOL ADMINISTRATORS / TEACHERS OCCUPY BLDG	15 24-Sep-14	15-Oct-14		□ SCHOOL ADMINISTRATOR
SC-120	STUDENT USE OF BUILDING	0 16-Oct-14			◆ STUDENT USE OF BUILDIN
		,	'		
		DIII EVI IDDADV	DENOVATIONS		
Remaining Level	el of Effort	BULEY LIBRARY RENOVATIONS			
Remaining Wor		PRELIMINARY CONST			SKANSKA
Critical Remain	ing Work	BL05 PAGE 32 OF 32 D	va i a Da i E = 15-Jan	1-13	



1.

Southern Connecticut State University - Buley Library Renovation BI-RS-225B CMR

Project:	Buley Library Renovations BI-RS-225B CMR				
Bid Package: Bid Package No.:					
Bid Due Date/Time: Friday, February 8 th , 2013 – 11am					
(BIDDER MUST SUBMIT SEPAF	RATE BID FORMS WHEN BIDDING MULTIPLE PACKAGES)				
Proposal Submitted By:					
Proposat Submitted by.					
Company Name Address					
Telephone Fax					
Subcontractor License No.					
Subcontractor EMR Rate					
Federal Tax ID No. Business Classification	MBE SBE				
business etassineation	IVIDE VVDE 3DE				
BASE BID					
Documents and any incider operational system for all w	reby proposes to provide for all work as defined in the Contraction tall work necessary to construct a complete, working, and full work as defined herein, for the totally inclusive lump sum amount and use taxes of:				
including all applicable sales a (Written)	s taxes or.				

BID PROPOSAL FORM

Note #1 - The award of subcontracts for a specific bid package will be based on the lowest qualified and responsible Subcontractor base bid plus those Supplemental Bids selected. The selection of supplemental bids will be determined after the bid opening and is contingent on the available project funds.

Note #2 - The award of supplemental bids will be taken in order as they appear in Note #3 of the Subcontractor Proposal Form. If project funds do not allow for a supplemental bid to be taken in its entirety, the owner reserves the right to add portions of the supplemental bid. The definition of "Supplemental Bid" is outlined in the Section #4.1.4 of the Instruction to Bidders.



Note #3 - If project funds do not allow for a supplemental bid to be taken in its entirety, the owner reserves the right to add portions of the supplemental bid in following order from first to last: BP15A, BP15, BP16, BP13, BP13B, BP09, BP08A, BP09A, BP08, BP09B, BP09C, BP12, BP10A, and BP13A. Remaining trades not listed will be selected at the owner's discretion.

2.

2.	CONTRACT
	Bidder has reviewed the Skanska USA Building Inc. Subcontract Agreement, acknowledges al requirements are included in the above lump sum price, and agrees to sign upon contract award without modification:
	Acknowledged (box must be marked)
3.	EXISTING INVENTORY MATERIALS
fo factor distant trace of 355	dder has reviewed the Existing Inventory Materials list included in section 00 31 25 , and subsequent ddendum #1 Inventory Update and has included those materials assigned to your specific bid package ruse on this project. Bidder is responsible for the transportation of inventory materials from storage cilities to your shop for fabrication or to the project site for installation. Any unused materials assigned your bid package will be the responsibility of this Subcontractor to remove from storage and legally spose of at no additional cost to the project unless specifically identified to be turned over to the owner the completion of the project. Materials currently stored on site shall be removed by the responsible ades prior to the start of construction. Delivery of any and all materials to the jobsite shall be ordinated with the Project Schedule and reviewed with Skanska's Superintendent. <i>Refer to section Of the project Schedule and reviewed with Skanska's Superintendent.</i> Refer to section Of the project of the owner at project ampletion.
	Acknowledged (box must be marked)
4.	COMMISSION ON HUMAN RIGHTS AND OPPORTUNTIES (SELECT NON-SET ASIDE BID PACKAGES)
	Select Non Set-Aside Subcontractors, as identified in the Invitation to Bid, shall award twenty five (25%) percent or more of the value of this Subcontract to DAS certified SBE's. This Subcontractor shall also award ten (10%) percent or more to DAS certified M/WBE's.
	Note: All SBE Set-Aside bidders will be required to award five (5%) percent or more of the value of this subcontract to DAS certified M/WBE's.
	Within five (5) days of Bid Opening, this apparent lowest bidder will disclose its estimated costs for the named SBE and M/WBE Sub-Subcontracts to verify compliance with this requirement.
	By submitting this bid, this Subcontractor has acknowledged and agreed to this requirement.
	Acknowledged (box must be marked)
	Failure to acknowledge and verify compliance with these requirements will result in a bid that is non-responsive and will be rejected.

ADDENDUM #2 **BID PROPOSAL FORM** 00 41 00 Page 2 of 6



5.	ADDENDA			
	Receipt of the following	Addenda is hereby acknow	wledged:	
	Addendum No Addendum No Addendum No	o. 2	Date 01-19 Date 01-22 Date	
6.	SUB-SUBCONTRACTORS	5		
	The following Sub-Subc	ontractors are included wit	th this proposal:	
	Sub-Subcontractor	Scope of Work	Business Classification (SBE, MBE, WBE)	EMR
_			_	
_				
_			_	
_				-
7.	SUPPLEMENTAL BIDS (A	Addendum #2)		
		olemental pricing indicated	rk of the bid package under wh I shall remain valid for the life o	
	A. <u>Supplemental Bid 1</u>	: Add to complete 2 nd Floo	r Fit-Out <i>(reference A-102A)</i>	\$
	Note: 3 rd and 4 th floor fi and A104.1 is not part of	t-out work identified in the	e contract documents <i>on draw.</i> Id as a separate project at a fut	ings A103A, A104A ure date.
8.	UNIT PRICES			
	specific scopes of work.		erations identifies established is Subcontractor has acknowle o this proposal.	
	A	Acknowledged (box must b	e marked) 🔲	
9.	LABOR & EQUIPMENT R	ATES		

A. LABOR RATES

Skanska may elect to have Subcontractor provide labor (or additional labor) in connection with its Scope. All additional labor shall be billed at the applicable rate as required by law. Each specified rate is inclusive of all of Subcontractor's costs and expenses to furnish the additional labor in accordance with all requirements of the Subcontract/Purchase Order.



This Subcontractor shall complete the requested information noted below based on their Scope of Work. This shall be used as reference only and does not constitute acceptance. This Subcontractor will be required to provide a complete breakdown in accordance with Exhibit C prior to issuance of a Subcontract.

	Trade	Straight Time			Premium Time			Double Time	
1.	Forman	\$	_ /hr	\$_		_/hr	\$_		/hr
2.	Journeyman	\$	_/hr	\$_		/hr	\$		/hr
3.	Apprentice	\$	_ /hr	\$_		_/hr	\$_		/hr
4.	Laborer	\$	_ /hr	\$_		_/hr	\$_		/hr
5.		\$	_/hr	\$		/hr	\$_		/hr
6.		\$	/hr	\$		/hr	\$		/hr

10. EQUIPMENT

Skanska may elect to have Subcontractor provide any of the following equipment in connection with its Scope at the applicable "Hourly", "Daily", "Weekly", or "Monthly" rate specified. Each specified rate is inclusive of all of Subcontractor's costs and expenses to furnish the equipment in accordance with all requirements of the Subcontract/Purchase Order, including but not limited to the following: transportation, delivery, pickup, fuel, energy costs, consumables, connections, maintenance, wear and tear, repair, depreciation, storage, tax, overhead, and profit. If an hourly rate is used, equipment shall be charged based upon actual usage within ½ hour.

This Subcontractor shall complete the requested information noted below based on their Scope of Work. This shall be used as reference only and does not constitute acceptance. This Subcontractor will be required to provide a complete breakdown in accordance with Exhibit C prior to issuance of a Subcontract.

		F	Rate	
Equipment Description	Hourly	Daily	Weekly	Monthly

Rental costs of Subcontractor equipment not shown on the list above shall be charged as follows:

- 80% of the rates shown in the latest edition of "Nationally Averaged Rental Rate and Model Reference Data for Construction Equipment" prepared by Associated Equipment Distributors, Chicago, Illinois ("AED"); or if not shown in AED,
- 80% of the rates shown in the latest edition of "Tool and Equipment Rental Guide" prepared by Mechanical Contractors Association of America ("MCA"); or if not shown in MCA,
- 60% of the rates shown in the latest edition of "Rental Rate Blue Book for Construction Equipment" published by Equipment Guidebook Company, Palo Alto, CA ("Blue Book"); or if not shown in the Blue Book,
- 60% of the rates shown in the latest edition of "Tool and Equipment Rental Schedule" published by National Electrical Contractors Association, Bethesda, MD ("NECA").



11. CHANGE ORDERS/ALLOWABLE MARKUPS (Addendum #2)

Subcontractor/Seller shall apply the following overhead and profit markups for changes in the Scope in accordance with State of Connecticut DPW/DCS Standard forms 735 and 737:

		OH&P <u>% Markup</u>
A.	Labor, Material and Equipment up to \$5,000	20%
В.	Labor, Material and Equipment \$5,001 to \$15,000	17%
С.	Labor, Material and Equipment \$15,001 to \$25,000	15%
D.	Labor, Material and Equipment \$25,001 and greater	12%

- The markup on labor shall be reflected in the labor rates stated in Section V and shown in the Labor Rate Breakdown.
- The markup on material shall be applied after all applicable discounts and rebates due Subcontractor/Seller are considered.
- The markup on third party rentals shall be applied to the direct invoiced cost. Equipment owned by the Subcontractor/Seller is not eligible for markup, and is subject to the rates shown in Subcontract Exhibit C Section IV.
- The markup on Sub-subcontractor/Subsupplier work/supply in connection with a change in Scope shall be applied to the direct invoiced cost from the Sub-subcontractor/Subsupplier. Sub-subcontractor's/Subsupplier's markup for its own direct cost shall not exceed the percentages listed above for labor, material, and third party rentals.
- The additional bond and insurance premium on a change in Scope shall be applied to the direct cost of the change and is not eligible for markup.
- Overhead and profit shall be inclusive of the following: home office costs, management, supervision, training, vehicles and pickups, travel, reproduction, temporary facilities, computers, office equipment, small tools, and other incidentals. Small tools are defined as tools that do not have a new unit cost in excess of \$750.00.
- CT DPW/DCS Form must be completed inclusive of associated backup documentation for each change order proposal submitted by the prime subcontractor.

12. BASE BID COST BREAKDOWN

The following information is required at time of bid:

Material Cost	\$
Labor Cost (Total Hours / Avg. Crew)	\$
Equipment Cost	\$
Insurance, Bond, Other Costs	\$
Tax, as Required	\$
Total Cost (Must Equal Base Bid)	\$

ADDENDUM #2 BID PROPOSAL FORM 00 41 00 Page 5 of 6



	In addition to the above cost breakdown, Skanska reserves the right to request additional cost breakdowns at the time of scope review and prior to Contract Award.
	By submitting this bid, this Subcontractor has acknowledged and agreed to this requirement.
	Acknowledged (box must be marked)
13.	QUANTITY BREAKDOWN
	Skanska reserves the right to request quantity breakdowns at the time of scope review and prior to Contract Award.
	By submitting this bid, this Subcontractor has acknowledged and agreed to this requirement.
	Acknowledged (box must be marked)
[BID PROPOSAL FORM ATTACHEMENTS (MUST BE SUBMITTED WITH BID PROPOSAL) Proposal Form Skanska Qualification Form DAS Prequalification Certificate (If Bid is in excess of \$500,000) Bid Bond Consent of Surety Non-Collusion Affidavit State of Connecticut OPM Ethics Form 6 Contractors Wage Certification Form Requirement Omitted via Addendum
S S F F T T T	SUBCONTRACTOR: SIGNATURE: PRINT NAME: TELEPHONE: TELEFAX: DATE: (Affix Corporate Seal – if Corporation)

ADDENDUM #2 BID PROPOSAL FORM 00 41 00 Page 6 of 6

END OF BID PROPOSAL FORM

ADDENDUM #2: BIDDING RFI LOG January 22nd, 2013

ADDENDUM #2 SUBCONTRACTOR RFIs #1-159

1.	Reference:	Drawing	E-002	Detail	Spec	00 31 25		
	QUESTION : Fixture Ty it is not available or h							
	K/R RESPONSE: The type A fixture is in the owner's inventory but shall be installed by the contractor. Reference Addendum #1, Existing Material Inventory 00 31 25.							
2.	Reference:	Drawing _	E-002	Detail	Spec			
	QUESTION : Fixture Type AA – this is a decorative post-top fixture that is noted to be surface mounted, but there is no pole specified. Since this is a decorative fixture we assume you need something decorative. Do you have a pole spec in mind?							
	K/R RESPONSE: The p The pole is a 10' alum connected to panelbo the fixture is an emer receptacles shall be g panelboard shall be u	ninum, round to pard LV-GS wit gency lighting rouped as 6 re	apered with GFI r th 2 #12, #12 gnd fixture then the r eceptacles per 20/	eceptacle in pole bas same conduit as the eceptacle wiring sha	se. The receptacles sha light fixture circuit ex ll be in its own ¾" co	all be cept where nduit. The		
3.	Reference:	Drawing	E-002	Detail	Spec			
	QUESTION: Fixture Type A10 – the description and spec is the same as Type A03 combo light, but the symbol on the plan is different. Do you have a spec for A10 or is it the same as A03? K/R RESPONSE: A-3 and A-10 are the same fixture with different number of heads (A-3 has 1 head, A-10 has 2 heads).							
4.	Reference:	Drawing	E-002	Detail	Spec			
	QUESTION : Fixture Ty but the spec is the sar like to use?	ne as A03 whi	ch is a combo ligh	nt fixture. Do you ha	ve spec for the track y			
	K/R RESPONSE: A-12	is a lighting fix	ture head on ligh	ting track LSI # 230 so	eries.			
5.	Reference:	Drawing _	E-002	Detail	Spec	00 31 25		
	QUESTION : Fixture Ty on the 2x4 and 2x2.					polic cells		
	K/R RESPONSE: Type Reference Addendum				l be installed by the co	ontractor.		
6.	Reference:	Drawing _		Detail	Spec	09 66 23		
	QUESTION: Bid Packa Original invite to bid t Carpet. Is the terrazzo	o bid shows se	et aside bid packa	ges BP# 09C "Ceram				

ADDENDUM #2: BIDDING RFI LOG January 22nd, 2013

	SKANSKA RESPONSE: BP-09D Poured Terrazzo is responsible for Specification Section 09 66 23 Thin Set Epoxy Terrazzo. There is no terrazzo tile on the project.							
7.	Reference:	Drawing	Detail	Spec <u>09 68 16</u>				
	 QUESTION: Spec Section #09 68 16 "Carpet (Glue Down) & other owner supplied items a. Our estimate is to include labor only to install owner supplied carpet. If we estimate the job and find the owner's carpet insufficient in quantity, do we include \$ to supply added carpet. b. Spec Section #09 68 16 sub section #1.4 D. "Carpet supplied for this project must be from same dye lot for each carpet type." Are we are to assume that each carpet type previously purchased is all the same dye lot. And if any additional carpet is needed to be purchased it will obviously be at least another dye lot. c. If additional carpet is needed to be purchased @ post bid, will the owner be issuing a change order for us to purchase or will SCSU / State deal directly with the carpet supplier? d. Spec Section #09 68 16 "Carpet" Subsection #1.7 "Warranty" B. Mfg. Warranty – We wouldn't be providing this warranty for carpet already purchased. Just for any new carpet needed 							
	OPA RESPONSE: a: no b: yes c: it is unlikely that additional carpet will be needed based on quantity of material in storage vs. quantity needed for bid. d: warranty for existing carpet shall be for installation.							
8.	Reference:	Drawing	Detail	Spec00 31 25				
	QUESTION : Confirmation of the following: Owner supplied Items: VCT, Carpet, Stair Treads, Rubber Tile & Misc. Ceramic Tile Pieces							
	SKANSKA RESPONSE	: See Material Invent	ory 00 31 25, as revised in Addendum	#1.				
9.	Reference:	Drawing	Detail	Spec07 13 00				
	QUESTION : Substitut Documentation Attac		Permabarrier Liquid; Sto Guard System	Vapor Seal.				
	OPA RESPONSE: Subs	stitution request for S	Sto Guard System is accepted.					
10.	Reference:	Drawing	Detail	Spec09 51 13				
	QUESTION : ACT-1 Arreplacement tile.	mstrong Crossgate G	Grooved has been discontinued by Arm	istrong. Please provide a				
		Oyster" Preformance	3 - 2.01 - A from "Crossgate grooved" - e characteristics and profiles of alterna rd.					
11.	Reference:	Drawing	Detail	Spec				
	Lutron do we have to	submit a substitutio	for Mecho shades or equal. If we bid th n form? We have to know if Lutron w viring than the 120volt Mecho or Drap	ould be accepted since it				
	for shade systems. Al	ll required wiring and	Flex Shade System and Lutron Sioia QE d controls to provide a complete system onsible for power wiring to junction bo	n are to be included by				

plans. Reference also RFIs #12 & #87.

ADDENDUM #2: BIDDING RFI LOG January 22nd, 2013

12.	Reference:	Drawing		Detail	Spec	BP-12 & 16 12 21 13	
	QUESTION : BP-12-The spec calls for use to wire the shades. Which electrical contractors are bidding this project that we could contact to bid the wiring for the shades?						
	OPA/SKANSKA RESPONSE: Shade wiring describe in spec Section 12 21 13, 2.1 A to E. Junction boxes and circuits provided on electrical plans. BP-16 Electrical shall furnish and install wiring to junction box. BP-12 shall be responsible to furnish and install wiring and terminations from the junction box to the shade system and all associated control wiring. Reference Pre-Bid Sign-In Sheet, emailed to all potential bidders with the Pre-Bid Meeting Agenda for electrical contractors. Both the Pre-Bid Sign-In Sheet and Pre-Bid Meeting Agenda are available on the project website under 'Bid Docs': https://partners.myskanska.com/usa/clients/scsu/Buley/SitePages/Home.aspx						
13.	Reference:	Drawing	FPD-100	Detail	Spec _		
		cap and make sa	afe for removal by o	ork on the existing sprinklen thers or do we drop to the fl			
				is responsible to isolate, cut noval of demolished piping t			
14.	Reference:	Drawing	FP-102	Detail	Spec _		
	QUESTION : FP-102 Second Floor supplemental Bid1 work appears to start south of column XH. What about the work between columnns XH and XK? Is this part of the base bid or is it excluded entirely?						
	OPA RESPONSE: Part	of Base Bid.					
15.	Reference:	Drawing		Detail	Spec _	BP-09B 21 10 00	
	QUESTION : Section 21 Painting of piping usu			paint all sprinkler piping. Is t or. Please clarify	his corre	ect?	
	SKANSKA RESPONSE:	BP-09B Painting	Subcontractor is re	sponsible for painting of spr	inkler pij	oing.	
16.	Reference:	Drawing	FP-201	Detail10	Spec _	21 10 00	
		this system. See	ction 21 10 00 Item 1	dicates that we are to provice I.02 B.11 indicates the same ork. Please advise.			
				shall furnish and install deving for a complete operation			
17.	Reference:	Drawing FI	P-103, FP-104	Detail	Spec _		
	system for the base bid	d for future fitou	ut. This is shown on	n Floor indicates for us to ins both floors starting south o e excluded? Please clarify.			

OPA RESPONSE: Work in Connector area between columns XH and XK on all floors is in Base Bid. S:\Project_Data_NewHaven\1312021 Buley Library Renovation\Addenda\Addendum #2\ADDENDUM #2 RFI LOG_012213.doc

ADDENDUM #2: BIDDING RFI LOG January 22nd, 2013

18.	Reference:	Drawing	FP-106	Detail	Spec			
	QUESTION : FP-106 4 th upright protection in the Mechanical Room	the future fito	ut area like the 3rd	and 4th floors? Do v	we install the upright	heads in		
	OPA RESPONSE: 4th not clouded.	floor existing a	addition work is no	ot in scope except for	r any rework of head	ls in portion		
19.	Reference:	Drawing		Detail	Spec _			
	QUESTION : We intend to satisfy the CHRO requirements thru material suppliers and not subcontracting of the work. Is this acceptable? Please advise.							
	CHRO RESPONSE : You can meet your requirements by purchasing material supplies. However, any work your company is not doing, we must see opportunities provided to set aside companies.							
20.	Reference:	Drawing	A901A	Detail	Spec _	BP-09C		
	QUESTION : Plan A901A upper left hand corner of plans shows CPT1 Remove and replace. Is this part of this contract work? If yes, is area larger than what is shown on plans?							
	OPA RESPONSE: Yes,	area of carpet	to be replaced is !	520 s.f.				
21.	Reference:	Drawing		Detail	Spec _	BP-09C		
	QUESTION: Do you h	ave the name	of the Bentley car	pet contact involved	with this job?			
	OPA RESPONSE: Con Sabato, 58 Morning C					on is: Fury		
22.	Reference:	Drawing	A601	Detail	Spec _	BP-09C		
	QUESTION : Plan A-60 These sizes won't ma			meeting 6" base and	floor tile and alignin	ig joints.		
	OPA RESPONSE: Join	t Between Co	ve Base and Wall v	vill not line up.				
23.	Reference:	Drawing 		Detail	Spec	BP-09C 00 31 25		
	QUESTION : Inventory not, what is its actual		45 Meyer tag No.	237 indicates a lenth	of 3149lf. Is this co	rrect? If		
	OPA RESPONSE: No, 3149 is a typo; use 149LF. This was addressed in Addendum #1 revision to 00 31 25 Existing Material Inventory List.							
24.	Reference:	Drawing		Detail	Spec	BP-09C 00 31 25		

- **QUESTION**: Inventory sheet- page #45 & 46 Ceramic tile.
 a. Is the quantity listed after the total # of boxes the quantity per box?
 - b. Page #46 there are 187 boxes a.o. 4 ¼" x 4 ¼" wall tile. Is this the Bright Linen tile?

ADDENDUM #2: BIDDING RFI LOG January 22nd, 2013

	Invent	ontract ory List	: tor is to assume qua t, as revised in Addo tor is to assume 187	endum #1.		·	n the Material
25.	Refe	rence:	Drawing		Detail	Spe	BP-09
	1. Is som	eone 'i	nibit A Item #20. Th furnishing the temp es and installs steel	o. steel cable & tu	rnbuckle to us?	•	nttach to?
	tempo	subcor orary ite subcor	: ntractor is responsil ems required to pre ntractor is responsil	event damage; inc	cluding wind lo	ading to installed f	raming.
26.	Refere	ence:	Drawing		Detail	Spec	BP-09 Exhibit A #33
	QUESTION: The this 36" x 96" s		references a 36" x rrect?	96" piece of ½" ¡	olywood in-wal	l blocking at each લ	glass sign. Is
	SKANSKA RESI glass signage.	PONSE	: BP-09 Scope Item	#33 identifies the	e minimum size	for in-wall blockin	g required for
27.	Refe	rence:	Drawing		Detail 	Spe	BP-09 Exhibit A #42
			references all block ens that are refere				same as the
	SKANSKA RESI	PONSE	: Reference Techno	ology drawings fo	r AV system co	mponents.	
28.	Refe	rence:	Drawing		Detail	Spec	BP-09 Exhibit A, #44
	QUESTION : This item references ³ / ₄ " premium grade surface mounted plywood. Is this plywood to be firetreated?						
	SKANSKA RESI	PONSE	: Yes				
29.	Refe	rence:	Drawing		Detail 	Spe	BP-09 Exhibit A #85
			references damage es. If so, how do we		ofing. Are we t	o be responsible fo	r damage
	SKANSKA RESI	PONSE	: BP-09 subcontract	tor is responsible	only for damag	e to firproofing by	your

craftsmen and your subcontractor's craftmen.

ADDENDUM #2: BIDDING RFI LOG January 22nd, 2013

30.	Reference:	Drawing		Detail		Spec _	
	QUESTION : In the pre that in it's entirety? A feed cables run on thi	re the data clo	osets going to be built	out and fitte			
	OPA RESPONSE: See I Room 220 shall be fit				4, but only stub	in emp	ty conduits.
31.	Reference:	Drawing	L-101, L-106	Detail		Spec	32 14 13.17
	QUESTION : Please sho Detail #14/L-106 and #		the transition between	en concrete p	avers and concr	ete side	ewalks.
	OPA RESPONSE: See	attached B-SK	L-01				
32.	Reference:	Drawing		Detail		Spec _	
	QUESTION : Please cla	rify the gravel	drip strips. No detail	or spec sectio	n shown.		
	OPA RESPONSE: Grav	el drip strips a	are no longer in this p	oject.			
33.	Reference:	Drawing		Detail		Spec _	00 41 00
	QUESTION: Are you to	aking combina	ation bids?				
	SKANSKA RESPONSE: Contractors may submit Bid Proposals on multiple Bid Packages, however each Bid Package Proposal must be submitted individually on its own Bid Proposal Form with all required attachments, copies and associated bonding and certifications. Note- Acknowledgement to Bid form must identify each packages for which the contractor will submit a bid.						
34.	Reference:	Drawing		Detail —		Spec	Exhibit A, BP-09, #39
	QUESTION: This item	references cor	ner guards. Where a	re they specifi	ed?		
	SKANSKA RESPONSE:	See Detail 8/	\ 300				
35.	Reference:	Drawing	A-515	Detail	01	Spec	
	SKANSKA QUESTION: #09? Where is this spe		ulation shown at curt	ain wall abov	e ceiling. Is this	part of	Bid Package
	OPA/SKANSKA RESPO thichness note shall be			ms #13 and 5	6. Specified in S	ection (07 21 00,
36.	Reference:	Drawing	A515	Detail	2	Spec	BP-08
	QUESTION : Bent meta here? 2- is this part of			lation in-fill.	1- how is batt in	sulatio	n installed
	OPA/SKANSKA RESPO curtainwall flashing a						

necessarily Schucco.

ADDENDUM #2: BIDDING RFI LOG January 22nd, 2013

37.	Reference:	Drawing _	A-550	Detail	E, 9, G, H, J	Spec 	BP-04 BP-08 BP-09
	QUESTION : A number Who is to furnish and			rigid insula	tion on AVB on	½" gyp she	athing.
	SKANSKA RESPONSE: and AVB behind all br			drywall. BF	P-04 Masonry/Pre	ecast owns	insulation
38.	Reference:	Drawing _	A-514	Detail	6	Spec _	
	QUESTION : 2 ½" rigid Where is this specified		own at curtain wall a	bove ceiling	gs. Is this part of	Bid Packag	ge 09?
	SKANSKA RESPONSE:	Reference R	FI #37 and Specificati	on 07 21 00).		
39.	Reference:	Drawing _	A-514	Detail	2	Spec _	
	QUESTION : Detail shothis specified?	ws ¾" lath a	nd plaster on susp. Sy	stem. Is thi	s part of Bid Pac	kage 09? V	Vhere is
	OPA/SKANSKA RESPO B-SKA-01 for extent o						
40.	Reference:	Drawing _	A-513	Detail	12	Spec _	
	QUESTION : This detail UL# requested for the					ain walls. V	Vhat is the
	OPA RESPONSE: See F	Partition Type	s on A-820, note 8 fo	r CMU, follo	ow HW-D-0097		
41.	Reference:	Drawing _	T-101	Detail		Spec	
	QUESTION : Drawing poke-through for the data?						
	OPA RESPONSE: Yes shall both be responsi and installing combinaresponsible for furnish the device. Each trade conduit.	ble for coordi ation poke-th ning and insta	inated installation of rough devices, powe Illing communication	these device r wiring and wiring, incl	es. BP-16 is resp d termination. B uding communi	onsible for P-13C shall cation term	furnishing be iination at
42.	Reference:	Drawing _	A-303	Detail		Spec	
	QUESTION : All (the mactual "corner guards						
	SKANSKA RESPONSE:	A-303 details	s indicate corner guar	ds. See 8/A	-300 for typical	corner guai	rd detail.
43.	Reference:	Drawing	A-300	Detail		Spec	

ADDENDUM #2: BIDDING RFI LOG January 22nd, 2013

QUESTION: There are various column details that show 1/16" anodized aluminum plate fastened to wallboard. What bid package does this aluminum fall under?

SKANSKA RESPONSE: BP-09 is responsible for cornerguards per Exhibit A Item #39.

			•			
44.	Reference:	Drawing	Detail		Spec	BP-08 00 31 25
1	manufacturer. Is the A	nwall and windows specificatio Architect going to open the spec Or are we going to have to subn	ifications up t	o other manufac	turer's lil	ke Oldcastle;
		Reference Stored Materials Inve vall manufacturer. No substitu		5, as modified in	Addendı	um #1.
45.	Reference:	Drawing	Detail		Spec	BP-02C, Exhibit A #6
		ify nosings at cast in place stairs called for by Bid Package 02C,			led by the	e site
9	SKANSKA RESPONSE:	BP-02C is responsible for Exhibi	t A Scope of V	Vork item #6 in it	s entirety	/.
46.	Reference:	Drawing	Detail		Spec	BP-06, Exhibit A #7
		ify all exposed wood at railings or as called for by Bid Package 0			d installe	ed by the
9	SKANSKA RESPONSE:	BP-06 is responsible for Exhibit A	A Scope of Wo	ork Item #7 in its	entirety.	
47.	Reference:	Drawing	Detail		Spec	BP-09, Exhibit A #39 & 71
		fy all corner guards are to be fu d for by Bid Package 09 scope o			psum bo	ard
	SKANSKA RESPONSE:	BP-09 is responsible for Exhibit	A Scope of Wo	ork Items #39 and	d 71 in th	eir entirety.
48.	Reference:	Drawing	Detail	6/A300 & 11/A205	Spec	BP-08, Exhibit A #18
		ify the 1/16" thick anodized pla ctor as called for by Bid Packag			L/A205 aı	re by the
:	SKANSKA RESPONSE:	BP-08 is responsible for Exhibit A	A Item #18.			
49.	Reference:	Drawing	Detail		Spec	BP-05A, Exhibit A #13
(QUESTION : Please ver	ify that the Bid Package 05A sco	ope of work ite	em 13 pertains to	embeds	required to

support work for this bid package only.

ADDENDUM #2: BIDDING RFI LOG January 22nd, 2013

SKANSKA RESPONSE: Correct, BP-05A is responsible for providing embeds to the concrete subcontractor required for the work of this bid package. 50. Reference: Drawing A513 Detail 2, 6, 8 BP-05A. Spec Exhibit A #15 QUESTION: Please provide an example detail of the angles as described by Bid Package 05A scope of work item 15. Note that many of the trades listed are responsible to furnish and install their own supports per the scopes of work. SKANSKA RESPONSE: Example details 2, 6 & 8/A513. BP-05A is responsible for Scope of Work Item #15 in its entirety. 51. Reference: Drawing A513 Detail 8 BP-05A, Spec Exhibit A #16 QUESTION: Please provide an example detail of the angles as described by Bid Package 05A scope of work item 16. Note that many of the trades listed are responsible to furnish and install their own supports per the scopes of work. SKANSKA RESPONSE: Example detail 8/A513. BP-05A is responsible for Scope of Work Item #16 in its entirety. 52. Reference: Drawing A514, S303 Detail 8/A514 Spec BP-05A. B&G/S303 Exhibit A #18 QUESTION: Please provide an example detail for the plate and anchors as described by Bid Package 05A scope of work item 18. SKANSKA RESPONSE: Example details B&G/S303, 8/A514. This Subcontractor is responsible for similar channel conditions shown on detail B/S309 53. Reference: Drawing S312 Detail 2 Spec **BP-05** BP-05A QUESTION: Reference BP-05A, Exhibit A #19- Please clarify which angles shown by S312 are to be by the misc metals subcontractor. There are no angles shown welded to roof deck as described. SKANSKA RESPONSE: Angles are welded to roof joist; BP-05 Structural Steel is responsible for furnishing and installation of angles and finish strip. Reference detail 2/S312. 54. Reference: Drawing Detail Spec **BP-05** BP-05A QUESTION: Reference BP-05A, Exhibit A #20- Please verify the demolition described by Bid Package 05A scope of work item 20 is to be performed by the misc metals subcontractor. It appears the wire fabric and dowel reinforcement are encased in existing concrete and this demolition should fall under Bid Package 03 scope of work item 5. SKANSKA RESPONSE: BP-05 Structural Steel shall be responsible for demo of wire fabric and dowels, due to the requirement of BP-05 Exhibit A Item #22 to establish and install pour stops. 55. **BP-05** Reference: Drawing Detail Spec BP-05A

ADDENDUM #2: BIDDING RFI LOG January 22nd, 2013

QUESTION: Reference BP-05A, Exhibit A #26- Please verify that the existing railing to be removed will be free from lead paint prior to removal.

SKANSKA RESPONSE: No, contractors are to assume the presence of lead based paint at existing metal components scheduled to be removed. BP-05 Structural Steel is responsible to perform appropriate remediation procedures at existing points of connection to facilitate rail removal, and remediation at points of connection for new railing installation. BP-05A Misc. Metals is responsible for removal and disposal of railing.

56.	Reference:	Drawing _	A702	Detail 	Spec	BP-05 BP-05A			
	QUESTION : Please ver new rails.	ify that exist	ing stair stringers wi	ll be free of lead b	ased paint prior to in	stallation of			
	SKANSKA RESPONSE:	Reference R	FI #55.						
57.	Reference:	Drawing		Detail 	Spec	BP-05A Exhibit A #27 & 33			
	QUESTION : Please verify that the glass canopy support structure and demo of existing structure are to be by the misc metals subcontractor as described by Bid Package 05A scope of work items 27 & 33 and not by the structural steel subcontractor. Note that this work is clearly shown by the structural steel drawings and is part of Bid Package 05 per Bid Package 08 scope of work item 6.								
	SKANSKA RESPONSE: entirety. BP-08 Item #				/ork Items #27 & 33 i	n their			
58.	Reference:	Drawing		Detail 	Spec	BP-05A, Exhibit A #27			
	QUESTION : Please ver Package 05A scope of					d by Bid			
	SKANSKA RESPONSE:	Yes, assume	e no lead.						
59.	Reference:	Drawing		Detail ——	Spec	BP-05A, Exhibit A #28			
	QUESTION : Please ve 05A scope of work ite				orts as described by E	Bid Package			
	SKANSKA RESPONSE: 05A as indicated in Ex		demolition of existi	ng siding and supp	ports is the responsib	ility of BP-			
50.	Reference:	Drawing		Detail 	Spec	BP-05A, Exhibit A #28			
	QUESTION: Please pr	ovide additic	onal information (ie.	Pictures, details, s	pec) regarding the sid	ding and			

QUESTION: Please provide additional information (ie. Pictures, details, spec) regarding the siding and support to be demo'd per Bid Package 05A scope of work item 28.

OPA/SKANSKA RESPONSE: OPA recommends viewing condition in field. Reference Addendum #2 General Item #1A for Follow-Up Site Visit on January 28th, 2013.

ADDENDUM #2: BIDDING RFI LOG January 22nd, 2013

61.	Reference:	Drawing	Detail	Spec	BP-05A, Exhibit A #28
			and support to be demo'd by the misc metawork item 28 will be free of lead paint prior		
	SKANSKA RESPONSE: item #28.	Yes, assume no le	ead. BP-05A is responsible for siding and su	oport dem	olition per
62.	Reference:	Drawing	Detail	Spec	BP-05A, Exhibit A #30
	QUESTION : Please proscope of work item 30		tions, etc for the anchor plates as described	by Bid Pac	kage 05A
	SKANSKA RESPONSE:	Reference RFIs 50	0-53 for miscellaneous plates and angles.		
63.	Reference:	Drawing	Detail	Spec	BP-05A, Exhibit A #34
	QUESTION: Please ver	ify that Bid Packag	ge 05A scope of work item 34 pertains to ne	w firepro	ofing only.
	SKANSKA RESPONSE:	BP-05A Scope of V	Work Item #34 pertains to new and existing	fireproof	ing.
64.	Reference:	Drawing	Detail	Spec	BP-05A, Exhibit A #35
	QUESTION : Please proitem 35.	ovide details and q	quantities for the clips described by Bid Pack	age 05A s	cope of work
	SKANSKA RESPONSE:	BP-05A shall inclu	ıde an allowance value of \$2,000 for Exhibit	t A Work I	tem #35.
65.	Reference:	Drawing	Detail	Spec	BP-05A, Exhibit A #42
	QUESTION : Please pro Package 05A scope of		ocations for the loading lanyard supports as	described	by Bid
			ling areas will be located in field during con termined at that time.	struction a	activities; tie
66.	Reference:	Drawing	A515 Detail 4 & 4.1	Spec	07 53 23
			of the rooftop pavers specifications and an increte or is there a system the architect is re		
	OPA RESPONSE: See	4/A-515 and 4.1/A	-515, and Spec 07 53 23 section 2.2 I, J		
67.	Reference:	Drawing	A812 Detail	Spec	08 80 00
	QUESTION: Please ide	entify glass types o	on drawings.		
	OPA RESPONSE: A-81 AL-7C: All Panels that		nall be B or B1 (tempered as required by cod e B1 Tempered glass.	e). A-811	, AL-7B and

ADDENDUM #2: BIDDING RFI LOG January 22nd, 2013

68.	Reference:	Drawing	Detail 	Spec	Div. 27 00 31 25			
	QUESTION : Throughout the Division 27 spec specific part numbers are indicated for teledata equipment, cable types, jack types and fiber cable and hardware. The stored materials list has equivalent material to that in the spec but not the exact materials specified. What part number takes presidence for bidding? Is the goal to reuse as much stored material as possible or to comply with the part numbers in the spec?							
			ng material matches then use it, it endum #1 part 00 31 25) should c		oduct			
69.	Reference:	Drawing	Detail	Spec				
	 Has the c Was it ste 	ontainer remained dry, t	and the 20 year warranty identifice that is, no moisture has gotten in? re; if it was outdoors there is temp	?	g which can			
	OPA/SKANSKA RESPO with non-freezing, dry		ssume material stored has been st	tored indoors in	basement			
70.	Reference:	Drawing	Detail	Spec	21 05 00			
	 QUESTION: Spec Section 21 05 00 Fire Sprinkler Section 3.03 Painting states the following: A. Painting of fire-suppression systems, equipment, and components is specified in Division 9 Sections "Interior Painting" and "Exterior Painting". B. Damage and Touchup: Repair to marred and damaged factory-painted finishes with materials and procedures to match original factory finish. Is the painting and touch up of the fire sprinkler piping the fire sprinkler contractors responsibility or the painters responsibility? Please clarify. 							
	coatings. BP-13 Fire P	rotection Subcontractor	ntractor is responsible for applicati is responsible for repair to marre shes damaged/caused by his cons	ed and damaged	d factory			
71.	Reference:	Drawing	Detail	Spec	BP-07 & BP-09			
	QUESTION: Please cla	arify who owns roof bloc	king. Blocking is called out in bot	th bid packages	7 & 9.			
	SKANSKA RESPONSE: bid.	If roof blocking is includ	led in your bid package it is requin	ed to be include	ed in your			
72.	Reference:	Drawing	Detail	Spec	07 13 00			
	scope this this section of the specialty rig the calls out installation of	as well as in the mason at is required to apply the of some air and vapor bar	7 13 00 "Air and Vapor Barrier Systope. This is typically carried in the specified product. Also line item rier. Can you please clarify this in iously mentioned specialty rig requirements.	the mason scope in 16 in the roofi installation or po	e because ng scope			

SKANSKA RESPONSE: BP-07 is responsible for section 07 13 00 as described in Exhibit A. Reference BP-07 scope of work item #14, 16, 19, 20. BP-07 is responsible for AVB per details 1 & 2/A551 and similar conditions. BP-03, BP-04 and BP-08 are each responsible for section 07 13 00 as described in applicable Exhibit A documents.

S:\Project_Data_NewHaven\1312021 Buley Library Renovation\Addenda\Addendum #2\ADDENDUM #2 RFI LOG_012213.doc

ADDENDUM #2: BIDDING RFI LOG January 22nd, 2013

73.	Reference:	Drawing _	_	Detail		Spec _	BP-07 & -09
	QUESTION: Whose so	ope would in	clude removal of ex	isting roofing?			
	SKANSKA RESPONSE #6 and #7 (as modifie			e of Work Item	#4 and BP-09	Scope of V	Vork Items
74.	Reference:	Drawing _		Detail		Spec _	07 53 23
	QUESTION : Carlisle is manufacturer? Produ			for white EPDN	1 roofing. Is	Firestone a	n acceptable
	OPA RESPONSE: Yes,	Firestone Rul	bberGuard EcoWhit	e 60mil EPDM is	acceptable.		
75.	Reference:	Drawing _	A6.01	Detail	8	Spec _	09 30 13
	QUESTION : Tile patte says full height tile we height or 6 ft wainsco	all finish plan					
	OPA RESPONSE: All t	ile is to 6'-0"					
76.	Reference:	Drawing _	S402	Detail —	4 & 5	Spec -	BP-07B, Exhibit A #4
	QUESTION: Per Exhib fire resistive coating t referenced regarding paint? I can't find exp	o reference d exposed stee	etail 4 & 5 on S-402 el (intumescent pain	. When you go	to the drawir	ng nothing	is
	OPA RESPONSE: Hori	zontal double	e C 12x30 butt weld	ed steel shall be	coated in Int	tumenscen ⁻	t paint.
77.	Reference:	Drawing _		Detail —		Spec _	BP-07B, Exhibit A #10
QUESTION : BP-07B scope item #10 states that this subcontractor is responsible for re touch up for ground floor existing fireproofing. Nowhere is it outlined to what externeeded. I am not sure how to quantify this. Can you provide quantities or an allowa our Base Bid?						ent this tou	ıch up is
	OPA /SKANSKA RESP BP-07B is directed to 11AM.						
78.	Reference:	Drawing _		Detail —		Spec _	BP-07B, Exhibit A #14
	QUESTION : BP-07B s subcontractor will be up each time?						own his set-
	SKANSKA RESPONSE	: Yes, the inte	ent of BP-07B Item#	14 is to assume	breakdown a	and set-up	of

equipment as needed.

ADDENDUM #2: BIDDING RFI LOG January 22nd, 2013

79.	Reference:	Drawing	Detail 	Spec _	BP-07B, Exhibit A #20
	QUESTION : BP-07B scope item #20 ask to provide temporary protection of floor, wall, etc. Does this mean you want plastic installed on the ground before our operation? Typically we would let the fireproofing fall to the ground and clean it up off the concrete.				
	SKANSKA RESPONSE: BP- 07B shall be responsible for the complete removal of fireproofing from all surfaces not required to receive fireproofing or fireproofing over spray. BP-07B shall be responsible for protection of any equipment or materials in the work area from overspray.				
80.	Reference:	Drawing	Detail	Spec _	BP-07B
	QUESTION: What is the	ne primer on the ex	xisting steel?		
	OPA RESPONSE: Unknown-see lead based testing report in front end of specification.				
81.	Reference:	Drawing	Detail	Spec _	07 81 00
	QUESTION : The specifications call for sealer above ceilings. Is the sealer necessary at all concealed locations?				
	OPA RESPONSE: Provide sealer to concealed fireproofing in Elevator Hoistway and above ceilings per section 3.04B in spec. 3.08A provide 1 hour and 2 hour per notes on drawing A-500 and A-501				
82.	Reference:	Drawing	Detail	Spec _	11 52 13
	QUESTION : Substitution Request for Draper Artisan Series E in lieu of Da-Lite Screen Designer Advantage Electrol Screens per specification section 11 52 13, 2.2A.				
	OPA RESPONSE: Draper Inc. Artisan Series E projection screens are an acceptable alternative.				
83.	Reference:	Drawing	Detail 	Spec _	BP-15B Exhibit A, #6
	QUESTION : BP-15B Item #6 states that the HVAC Instrumentation and Controls contractor be responsible for IAQ testing and building flushouts. This work is typically performed by the mechanical contractor (BP-15A) Is the intent to have 15B subcontract a contractor to perform these services?				
	SKANSKA RESPONSE: BP-15A is responsible to perform IAQ testing and flushout inclusive of filter changes required. BP-15B HVAC Instrumentation and Controls is required to have all point-to-point verification complete prior to building flushout, verify and log that services have been performed through BAS trending points. BP-15B shall coordinate with BP-15A to complete building flushout prior to substantial completion as identified in the project schedule.				
84.	Reference:	Drawing	Detail	Spec _	BP-15B Exhibit A #9
	OUESTION: BP-15R if	rem #9 states the H	IVAC Instrumentation and Controls contract	tor be resr	onsible for

SKANSKA RESPONSE: BP-15B Instrumentation and Controls Subcontractor shall furnish and install all fiber-optics required by BAS.

Is the intent to have 15B install all fiber required by the BAS back to the nearest data closet?

furnishing and installing fiber-optics. This work is typically performed by the electrical contractor, Div. 26.

ADDENDUM #2: BIDDING RFI LOG January 22nd, 2013

85.	Reference:	Drawing		Detail		Spec _	BP-15A, BP-15B, BP-16
	QUESTION : The HVAO responsible for furnish						are both
	SKANSKA RESPONSE: VFDs and from VFDs t outputs specified and	o motors. BP-	15B shall furnish and	install control	wiring for all V	'FD inpι	
86.	Reference:	Drawing		Detail		Spec	Exhibit A BP-15B #12
	QUESTION : Item #12 sfurnishing and installi						nsible for
	SKANSKA RESPONSE: in coordination with E			shing and insta	alling valve and	d dampe	er actuators
87.	Reference:	Drawing _		Detail		Spec	BP-12
	QUESTION: Shade dear roller shades. This sys shades are not connecte team consider an alter OPA RESPONSE: Drap shade systems. All rec BP-16 electrical contra Any alternative wiring responsibility of BP-12	tem requires of ted to a low of the second test of	the manufacturer's envoltage product (projects of the product (projects of the provided in the provided in the provided in the provided in the provided in the provided in the providition of the providition of the providition in the providition of the providiti	gineer to prog ection screens, essible to BP-1 d Lutron Sioia e a complete s g to junction b	gram at signific lighting, etc.), .2 contractors? QED systems a system are to b oxes as identifi	ant cos would t re acce e incluc ed on tl	t. As these the design otable for led by BP-12. he plans.
88.	Reference:	Drawing _	T-201	Detail		Spec	
	QUESTION : On Drawi 408 in the occupied by	uilding. Is this	part of the base bid?			ata clos	ets 119 and
	OPA RESPONSE: Wor	k in room 119	is part of base bid, bu	ıt room 408 is	not.		
89.	Reference:	Drawing _		Detail		Spec _	09 21 16
	QUESTION : Specificat Level 5, Ie. Skim Coat. ceilings?						
	OPA RESPONSE: Yes						
90.	Reference:	Drawing	A514	Detail	2	Spec	
	QUESTION: Drawing 2	2/A514 shows	plaster on lath attach	ed to framing.	Who owns th	e plaste	er work?
	OPA/SKANSKA RESPC lath attached to frami)NSE Bid Pack	age 09 Gypsum Board	Assemblies sh	nall be respons		

ADDENDUM #2: BIDDING RFI LOG January 22nd, 2013

91.	Reference:	Drawing	Detail 	Spec	BP-09, Exhibit A
		pe of Work lists Section 10 21 cope of Work nothing is men			
	SKANSKA RESPONSE:	Reference BP-09 Exhibit A Ite	m #25 regarding blocking.		
92.	Reference:	Drawing	Detail — —	Spec	BP-09 Exhibit A #7
	QUESTION: Please cla	arify BP-09 Scope of Work #7			
		Item #7 references EPDM "fl m #2 as referencing item #6.	oor protection". Reference	to Item #5 has	been
93.	Reference:	Drawing	Detail 	Spec	BP-09 Exhibit A #35 & #77
		pe items #35 & #77 discuss F8 second floor fit-out drawings			
	SKANSKA RESPONSE:	Yes.			
94.	Reference:	Drawing	Detail 	Spec	BP-09 Exhibit A #86
		pe of work item #86 talks abo t find anything referring to ov			in contract
	Existing Materials incl	Reference 00 31 25 Existing I uded in BP-10 and BP-08A, as d BP-08A are responsible for I	defined to be furnished to t	this Subcontrac	tor for
95.	Reference:	Drawing	Detail 	Spec 	BP-09B 27 11 00
	QUESTION: What bid	package is responsible for pai	nting the plywood in the da	ita closets?	
	SKANSKA RESPONSE:	Bid Package 09B Painting is re	esponsible for painting plyw	vood in data clo	sets.
96.	Reference:	Drawing	Detail	Spec	BP-02
		e of work calls out the following id insulation; #41- stone ballanew electrical service			
	SKANSKA RESPONSE:	#11 rigid insulation- referenc	e A512; #41 stone ballast st	trips are no lond	ger included

S:\Project_Data_NewHaven\1312021 Buley Library Renovation\Addenda\Addendum #2\ADDENDUM #2 RFI LOG_012213.doc

in this project; #51 new site bollards are no longer included in this project; #56 sanitary sewer- see drawing P-100; #58 transformer pads for new electrical service- No new pad identified per Riser Diagram

on E-300 and Site Electrical Plan on E-003.

ADDENDUM #2: BIDDING RFI LOG January 22nd, 2013

97.	Reference:	Drawing		Detail _		Spec	
	QUESTION : Div. 21 w fire protection contra construction process. connection piping that disconnected from the contracted standpipes	ctor to provide (Existing stairwe It are in scope to e standpipe and	1) fire standpipe wi ells have standpipes be removed. It see are inactive. Can v	th 2 ½" hose and valves c ems that a love ve demo the	e valves on each connected to fire ot of the valves h	floor durir edepartme ave been	ng nt
	OPA RESPONSE: Insta acceptable as long as State Building Code 3	the standpipe ri	ser is operational d	uring constr	uction and in acc		
98.	Reference:	Drawing	S-309	Detail _	В	Spec	
	QUESTION : Drawing access	S-309 Detail B p	lease identify the co	olumn line v	where the new co	oncrete fill	occurs for
	OPA RESPONSE: Alongirder. Three connect			at new beam	n connections to	existing 27	7 WF 84
99.	Reference:	Drawing	A515, S302	Detail _		Spec	
	QUESTION: Please cla	arify the wall adj	acent to the curb o	n the first flo	oor off column li	ne X4, X9	and XB
	OPA RESPONSE: See of	details 4.1 / A-51	5 and B / S-302				
100	. Reference:	Drawing		Detail _		Spec	
	QUESTION: Where do	oes the typical ex	xterior pad occur?	Isn't this by	the site concrete	contracto	r BP-02C?
	OPA RESPONSE: Ther	e are no new ex	terior pads.				
101	. Reference:	Drawing	A-321	Detail _	5 & 6	Spec	BP-04
	QUESTION: What bid	package is respo	onsible for the parg	ing of stair v	valls detail 5 & 6	on A-321	?
	SKANSKA RESPONSE:	BP-04 Masonry	/Precast is responsil	ole for pargi	ng stair walls.		
102	. Reference:	Drawing		Detail _		Spec	BP-03
	QUESTION: What bid	package is resp	onsible for the con	crete floor s	ealer at exposed	floors?	
	SKANSKA RESPONSE:	BP-03 Concrete	e is responsible for o	concrete floo	or sealer.		
103	. Reference:	Drawing		Detail _		Spec	BP-04
	QUESTION: What bid	package is respo	onsible for patching	of walls at	Stair D and E?		
	SKANSKA RESPONSE: rating.	BP-04 Masonry	/Precast is responsil	ole for patch	ning stair walls to	o maintain	2-hour
104	. Reference:	Drawing	AD-101	Detail _	2	Spec	BP-09
	QUESTION: What bid	package is respo	onsible for construc	tion of the t	emporary deck	detail 2/AD)-101?

 $S:\Project_Data_NewHaven\\1312021\ Buley\ Library\ Renovation\\ \Addenda\\ Addendum\ \#2\\ \ADDENDUM\ \#2\ RFI\ LOG_012213. doc$

ADDENDUM #2: BIDDING RFI LOG January 22nd, 2013

SKAI	NSKA RESPONSE:	BP-09 is respo	onsible for constru	ction of temporary w	ood deck.	
105.	Reference:	Drawing	AD-101	Detail	Spec	BP-03 BP-09C & BP-09D
QUE	STION: What bid	package is re	sponsible for the re	emoval of leveling m	aterial on AD-101?	
deck of ex accid	and removal of t isting electrical s Iental material fa are responsible fo	copping slab sh ubstation and lling and wate or review and	nown on AD-101. equipment located er; not knowing the acceptance of sub-	or removal of leveling BP-03 Concrete is als d in basement under e condition of the de strate conditions and respectively, and Sp	so responsible for th the removal area ac ck concrete. BP-090 I any preparation re	e protection gainst Cand BP- quired in
106.	Reference:	Drawing	AD-102	Detail	Spec _	BP-09
QUE	STION: What bid	package is re	sponsible for const	truction of the tempo	orary wood deck on	AD-102?
	NSKA RESPONSE: constructed.	AD-102 show	vs an existing temp	orary wood deck to l	be demolished, not	a new deck
107.	Reference:	Drawing	AD-104	Detail	Spec _	BP-05
QUE	STION: What bid	package is re	sponsible for the g	rinding of the steel s	truts on AD-104?	
SKAI	NSKA RESPONSE:	BP-05 is respo	onsible for grinding	g steel struts.		
108.	Reference:	Drawing		Detail	Spec	BP-02C 03 30 00
QUE	STION: Under spe	ec section 03 3	0 00 1.01 B-1 plan	ters are by BP-02C. F	Please confirm	
SKAI draw		Correct, BP-0	02C is responsible 1	or planter walls iden	tified on the landsca	ape
109.	Reference:	Drawing		Detail	Spec _	
QUE	STION: Under spe	ec section 03 3	0 00 2.01G expose	ed concrete floors, is	this new concrete or	nly?
OPA	RESPONSE: Yes					
110.	Reference:	Drawing		Detail	Spec _	
Cond				00 and 07 95 00 as fa ading dock and colur		
	RESPONSE: Yes a			: X3.2 and X10. Wate	erproof all patches i	n

ADDENDUM #2: BIDDING RFI LOG January 22nd, 2013

111.	Reference:	Drawing _		Detail	Spec	BP-03
QUES	STION: Under BP	-03 scope of	work item #58 pleas	se confirm safety ra	ilings by BP-05.	
SKAN Exhib		BP-03 Conc	rete shall include sco	ope of work item #5	58 safety railings as d	efined in
112.	Reference:	Drawing _	A511, A512	Detail	Spec _	BP-03
			work items #64-66 p undation walls on C		t shown on drawings a-511, and F / A-512	. Existing
SKAN	ISKA RESPONSE:	Reference F	RFI #110 and BP-03 S	cope of Work Items	s #64-66.	
113.	Reference:	Drawing _		Detail	Spec _	Various
			work item #74 are w by others. Please co		sembly for the slabs o	only? Wall
A Iter	m #74. This inclu	des both floo		to-floor joint system	lies within concrete, ns. BP-04, BP-08 and	
114.	Reference:	Drawing _	A512	Detail	Spec	
QUES	STION: Under BP-	03 scope of	work item #76 wher	e does this occur? N	lot shown on drawin	gs.
SKAN	ISKA RESPONSE:	Reference o	lrawing A512.			
115.	Reference:	Drawing _		Detail	Spec _	00 31 25
43 of	the inventory sh	eet for BP-07		s relevant to our ma	etc) of the items lest aterial take-off on wh requirements.	
	ISKA RESPONSE: te for additional			25 Material Invento	ory Narrative and Inve	entory List
116.	Reference:	Drawing _		Detail	Spec	21 20 00
	closely spaced sp a. Please co shown o b. If closele	rinklers. Infirm that th In the FP drav	ne stairways do not r vings.	equire closely space	draft stops at open sted sprinklers as they a	are not
OPA	RESPONSE: Stairs	s do not have	closely spaced sprir	nklers. Delete Paraç	graph 1.02 B 14	
117.	Reference:	Drawing _		Detail	Spec _	21 10 00
QUES	STION: Please co	nfirm paintir	g is not part of the F	Fire Protection scope	e of work (21 10 00-	2.03)

ADDENDUM #2: BIDDING RFI LOG January 22nd, 2013

		ge to factory finishes or to	rtield applied finishes. BP-13 Fire buch up of damage to field applied		
118	. Reference:	Drawing	Detail	_ Spec _	
		nfirm that a detection and otection scope of work.	d power wiring for the preaction s	sprinkler syste	em is not
	SKANSKA RESPONSE	Reference RFI #16.			
119	. Reference:	Drawing	Detail	Spec	
	QUESTION: Please co	nfirm that 6' long Flexhead	d assemblies are to be used for all	pendant spr	inklers
	K/R RESPONSE: 6' flex fittings shall be utilize		utilized throughout, when not pra	actical, sch 40), piping and
120	. Reference:	Drawing	Detail	_ Spec _	
		rture data center areas to Art Gallery with this word	be protected by preaction sprinkleding.	er systems. T	here is a
			be protected by wet sprinklers. Tich time the wet sprinkler system i		
121	. Reference:	Drawing	Detail	Spec	
	QUESTION : Are the ca	abinets noted on the FP dr	awings to be fire rated if located i	n a fire rated	l wall?
	K/R RESPONSE: All ca	pinets must be the rated v	ersion when installed in a rated w	all.	
122	. Reference:	Drawing	Detail	•	BP-15A BP- 15B, BP-16
	QUESTION: VFD's are	included in BP-15A item 7	70 and BP-15B item #11. Please cl	arify.	
	VFDs and from VFDs to outputs specified and	o motors. BP-15B shall fu	o's. BP-16 shall install VFDs and as rnish and install control wiring for terface to provide a fully function om VFDs to motors.	r all VFD inpu	ıts and
123	. Reference:	Drawing	Detail	Spec _	07 13 00, 2.03
	QUESTION: Substituti	on Request BASF Wall Sys	tems Enershield System. See atta	ched produc	t data.
	OPA RESPONSE: Acce	epted			
124	. Reference:	Drawing	Detail	Spec	BP-09C Exhibit A #13
	QUESTION: Sloping fl	oors to drains. Does this n	mean all the bath rooms will requi	ire mudset?	_

S:\Project_Data_NewHaven\1312021 Buley Library Renovation\Addenda\Addendum #2\ADDENDUM #2 RFI LOG_012213.doc

ADDENDUM #2: BIDDING RFI LOG January 22nd, 2013

SKANSKA RESPONSE: No, Reference Specification 09 30 13 Subsection 3.1 and 3.2, and Specification 01 35 16 Subsection 3.5. BP-09C will be required to inspect areas to receive tile, and grind or fill substrates as required to comply with acceptable variations. See Addendum #2 General Item #1A for follow-up site review scheduled for Monday 1.28.13.

125.	Reference:	Drawing	A-900A	Detail		Spec	
			s that have names an aple #006 "Future Da		ut no finishes l	isted don't get	
	RESPONSE: Any se. Future Data		as a floor finish has a no base.	base any roc	om with no floo	or finish indicated h	as
126.	Reference:	Drawing	A-900A, A601	Detail	8/A601	Spec	
	7, & TL-8 in floo		n's Room shows TL-4 . TL-4 shown as wall				TL-
	RESPONSE: Note yout and pattern		ed to drawings A-901	В, 902В, 903	B & 904B: See	detail 8/A-601 for f	ull
127.	Reference:	Drawing	_	Detail		Spec <u>09 65</u>	43
QUES multio	•	ion 09 65 43	Linoleum Flooring. \	Vhat type of	welding rod is	to be supplied? Sol	lid or
OPA F	RESPONSE: Shall	be selected	by Architect in submi	ttal phase.			
128.	Reference:	Drawing	A-900A	Detail		Spec	
	TION: Corridor # needed there?	#021- Note to	o remove and replace	floor mat FL	M1. Outline o	f mat not shown. V	Vhat
OPA F	RESPONSE: See A	A-100 aproxi	mitaly 4′ x 5′ VIF.				
129.	Reference:	Drawing	AD105	Detail		Spec	
QUES	a. At th	ne existing co ne 4 th floor ro ne penthouse		f to be demo	lished:		
OPA F	RESPONSE: fully	adhered 45	mil epdm with rigid ir	sulation on t	opping slab.		
130.	Reference:	Drawing	A515	Detail	4, 4.1, 4.2	Spec	
	TION : Details 4, to be covered w		on drawing A515 sho	w pavers. Ple	ease indicate th	ne extent of the roo	ıf
OPA F	RESPONSE: See I	101 and A-	101 area XA1 / XB – է	etween X3.2	/X4 and X9/ X	10	
131.	Reference:	Drawing	A-100	Detail		Spec	
			that millwork MW12 2 to be part of the ba				5/

 $S:\Project_Data_NewHaven\\ 1312021\ Buley\ Library\ Renovation\\ Addendum\ \#2\\ ADDENDUM\ \#2\ RFI\ LOG_012213. doc$

ADDENDUM #2: BIDDING RFI LOG January 22nd, 2013

	SKANSKA RESPONSE	: Base Bid					
132	. Reference:	Drawing	A-100	Detail		Spec _	
	QUESTION : The Men' A-600. Do we include only?						
	SKANSKA RESPONSE washrooms are include						n
133.	. Reference:	Drawing	A-302	Detail	11	Spec _	
	QUESTION : The Solid window sill noted as solid surface material First, Second, Third ar	1" thick. The S to make it the	LDS2 Corian Solion 1" thickness? A	d Surface material re we to provide S	is ½" thick	. Are we to	glue up the
	OPA RESPONSE: Yes,	Provide 1" thi	ck sills for 1st in ba	ase bid and 2 nd in s	suplementa	l bid #1.	
134.	. Reference:	Drawing	A-603	Detail	1	Spec _	VARIOUS
	QUESTION : Should th included in the Base E Tackable Wall Panels Base Bid Package?	Bid or are they t	to be part of Supp	olemental Bid #1?	Are the Pla	am Panels ar	nd the
	OPA RESPONSE: Add shall be gypsum boar				inish on no	n room side	of walls
135.	. Reference:	Drawing	A106	Detail		Spec _	07 53 23
	QUESTION : Are the 3 required for the taper		ıcturally sloped?	If not sloped, who	at is the mir	nimum thick	ness
	OPA RESPONSE: The '4" per foot pitch.	topping slab is	sloped at 1/8" pe	er foot pitch and n	ew roof wil	l be required	l to slope at
136.	. Reference:	Drawing		Detail		Spec _	BP-10A
	QUESTION : For Bid Pa a window and insert. access the slot on the	How are these					
	OPA RESPONSE: Fram	ne will have slo	t in it.				
137.	. Reference:	Drawing		Detail		Spec _	09 51 13
	QUESTION : ACT-1 Ar what material is to be			continued and is r	no longer av	vailable. Ple	ase advise
	SKANSKA RESPONSE	: See Response	to RFI #10.				
138.	. Reference:	Drawing		Detail		Spec _	09 51 13
	S:\Project_Data_NewHaven	\1312021 Buley Lil	orary Renovation\Add	enda\Addendum #2\AD	DENDUM #2	RFI LOG_0122	13.doc

ADDENDUM #2: BIDDING RFI LOG January 22nd, 2013

QUESTION: Suspension system for metal ceilings calls for a platinum baked enamel finish. Is this correct for both types of metal ceilings? This is also the same finish called for Acoustical Ceilings ACT-1.

C	PA RESPONSE: Yes						
139.	Reference:	Drawing _		Detail _	1/A205	Spec _	
	UESTION : Detail call erforated panel to m		etal infill panel betw	een fixtures.	Please clarify.	Is this a no	n-
C	PA RESPONSE: Yes						
140.	Reference:	Drawing _	A200-A204.1	Detail _		Spec _	
	QUESTION : The Gene eiling scope of work				•	e acoustical	metal (
	PA/SKANSKA RESPO ems #68 & 69.)NSE: RCP No	te 6 is for non-acces	ssible ceiling s	ystems. Refer	ence BP-09	Exhibit A
141.	Reference:	Drawing _		Detail _	10/A205	Spec _	
Ç	UESTION : This detai	l calls for a "jo	oint" between the so	offit and the v	vall angle. Ple	ase clarify.	
C	PA RESPONSE: Dele	te joint note a	and joint space on de	etail 9 & 10 or	n A-205.		
142.	Reference:	Drawing _		Detail _		Spec _	BP-08
Ç	UESTION : Are fire ra	ited doors pai	t of bid package 08	?			
S	KANSKA RESPONSE:	Reference B	P-08 Exhibit A Scope	of Work Iten	n #12 as modif	ied in Adde	ndum #2.
143.	Reference:	Drawing _		Detail _		Spec _	Various
	UESTION : Do we hangineer) we hired alr				ngineering if t	he PE (Profe	essional
	KANSKA RESPONSE: xhibits G and Y.	No, provided	d Professional Engin	eer satisfies th	ne requiremen	ts of Subco	ntract
144.	Reference:	Drawing _		Detail _		Spec _	BP-08
1	UESTION : We are bi 01.5, 101.6, and 101 dditional hardware v	.7, are marke	d as existing. What				
C	PA RESPONSE: See h	nardware sche	edule in spec. Provid	e what is indi	cated.		
145.	Reference:	Drawing _	A102	Detail _		Spec _	Base Bid
	UESTION : BP-06 Ba: id: solid surface vani						

base @ Stair B 2nd floor. If this is not correct clarify the base bid scope for the 2nd floor.

S:\Project_Data_NewHaven\1312021 Buley Library Renovation\Addenda\Addendum #2\ADDENDUM #2 RFI LOG_012213.doc

2nd to 3rd floors, wood handrail from 2nd to 4th floors @ Stair B and plam wall panels with blackened steel

ADDENDUM #2: BIDDING RFI LOG January 22nd, 2013

			ween column line ified in the Notes s			•	hown on
146.	Reference:	Drawing	A103	Detail _		Spec _	Base Bid
bid: s		ty @ Rm #317	- We will include of .1, & 318.1 & Type or the 3rd floor.				
			veen column lines ified in the Notes s				nown on
147.	Reference:	Drawing	A104	Detail _		Spec _	Base Bid
	Solid Surface van		- We will include of 1.1 & 432.1. If this				
			veen column lines ified in the Notes s				nown on
148.	Reference:	Drawing	A300	Detail	4	Spec _	
QUE:	STION: Column p	anels 4/A-300	Clarify if wood re	veals are requir	ed		
Add		A-300: Reduce	rizontal space beto e reveal width to 3 main 3/8".				
149.	Reference:	Drawing	A302	Detail _	7	Spec _	
the f		erry can the co	-302- ¾" birch ply re material be par ted?				or Cherry? If
			ywood, no partica nd solid wood shal		arent finish. I	Note will be a	added to A-
150.	Reference:	Drawing	A302	Detail _	5&6	Spec _	
requi	ire ¾" birch plyw	ood panels sir	- Will the area dire milar to window Ty tent of the plywoo	ypes B, C, & D?	Will the plyv	vood clad the	
OPA	RESPONSE: Plyw	ood cladding	on all steel no par	el above staine	d glass at wir	ndow "A".	
151.	Reference:	Drawing	A302	Detail _	5 & 6	Spec _	
	STION: Window ' lemental Bid #1?		Reading 5, 6/A-30)2- Should this i	tem be inclu	ded in the Ba	se Bid or
OPA	RESPONSE: Base	Bid					

ADDENDUM #2: BIDDING RFI LOG January 22nd, 2013

152	52. Reference: Dra	wing A302	Detail	2, 3, 4	Spec
	QUESTION: Window "B, C, arched top of the stained g Clarify if the shaded arched window or birch plywood?	plass window or will it d triangle shaped area	follow the straight	horizontal tube ab	ove the window?
	OPA RESPONSE: Plywood i at arch to mount enclosure			ed area is enclosure	e material. Blocking
153	Reference: Dra	wingA668	Detail		Spec <u>06 40 23</u>
	QUESTION: Grilles @ MW3 perforated grille 1/32" thic Grille model AG10 w/ "A"	k. Spec section 06 40	23 - 2.4E notes the	grilles at radiators	to be Architectural
	OPA RESPONSE: Provide SS	s perforated grilles at	casework.		
154	54. Reference: Dra	wingA701	Detail	A9 & A11C	Spec
	QUESTION : 2x4 hdwd enve 2x4's remain visible or do v			/A-701- Will the fa	steners for the
155	OPA RESPONSE: Provide w 55. Reference: Dra		Detail	A9	Spec BP-06
	QUESTION : Spiral staircase treads?	top platform A9/A-70)1- Will the square 1	op landing require	hardwood like the
	OPA RESPONSE: Yes. Note Except, All hard wood Han hardwood treads and land	drails at stair A & B sh			
156	56. Reference: Dra	wingA700	Detail	A8	Spec BP-06
	QUESTION : Blackened stee scope?	el base A8/A-700- Sho	uld the blackened s	teel base be include	ed with millwork
	SKANSKA RESPONSE: Yes 1/4" plywood substrate.	, BP-06 is responsible t	for furnishing and ir	nstalling the blacke	ned steel base on
157	57. Reference: Dra	wing 	Detail 	A1/A700, A1/A701	Spec
	QUESTION: Access panel @	Stair A&B A1/A-700	& A1/A-701- "Acces	ss Panel" is noted.	Clarify detail.
	OPA RESPONSE: Removablaccess to cavity.	le section of wall mate	erial with concealed	attachment to pro	ovide person size
158	58. Reference: Dra	wing <u>A659, A82</u>	0 Detail	VARIOUS	Spec
	QUESTION : MW10 7,8,9/A details a painted poplar wo				ap. Sect. 11/A-820

OPA RESPONSE: Detail 11/A-820 shall be changed to 1" solid surface cap

ADDENDUM #2: BIDDING RFI LOG January 22nd, 2013


199. Reference. Drawing Detail 1/A009 Spec 10112	159. I	Reference:	Drawing	Detail	1/A603	Spec	10 11 2
--	--------	------------	---------	--------	--------	------	---------

QUESTION: 1/A603 Lobby East Wall Elevation. Corridor walls note "Plam 1 TYP. and BB1 Tackable Panel TYP". BP-06 Exhibit A does not list a specification section for the Tackable Wall Panels, but BP-06 Scope item #15 states "The Subcontractor is responsible for furnishing and installing tackable and plastic wall panels. Scope includes all required $\frac{3}{4}$ " x $\frac{3}{4}$ " aluminum trim angles and blocking as required for a complete installation. BP-09 will be responsible for furnishing and installing required $\frac{1}{2}$ " plywood attached directly to metal stud framing. Refer to details 2, 3, 4, and 5 on A-603 for examples of this scope of work."

Specification Section 10 11 23 Tackable Wall Surface, the Tackable Wall Panels are noted as (TKBS) Tackable Wall surfacing. Is the BB1 Tackable Wall Panel the same as the TKBS Tackable Wall Surfacing and is it to be supplied and installed by BP-06? BP-09 lists section 10 11 23 tackable wall surfaces in the Scope of Work. Please confirm if 10 11 23 Tackable Wall Surfaces is to be supplied and installed by BP-06 or by BP-09?


OPA/SKANSKA RESPONSE: BB1 is TKBS and will be changed on A-603. BP-06 is responsible for Exhibit A Scope of Work Item #15 in its entirety, inclusive of painted wood trim shown on reference details. BP-06 Subcontractor is responsible for coordinating installation details with BP-09 and BP-08A for a complete installation. Reference to Specification Section 10 11 23 is added to BP-06 Specification Sections via this Addendum #2.

BP-09 is responsible for furnishing and installing $\frac{1}{2}$ " plywood attached directly to metal stud framing, and coordinating the installation of $\frac{1}{2}$ " plywood wall panel substrate with BP-06 wall panel assembly details and BP-08A door frame installation as required.



SCSU Buley Library Sketch Log

SK #	Dist.	Title	Date
B-SKL-01	Roming	Added Site Plan Detail	01/10/13
B-SKA-01	OPA	Plaster Ceiling	01/21/13
B-SKA-02	OPA	Light Fixture	01/21/13
B-SKP-01	KR	Sump Pump Clarifications	01/17/13
B-SKP-02	KR	Sump Pump Clarifications	01/17/13
B-SKP-03	KR	Fixture Schedule Revision	01/17/13
B-SKP-004	KR	Water Heater Schedule Revision	01/17/13
B-SKM-01	KR	AHU-5 Condensate Piping	01/17/13
B-SKM-02	KR	AHU-1 Condensate Piping	01/17/13
B-SKM-03	KR	AHU-3 Condensate Piping	01/17/13
B-SKM-04	KR	Cooling Tower Overflow Drain	01/17/13
B-SKM-05	KR	Cooling Tower Schedule Revisions	01/17/13
B-SKE-01	KR	added GFI outlet near Reloc. Condensing Units basement	01/17/13
B-SKE-02	KR	Added Circuit to Room 214	01/17/13
B-SKE-03	KR	Exist. Distribution Panel HD-4NEH-2 Sect. Revisions	01/17/13
B-SKE-04	KR	Added Circuit to Cooling Tower 2	01/17/13
B-SKE-05	KR	Lighting Fixture Schedule Revisions	01/18/13
B-SKE-06	KR	Lighting Fixture Schedule Revisions	01/18/13
B-SKE-07	KR	Demolition/Installation of Oil Filled Transformer	01/18/13
B-SKE-08	KR	Demolition/Installation of Oil Filled Transformer	01/18/13





CONCRETE PAVEMENT & PRECAST PAVER CONNECTION

NOT TO SCALE



ADDED SITE PLAN DETAIL

BULEY LIBRARY RENOVATIONS

SOUTHERN CONNECTICUT STATE UNIVERSITY

NEW HAVEN, CONNECTICUT

Project No. B1-RS-225B

M.R. ROMING ASSOCIATES P.C. Landscape Architects • Land Planners West Hartford Connecticut (860) 233-1265 JANUARY 9, 2013

B-SKL-01


DRAWING REF: L-106

DRAWING REF: A-201






X102 XIØ




FIRST FLOOR REFLECTED CEILING PLAN 8KA-ØI /16"=1'-@"

ADD TO PART 2 OF SECTION Ø9 21 16

- 2.5 METAL LATH AND PLASTER SYSTEM
 - A. 3" thick, 3 Coat Metal Lath and Plaster System on suspended metal carrying channels meeting minimum recommended requirements of USG 3 coat metal lath and plaster system. All materials for system shall be by one manufacturer.
 - B. Metal Lath: Galvanized, small diamond mesh, self furring, metal lath for ceilings 3.4lb. / sq. yd.
 - C. Scratch and Brown Coat Plasters: USG Structo-Base Gypsum Plaster.
 - D. Finish Coat Plaster: USG Structo-Gauge Gauging Plaster.
 - E. Accessories: USG Accessories as detailed in drawings and to provide a complete 3 coat metal lath and plaster system.








BULEY LIBRARY RENOVATIONS
SOUTHERN CONNECTICUT STATE UNIVERSITY

UTHERN CONNECTICUT STATE UNIVERSIT NEW HAVEN, CONNECTICUT Project No. BI-RS-225B M.R. ROMING ASSOCIATES P.C. Landscape Architects • Land Planners West Hartford Connecticut (\$600) 233-1265 B-SKP-01

DRAWING REF: P-100





SUMP PUMP CLARIFICATIONS
BULEY LIBRARY RENOVATIONS
SOUTHERN CONNECTICUT STATE LINIVERSITY

SOUTHERN CONNECTICUT STATE UNIVERSITY
NEW HAVEN, CONNECTICUT
Project No. BI-RS-225B

M.R. ROMING ASSOCIATES P. Landscape Architects • Land Planner West Hartford Connecticu (880) 233-1265 JANUARY 16, 2013 **B-SKP-02**

DRAWING REF: P-100

H	≤		J E	
	MSK	©r WC	FIXTURE TAG	_
HOSE BIBB	MOP RECEPTOR	FOUNTAIN	FIXTURE TYPE	
NIBCO #46-U WITH WATTS NF8 SERIES W/ WATTS NF8 VACUUM BREAKER MIFAB MHY-9141 SERIES W/ VACUUM BREAKER STANDARD WOODFORD MODEL 24 W/ VACUUM BREAKER STANDARD	FIAT TSB-100 SERIES ACCESSORIES: HOSE FIAT 832-AA, MOP HANGER FIAT 889CC BUMPER GUARD FIAT 1239-BB STRAINER FIAT 1453-BB	(UNIT IS COMPLIANT WHEN INSTALLED IN AN ALCOVE AND IS ALSO COMPLIANT WHEN MOUNTED ON AN EXPOSED WALL WITH A WING WALL THAT IS LOCATED ON THE LEFT SIDE. PROVIDE APRON UNDER THE UNIT WHERE APPLICABLE CONDITIONS APPLY. REFER TO ARCHITECTURAL DRAWINGS.)	FIXTURE MANUFACTURER MODEL, MODEL NO.	
	TERRAZZO		MATERIAL	PL
UNFINISHED AREAS, BRONZE BODY, REMOVABLE VALVE SEAT & STEM ASSEMBLY, THREADED END.	24" X 24" X 12" DEEP, BASIN DRAIN FITTING & STRAINER, EDGE GUARD. FAUCET: WALL MOUNTED WITH BUCKET HOOK, VACUUM BREAKER, WALL BRACKET & HOSE THREAD END. HOSE, WALL BRACKET & MOP HANGER.	GENERAL -A.D.A. COMPLIANT, STAINLESS STEEL BASIN WITH REMOVABLE DRAIN STRAINER. BUBBLER SHALL BE TWO-STREAM, MOUND BUILDING TYPE. SEPARATE VALVE AND AUTOMATIC STREAM REGULATOR SHALL BE MOUNTED WITHIN CABINET. REFRIGERATION SYSTEM SHALL EMPLOY HIGH EFFICIENCY, POSITIVE START COMPRESSOR USING R134A, NON-PRESSURIZED TANK WITH TOTALLY ENCAPSULATED INSULATION AND BE CONTROLLED BY POSITIVE SENSING THERMOSTAT. SHALL HAVE FRONT AND SIDE PUSH-BAR WATER CONTROLS WITH RAISED LETTERING FOR THE VISUALLY IMPAIRED. COOLER SHALL COMPLY WITH ANSI 117:1 AND ADA FOR VISUAL AND MOTION DISABILITIES. THE MANUFACTURER SHALL CERTIFY THE UNIT TO MEET THE REQUIREMENTS OF NSF/ANSI 61 & 372 AND THE SAFE DRINKING WATER ACT. UNIT COMPLIES WITH ARI STANDARD 1010. ELECTRICAL RATING; 370WATTS MINIMUM COOLING CAPACITY: 8.0 GPH (80 DEGREES ENTERING TO 50 DEGREES DRINKING AT 90 DEGREES AMBIENT)	DESCRIPTION	PLUMBING FIXTURE SCHEDULE
t	1/2"	3/8 _"	SUPPLY	DUL
1	ယ္ခ	1-1/4"	TRAP	M
ı	ယ္ခ	1-1/2"	WASTE/ SANITARY	
i	2"	1/2"	MINIMUM BRANCH SIZES Y VENT COLD WATER	
3/4"	3/4"	1/2"		
-	3/4"		HOT WATER	
			REMARKS	



FIXTURE SCHEDULE REVISIONS

BULEY LIBRARY RENOVATIONS

SOUTHERN CONNECTICUT STATE UNIVERSITY

NEW HAVEN, CONNECTICUT

Project No. BI-RS-225B



		~				
GROUND FL 2.1 GALLON SECOND FLO THERMOSTA 3RD FLOOR	WHA, WH5, WH6	WH3	WH1 & WH2	UNIT NO.		
OOR/FIRST F CAPACITY T OOR: WH3: I TIC MIXING (WH4) & 4TH	NIA	50)19	(GAL.)	10101	
LOOR: WH1. HERMOSTAT EXPANSION : VALVE: (TMV FLOORS (WI	- >	I	§.	RECOVERY		
GROUND FLOOR/FIRST FLOOR: WH1&WH2: EXPANSION TANKS (2-EXP-1's) MODEL AMTROL THERM-X-TROL, ST-5-C, ASME 2.1 GALLON CAPACITY THERMOSTATIC MIXING VALVE: (TMV-1 & TMV-2) SYMMONS TEMPCONTROL MODEL NO. 6-200-A-RC SECOND FLOOR: WH3: EXPANSION TANK (EXP-1) MODEL AMTROL THERM-X-TROL, ST-12-C, ASME, 6.4 GALLON CAPACITY THERMOSTATIC MIXING VALVE: (TMV-3) SYMMONS TEMPCONTROL MODEL NO. 6-400-A-RC 3RD FLOOR (WH4) & 4TH FLOORS (WH5 & WH6): FOR S1 APPLICATIONS ONLY	73	100) je	RISE (°F)	1	
ISION TANKS VE: (TMV-1 & MODEL AMTR TEMPCONTR DR S1 APPLIC	TMV-5/ TMV-6	TMV-3	TMV-1/	VALVE		
(2-EXP-1's) M TMV-2) SYMN OL THERM-X OL MODEL N ATIONS ONL'	\ \ \	ï) }; }	GAS PRESS.		
IODEL AMTRO WONS TEMPC -TROL, ST-12: O. 6-400-A-RO Y	<u>}</u>	:	};	MBH	GAS	
OL THERM-X-1 CONTROL MOI C, ASME, 6.4	<u>}</u>	ī	\ \{\}'	GPH		DOMESTIC WATER HEATER SCHEDULE
TROL, ST-5-C, ASME DEL NO. 6-200-A-RC GALLON CAPACITY	}	-	<u>}</u> ,	MBH INPUT	OIL	STIC
ST-5-C, ASME, O. 6-200-A-RC ON CAPACITY	277	480	\\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\	VOLTAGE		WATE
	7	3	<u>}</u>	AGE PHASE	ELEC	R HE
	16kW		1500 W	E WATTS	ELECTRICAL	ATER
	}		SOO W COMEBELEMENT -	모표		SCHI
	}		}	HEATING BTUH		EDUL
			$\left ight angle ^{+} \left ight.$	BOILER GPM	INDIRECT	m
NOTE #1: ITE INSTALLED B' REVIEW INVE EQUIPMENT/F QUANTITIES / NOTE #2: M VERIFIED IN INVENTORY	\ \		\{\} \}	BOILER TEMP		
NOTE #1: ITEM FURNISHED BY OWNER AND INSTALLED BY CONTRACTOR. CONTRACTOR TO REVIEW INVENTORY AND SUPPLEMENT MATCHING EQUIPMENT/FIXTURES WHERE EXISTING QUANTITIES ARE INSUFFICIENT. NOTE #2: MODEL NUMBER, VOLTAGE & PHASE VERIFIED IN FIELD, NUMBER IS NOT LISTED IN INVENTORY	EX160TC	LOCHINVAR LTX052KK**	LOCHINVAR	MODEL NO.	MANUFACTURER	
BY OWNER AND R. CONTRACTO JPPLEMENT MA1 JPPLEMENT MA1 ERE EXISTING ENT. R, VOLTAGE & ER IS NOT LIST	AX A	IVAR !KK**	WAR	NO.	TURER	
IER AND IRACTOR TO ENT MATCHING TING TAGE & PHASE TO BE OT LISTED IN		REFER TO N	REFER TO !	REMARKS		
R R		REFER TO NOTE #1 & #2	REFER TO NOTE #1 & #2			
			$\left \left\langle \cdot \right \right $			
			/ 	ı		



WATER HEATER SCHEDULE REVISIONS


BULEY LIBRARY RENOVATIONS


SOUTHERN CONNECTICUT STATE UNIVERSITY


NEW HAVEN, CONNECTICUT

Project No. BI-RS-225B










301 Main Street, Danbury, CT 06810 203.778.1017 F 203.778.1018 1370 Broadway, New York, NY 10018 212.695.2422 F 212.695.2423 www.kohlerronan.com E-mail krce@kohlerronan.com

SOUTHERN CONNECTICUT STATE UNIVERSITY

NEW HAVEN, CONNECTICUT Project No. BI-RS-225B

M.R. ROMING ASSOCIATES P.C. Landscape Architects • Land Planners West Hardford Connecticut

DRAWING REF: 1 / M-201





301 Main Street, Danbury, CT 06810 203.778.1017 F 203.778.1018 1370 Broadway, New York, NY 10018 212.695.2422 F 212.695.2423 www.kohlerronan.com E-mail kroe@kohlerronan.com

COOLING TOWER OVERFLOW DRAIN BULEY LIBRARY RENOVATIONS SOUTHERN CONNECTICUT STATE UNIVERSITY

ERN CONNECTICUT STATE UNIVERSITY NEW HAVEN, CONNECTICUT
Project No. BI-RS-225B

M.R. ROMING ASSOCIATES P.C. Landscape Architects • Land Planners West Hartford Connecticut (860) 233-1265 JANUARY 16, 2013

B-SKM-04

DRAWING REF: 1 / M-105

								CO	OLING	G TOV	WERS						
UNIT			WATER	R DATA	1	А	IR DATA	FAI	N DATA		Е	LECTRICA	L		OPER		
NO	LOCATION	GPM	EWT	LWT	HEAD	WB	CFM	SP	TYPE	HP	VOLTS	PH	RPM	HTR	LBS	MAKE/MODEL	REMARKS
CT-1	ROOF	1200	95°F	85°F	-	79.77°F	132,000	-	INDUCED FLOW	20	460	3	1200	-	26,510	MARLEY NC8307FL1	3
CT-2	ROOF	1200	95°F	85°F	-	79.77°F	132,000	-	INDUCED FLOW	20	460	3	1200	-	26,510	MARLEY NC8307FL1	1, 2, 4, 5

NOTES:


- COOLING TOWER FURNISHED BY OWNER AND INSTALLED BY MECHANICAL CONTRACTOR
- MECHANICAL CONTRACTOR TO FIELD INSTALL METRIX VIBRATION CUTOFF SWITCH, PROBE TYPE ELECTRONIC WATER LEVEL SENSOR FOR MAKE UP & LOW ALARM, QUICK ACTING SOLENOID FOR MAKE UP
- EXISTING EQUIPMENT IN OPERATION. INDICATED FOR REFERENCE ONLY.
- COOLING TOWER SHALL BE FULLY CLEANED PRIOR TO OPERATION.


PROVIDE FACTORY ALITHORIZED STARTUR
PROVIDE AND INSTALL SUMP HEATER IN BASIN PER MANUFACTURERS RECOMMENDATION



COOLING TOWER SCHEDULE REVISION BULEY LIBRARY RENOVATIONS SOUTHERN CONNECTICUT STATE UNIVERSITY NEW HAVEN, CONNECTICUT Project No. BI-RS-225B









KOHLER RONAN, LLC CONSUMERS MANAGEMENT BULEY LIBRARY RENOVATIONS
SOUTHERN CONNECTICUT STATE UNIVERSITY
NEW HAVEN, CONNECTICUT
Project No. BI-RS-225B

M.R. ROMING ASSOCIATES P.C. Landscape Archifects • Land Planners West Harthof (860) 233-1265

JANUARY 16, 2013

B-SKE-02

DRAWING REF: 1 / E-102

EXIST. DISTRIBUTION PANEL HD-4NEH - 2 SECT. 3 PHASE 480/277 VOLTS 4 WIRE 65,000 AIC MAIN BUS SIZE: -NEUTRAL: 100% GROUND BUS: FULL MAIN DEVICE: -MOUNTING: SURFACE OVERCURRENT DEVICE CIRCUIT LOAD ITEM FEEDER SIZE REMARKS NUMBER FRAME POLE 3 #4 + #10G - 1-1/4" C 100 60 EXISTING LV-4NEH 2 3 RF-2 3 #4 + #10G - 1-1/4" C 100 60 3 EXISTING CT-1 6 CT-2 100 45 3 3 #6 + #10G - 1" C 8 . EXISTING RF-4 EXISTING RF-3 10 AHU-1 3 #3/0 + #6G - 2" C 11 200 150 3 3 #3/0 + #6G - 2" C 12 150 200 3 EXISTING AHU-4 13 14 EXISTING AHU-3 EXISTING PAN HTR CT-1 15 3 #10 + #10G - 3/4" C PAN HTR CT-2 16 50 30 3 EXISTING EF-5 17 EXISTING EF-9 18 19 EXISTING EF10 -20 EXISTING EF-11 EXISTING EF-12 22 EXISTING EF-13 EXISTING FREEZE PUMPS 11-12 23 24 25 26



KOHLER RONAN, LLC CONSUMERS ENCHANGES

28


AHU-1 CONDENSATE PIPING
BULEY LIBRARY RENOVATIONS
SOUTHERN CONNECTICUT STATE UNIVERSITY
NEW HAVEN, CONNECTICUT
Project No. BI-RS-225B

M.R. ROMING ASSOCIATES P.C. Landscape Architects • Land Planners West Hartford (860) 233-1265

B-SKF-0

JANUARY 16, 2013

DRAWING REF: 1 / E-400



TYPE	LAMP	VOLTAGE	MOUNTING	DESCRIPTION IN STO				
数	LED	277V	SURFACE MOUNT	DIE CAST ALUMINUM SINGLE FACE EXIT SIGN WITH EMERGENCY BATTERY BACKUP				
+25	LED	277V	SURFACE MOUNT	COOPER LIGHTING SURE-LITES #CX71SD COMBINATION EXIT SIGN AND UNIVERSAL HANDICAP ACCESSIBLE SIGN. DIE CAST ALUMINUM SINGLE FACE WITH EMERGENCY BATTERY BACKUP. RAZOR: RZP-EMFA-18BT.				
			SURFACE	RAZOR:RZR-EM-R-1-BB-T-SA DIE CAST ALUMINUM DOUBLE FACE EXIT SIGN WITH EMERGENCY				
	LED	277V	MOUNT	BATTERY BACKUP - COOPER LIGHTING SURE-LITES #CX72SD				
			SURFACE MOUNT	LOW HEIGHT EMERGENCY SELF-LUMINOUS TRITIUM SIGN WITH GUARANTEED LUMINOUS LIFE UP TO 20 YEARS AS SPECIFIED. THESE SIGNS CONSIST OF GAS LAMPS WITH THERMOPLASTIC HOUSING. SIGNITEX LIGHTING INC. # EMA202GBA-2PSC				
EXII			SURFACE MOUNT	COMBINATION LOW HEIGHT EMERGENCY SELF-LUMINOUS TRITIUM SIGN AND UNIVERSAL SIGN OF HANDICAP ACCESSIBLE IN ONE INCLOSURE. THESE SIGNS CONSIST OF GAS LAMPS WITH THERMOPLASTIC HOUSING.				
$\overline{}$		\vdash	\vee	SIGNTEN IGHTING INC # EN A202 GBA-WC-2PSC	<u> </u>			
А	(2)32W T8	277V	PENDANT MOUNT	4 FT LONG, DIE FORMED HIGH REFLECTANCE ALUMINUM - COOPER LIGHTING NEO-RAY #8B-W-M-2T8-1C-277-AC-T1-ET	Х			
AA	60W LED	277V	SURFACE MOUNT	POLE MOUNTED SITE LIGHT FIXTURE, 5 LED 4K 60W ARRAY, 12 'HIGH TAMPERED ALUMINIUM POLE AND LANTERN TO MATCH TO MATCH CAMPUS STANDARD. HOLOPHARE, GRANVILLE CLASSIC LED:GVD-60-4K-X-M-X-3-N-X-X				
A01A	32W T8	277V	CEILING SUSPENDED	1'-3/4"X4" LINEAR FLUORESCENT FIXTURE WITH SEMI-SPECULAR REFLECTOR, COLD ROLLED STEEL HOUSING AND INTEGRAL ELECTRONIC BALLAST - BARTCO #BFL208 CUSTOM				
A01B	(2)32W T8	277V	CEILING PENDANT	1'-3/4"X8' LINEAR FLUORESCENT FIXTURE WITH SEMI-SPECULAR REFLECTOR, COLD ROLLED STEEL HOUSING AND INTEGRAL ELECTRONIC BALLAST				
A01C	(3)32W T8	277∨	CEILING PENDANT	BARTCO #BFL208 CUSTOM 1'-3/4"X12' LINEAR FLUORESCENT FIXTURE WITH SEMI-SPECULAR REFLECTOR, COLD ROLLED STEEL HOUSING AND INTEGRAL ELECTRONIC BALLAST				
A02	28W T5	277V	CEILING SURFACE	BARTCO #BFL208 CUSTOM 5'x4' LINEAR FLUORESCENT WALLWASHER WITH BAFFEL LOUVER, SPECULAR REFLECTOR AND EXTRUDED ALUMINUM HOUSING				
A03	(2)15W PAR30	120V	CEILING RECESSED	ELLIPTIPAR #F144-T155XX-2-X-X 9.5"X32" RECESSED FIXTURE WITH OVERLAP FLANGE AND DIE FORM STEEL CONFIG. C032				
A04	20W LED	277V	CEILING RECESSED	COOPER LIGHTING - RSA LIGHTING COMBOLIGHT SERIES 4" ROUND DOWNLIGHT WITH CLEAR COMFORT DIFFUSER, OVERLAP FLANGE, SEMI-SPECULAR REFLECTOR, COLD ROLLED STEEL HOUSING AND INTEGRAL ELECTRONIC HOUSING LIGHTOLER #C4L10DL				
A07	32W T8	277V	CEILING SURFACE	4.5°X4' LINEAR FLUORESCENT FIXTURE WITH WITH EXTRUDED ALUMINUM HOUSING AND INTEGRAL ELECTRONIC BALLAST				
A08	32W T8	277V	CEILING SURFACE	ELLIPTIPAR #F109-A132-X-X-2-X-X 4' LINEAR FLUORESCENT FIXTURE WITH EXTRUDED ALUMINUM HOUSING AND INTEGRAL ELECTRONIC BALLAST				
A09	20W LED	277V	CEILING RECESSED	ALIGHT #84 SERIES ARRIS4 4" ROUND DOWNLIGHT WITH CLEAR COMFORT DIFFUSER, OVERLAP FLANGE, SEMI-SPECULAR REFLECTOR, COLD ROLLED STEEL HOUSING AND INTEGRAL ELECTRONIC BALLAST				
A10	15W LED	120V	CEILING RECESSED	LIGHTOLIER #C4L10LW FIXTURE WITH OVERLAP FLANGE AND DIE FORM STEEL HOUSING CONFIG. C01 - COOPER LIGHTING - RSA LIGHTING COMBOLIGHT SERIES				
A12	75W PAR30	120V	CEILING SURFACE	LTG FIXTURE HEAD ON LSI TRACK; PROVIDE 120 V TRANSFORMER - LIGHTING SERVICES INC (LSI) 230 SERIES				
A013	70W LED	277V	CEILING PENDANT	4' LONG DOWNLIGHT, 6' DIAM. DELRAY LIGHTING #8300 SERIES				
В	(3)32W T8	277V	CEILING RECESSED	SPECULAR / MIRRORED PARABOLIC LOUVER, 12 CELLS, WITH FB031 LAMP. HOUSING: DIE-FORMED PARA-CONTOURED.	Х			
С	32W	277V	CEILING RECESSED	COOPER LIGHTING METALUX #2P5GAX-3UL 5/8-S34ML-277-EB81 6" WALL WASH DOWNLIGHT WITH 1 GX24 TRIPLE TUBE LAMP -	X			



SKETCH DESCRIPTION **BULEY LIBRARY RENOVATIONS** SOUTHERN CONNECTICUT STATE UNIVERSITY NEW HAVEN, CONNECTICUT Project No. BI-RS-225B



301 Main Street, Danbury, CT 06810 203.778.1017 F 203.778.1018 1370 Broadway, New York, NY 100 212.695.2422 F 212.695.2423

JANUARY 18 2013

DRAWING REF: 1 / E-002

			LIGI	HTING FIXT	URE SCHEDULE	
1	TYPE	LAMP	VOLTAGE	MOUNTING	DESCRIPTION	IN STOCK
	F	(3)32W T8	277V	CEILING MOUNT	CLEAR HEAVY ACRYLIC BAKET TYPE DIFFUSER HEAVY GAUGE STEEL HOUSING DIE EMBOSSED COLUMBIA #WP-W-4-332-EB8-277-X	х
	G	(3)32W T8	277V	CEILING RECESSED	3 LAMP SILVER LOUVER WITH CELL CONFIGURATION OF 3 ROWS OF 9 (27 CELLS) AND SPECULARMIRRORED FINISH ON LOUVER. WITH FO32 LAMP. COOPER LIGHTING METALUX #2P5GAX-332S39MI-277-EB81	х
	J	(2)32W T8	277V	WALL MOUNT	LINEAR FLUORESCENT FIXTURE WITH HIGH GLOSS WHITE ENAMEL FINISH. COLUMBIA W4-232-EB8-277-X	х
	KR	(2) 32W - T8	120/277V	CEILING PENDANT	4FT. INDUSTRIAL FLUORESCENT FIXTURE WITH 10/15% UPLIGHT, WHITE ENAMEL FINISHED REFLECTOR AND WHITE FINISHED HOUSING LITHONIA #AF10 2 32 MVOLT GEB10IS	
	ELV1	32W T8	277V	WALL SURFACE	2 LAMP FIXTURE WITH INTERNAL PRISMATIC LENS DIMENSIONS 48 in X 7 in x 5 in (L x W x D) COOPER LIGHTING #VT2-232DR-277-EB81	х
	ELV3	100W	277V	WALL SURFACE	INCANDESCENT LIGHT WITH POLYCARBONATE HIGH ABUSE LUMINAIRE AND PRISMATIC REFRACTOR COOPER LIGHTING FAIL SAFE #IB-P-100-277-VRSD	х








301 Main Street, Danbury, CT 06810 203.778.1017 F 203.778.1018 1370 Broadway, New York, NY 100 212.695.2422 F 212.695.2423

JANUARY 18, 2013





BULEY LIBRARY RENOVATIONS SOUTHERN CONNECTICUT STATE UNIVERSITY NEW HAVEN, CONNECTICUT Project No. BI-RS-225B



1370 Broadway, New York, NY 100 212.695.2422 F 212.695.2423

DRAWING REF: ED-100

DEMOLITION KEY NOTES

- E.C. SHALL TRANSFER ALL EXISTING LOADS PROVIDED WITH TEMPORARY POWER FROM THE PANELS IN THIS ROOM TO THE PANELS IN THE NEW ELECTRICAL ROOM, DE-ENERGIZE AND REMOVE ALL PANELS, TRANSFORMERS AND ASSOCIATED FEEDERS AND WIRING.
- 2 DE-ENERGIZE AND REMOVE EXISTING SUB-STATION AND ASSOCIATED FEEDERS.
- PERFORM ALL REQUIRED WORK IN ORDER TO COMPLETE THE CAMPUS POWER SUPPLY LOOP AS INDICATED ON THIS PLAN, DE-ENERGIZE AND REMOVE EXISTING LOOP SWITCHES AND ASSOCIATED FEEDERS.
- DISCONNECT AND REMOVE ALL ABANDONED AND INACTIVE PANELBOARDS, BOXES AND TRANSFORMERS AND ASSOCIATED FEEDERS AND WIRES.
- PULL OUT THE CABLES BETWEEN THE MANHOLE E-21 AND THE SERVICE END BOXES CAP THE CONDUITS WATER TIGHT AND REMOVE THE BOXES.
- REMOVE EXISTING F.A. PANELS AND ASSOCIATED WIRING. PRIOR OF REMOVAL CONTRACTOR SHALL VERIFY WITH THE F.A. VENDOR AND THE CAMPUS PERSONNEL THAT THE PANELS IS INACTIVE.
- REMOVE EXISTING TELECOM PANELS AND ASSOCIATED WIRING. PRIOR OF REMOVAL CONTRACTOR SHALL VERIFY WITH THE CAMPUS PERSONNEL THAT THE PANEL IS INACTIVE.
- REMOVE ALL ABANDONED AND INACTIVE STUB-UP CONDUITS AND BOXES THROUGHOUT THE SPACE.
- REMOVE ALL ABANDONED PANELBOARDS, PULL BOXES AND CONDUITS ON THE GROUND FLOOR AND ON UPPER FLOORS IF ANY.
- E.C. SHALL DISCONNECT BRANCH CIRCUIT TO EXISTING CHILLER AND RECONNECT TO NEW CHILLER.
- E.C. SHALL DISCONNECT EXISTING HIGH VOLTAGE CABLES FROM EXISTING HIGH VOLTAGE SWITCHGEAR AND PULL ADEQUATE AMOUNT OF CABLE INTO EXTERIOR MANHOLE TO PERFORM HIGH VOLTAGE SPLICING AND DISCARD EXCESS CABLE. HIGH VOLTAGE SPLICE KITS SHALL BE AS MANUFACTURED BY 3M OR RAYCHEM AND SHALL BE SUITABLE FOR CABLE TYPE. EMPTY CONDUITS FROM MANHOLE TO BUILDING SHALL BE FILLED COMPLETE WITH CONCRETE.
- E.C. SHALL DISCONNECT AND REMOVE EXISTING EXTERIOR, OIL FILLED TRANSFORMER PRESENTLY SERVING THE LIBRARY AND REPLACE WITH NEW TRANSFORMER AS MANUFACTURED BY AB EM=PEQ 1288, STYLE# F5EE2663YZ, BELL-GREEN 2 COAT URETHANE 2500KVA, 13.8KV/480Y/277 VOLT 3Ø, 4 WIRE AND RECONNECT. COORDINATE SHUTDOWN WITH SCSU.



SKETCH DESCRIPTION

BULEY LIBRARY RENOVATIONS

SOUTHERN CONNECTICUT STATE UNIVERSITY

NEW HAVEN, CONNECTICUT

Project No. BI-RS-225B



JANUARY 18, 2013

B-SKE-08

DRAWING REF: ED-100