

Page 1 of 6

Addendum No.: One Date Of Addendum: January 7, 2019

# CT DAS | Construction Services | Office of Legal Affairs, Policy, and Procurement Bathroom renovations and ADA Upgrades 410 Capitol Avenue Hartford, CT BI – 2B – 400

Bid Due Date / Time: 1/16/2019 1:00 PM

#### TO: Prospective Bid Proposers:

This Addendum forms part of the "Contract Documents" and modifies or clarifies the original "Contract Documents" for this Project dated 9/14/18. Prospective Bid Proposers <u>shall</u> acknowledge receipt of the total number the Addenda issued for this Project on the space provided on Section 00 41 00 Bid Proposal Form.

Failure to acknowledge receipt of the total number the Addenda issued for this Project on the space provided on Section 00 41 00 Bid Proposal Form <a href="mailto:shall">shall</a> subject Bid Proposers to disqualification.

The following clarifications are applicable to drawings and specifications for the project referenced above. *Questions (Items 10-29) are transcribed verbatim from the RFI-s received.* 

#### <u>Item 1:</u>

In Section 02 82 13 Asbestos Abatement, Paragraph 1.2 DESCRIPTION OF WORK

DELETE: Sub-Paragraphs B, C, D.

#### SUBSTITUTE:

- B. The results of laboratory analysis indicate asbestos-containing material (ACM) is present in the areas of the building to be renovated in this project. A complete listing of all suspect materials sampled, results of testing is documented in attached asbestos inspection reports. See also Floor Plans included in Section 05 80 00.1 2016 ATC Report Appendix B Drawings. Specifically the following materials have been determined to be ACM:
  - 1. Joint Compound in gypsum board walls in Janitor's Rooms.
  - 2. 12"x12" Gray Floor Tile and Associated Mastic in all Janitor's Rooms.
  - 3. Mirror Adhesive (Presumed).
  - 4. Joint compound in gypsum board walls behind ceramic tile (Presumed).
- C. The scope of work includes the removal of ACM as part of building renovation. Coordinate locations and identity of building components or materials to be removed under this section with other sections of the Project Manual and contract drawings A0.02, A1.00, A1.01, P1.01, M1.01, and E1.01. Coordinate with Project Phasing as specified in section 01 11 00 Summary of Work, 1.5 Work Sequence.
- D. The scope of work in this section includes but is not limited to the removal of the following ACM:
  - 1. Gypsum Board Wall at all locations where walls are demolished and where new penetrations are required. See A.1.00, P1.01, M1.01, A1.01.
  - 2. Gypsum wall board behind ceramic tile on all walls called to have the tile removed.
  - 12"x12" Gray Floor Tile and Associated Mastic at Janitors Closets West (all four floors), Floor Tile and Residual Mastic and Janitors Closets East (all four floors).
  - 4. Mirror Adhesive (Presumed) at all locations."

#### Item 2:

In Drawing A1.00, DEMOLITION LEGEND:

DELETE: Note 8

SUBSTITUTE: Note 8: Remove gypsum board wall and tile from floor to underside of deck. Asbestos Abatement required because of ACM presumed present in joint compound.

ADD: Note 19: Dimensions of cuts in walls are dimensions of finished construction. See A1.01.



Page 2 of 6

Addendum No.: One Date Of Addendum: January 7, 2019

#### Item 3:

In Drawings A.1.00, A.1.01:

ADD: Cut new doors in the existing walls at Corridor East on 2<sup>nd</sup>, 3<sup>rd</sup> and 4<sup>th</sup> floors, for access to sprinkler valves in Janitor's Closets.

See 1/SKA-1, 2/SKA-1.

#### Item 4:

In Drawing A.3.01, DOOR SCHEDULE:

SUBSTITUTE: 3/SKA-1

#### Item 5:

In Drawing A.2.01, Detail 10 DF GUARD PANEL:

SUBSTITUTE: 4/SKA-1

#### Item 6:

In Drawing A.2.01, Detail 3.4 MEN'S ROOM WEST WALL:

SUBSTITUTE: 5/SKA-1

#### Item 7:

In Drawing P2.01:

ADD: Route new water piping through bathrooms to avoid additional ceiling demo work. See SKP-1.

#### Item 8:

In Drawing P2.02:

ADD: Insulate and heat trace 3" Drain pipe in lower level ceiling. See SKP-2.

#### Item 9:

In Drawing E2.01: GENERAL NOTES:

ADD: Provide 20 amp, 120 volt circuit (2#12+#12G) from first floor receptacle panel to pipe heat tracing in lower level ceiling. Provide new 20 amp GFI circuit breaker for new circuit.

#### <u>Item 10:</u>

Question: Is there a spec for the fritted glass panel next to the water cooler on the 1st floor?

Answer: Provide 3/4" thick, clear laminated tempered glass with polished edges and 1/2" radius corners. See 4/SKA-1.

#### Item 11:

Question: What is the floor to bottom of deck height at each floor?

Answer: Floor-to-floor height is 12'-5" +/-, 4th floor-to-roof height is 13'-0" +/- (verify in field).



Page 3 of 6

Addendum No.: One Date Of Addendum: January 7, 2019

#### Item 12:

Question: Can you please confirm the existing deck height?

Answer: see Answer to Item 11 above.

#### Item 13:

Question: Drawing E2.01:

- a. The light fixture over the sinks in the West Mens room on floors 2-4 indicates "B-2". This fixture does not appear on the lighting schedule. Please advise
- b. Storage rooms on the 2<sup>nd</sup>-4<sup>th</sup> floor indicate a Type "A" light fixture for the 3 lights within these rooms. This fixture does not appear on the light fixture schedule. Please advise.

#### Answer:

- a. The light fixture over the sinks in the West Men's room on floors 2-4 indicated "B-2" shall be "A-7".
- b. Storage rooms on the 2<sup>nd</sup>-4<sup>th</sup> floor light fixture indicated Type "A" shall be Type "B".

#### Item 14:

Question: Are we to include fees for building permit in bid?

Answer: No building permit fees required.

#### Item 15:

Question: On <u>drawing A1.00</u> there is a note saying all demo work will be included even if it is not shown on drawing. We have no way of knowing if asbestos will be uncovered behind the walls and ceilings. Is it confirmed that the pipes do not have asbestos?

Answer: See Section 01 35 16 and 01 20 00 regarding requirements and unit prices if additional asbestos containing materials are encountered.

#### **Item 16:**

Question: Invitation to Bid (Spec 00 11 16) indicates that the walkthrough was mandatory, however the Pre-Bid Agenda indicates that is was recommended. Please confirm the invitation is correct and that the walkthrough was Mandatory.

Answer: Walk-through was Mandatory. Sign-in sheet attached to the Addendum.

#### Item 17:

Question: Specification 00 62 16.1 regarding the Asbestos Insurance, it indicates that the General Contractor is to carry this insurance. Since abatement is a licensed trade, there are few if any general contractors that would self perform this work. Would this insurance only be applicable to the contractor actually doing the abatement work or is this specification correct and the insurance is to be carried by the general contractor as well.

Answer: This insurance requirement to be applicable to the contractor doing the abatement work.

#### Item 18:

Question: Spec Section 00 41 00 2.9.1 Special Hazards Insurance:

If a subcontractor is performing the abatement scope and carries the asbestos abatement liability insurance is that sufficient? Or is the prime contractor required to have this coverage?

Answer: See Answer to Item 17 above.

Page 4 of 6

Addendum No.: One Date Of Addendum: January 7, 2019

#### Item 19:

Question: On the door schedule door 1.5 calls out for the frame as existing. It is a new drywall. Are we using one of the removed frames or providing a new frame?

Answer: Provide new frame. See 3/SKA-1 for Door Schedule.

#### Item 20:

Question: 9/A2.01 shows insulation in the walls. However, in specification 072100 there are 3 different types of insulation specified. Please advise which type of insulation should be used.

Answer: Provide insulation specified in Section 07 21 00 Paragraph 2.03 SOUND ATTENUATION BATT INSULATION.

#### **Item 21:**

Question: Specification 061000 2.01 F.2 indicates that the Millwork vendor and installer is to be AWI QCP certified. It will be difficult to get the QCP contractors to bid this project due to the size of the millwork package. Can this requirement be waived as long as the millwork is built to QCP standards?

Answer: Yes, the requirement can be waived as long as the millwork is built to QCP standards.

#### <u>Item 22:</u>

#### Questions:

Regarding the art hanging rails:

- a. Specification 055000 2.03 calls for hanging rods while Drawing 6/A3.01 calls for hanging cables. Please advise which is correct
- b. Please indicate desired length of cables or rods.
- c. Please confirm if these rails are to go on the north and south corridor walls of 2<sup>nd</sup>-4<sup>th</sup> floor as well. The note on 2/A1.01 indicates to match wall finishes and does not mention these rails.
- d. Section 055000 3.01 D calls for 2 hanging rods per foot. Based on the linear footage from the elevations (figuring North and South as well on the 2<sup>nd</sup>-4<sup>th</sup> floor), there would be around 900 hangers. Please advise if this is the correct quantity that is desired.

#### Answers:

- a. Provide hanging cables.
- b. Length of cables: 2'.
- c. Provide rails on all walls.
- d. Provide 25 hanging cables per floor.

#### Item 23:

Question: Upon removal of the existing floor system, which prep shall be used prior to installing the new floor? Spec 093000 2.06 A indicates to use a filler recommended by the manufacturer, however there is also Spec 096510 which indicates to use a self leveler on the entire floor.

Answer: Use self leveler as per Section 9 65 10.

#### <u>Item 24:</u>

Question: Regarding the demo of the existing floor tiles, what is under the tile? Is it a mud job, if so how thick? Or is it thinset?

Answer: Thinset presumed.

Page 5 of 6

Addendum No.: One Date Of Addendum: January 7, 2019

#### Item 25:

Question: In the men's rooms, Specification 102800 3.05 and floor plans show/indicate 3 mirrors in each room. However the elevations only show 2 mirrors. Please advise which is correct. If there are to be 3 please provide size for 3<sup>rd</sup> one.

Answer: 1'6" wide by 6' tall mirror, installed by the entry door, see location in plan 1/A1.01 and elevation 4/SKA-1.

#### Item 26:

Question: The wall mirrors are spec-ed to have z clips for hanging but the manufacturers will not mount z clips on them as the epoxy fails over time. Is there an alternate preferred hanging method?

Answer: The intent is to conceal mount the mirrors. Provide concealed mounting system as per manufacturer's recommendations.

#### Item 27:

Question: Regarding Specification 014523.13:

a. There are several parts of this specification that make reference to Green Building and related credits. As far as we can tell this is not a LEED or CT High Performance Building project. Also majority of this specification seems to be written for new building construction. The only new equipment is 2 exhaust fans on the roof, the supply air is part of the existing system that is to [be] reused. Please confirm if this specification is needed or not.

Answer: This is not a LEED or CT High Performance Building Project. The specification is for air-quality testing for indoor air pollutant constraints.

#### Item 28:

Question: For the new roof top exhaust fans and curbs. What is the existing roof system: EPDM, PVC, ballasted, etc? Is it under warranty? If so, which manufacturer is it warrantied under?

Answer: Existing roof system is EPDM. Warrantee is 20 years, beginning date 12/05/2013. See attached warrantee Certificate.

#### Item 29:

Question: Detail 5 on A3.01 indicates that corner guards are to be a 2 piece system, wall clip with a snap on cover. Specification 097216 2.06 A indicates the same. However, basis of design Roppe Rubber accessory #19 is a single piece molded guard that glues directly to the wall. Johnsonite is the same. Pawling does offer the retainer and vinyl covers however there are multiple types. Please advise which product is correct, the single molded piece or the 2-piece system. If the 2-piece system is correct, please provide a basis of design with model number.

Answer: Provide 2- piece system with snap on cover. Use the following products as base of design: Pawling: CG-20 corner guards, and CG-11 end wall guards. Similar products by Wallguard: Series 2305 corner guards, and Wallguard Series 2320 end wall guards.

#### Item 30:

Substitution Request: CSI 1.5C Request Form Speedflow Plus M17 & Dyson Airblade V.

Substitution accepted for SpeedFlow Plus M17-ACS-UL (satin stainless steel) manufactured by Saniflow.

#### <u>Item 31:</u>

Specification Section 50.80 00:



Page 6 of 6

Addendum No.: One

Date Of Addendum: January 7, 2019

ADD: 50.80.00.4 EMSL Analytical, Inc. 12/13/2018: Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 method using Polarized Light Microscopy. 12/13/2018.

(attached to this addendum)

#### **Attachments:**

Pre-Bid meeting Sign-in sheet.

SKA-1

SKP-1

SKP-2

**EPDM Roofing System Limited Warranty** 

EMSL Analytical Test Report

All questions must be **emailed** (not **verbal** or by **phone**) to the consulting Architect/Engineer (Mark A. Welch, Email: <u>markw@oakparkarchitects.com</u>) with copies sent to the DAS/CS Project Manager (Ashour Gevargisnia, Email: <u>ashour.gevargisnia@ct.gov</u>) and Construction Manager (Karen DePersia, Email: <u>karend@csgroup-llc.com</u>)

**End of Addendum One** 

Mellanee Walton, Associate Fiscal Administrative Officer

State of Connecticut

Department of Administrative Services, Construction Services

Office of Legal Affairs, Policy, and Procurement

450 Columbus Boulevard, Suite 1302

Hartford, CT 06103



	, Did Fi	lase Meeting Attendance Log
		Page 1 of 25
DAS/CS Project Title:	BATHROOM RENOVATIONSS	UPGRADIE TO ADA
DAS/CS Project No.:	BI-2B-400	Meeting Purpose (insert "X" below):
Date:	12/10/18	Pre-Bid Meeting
Meeting Start Time:	10-00 AM	Post Bid Review Meeting
Meeting Location:	410 CAPITOL BULLING HARPS	Other:
To Insert Information in the To Activate E-Mail Address Γο Add More Pages: Left-c	CS PROJECT MANAGER (delete these Ins Header: Double-Click on the header with theses: After typing the e-mail address, press the click (& hold) your mouse, drag the mouse over	e left mouse button. Insert information.
Name: MIKE	CLIPFORD	Title: Presidut
Company/Department:		E-mail:
Street:	BUFLDENS	Phone: 2
2099	MATE St.	860 706 0359
City/State/Zip	TPORD CT 06/20	FAX: 860 727 /180
- Action to	0, 00,20	300 121 1180
	ellino	Title: Estimator
Company/Department:	J.A. Rosa Construction un	
Street: 17 Town	Live Ad	Phone: 203-879-3495
	H CT 06716	FAX: 1/A
Name:	*	Title
Name: DeinoFlyon		Title: Per
Company/Department: るかいてい Covsで	-41	E-mail: SOLDMAN @ BRATTON CONSTRUCTION, CD
Street:		Phone: 203-234-2353
339 VASH, NOTON	DV6	103-634-2333
No HAVON CT (	16473	FAX: 203-234 .0010
	in the second se	
Name: Nick Baco	Ne .	Title: Estemata
Company/Department:		E-mail:
Mantegno Co	inst	Phone:
otreet: 75 Progress  City/State/Zip	Ln	Phone: 303 597 - 9014 FAX:
City/State/Zip	T 16305	FAX:
WETEL SELY, C	1 06/0)	
lame: ERIC MAT	TEZN	Title: A
company/Department:	TORN CONSTRUCTION, INC	E-mail:
	-130 1.41 / - 100 1 unbilled a / 1. [/]	PCILLE COM THEGO CON CTO CTUL
		Phone:
26M BUSH	MELC HOLLOW RD	Phone: 822 -8457
John Busit		Phone:



DAS/CS Project Title: BAJORO ON RENOVATIONS &	UPURADE APA 2 OF 5
DAS/CS Project No.: BI-2B-400	Meeting Purpose (insert "X" below):
Date: 12/10/18	Pre-Bid Meeting
Meeting Start Time: 10:00 AM	Post Bid Review Meeting
	Transcriber 1
Meeting Location: 410 CAPITAL AVE	Other:
Name: Richard DiLullo	Title: Engineer
Company/Department:  CGL Consulting Engineers LLC  Street:	E-mail: rdilollo @ gglinc. con
Street: 32 Maple Ave	Phone: 860-236-4288
City/State/Zip Windsor, CT 06095	FAX:
Name: 7	Title: President
Company/Department:	E mails
Street: Construction Group	Phone: 203.699.8387
531 CORTLAND CIA	203.699.8587
City/State/Zip CT D6410	FAX:
Name: Kerri Verstace	Title:
Company/Department:	Froperty Mont. Ligison
Street: O Chinal Street:	Phone:
Street: 0 Columbus BdV. Svite 1403 City/State/Zip Ford, CT 01e103	860-713-5746 FAX:
Hartford, C7 04103	
Name: LOANA BARAC	Title: PROJ DESIGNER
Company/Department:	E-mail: Joonab @ opa-arde
Street:	Phone: 860 232 CGG4 K119
City/State/Zip West-flacator 06119	FAX:
Name: Koven DeParsia	Title:
Company/Department:	E-mail:
CSG Street:	Varend 2 csamun-11e.com
street.	Phone: \$40 876-0337
City/State/Zip	FAX:
Name:	Title:
Jason la Fleur	OPM
Company/Department:	E-mail:
treet:	Phone: Jason Lacsgroup-11c.com
City/State/Zip	FAX: 860 818-6712
Tryotatericip	FAA:



- CONSTRUCTION OF THE CONS	TOTAL A		
DAS/CS Project Title: BATH ROOM	1 RENOVATIONS	EUPGRAPE APA 3.F.	
- 61	The state of the s	Meeting Purpose (insert "X" below):	
Date: [2//0/18			
Meeting Start Time: 10.00 AM	1	Pre-Bid Meeting	
	1 11	Post Bid Review Meeting  Other:	
1470 CAPITAL	AVE HARTIER	Other.	
Name: Alcoly Acurla	l	Title: Causel -	
Company/Department:	M/a	E-mail: looke MM 100- 44	
Street: Bearing	7	PHACOLY AAIQ KAI	
City/State/Zip	V	860-129-7973	
west Hurtford CF		860-233-2509	
Name: DATE ITCA COL		Title: FOTIMATAR	
RUEL LEGASPI		E31110101C	
Company/Department: NOSAL BUILD	ERS, INC.	E-mail: ROEL@MASALBUILDERS.	
ST FIELDSTONE	Street: 85 FIELDSTONE COURT		
City/State/Zip CHESHIRE, CT	06410	Phone: 203-439-9320 FAX:	
Name: + 1/		Title:	
Sonathan Sygrave Company/Department:		Estimatar E-mail:	
Sarazin beneral Ce	entractiers	isvarove @ savozn. Com	
Street: 6 Commerce Driv		Phone: 860-456-4576	
City/State/Zip		FAX:	
North Windham, (	CT 0625%	860-456-8957	
Name:	7	Title:	
Company/Department:		E-mail:	
Street:	1	Phone:	
City/State/Zip		FAX:	
Name:	1	Title:	
Company/Department:		E-mail:	
Street:		Phone:	
City/State/Zip	1.		
onty/Gtate/Zip	*	FAX:	
lame:		Title:	
Company/Department:		E-mail:	
Street:		Phone:	
City/State/Zip		FAX:	
		FAA	



DAS/CS Project Title:	Page 2-of 2		
DAS/CS Project No.:	Meeting Purpose (insert "X" below):		
Date:	Pre-Bid Meeting		
Meeting Start Time:	Post Bid Review Meeting		
Meeting Location:	Other:		
	, , ,		
Name: MARIC WECCH	Title: PRINCIPAL/MEMBER		
Company/Department: ARCHITECTS, LCC	E-mail: MONKWO OAKPARK ARICHTOOD.		
Street: 312 PARIK ROAD	Phone: 860-232-6664 X112		
WEST WARTFORM, CT 06107	FAX: 860-237-6121		
Name:			
CHRIS CYKLEY	Title: PRESIDENT		
Company/Department: SOLUTIONS GROUP.	E-mail:		
Street:	Phone:		
POBox 211860	203·206·1281		
W. HARTKORD, CT	FAA:		
Name:			
*	Title:		
Company/Department:	E-mail:		
treet:	Phone:		
ity/State/Zip	FAX:		
· · · · · · · · · · · · · · · · · · ·			
ame:	Title:		
ompany/Department:			
	E-mail:		
reet:	Phone:		
lty/State/Zip	FAX:		
ame:	Title:		
ompany/Department:	E-mail:		
reet:	Phone:		
	Ç.		
y/State/Zip	FAX:		
me:	Title:		
mpany/Department:	E-mail:		
eet:	Phone:		
71			

## Pre-Bid Meeting Sign-In

50F5 AG

CT Project: BI-2B-400

Restroom Renovations and ADA compliance upgrades

12/10/2018

CONTRACTOR NAME BIDDER CONTACT	EMAIL	TELEPHONE
Richard Ditullo	rdilollo @ 99 line com	860-736-4788
/ /		
Frank Mastriano	estimating a bolimer construction con	203-335-4204
Holzner Construction		
596 John Street		
Bridgepost, IGT QGOY	1 0 100	
JON STOCKTORY	estimating a proneir builder	sction
Money Byllders	0 1111	860-550-1137
336 Stamm Rd,		860-330-112 1
Mewington CT, 06/11		
Marco Caminto	marcoc @ pioneer builders ct. Com	860-818-8114
Pioneer, Builders		12 200
336 Stamm Rd		
Newington, CT 06/11		
Score Construction	CROSSIGNOL & SCOPECONS TRUCTION, COM	860. 832. 8335
CHRIS ROSS TONOL		
416 SLATER RD.		
NEW BRITAIN, CT 06053		
JON HOAMS	JONCANNULLECAM	860-644-2427
Orlando Annuli, 4 Suns		
147 Have Road		
Manchester, CT D6042		
Tonathan Rule	jarohan Qadorovan com	4606420700x35
> Dorovan Associales		
27 Rade 32 North Franklin Ct		
PONNUD BYAGG	rghay EMBICT, ZOM	860.57W 0555
MILLENKIUM BULLDES INC	- Test English (200 III	
50 MYROD ROKD		
ROCKY HILL CX 06089		
LIGHTRY PERREN	RIGHARD, PERROL @ G.GOV	060.713.5717
DAZ BAZALATIES	Maria Constant Con	an. 112.211
DAS FACILITIES MAMAGEMENT		
VIII - 1 / OIV WITT		



#### RED SHIELD ROOFING SYSTEM LIMITED WARRANTY

Warranty No: RO064936

FBPCO # AE5642

Square Footage:

Building Owner: STATE OF CT-DCS

Building Identification: 410-470 CAPITOL AVENUE-BI-2B-280

Building Address: 410-470 CAPITOL AVE., HARTFORD, CT, CT, 06106 Warranty Period Of: TWENTY (20) Years, Beginning On: 12/05/13

Roofing Contractor: SILKTOWN ROOFING INC (04832)

For the warranty period indicated above, Firestone Building Products Company, LLC ("Firestone"), an Indiana limited liability company, warrants to the Building Owner ("Owner") named above that Firestone will, subject to the Terms, Conditions and Limitations set forth below, repair any leak in the Firestone Roofing System ("System").

#### TERMS, CONDITIONS AND LIMITATIONS

Products Covered. The System shall mean only the Firestone brand roofing membranes, Firestone brand roofing insulations, Firestone brand roofing 1. metal, and other Firestone brand roofing accessories when installed in accordance with Firestone technical specifications by a Firestone-licensed applicator

Notice. In the event any leak should occur in the System, the Owner must give notice in writing or by telephone to Firestone within thirty (30) days of any occurrence of a leak. Written notice may be sent to Firestone at the street address or fax number shown on the reverse side of this Limited Warranty. Evidence of this notice shall be the receipt by Owner of a Firestone Leak Notification Acknowledgement. By so notifying Firestone, the Owner authorizes Firestone or its designee to investigate the cause of the leak.

Investigation. If upon investigation, Firestone determines that the leak is not excluded under the Terms, Conditions and Limitations set forth in this Red Shield Roofing System Limited Warranty (the "Limited Warranty"), the Owner's sole and exclusive remedy and Firestone's total liability shall be limited to the repair of the leak. Should the investigation reveal that the leak is excluded under the Terms, Conditions and Limitations, the Owner shall be responsible for payment of the investigation costs. Failure by Owner to pay for these costs shall render this Limited Warranty null and void. Firestone will advise the Owner of the type and/or extent of repairs required to be made at the Owner's expense that will permit this Limited Warranty to remain in effect for the unexpired portion of its term. Fallure by the Owner to properly make these repairs in a reasonable manner using a Firestone-licensed applicator and within 60 days shall render this Limited Warranty null and void.

No Dollar Limit (NDL). There is no dollar limit placed on warranted leak repairs to the extent such repairs are covered by this Limited Warranty

Disputes. Any dispute, controversy or claim between the Owner and Firestone concerning this Limited Warranty shall be settled by mediation. In the event that the Owner and Firestone do not resolve the dispute, controversy or claim in mediation, the Owner and Firestone agree that neither party will commence or prosecute any suit, proceeding, or claim other than in the courts of Hamilton County in the state of Indiana or the United States District Court, Southern District of Indiana, Indianapolis Division. Each party irrevocably consents to the jurisdiction and venue of the above-identified courts.

Payment Required. Firestone shall have no obligation under this Limited Warranty unless and until Firestone and the licensed applicator have been

paid in full for all materials, supplies, services, approved written change orders, warranty costs and other costs which are included in, or incidental to, the System. In the event that repairs not covered by this Limited Warranty are necessary in the future, Firestone reserves the right to suspend this Limited Warranty until such repairs have been completed and the licensed applicator and/or Firestone has been paid in full for such repairs.

Exclusions. Firestone shall have no obligation under this Limited Warranty, or any other liability, now or in the future if a leak or damage is caused by:

(a) Natural forces, disasters, or acts of God including, but not limited to, fires, hurricanes, tomadoes, hall, wind-blown debris, lightning, earthquakes, volcanic activity, atomic radiation, insects or animals; (b) Winds of peak gust speed at or in excess of 55MPH calculated at ten(10) meters above ground using available meteorological data; (c) Act(s), conduct or omission(s) by any person, or act(s) of war, terrorism or vandalism, which damage the System or which impair the System's ability to resist leaks; (d) Failure by the Owner to use reasonable care in maintaining the System, said maintenance to include, but not be limited to, those items listed on the reverse side of this Limited Warranty entitled "Building Envelope Care and Maintenance Guide"; include, but not be limited to, those items listed on the reverse side of this Limited Warranty entitled "Building Envelope Care and Maintenance Guide";
(e) Deterioration or failure of building components, including, but not limited to; the roof substrate, walls, mortar, HVAC units, skylights etc.; (f)
Construction generated moisture, condensation or infiltration of moisture in, from; through, or around the walls, copings, rooftop hardware or equipment, skylights, building structure or underlying or surrounding materials; (g) Acid, oil, harmful chemicals, or the reaction between them; (h) Alterations or repairs to the System that are not completed in accordance with Firestone's published specifications, not completed by an approved contractor, and/or not completed with proper notice to Firestone; (i) The design of the roofing system: Firestone does not undertake any analysis of the architecture or engineering required to evaluate what type of System is appropriate for a building and makes no warranty express or implied as to the suitability of its Products for any particular structure; such a determination is the responsibility of the architect, engineer or design professional; (j) Improper selection of materials for the roof assembly or the failure to accurately calculate wind upilit and/or roof loads; (k) Deterioration to metal roofing materials and accessories caused by marries salt water; atmosphere, or by regular spray of either salt or fresh water; or. (l) Change in building use or numbers.

materials for the roof assembly of the failure to accurately calculate wind uplift and/or roof loads; (k) Deterioration to metal roofing materials and accessories caused by marine salt water; atmosphere, or by regular spray of either salt or fresh water; or, (I) Change in building use or purpose.

Transfer. This Limited Warranty shall be transferable subject to Owner's payment of the current transfer fee set by Firestone.

Term. The term of this Limited Warranty shall be for the period set forth above and such term shall not be extended under any circumstances.

Roof Access. During the term of this Limited Warranty, Firestone's designated representative or employees shall have free access to the roof during regular business hours. In the event that roof access is limited due to security or other restrictions, Owner shall reimburse Firestone for all reasonable cost incurred during inspection and/or repair of the System that are due to delays associated with said restrictions. Owner shall be responsible for the damage caused by, removal and replacement of any overburdens, superstrata or overlays, either permanent or temporary, excluding accepted stone ballast or pavers, as necessary to expose the system for inspection and/or repair.

Water Firestone's failure for endorre any of the terms or conditions stated to the terms of the provided of the terms of the provided of the terms of the permanent or temporary.

Walver. Firestone's fallure to enforce any of the terms or conditions stated herein shall not be construed as a waiver of such provision or of any other terms and conditions of this Limited Warranty.

Governing Law. This Limited Warranty shall be governed by and construed in accordance with the laws of the State of Indiana without regard to that State's rules on conflict of laws

Severability. If any portion of this Limited Warranty is held by a court of competent jurisdiction to be invalid; void or unenforceable, the remaining provisions shall nevertheless continue in full force.

FIRESTONE DOES NOT WARRANT PRODUCTS INCORPORATED OR UTILIZED IN THIS INSTALLATION THAT WERE NOT FURNISHED BY FIRESTONE. SPECIFICALLY DISCLAIMS LIABILITY UNDER ANY THEORY OF LAW ARISING OUT OF THE INSTALLATION OF, PERFORMANCE OF, OR DAMAGES SUSTAINED BY OR CAUSED BY, PRODUCTS NOT FURNISHED BY FIRESTONE.

THIS LIMITED WARRANTY SUPERSEDES AND IS IN LIEU OF ALL OTHER WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE, AND FIRESTONE HEREBY DISCLAIMS ALL SUCH WARRANTIES. THIS LIMITED WARRANTY SHALL BE THE OWNER'S SOLE AND EXCLUSIVE REMEDY AGAINST FIRESTONE, AND FIRESTONE SHALL NOT BE LIABLE FOR ANY CONSEQUENTIAL, SPECIAL, INCIDENTAL OR OTHER DAMAGES INCLUDING, BUT NOT LIMITED TO, LOSS OF PROFITS OR DAMAGES TO THE BUILDING OR ITS CONTENTS OR THE ROOF DECK. THIS LIMITED WARRANTY CANNOT BE AMENDED, ALTERED OR MODIFIED IN ANY WAY EXCEPT IN WRITING SIGNED BY AN AUTHORIZED OFFICER OF FIRESTONE. NO OTHER PERSON HAS ANY AUTHORITY TO BIND FIRESTONE WITH ANY REPRESENTATION OR WARRANTY WHETHER ORAL OR WRITTEN.

FIRESTONE BUILDING PRODUCTS COMPANY, LLC

By: Phil LaDuk

Authorized

Director, Quality Assurance



Attention: Ed Fennell

#### **EMSL** Analytical, Inc.

29 North Plains Highway, Unit # 4 Wallingford, CT 06492

Tel/Fax: (203) 284-5948 / (203) 284-5978 http://www.EMSL.com / wallingfordlab@emsl.com

ATC Group Services LLC

290 Roberts Street

Suite 301

EMSL Order: 241806451 Customer ID: ATCE54

**Customer PO:** 18-10133-0001

Project ID:

Phone: (860) 282-9924

Fax: (860) 282-9826

Received Date: 12/13/2018 12:10 PM

**Analysis Date:** 12/13/2018 **Collected Date:** 12/13/2018

East Hartford, CT 06108 **Project:** 2257318040/ 410 CAPITOL AVE HARTFORD, CT

#### Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

Sample		Non-Asbestos			<u>Asbestos</u>
	Description	Appearance	% Fibrous	% Non-Fibrous	% Type
121218-1A 241806451-0001	Second floor right men's - gypsum board ceiling	Gray Non-Fibrous Homogeneous	5% Cellulose	95% Non-fibrous (Other)	None Detected
121218-1B 241806451-0002	Second floor right women's - gypsum board ceiling	Gray Non-Fibrous Homogeneous	4% Cellulose	96% Non-fibrous (Other)	None Detected
121218-1C 241806451-0003	Third floor left men's - gypsum board ceiling	Gray Non-Fibrous Homogeneous	4% Cellulose 5% Glass	91% Non-fibrous (Other)	None Detected
121218-1D 241806451-0004	Third floor left women's - gypsum board ceiling	Gray Non-Fibrous Homogeneous	5% Cellulose 2% Glass	93% Non-fibrous (Other)	None Detected
121218-2A 241806451-0005	Second floor right men's - joint compound ceiling	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
121218-2B 241806451-0006	Second floor right women's - joint compound ceiling	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
121218-2C 241806451-0007	Third floor left men's - joint compound ceiling	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
121218-2D 241806451-0008	Third floor left women's - joint compound ceiling	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected

Analyst(s)

Almedina Hodzic (6) Lauren Butkus (2) Umedina Hodzic

Almedina Hodzic, Asbestos Laboratory Manager or Other Approved Signatory

EMSL maintains liability limited to cost of analysis. The above analyses were performed in general compliance with Appendix E to Subpart E of 40 CFR (previously EPA 600/M4-82-020 "Interim Method"), but augmented with procedures outlined in the 1993 ("final") version of the method. This report relates only to the samples reported above, and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. All samples received in acceptable condition unless otherwise noted. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. EMSL recommends gravimetric reduction for all non-friable organically bound materials prior to analysis. Estimation of uncertainty is available on request.

Samples analyzed by EMSL Analytical, Inc. Wallingford, CT NVLAP Lab Code 200700-0,

Initial report from: 12/13/2018 16:15:46

OakPark Architects<sup>LLC</sup>

\**∆** | ∆



DECORATIVE PATTERN PRINTED ON TRANSPARENT ADHESIVE PVC FILM, MOUNTED TO GLASS ON EXTERIOR SIDE. FILE PROVIDED BY

ARCHITECT.

1'-4/2"

Ō

EQ

DF GUARD PANEL


3"

WALL

PANEL

SS U-SHAPE BRACKETS, ON CONTINUOUS SS BASEPLATE, HDI SYSTEMS OPTIK POD RECTANGULAR OR SIMILAR. FLAT HEAD ALLEN DRIVE SS FASTENERS AT 16" O.C. PROVIDE SOLID, SECURED BLOCKING ATTACHED TO STUDS AT FASTENER LOCATIONS. NEOPRENE GASKETS BETWEEN GLASS AND BRACKETS AND BETWEEN BASEPLATE AND FLOOR TILE. ISOLATE MATERIALS TO PREVENT

GALVANIC REACTION.



SKA-1

MEN'S ROOM ELEVATION SCALE: 1/4"= 1'-0"

SCALE: 1/2"= 1'-0' NEW DOOR AND FRAME

3/4" THICK STRUCTURAL GLASS, LAMINATED,

WITH POLISHED EDGES 1/2" RADIUS CORNERS

4" X 1/2" SS BAR

FASTENED TO WALL AND FLOOR

TEMPERED, CLASS 1 CLEAR GLASS

**DOOR SCHEDULE** DOOR FRAME ROOM NAME & SILL THRESH HDW SET# NUMBER TYPE FINISH LABEL LABEL JAMB HEAD DR # SIZE MAT MAT TYPE FINISH REMARKS ALL FLOORS PATCH FRAME AT REMOVED ME-1, 2, 3, 4 1.1-4.1 3'-@"×7'-@" \* HM PT. 9 HMEXIST PT. 10 CT Д 4 AUTOMATIC DOOR CLOSER REPAIR/PATCH FRAME MW-1, 2, 3, 4 3'-@"XT'-@" \* HM Д PT. 9 EXIST PT. 10 CT REPAIR/PATCH FRAME JE-1, 2, 3, 4 1.3-4.3 3'-Ø"XT'-Ø" \* HMPT. 9 EXIST PT. 10 CT 2 Д REPAIR/PATCH FRAME 2 JW-1, 2, 3, 4 1.4-4.4 3'-@"XT'-@" \* HMД PT. 9 EXIST PT. 10 CT REPAIR/PATCH FRAME 2.5-4.5 3'-@"XT'-@" \* PT. 9 PT. 10 CT WE-2, 3, 4 HMHMEXIST 4 Д \_ REPAIR/PATCH FRAME WW-1, 2, 3, 4 16-46 3'-0"X7'-0" \* HMД PT. 9 EXIST PT. 10 CT BABY-1 1.7 3'-@"XT'-@" \* HMPT. 9 HMPT. 10 J-1 H-1 CT Д HM-1 STOR-2, 3, 4 2.7-4.7 3'-@"XT'-@" \* HMPT. 9 PT. 10 J-1 H-1 3 Д HM-1 CT HM-1 PT. 10 J-1 LACT-1, 2, 3, 4 1.8-4.8 3'-0"XT'-0" \* WOOD A' CLEAR HMH-2 CT PROTECT FLOOR QUARRY TILE AT JE-2, 3, 4 3'-0"X7'-0" PT. 9 HM-1 PT. 10 J-1 H-2 CT 2.9-4.9 CORRIDOR DURING WALL DEMOLITION. \*REPLACE CONT. HINGE W/ 3 (HEAVY WEIGHT) T4A3386 4-1/2" x 4-1/2" U932D MK. HM-1 J-1 WE-1 1.5 3'-Ø"XT'-Ø" \* HMPT. 9 HMPT. 10 H-2 CT

CORR E

EXIST

**CUT WALL FOR** 

REFER ALSO TO

NOTE 10/A1.00.

NEW 3' x 7' DOOR.

4'-3"

SKA-1

= = =

Φ

JAN.

EXIST

SCALE: 1/4"= 1'-0"

CERAMIC TIL

P TEL

CERAMIC TIL

SPRINKLER

JE-2

JAN

 $\bigcirc$ 

PARTIAL DEMO PLAN

(2ND, 3RD, 4TH FLOOR)

EXISTING

02.9 EXISTING

E CHARRY TILE

02.3

CERAMIC TILE ENDIFFICE ADARRY TILE

CORR

CE-2


QUARRY TILE

MATCH EXISTING HARDWARE TYPE AND FINISHES. VERIFY HM FRAME DIMENSIONS IN FIELD. NEW DOORS AND FRAMES TO MATCH EXISTING. EXISTING DOORS TO BE REFINISHED: HM DOORS: PT 9. HM FRAMES: PT 10. WOOD DOORS: CLEAN ONLY.



DOOR SCHEDULE

PARTIAL FLOOR PLAN (2ND, 3RD, 4TH FLOOR) SCALE: 1/4"= 1'-0" SKA-1



## TYPICAL SECOND, THIRD AND FOURTH FLOOR PLUMBING PARTIAL WATER PIPING PLAN

SCALE: 1/4"=1'-0"

**GENERAL NOTE:** 

LOCATE CW TO  $\overline{\text{DF}-1}$  ABOVE RESTROOM CEILING.

QGL CONSULTING ENGINEERS, LLC


32 Maple Ave Windsor, CT. 06095 TEL (860) 236-4288 ADDENDUM 1
BATHROOM RENOVATIONS
AND ADA UPGRADES
410 CAPITOL AVENUE, HARTFORD, CT

Project No. BI-2B-400

JANUARY 4, 2019

SKP-1

DRAWING REF: P 2.01



### FIRST FLOOR PARTIAL DRAIN AND VENT PLAN

SCALE: 1/4"=1'-0"

#### **GENERAL NOTES:**

- 1. INSULATE 3" DRAIN PIPE IN LOWER LEVEL CEILING WITH 1.5" FIBERGLASS PIPE INSULATION
- 2. HEAT TRACE 3" DRAIN PIPE IN LOWER LEVEL CEILING WITH 5 WATT/FOOT HEAT TRACE CABLE.
  HEAT TRACE TO BE EQUAL TO RAYCHEM 120 VOLT, BTV, CABLE SHALL BE PROVIDED WITH CONNECTION
  AND TERMINATION KIT AND AMBIENT SENSING THERMOSTAT. THERMOSTAT SHALL ENABLE CABLE WHEN
  AMBIENT SPACE IS BELOW 35°F
- 3. HEAT TRACE SHALL BE AS MANUFACTURED BY RAYCHEM, CHROMALOX OR EMERSON

QGL CONSULTING ENGINEERS, LLC

32 Maple Ave Windsor, CT. 06095 TEL (860) 236-4288 ADDENDUM 1
BATHROOM RENOVATIONS
AND ADA UPGRADES

410 CAPITOL AVENUE, HARTFORD, CT Project No. BI-2B-400 JANUARY 4, 2019

SKP-2

DRAWING REF: P 2.02