



Town of Groton
Solicitation Information
May 2018

ADDENDUM 1

RFQ 18-46 Sluice Gate Rehabilitation Rebid

A pre-bid meeting was held on May 22, 2018 at 10:00 a.m.; pre-bid sign in sheet to follow.

Questions/Clarifications

1. Do we have to include the town of Groton building permit fees in our bid?

Groton building permit fees are waived.

2. To install the coating system as specified in section 4 of the specification on the sluice gates. The sluice gate needs to dry and clean.

A. Who is responsible stop the flow thru the existing sluice gate and to bypass the flow around the gate as the coating is being applied and when it's drying?

Contractor is responsible for all activities associated with the coating system. Pump stations must remain in operation throughout project. Contractor may erect protective or watertight enclosure or similar solution around materials to be coated during coating and drying. Contractor may offer alternative solutions post contract award. Owner may be able to temporarily isolate pump station to stop flow to allow activities in the dry.

B. Is the contractor responsible for removing the water from the channel and stopping the flow from the channel during the inspection and application of the coating on the existing sluice gate? See answer above.

C. Is the contractor responsible to furnish and install a new coating on the existing two 90 degree operator gear boxes and shafting? Valve shafts, gear boxes and floorstand are not being coated.

D. Is the contractor responsible for applying a new coating system to the existing floorstand operator located on the second floor control room? Valve shafts, gear boxes and floorstand are not being coated.

