02.02 - DETOUR
INDEX OF DRAWINGS

DRAWING NUMBER	DRAWING TITLE	DRAWING NUMBER	
DET - 01	INDEX OF DRAWINGS		
DET - 02	SITE 1 - DETOUR		

DESIGNED BY:

LOCHNER
H.W. LOCHNER, INC
55 Hartland Street, Suite 401
East Hartford, CT 06108

Richard Arthur Bray
2017.12.29
12:46:09-05'00'

VOLUME 2 SUBSETS

SUBSET NO.	SUBSET TITLE	SUBSET SHEET COUNT
01	TRAFFIC	9
02	DETOUR	2
03	LANDSCAPE DESIGN	5
04	ENVIRONMENTAL	5
05	MISCELLANEOUS DETAIL SHEETS	6

REV.	DATE	REVISION DESCRIPTION	SHEET NO.
-	-	-	-
-	-	-	-
-	-	-	-
-	-	-	-
-	-	-	-
-	-	-	-

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

PLOTTED: 12/29/2017

DESIGNER/DRAFTER: BC/CR
CHECKED BY: RB
NOT TO SCALE

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

FILENAME: ...\HW..MSH..170..3192..DETOUR..INDEX.dgn

LOCHNER
H.W. LOCHNER, INC
55 Hartland St
East Hartford, CT 06108

APPROVED BY: R. BRAY DATE: 12/06/17

PROJECT TITLE:
REHABILITATION OF FOUR RAILROAD BRIDGES ON THE HOUSATONIC LINE

TOWN: **CANAAN, KENT, AND NEW MILFORD**

DRAWING TITLE: **DETOUR INDEX OF DRAWINGS**

PROJECT NO. **170-3192**
DRAWING NO. **DET - 01**
SHEET NO. **02.02.01**

NOTES:

1. ALL DETOUR SIGNS SHALL BE MOUNTED ON EXISTING POLES OR POSTS, ON PORTABLE SIGN SUPPORTS OR INSTALLED IN GRASS AREAS. SIGNS SHALL BE POST MOUNTED WHERE FEASIBLE. ALL POST MOUNTED SIGNS SHALL BE MOUNTED A MINIMUM 7 FT ABOVE THE ROADWAY.
2. THE EXACT LOCATION OF SIGNS IS TO BE VERIFIED BY THE ENGINEER.
3. DETOUR SIGNS ARE TO BE PAID UNDER ITEM NO. 1220001A - CONSTRUCTION SIGNS - TYPE III REFLECTIVE SHEETING.
4. THE CONTRACTOR MAY BE REQUIRED TO SHIFT, COVER OR TEMPORARILY RELOCATE EXISTING SIGNS TO ACCOMMODATE TEMPORARY DETOUR SIGNING. THIS WORK SHALL BE INCLUDED AND PAID UNDER ITEM NO. 0971001A MAINTENANCE AND PROTECTION OF TRAFFIC.
5. ALL DETOUR SIGNS SHALL BE COVERED OR REMOVED WHEN THE DETOUR IS NOT IN EFFECT.

DETOUR SIGN LEGEND:

A	STOP	INSTALL 31-0553
B	ROAD CLOSED	INSTALL 80-9080
C	RIVER ROAD CLOSED TO THRU TRAFFIC / DETOUR ↑	INSTALL 80-9928 80-9710
D	RIVER ROAD CLOSED TO THRU TRAFFIC / DETOUR →	INSTALL 80-9928 80-9710
E	RIVER ROAD CLOSED TO THRU TRAFFIC / DETOUR ←	INSTALL 80-9928 80-9710
F	RIVER ROAD CLOSED AHEAD LOCAL TRAFFIC ONLY	INSTALL 80-9928
G	RIVER ROAD CLOSED 1000 FT AHEAD	INSTALL 80-9928
H	RIVER ROAD / DETOUR →	INSTALL 80-9916 80-9710
I	RIVER ROAD / DETOUR ←	INSTALL 80-9916 80-9710
J	RIVER ROAD / DETOUR ↑	INSTALL 80-9916 80-9710
K	RIVER ROAD / END DETOUR	INSTALL 80-9916 80-9708
L	RIVER ROAD SOUTHBOUND CLOSED TO THRU TRAFFIC / DETOUR ↑	INSTALL 80-9928 80-9710
M	RIVER ROAD SOUTHBOUND CLOSED TO THRU TRAFFIC / DETOUR →	INSTALL 80-9928 80-9710
N	RIVER ROAD SOUTHBOUND CLOSED TO THRU TRAFFIC / DETOUR ←	INSTALL 80-9928 80-9710

SYMBOL LEGEND:

CONSTRUCTION BARRICADE TYPE III

SIGN LOCATION



REV.	DATE	REVISION DESCRIPTION	SHEET NO.
-	-	-	-
-	-	-	-
-	-	-	-
-	-	-	-
-	-	-	-
-	-	-	-

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

PLOTTED: 12/29/2017

DESIGNER/DRAFTER: BC/CR

CHECKED BY: RB

NOT TO SCALE

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

FILENAME: ...\HWY_MSH_170_3192_MP_15.00_DET-02.DGN

LOCHNER
H.W. LOCHNER, INC
55 Hartland St
East Hartford, CT 06108

APPROVED BY: R. BRAY DATE: 12/06/17

STATE OF CONNECTICUT RICHARD A. BRAY LICENSED PROFESSIONAL ENGINEER

PROJECT TITLE:
BRIDGE NO. 09200R HOUSATONIC RAILROAD MP 15.00 OVER UNNAMED BROOK

TOWN: **NEW MILFORD**

DRAWING TITLE: **SITE 1 - DETOUR**

PROJECT NO. **170-3192**

DRAWING NO. **DET-02**

SHEET NO. **02.02.02**