03 - TRAFFIC

INDEX OF DRAWINGS

DRAWING NUMBER	DRAWING TITLE	DRAWING NUMBER	DRAWING TITLE
TR-01	TRAFFIC - INDEX OF DRAWINGS		
TR-02	GENERAL SIGNING NOTES		
TR-03	INDEX OF PLANS		
TR-04 - TR-15	SIGNING - MAINLINE		
TR-16 - TR-27	SIGNING - RAMPS		
TR-28 - TR-38	CROSS SECTIONS		
TR-GS-01 - TR-GS-03	TRAFFIC ENGINEERING GUIDE SHEETS (X, Y, Z)		

THE DESIGN APPEARS TO CONFORM TO APPLICABLE CRITERIA. APPROVAL IS NOT TO BE CONSTRUED TO MEAN THAT ALL ASPECTS OF THE DESIGN HAVE BEEN PERSONALLY CHECKED BY THE UNDERSIGNED.

Mark F. Makuch, P.E.
2018.07.25
14:29:34-04'00'

TRANSPORTATION PRINCIPAL ENGINEER

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/2/2018

DESIGNER/DRAFTER: DR

CHECKED BY: MAC

SCALE AS NOTED

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_SPM_173_441_TR-01.dgn

SIGNATURE/ BLOCK:

OFFICE OF ENGINEERING

APPROVED BY:

PROJECT TITLE:

REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8

TOWN: BRIDGEPORT, TRUMBULL, SHELTON

DRAWING TITLE: TRAFFIC INDEX OF DRAWINGS

PROJECT NO. 173-441

DRAWING NO. TR-01

SHEET NO. 03.01

GENERAL SIGNING NOTES

1. THE RELATIVE LOCATION OF EACH SIGN ON OVERHEAD STRUCTURES IS SHOWN READING ALPHABETICALLY FROM LEFT TO RIGHT AS VIEWED BY TRAFFIC.

2. REFER TO EACH INDIVIDUAL SIGNING PLAN FOR "SIGNING INSTALLATION NOTES" WHICH ARE SPECIFIC TO EACH SIGN WITHIN THE PROJECT.

3. ALL SIGN FOUNDATIONS SHALL BE FIELD STAKED AND THE LOCATIONS APPROVED BY AN ENGINEER FROM THE DIVISION OF TRAFFIC ENGINEERING OR DESIGNEE A MINIMUM OF 7 DAYS PRIOR TO INSTALLATION.

4. ALL EXTRUDED ALUMINUM SIGNS, SIDE MOUNTED SUPPORTS, AND FOUNDATIONS LOCATED WITHIN THE SIGNING LIMITS ARE TO BE REMOVED UNLESS OTHERWISE NOTED. ALL OVERHEAD AND BRIDGE MOUNTED SUPPORTS ARE TO BE REMOVED UNLESS OTHERWISE NOTED.

5. ALL PROPOSED EXTRUDED ALUMINUM SIGNS ARE TO BE NEW SIGNS ON NEW SUPPORT(S) AND FOUNDATION(S) UNLESS OTHERWISE NOTED.

6. ALL SHEET ALUMINUM SIGNS LOCATED WITHIN THE SIGNING LIMITS ON ROUTE 8 ARE TO BE REMOVED UNLESS OTHERWISE NOTED. ALL SHEET ALUMINUM SIGNS SHOWN ON ALL OTHER ROADWAYS ARE TO BE REMOVED UNLESS OTHERWISE NOTED OR AS DIRECTED BY THE ENGINEER. ALL SIGNS NOT SHOWN ON THESE ROADWAYS ARE TO REMAIN UNLESS OTHERWISE NOTED BY THE ENGINEER.

7. THE REMOVAL OF EXISTING SIDE-MOUNTED EXTRUDED ALUMINUM SIGNS, SIGN SUPPORTS, FOUNDATIONS AND SHEET ALUMINUM SIGNS AND POSTS, AS WELL AS BRIDGE MOUNTED SHEET ALUMINUM SIGNS, WILL BE PAID FOR UNDER ITEM NO. 1206013: REMOVAL OF EXISTING SIGNS.

8. CERTAIN OVERHEAD SIGN SUPPORTS HAVE BEEN IDENTIFIED AS CONTAINING HAZARDOUS LEVELS OF LEAD. REFER TO THE SPECIAL PROVISIONS FOR ITEM NOS. 0020903A: LEAD COMPLIANCE FOR MISCELLANEOUS EXTERIOR TASKS FOR THE REQUIRED PROCEDURES FOR REMOVING AND HANDLING HAZARDOUS MATERIALS, AS WELL AS A LISTING OF THE SPECIFIC CONTAMINATION LOCATIONS.

9. "CALL BEFORE YOU DIG" (C.B.Y.D.), CT DOT HIGHWAY OPERATIONS, AND CT DOT ELECTRICAL SHALL BE CONTACTED PRIOR TO THE INSTALLATION OF ANY NEW SIGNS.

10. THE CONTRACTOR SHALL CLEAR, GRUB, AND TRIM AS DIRECTED BY THE ENGINEER TO PROVIDE ADEQUATE SIGHTLINE TO THE SIGNS. THIS WORK SHALL BE PAID FOR UNDER ITEM NO. 0952001A: SELECTIVE CLEARING AND THINNING AND ITEM NO. 0201001: CLEARING AND GRUBBING.

11. INCIDENT MANAGEMENT SYSTEM (IMS) EQUIPMENT IS NOT INCLUDED IN THE CONTRACT UNLESS SPECIFIED OTHERWISE.

12. N.I.C. (XXX-XXXX): DENOTES NOT IN CONTRACT AND PROJECT NUMBER INCLUDED UNDER (IF APPLICABLE).

13. SHEET ALUMINUM AND EXTRUDED ALUMINUM LOGO SERVICE SIGNS ARE TO BE NOT IN CONTRACT (N.I.C.) UNLESS OTHERWISE SHOWN ON THE PLANS.

14. WHEN A SIGN IS TO BE REPLACED, THE EXISTING SIGN SHOULD NOT BE REMOVED UNTIL THE REPLACEMENT SIGN IS INSTALLED.

15. ALL PRIVATE AND CITY/TOWN OWNED SIGNS ARE TO REMAIN UNLESS OTHERWISE NOTED.

16. SIGNS SHALL NOT BE PLACED LESS THAN 10 FEET FROM UTILITY POLES.

17. INSTALL NEW MILE MARKER SIGNS (SIGN NO. 51-5307) ON ROUTE 8 NB & SB AT ONE MILE INTERVALS WITHIN THE PROJECT LIMITS. INSTALL NEW MILE MARKER SIGNS (SIGN NOS. 51-5104 & 51-5302) ON ROUTE 8 NB & SB AT 0.20 MILE INTERVALS WITHIN THE PROJECT LIMITS. EACH LOCATION SHALL BE MEASURED AND VERIFIED BY THE CONTRACTOR PRIOR TO INSTALLATION. NOTE THAT THESE SIGNS ARE NOT SHOWN ON THE PLANS. THIS WORK WILL BE PAID FOR UNDER ITEM NO. 1208931: SIGN FACE - SHEET ALUMINUM (TYPE IX RETROREFLECTIVE SHEETING).

18. DELINEATORS SHALL BE INSTALLED WITHIN THE PROJECT LIMITS ON THE ROUTE 8 MAINLINE, RAMPS, AND TURNINGS ROADWAYS. EXISTING WHITE AND YELLOW DELINEATORS ARE TO BE REMOVED IN AREAS WHERE NEW ONES ARE INSTALLED. INSTALL DELINEATORS IN ACCORDANCE WITH TRAFFIC ENGINEERING STANDARD DRAWINGS TR-1205-01: DELINEATION, DELINEATORS, AND OBJECT MARKER DETAILS.

19. ALL OBJECT MARKERS TO REMAIN UNLESS OTHERWISE NOTED.

20. ALL CHEVRON SIGN (SIGN NO. 41-4211 & 41-4260) POSTS ARE TO HAVE RETROREFLECTIVE STRIP(SIGN NO. 41-5008) INSTALLED EXCEPT FOR THOSE INSTALLED ON BARRIER. REFLECTORS ARE TO BE PAID FOR UNDER ITEM NO. 1208931: SIGN FACE - SHEET ALUMINUM (TYPE IX RETROREFLECTIVE SHEETING). ALL NEW CHEVRON SIGNS ARE TO BE SPACED 80 FEET APART UNLESS OTHERWISE NOTED.

21. ALL RAMP SIGNS ARE TO HAVE A MINIMUM SPACING OF 100 FEET BETWEEN SIGNS WHERE FEASIBLE.

22. THE REMOVAL OF EXISTING OVERHEAD SIGNS WILL BE PAID FOR UNDER ITEM 1206011: REMOVAL OF EXISTING OVERHEAD SIGNING.

OVERHEAD SIGN CROSS-SECTION NOTES

1. ALL INFORMATION ON THE OVERHEAD SIGN CROSS-SECTION SHEETS ARE APPROXIMATE.

2. THE CONTRACTOR SHALL VERIFY ALL INFORMATION PROVIDED ON THE OVERHEAD SIGN CROSS-SECTION SHEETS.

3. THE OVERHEAD SIGN CROSS-SECTION SHEETS ARE USED TO SHOW THE APPROXIMATE LOCATIONS OF THE SIGN SUPPORT FOUNDATIONS AND SIGNS RELATIVE TO THE ROADWAY LANES AND CROSS-SLOPE.

4. ALL OVERHEAD SIGNS SHALL BE INSTALLED WITH A MINIMUM VERTICAL CLEARANCE OF 18 FEET AS MEASURED FROM THE BOTTOM OF THE SIGN TO THE HIGH POINT OF THE ROADWAY EXCLUDING BRIDGE MOUNTED OVERHEAD SIGNS. BRIDGE MOUNTED SIGNS SHALL BE INSTALLED SUCH THAT THE BOTTOM OF THE SIGN EXCEEDS THE VERTICAL CLEARANCE OF THE BRIDGE GIRDERS BY A MINIMUM OF 1 FOOT.

5. ALL OVERHEAD SIGNS ARE TO BE INSTALLED VERTICALLY CENTERED ON THE HORIZONTAL MEMBER OF THE OVERHEAD SIGN SUPPORT, UNLESS A MINIMUM VERTICAL CLEARANCE OF 18 FEET CANNOT BE ACHIEVED.

6. ALL NEW OVERHEAD SIGN SUPPORTS SHALL BE INSTALLED SUCH THAT THE EDGE OF FOUNDATIONS ARE NOT LOCATED WITHIN THE DEFLECTION ZONE OF A GUIDERAIL OR OTHER BARRIER AS MEASURED FROM THE BACK OF GUIDERAIL TO THE LEADING EDGE OF THE FOUNDATION.

7. ALL OVERHEAD SIGNS INSTALLED ON THE SAME OVERHEAD SIGN SUPPORT SHALL HAVE A MINIMUM OF 1 FOOT SPACING BETWEEN SIGNS.

8. ALL VERTICAL OVERHEAD SIGN SUPPORT MEMBERS ARE SHOWN NOT TO SCALE UNLESS DIMENSIONED OTHERWISE.

9. NEW OVERHEAD SIGN SUPPORTS THAT REPLACE EXISTING OVERHEAD SIGN SUPPORTS ARE TO BE INSTALLED AS NEAR THE EXISTING LOCATION AS FEASIBLE UNLESS OTHERWISE NOTED.

SIGN NUMBERING LEGEND

MAINLINE 000X-000-00.00 X

000X = ROUTE WITH CARDINAL DIRECTION
000 = TOWN NUMBER
00.00 = APPROXIMATE MILE POINT
X = SIGN LETTER PER LOCATION

RAMPS 000X-000-R000-EX00 X

000X = ROUTE WITH CARDINAL DIRECTION
000 = TOWN NUMBER
R000 = SIGN ASSOCIATED RAMP NUMBER
EX00 = EXIT NUMBER FOR ASSOCIATED SIGN
X = SIGN LETTER PER LOCATION

SYMBOL & BORDER LEGEND

OVERHEAD SIGN SUPPORT

CANTILEVER SIGN SUPPORT

SIDE MOUNTED EXTRUDED ALUMINUM SIGN SUPPORT

SIDE MOUNTED SHEET ALUMINUM SIGN SUPPORT (1, 2, 3 POST)

—100YR— 100-YR FEMA FLOOD PLAIN LIMIT

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/2/2018

DESIGNER/DRAFTER: DR
CHECKED BY: MAC
SCALE AS NOTED

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_SPM_173_441_TR-02.dgn

SIGNATURE/BLOCK: OFFICE OF ENGINEERING
APPROVED BY: Mark Makuch

PROJECT TITLE: REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8

TOWN: BRIDGEPORT, TRUMBULL, SHELTON

DRAWING TITLE: GENERAL SIGNING NOTES

PROJECT NO. 173-441
DRAWING NO. TR-02
SHEET NO. 03.02

DRAWING TR-07 DRAWING TR-06
DRAWING TR-06 DRAWING TR-05
DRAWING TR-05 DRAWING TR-04
DRAWING TR-04 BEGIN PROJECT LIMITS
DRAWING TR-10 DRAWING TR-09
DRAWING TR-09 DRAWING TR-08
DRAWING TR-08 DRAWING TR-07
DRAWING TR-07 DRAWING TR-06
DRAWING TR-11 DRAWING TR-10
DRAWING TR-10 DRAWING TR-09
DRAWING TR-13 DRAWING TR-12
DRAWING TR-12 DRAWING TR-11
DRAWING TR-15 DRAWING TR-14
DRAWING TR-14 DRAWING TR-13
DRAWING TR-13 DRAWING TR-12
END PROJECT LIMITS DRAWING TR-15
Trumbull
Bridgeport
Shelton
WOODCREST AVENUE
CHOPSEY HILL
HIGHLAND AVE
MASSILLON
SLAND
PROSPECT
SOUTH
GENERAL SAWYER
JASON KA
E008 802
E015 809
E008 142A
E008 142
E008 144
E008 012A
E008 011A
E008 021A
E008 020A
E008 024
E008 025
E008 023
E008 014A
E008 013
E008 003A
E008 125A
E008 125
E008 127
E008 126A
E095 805
E095 305
E095 806
E095 305A
E095 306
E095 804
E095 345
E095 344
E025 001
E008 009
E008 008
E008 007
E008 006
E008 005
E008 004
E008 003
E008 002
E008 001
E008 012
E008 010
E008 011
E008 013
E008 014
E008 015
E008 016
E008 017
E008 018
E008 019
E008 020
E008 021
E008 022
E008 023
E008 024
E008 025
E008 026
E008 027
E008 028
E008 029
E008 030
E008 031
E008 032
E008

SIGN INSTALLATION		
SIGN	LEGEND	CTDOT #
(C) Assembly #		41-4260R 41-5008
(D) Assembly #		41-4260R
Assembly #(E)	BACK TO BACK	41-4260R 41-4260L

SIGNING NOTES

(A) REMOVE EXISTING SIDEMOUNTED PANEL, STRUCTURE, AND FOUNDATION

(B) NOT IN CONTRACT

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/2/2018

DESIGNER/DRAFTER: DR

CHECKED BY: MAC

SCALE IN FEET 0 200 400

SCALE 1"=200'

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_SPM_173_441_TR-04.dgn

SIGNATURE/ BLOCK: OFFICE OF ENGINEERING

APPROVED BY: Mark Makuch

PROJECT TITLE: REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8 -

TOWN: BRIDGEPORT, TRUMBULL, SHELTON

DRAWING TITLE: SIGNING - MAINLINE

PROJECT NO. 173-441

DRAWING NO. TR-04

SHEET NO. 03.04

SIGNING NOTES

(A) REMOVE EXISTING SIDEMOUNTED PANEL, STRUCTURE, AND FOUNDATION

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/2/2018

DESIGNER/DRAFTER: DR

CHECKED BY: MAC

SCALE IN FEET 0 200 400

SCALE 1"=200'

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_SPM_173_441_TR-05.dgn

SIGNATURE/BLOCK: OFFICE OF ENGINEERING

APPROVED BY: Mark Makuch

PROJECT TITLE: REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8 -

TOWN: BRIDGEPORT, TRUMBULL, SHELTON

DRAWING TITLE: SIGNING - MAINLINE

PROJECT NO. 173-441

DRAWING NO. TR-05

SHEET NO. 03.05

EXIT 3
Transportation Center
008S-015-02.53 A
EXIT 5
1
Boston Ave
North Ave
EXIT ONLY
008S-015-02.99 A
MILEAGE 02.99
SIGN SUPPORT NO. 20608
ATTRACTIONS - EXIT 5
Beardsley Zoo
Beardsley State Park
St. Vincent College
Discovery Museum & Park
008S-015-03.18 A
CATALOG NO. 524747
JUNCTION
95
2 MILES
EXIT 3
Main St
Washington Ave
1/2 MILE
008S-015-02.35 A B
MILEAGE 02.35
SIGN SUPPORT NO. 20609
NIC
(PARAPET)
URGENT MESSAGE WHEN FLASHING
HIGHWAY ADVISORY
RADIO
TUNE TO 1670 AM
NIC
606
51-6124
EXIT
5
REMOVE
20608
606
41-5589
RAMP
25
M.P.H.
REMOVE
20607
EXIT 3
Main St
Washington Ave
1 MILE
EXIT 5
1
Boston Ave
North Ave
1/2 MILE
EXIT ONLY
008S-015-03.31 A B
MILEAGE 03.31
SIGN SUPPORT NO. 20606
REMOVE
20606
MATCH MARK - SEE DRAWING NO. TR-07
RAMP 007A
RAMP 007
EXIT 5
RAMP 005
RAMP 008
RAMP 006
RAMP 006A
MATCH MARK - SEE DRAWING NO. TR-05
Reservoir Avenue
Sylvan Avenue
Seitsam Road
Lakeview Avenue
Island Brook Avenue
Clarence Avenue
Housatonic River
Pleasure Beach Park
Pleasure Beach Avenue
Seaside Park
Park Avenue
Boston Avenue
Hollywood Avenue
Nutmeg Shopping Center
Cherry Street
Front Street
Water Street
Bridgeport Avenue
Connecticut Turnpike
Connecticut Turnpike Exit Ramp
Connecticut Turnpike Entrance Ramp
Connecticut Turnpike Southbound
Connecticut Turnpike Northbound
Eric Street
Eric Street
Hanover Street
Hanover Place
Hanover Avenue
Hanover Street
Overbrook Place
Overbrook Avenue
Overbrook Place
Sylvan Avenue
Sylvan Avenue
Sylvan Avenue
Sylvan Avenue
Island Brook
Island Brook
Island Brook Avenue
Island Brook Avenue
Island Brook Avenue
Island Brook Avenue
Clarence Avenue
Clarence Avenue
Clarence

SIGN INSTALLATION		
SIGN	LEGEND	CTDOT #
(B) Assembly #		41-4260R 41-5008

SIGNING NOTES

(A) REMOVE EXISTING SIDEMOUNTED PANEL, STRUCTURE, AND FOUNDATION

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/2/2018

DESIGNER/DRAFTER: DR

CHECKED BY: MAC

SCALE IN FEET 0 200 400

SCALE 1"=200'

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_SPM_173_441_TR-07.dgn

SIGNATURE/BLOCK: OFFICE OF ENGINEERING

APPROVED BY: Mark Makuch

PROJECT TITLE: REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8

TOWN: BRIDGEPORT, TRUMBULL, SHELTON

DRAWING TITLE: SIGNING - MAINLINE

PROJECT NO. 173-441

DRAWING NO. TR-07

SHEET NO. 03.07

SIGNING NOTES

(A) REMOVE EXISTING SIDEMOUNTED PANEL, STRUCTURE, AND FOUNDATION

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/2/2018

DESIGNER/DRAFTER: DR

CHECKED BY: MAC

SCALE IN FEET 0 200 400

SCALE 1"=200'

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_SPM_173_441_TR-08.dgn

SIGNATURE/BLOCK: OFFICE OF ENGINEERING

APPROVED BY: Mark Makuch

PROJECT TITLE: REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8 -

TOWN: BRIDGEPORT, TRUMBULL, SHELTON

DRAWING TITLE: SIGNING - MAINLINE

PROJECT NO. 173-441

DRAWING NO. TR-08

SHEET NO. 03.08

SIGNING NOTES

(A) REMOVE EXISTING SIDEMOUNTED PANEL, STRUCTURE, AND FOUNDATION

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/2/2018

DESIGNER/DRAFTER: DR

CHECKED BY: MAC

SCALE IN FEET
0 200 400
SCALE 1"=200'

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_SPM_173_441_TR-09.dgn

SIGNATURE/BLOCK: OFFICE OF ENGINEERING

APPROVED BY: Mark Makuch

PROJECT TITLE: REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8 -

TOWN: BRIDGEPORT, TRUMBULL, SHELTON

DRAWING TITLE: SIGNING - MAINLINE

PROJECT NO. 173-441

DRAWING NO. TR-09

SHEET NO. 03.09

SIGNING NOTES

(A) REMOVE EXISTING SIDEMOUNTED PANEL, STRUCTURE, AND FOUNDATION

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/2/2018

DESIGNER/DRAFTER: DR

CHECKED BY: MAC

SCALE IN FEET 0 200 400

SCALE 1"=200'

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_SPM_173_441_TR-10.dgn

SIGNATURE/ BLOCK: OFFICE OF ENGINEERING

APPROVED BY: Mark Makuch

PROJECT TITLE: REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8 -

TOWN: BRIDGEPORT, TRUMBULL, SHELTON

DRAWING TITLE: SIGNING - MAINLINE

PROJECT NO. 173-441

DRAWING NO. TR-10

SHEET NO. 03.10

SIGNING NOTES

(A) REMOVE EXISTING SIDEMOUNTED PANEL, STRUCTURE, AND FOUNDATION

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/2/2018

DESIGNER/DRAFTER: DR

CHECKED BY: MAC

SCALE IN FEET 0 200 400

SCALE 1"=200'

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_SPM_173_441_TR-11.dgn

SIGNATURE/ BLOCK: OFFICE OF ENGINEERING

APPROVED BY: Mark Makuch

PROJECT TITLE: REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8 -

TOWN: BRIDGEPORT, TRUMBULL, SHELTON

DRAWING TITLE: SIGNING - MAINLINE

PROJECT NO. 173-441

DRAWING NO. TR-11

SHEET NO. 03.11

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/2/2018

DESIGNER/DRAFTER: DR

CHECKED BY: MAC

SCALE IN FEET
0 200 400
SCALE 1"=200'

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_SPM_173_441_TR-12.dgn

SIGNATURE/ BLOCK:
OFFICE OF ENGINEERING

APPROVED BY:
Mark Makoski

PROJECT TITLE:
REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8
-

TOWN:
BRIDGEPORT, TRUMBULL, SHELTON

DRAWING TITLE:
SIGNING - MAINLINE

PROJECT NO. 173-441

DRAWING NO. TR-12

SHEET NO. 03.12

SIGNING NOTES

(A) REMOVE EXISTING SIDEMOUNTED PANEL, STRUCTURE, AND FOUNDATION

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/2/2018

DESIGNER/DRAFTER: DR

CHECKED BY: MAC

SCALE IN FEET 0 200 400

SCALE 1"=200'

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_SPM_173_441_TR-13.dgn

SIGNATURE/BLOCK: OFFICE OF ENGINEERING

APPROVED BY: Mark Makuch

PROJECT TITLE: REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8 -

TOWN: BRIDGEPORT, TRUMBULL, SHELTON

DRAWING TITLE: SIGNING - MAINLINE

PROJECT NO. 173-441

DRAWING NO. TR-13

SHEET NO. 03.13

SIGNING NOTES

(A) REMOVE EXISTING SIDEMOUNTED PANEL, STRUCTURE, AND FOUNDATION

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/2/2018

DESIGNER/DRAFTER: DR

CHECKED BY: MAC

SCALE IN FEET 0 200 400

SCALE 1"=200'

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_SPM_173_441_TR-14.dgn

SIGNATURE/ BLOCK: OFFICE OF ENGINEERING

APPROVED BY: Mark Makuch

PROJECT TITLE: REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8 -

TOWN: BRIDGEPORT, TRUMBULL, SHELTON

DRAWING TITLE: SIGNING - MAINLINE

PROJECT NO. 173-441

DRAWING NO. TR-14

SHEET NO. 03.14

SIGNING NOTES

(A) REMOVE EXISTING SIDEMOUNTED PANEL, STRUCTURE, AND FOUNDATION

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/2/2018

DESIGNER/DRAFTER: DR

CHECKED BY: MAC

SCALE IN FEET 0 200 400

SCALE 1"=200'

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_SPM_173_441_TR-15.dgn

SIGNATURE/ BLOCK: OFFICE OF ENGINEERING

APPROVED BY: Mark Makuch

PROJECT TITLE: REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8 -

TOWN: BRIDGEPORT, TRUMBULL, SHELTON

DRAWING TITLE: SIGNING - MAINLINE

PROJECT NO. 173-441

DRAWING NO. TR-15

SHEET NO. 03.15

MAINLINE: 008	EXIT #: 1	TOWN: BRIDGEPORT	RAMP ID: 008-122 & 008-123

EXISTING SIGNS TO REMAIN

SIGN	LEGEND	CT DOT #	SIGN	LEGEND	CT DOT #
* A	36" × 4"	31-5003 (RED)	* E	ONE WAY 18" × 54"	31-1178R
* B	DO NOT ENTER 48"	31-1121	* F	36" / NO LEFT TURN 30"	31-1629 / 31-1630
* C	42" WRONG WAY 30"	31-1123	* M	24" NO PEDESTRIANS 12"	31-1774
* D	ONE WAY 18" × 54"	31-1189L			

* NIC (NOT IN CONTRACT): EXISTING TO REMAIN

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/2/2018

DESIGNER/DRAFTER: DR
CHECKED BY: MAC
SCALE IN FEET 0 50 100
SCALE 1"=50'

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_SPM_173_441_TR-16.dgn

SIGNATURE/ BLOCK:
OFFICE OF ENGINEERING
APPROVED BY:

PROJECT TITLE:
REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8
-

TOWN: BRIDGEPORT, TRUMBULL, SHELTON
DRAWING TITLE: SIGNING - RAMPS

PROJECT NO. 173-441
DRAWING NO. TR-16
SHEET NO. 03.16

MAINLINE: 008	EXIT #: 2	TOWN: BRIDGEPORT	RAMP ID: 008-124, 008-125, 126, & 008-127

EXISTING SIGNS TO REMAIN

SIGN	LEGEND	CT DOT #	SIGN	LEGEND	CT DOT #
* A	36" 4"	31-5003 (RED)	* E	ONE WAY 18" 54"	31-1178R
* B	DO NOT ENTER 48"	31-1121	* F	36" NO RIGHT TURN 30"	31-1627 31-1628
* C	42" WRONG WAY 30"	31-1123	* M	24" NO PEDESTRIANS 12"	31-1774
* D	ONE WAY 18" 54"	31-1189L			

* NIC (NOT IN CONTRACT): EXISTING TO REMAIN

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/2/2018

DESIGNER/DRAFTER: DR

CHECKED BY: MAC

SCALE IN FEET 0 50 100

SCALE 1"=50'

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_SPM_173_441_TR-17.dgn

SIGNATURE/ BLOCK: OFFICE OF ENGINEERING

APPROVED BY: Mark Makuch

PROJECT TITLE: REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8 -

TOWN: BRIDGEPORT, TRUMBULL, SHELTON

DRAWING TITLE: SIGNING - RAMPS

PROJECT NO. 173-441

DRAWING NO. TR-17

SHEET NO. 03.17

MAINLINE: 008	EXIT #: 3	TOWN: BRIDGEPORT	RAMP ID: 008-001 & 008-002

EXISTING SIGNS TO REMAIN

SIGN	LEGEND	CT DOT #	SIGN	LEGEND	CT DOT #
* A	36" / 4"	31-5003 (RED)	* E	ONE WAY 18" / 54"	31-1178R
* B	DO NOT ENTER 48"	31-1121	* F	36" / NO LEFT TURN 30"	31-1629 / 31-1630
* C	42" / WRONG WAY 30"	31-1123	* M	24" / NO PEDESTRIANS 12"	31-1774
* D	ONE WAY 18" / 54"	31-1189L			

* NIC (NOT IN CONTRACT): EXISTING TO REMAIN

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/2/2018

DESIGNER/DRAFTER: DR
CHECKED BY: MAC
SCALE IN FEET 0 100 200
SCALE 1"=100'

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_SPM_173_441_TR-18.dgn

SIGNATURE/ BLOCK: OFFICE OF ENGINEERING
APPROVED BY: Mark Makuch

PROJECT TITLE: REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8 -

TOWN: BRIDGEPORT, TRUMBULL, SHELTON

DRAWING TITLE: SIGNING - RAMPS

PROJECT NO. 173-441
DRAWING NO. TR-18
SHEET NO. 03.18

MAINLINE: 008	EXIT #: 4	TOWN: BRIDGEPORT	RAMP ID: 008-003 & 008-004

EXISTING SIGNS TO REMAIN

SIGN	LEGEND	CT DOT #	SIGN	LEGEND	CT DOT #
* A	36" 4"	31-5003 (RED)	* E	ONE WAY 18" 54"	31-1178R
* B	DO NOT ENTER 48"	31-1121	* F	36" NO LEFT TURN 30"	31-1629 31-1630
* C	42" WRONG WAY 30"	31-1123	* M	24" NO PEDESTRIANS 12"	31-1774
* D	ONE WAY 18" 54"	31-1189L			

* NIC (NOT IN CONTRACT): EXISTING TO REMAIN

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/2/2018

DESIGNER/DRAFTER: DR

CHECKED BY: MAC

SCALE IN FEET 0 50 100

SCALE 1"=50'

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_SPM_173_441_TR-19.dgn

SIGNATURE/ BLOCK: OFFICE OF ENGINEERING

APPROVED BY: Mark Makuch

PROJECT TITLE: REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8 -

TOWN: BRIDGEPORT, TRUMBULL, SHELTON

DRAWING TITLE: SIGNING - RAMPS

PROJECT NO. 173-441

DRAWING NO. TR-19

SHEET NO. 03.19

MAINLINE: 008	EXIT #: 5	TOWN: BRIDGEPORT	RAMP ID: 008-005, 008-006, 008-007, & 008-008

EXISTING SIGNS TO REMAIN

SIGN	LEGEND	CT DOT #	SIGN	LEGEND	CT DOT #
* A	36" 4"	31-5003 (RED)	* E	ONE WAY 18" 54"	31-1178R
* B	DO NOT ENTER 48"	31-1121	* F	36" NO LEFT TURN 30"	31-1629 31-1630
* C	42" WRONG WAY 30"	31-1123	* M	24" NO PEDESTRIANS 12"	31-1774
* D	ONE WAY 18" 54"	31-1189L			

* NIC (NOT IN CONTRACT): EXISTING TO REMAIN

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/2/2018

DESIGNER/DRAFTER: DR
CHECKED BY: MAC
SCALE IN FEET 0 100 200
SCALE 1"=100'

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_SPM_173_441_TR-20.dgn

SIGNATURE/BLOCK: OFFICE OF ENGINEERING
APPROVED BY: Mark Makuch

PROJECT TITLE: REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8 -

TOWN: BRIDGEPORT, TRUMBULL, SHELTON

DRAWING TITLE: SIGNING - RAMPS

PROJECT NO. 173-441
DRAWING NO. TR-20
SHEET NO. 03.20

MAINLINE: 008	EXIT #: 7	TOWN: BRIDGEPORT	RAMP ID: 008-009 & 008-010

EXISTING SIGNS TO REMAIN

SIGN	LEGEND	CT DOT #	SIGN	LEGEND	CT DOT #
A *	36" / 4"	31-5003 (RED)	E *	ONE WAY 18" / 54"	31-1178R
B *	DO NOT ENTER 48"	31-1121	F *	36" / NO LEFT TURN 30"	31-1629 / 31-1630
C *	42" / WRONG WAY 30"	31-1123	M *	24" / NO PEDESTRIANS 12"	31-1774
D *	ONE WAY 18" / 54"	31-1189L			

* NIC (NOT IN CONTRACT): EXISTING TO REMAIN

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/2/2018

DESIGNER/DRAFTER: DR

CHECKED BY: MAC

SCALE IN FEET 0 100 200

SCALE 1"=100'

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_SPM_173_441_TR-21.dgn

SIGNATURE/ BLOCK:
OFFICE OF ENGINEERING

APPROVED BY:
Mark Makovch

PROJECT TITLE:
REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8
-

TOWN:
BRIDGEPORT, TRUMBULL, SHELTON

DRAWING TITLE:
SIGNING - RAMPS

PROJECT NO. 173-441

DRAWING NO. TR-21

SHEET NO. 03.21

MAINLINE: 008 & 015	EXIT #: 8 & 52	TOWN: TRUMBULL	RAMP ID: 008-141, 015-810, 008-140, & 008-142

EXISTING SIGNS TO REMAIN

SIGN	LEGEND	CT DOT #	SIGN	LEGEND	CT DOT #
* (A)	36" / 4"	31-5003 (RED)	* (E)	ONE WAY 18" / 54"	31-1178R
* (B)	DO NOT ENTER 48"	31-1121	* (F)	36" / NO LEFT TURN 30"	31-1629 / 31-1630
* (C)	42" / WRONG WAY 30"	31-1123	* (M)	24" / NO PEDESTRIANS 12"	31-1774
* (D)	ONE WAY 18" / 54"	31-1189L			

* NIC (NOT IN CONTRACT): EXISTING TO REMAIN

SIGN INSTALLATION

SIGN	LEGEND	CTDOT #
Assembly # (G)		41-4211R 41-5008

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/2/2018

DESIGNER/DRAFTER: DR
CHECKED BY: MAC
SCALE IN FEET 0 200 400
SCALE 1"=200'

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_SPM_173_441_TR-22.dgn

SIGNATURE/BLOCK: OFFICE OF ENGINEERING
APPROVED BY: Mark Makuch

PROJECT TITLE: REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8 -

TOWN: BRIDGEPORT, TRUMBULL, SHELTON
DRAWING TITLE: SIGNING - RAMPS

PROJECT NO. 173-441
DRAWING NO. TR-22
SHEET NO. 03.22

MAINLINE: 008 & 015	EXIT #: 9, 10, & 52	TOWN: TRUMBULL	RAMP ID: 008-801, 008-143, 008-144, 008-802, 015-215, 015-809, & 015-810

EXISTING SIGNS TO REMAIN

SIGN	LEGEND	CT DOT #	SIGN	LEGEND	CT DOT #
* A	36" / 4"	31-5003 (RED)	* E	ONE WAY 18" / 54"	31-1178R
* B	DO NOT ENTER 48"	31-1121	* F	36" / NO LEFT TURN 30"	31-1629 / 31-1630
* C	42" / WRONG WAY 30"	31-1123	* M	24" / NO PEDESTRIANS 12"	31-1774
* D	ONE WAY 18" / 54"	31-1189L			

* NIC (NOT IN CONTRACT): EXISTING TO REMAIN

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/2/2018

DESIGNER/DRAFTER: DR
CHECKED BY: MAC
SCALE IN FEET 0 200 400
SCALE 1"=200'

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_SPM_173_441_TR-23.dgn

SIGNATURE/ BLOCK: OFFICE OF ENGINEERING
APPROVED BY: Mark Makuch

PROJECT TITLE: REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8 -

TOWN: BRIDGEPORT, TRUMBULL, SHELTON

DRAWING TITLE: SIGNING - RAMPS

PROJECT NO. 173-441
DRAWING NO. TR-23
SHEET NO. 03.23

MAINLINE: 008	EXIT #: 11	TOWN: TRUMBULL	RAMP ID: 008-011, 008-012, 008-013, & 008-014

EXISTING SIGNS TO REMAIN

SIGN	LEGEND	CT DOT #	SIGN	LEGEND	CT DOT #
A *	36" 4"	31-5003 (RED)	E *	ONE WAY 18" 54"	31-1178R
B *	DO NOT ENTER 48"	31-1121	F *	36" NO LEFT TURN 30"	31-1629 31-1630
C *	42" WRONG WAY 30"	31-1123	M *	24" NO PEDESTRIANS 12"	31-1774
D *	ONE WAY 18" 54"	31-1189L			

* NIC (NOT IN CONTRACT): EXISTING TO REMAIN

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/2/2018

DESIGNER/DRAFTER: DR

CHECKED BY: MAC

SCALE IN FEET 0 200 400

SCALE 1"=200'

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_SPM_173_441_TR-24.dgn

SIGNATURE/ BLOCK: OFFICE OF ENGINEERING

APPROVED BY: Mark Makuch

PROJECT TITLE: REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8 -

TOWN: BRIDGEPORT, TRUMBULL, SHELTON

DRAWING TITLE: SIGNING - RAMPS

PROJECT NO. 173-441

DRAWING NO. TR-24

SHEET NO. 03.24

MAINLINE: 008	EXIT #: 12	TOWN: SHELTON	RAMP ID: 008-015, 008-016, 008-017, & 008-018

EXISTING SIGNS TO REMAIN

SIGN	LEGEND	CT DOT #	SIGN	LEGEND	CT DOT #
* A	36" 4"	31-5003 (RED)	* E	ONE WAY 18" 54"	31-1178R
* B	DO NOT ENTER 48"	31-1121	* F	36" NO LEFT TURN 30"	31-1629 31-1630
* C	42" WRONG WAY 30"	31-1123	* M	24" NO PEDESTRIANS 12"	31-1774
* D	ONE WAY 18" 54"	31-1189L			

* NIC (NOT IN CONTRACT): EXISTING TO REMAIN

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/2/2018

DESIGNER/DRAFTER: DR

CHECKED BY: MAC

SCALE IN FEET 0 100 200

SCALE 1"=100'

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_SPM_173_441_TR-25.dgn

SIGNATURE/ BLOCK: OFFICE OF ENGINEERING

APPROVED BY: Mark Makuch

PROJECT TITLE: REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8 -

TOWN: BRIDGEPORT, TRUMBULL, SHELTON

DRAWING TITLE: SIGNING - RAMPS

PROJECT NO. 173-441

DRAWING NO. TR-25

SHEET NO. 03.25

MAINLINE: 008	EXIT #: 13	TOWN: SHELTON	RAMP ID: 008-019, 008-020, 008-021, & 008-022

EXISTING SIGNS TO REMAIN

SIGN	LEGEND	CT DOT #	SIGN	LEGEND	CT DOT #
* A	36" / 4"	31-5003 (RED)	* E	ONE WAY 18" / 54"	31-1178R
* B	DO NOT ENTER 48"	31-1121	* F	36" / NO LEFT TURN 30"	31-1629 / 31-1630
* C	42" / WRONG WAY 30"	31-1123	* M	24" / NO PEDESTRIANS 12"	31-1774
* D	ONE WAY 18" / 54"	31-1189L			

* NIC (NOT IN CONTRACT): EXISTING TO REMAIN

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/2/2018

DESIGNER/DRAFTER: DR

CHECKED BY: MAC

SCALE IN FEET 0 100 200

SCALE 1"=100'

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_SPM_173_441_TR-26.dgn

SIGNATURE/ BLOCK:
OFFICE OF ENGINEERING

APPROVED BY:
Mark Makuch

PROJECT TITLE:
REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8
-

TOWN:
BRIDGEPORT, TRUMBULL, SHELTON

DRAWING TITLE:
SIGNING - RAMPS

PROJECT NO. 173-441

DRAWING NO. TR-26

SHEET NO. 03.26

MAINLINE: 008	EXIT #: 14	TOWN: SHELTON	RAMP ID: 008-023, 008-024, 008-025, & 008-026

EXISTING SIGNS TO REMAIN

SIGN	LEGEND	CT DOT #	SIGN	LEGEND	CT DOT #
* A	36" 4"	31-5003 (RED)	* E	ONE WAY 18" 54"	31-1178R
* B	DO NOT ENTER 48"	31-1121	* F	36" NO LEFT TURN 30"	31-1629 31-1630
* C	42" WRONG WAY 30"	31-1123	* M	24" NO PEDESTRIANS 12"	31-1774
* D	ONE WAY 18" 54"	31-1189L			

* NIC (NOT IN CONTRACT): EXISTING TO REMAIN

SIGN INSTALLATION

SIGN	LEGEND	CTDOT #
Assembly # G		41-4211R 41-5008

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/2/2018

DESIGNER/DRAFTER: DR
CHECKED BY: MAC
SCALE IN FEET 0 100 200
SCALE 1"=100'

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_SPM_173_441_TR-27.dgn

SIGNATURE/BLOCK: OFFICE OF ENGINEERING
APPROVED BY: Mark Makuch

PROJECT TITLE: REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8 -

TOWN: BRIDGEPORT, TRUMBULL, SHELTON

DRAWING TITLE: SIGNING - RAMPS

PROJECT NO. 173-441
DRAWING NO. TR-27
SHEET NO. 03.27

NEW SIGN SUPPORT NO. 20478
OVERHEAD SIGN SUPPORT CROSS-SECTION
(LOOKING NORTH AT FRONT OF SIGN)
SIGN NO. 015N-144-R143-D
SIGN NO. 015N-144-R143-E

NEW SIGN SUPPORT NO. 20502
OVERHEAD SIGN SUPPORT CROSS-SECTION
(LOOKING WEST AT FRONT OF SIGN)
SIGN NO. 015S-144-R810-A
SIGN NO. 015S-144-R810-B

NEW SIGN SUPPORT NO. 20503
OVERHEAD SIGN SUPPORT CROSS-SECTION
(LOOKING SOUTH AT FRONT OF SIGN)
SIGN NO. 015S-144-R215-A
SIGN NO. 015S-144-R215-B

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/2/2018

DESIGNER/DRAFTER: **DR**
CHECKED BY: **MAC**
NOT TO SCALE

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_SEC_0173-441.dgn

SIGNATURE/ BLOCK:
OFFICE OF ENGINEERING
APPROVED BY:
Mark Makuch

PROJECT TITLE:
REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8

TOWN:
BRIDGEPORT, TRUMBULL & SHELTON

DRAWING TITLE:
CROSS SECTIONS

PROJECT NO. **173-441**
DRAWING NO. **TR-28**
SHEET NO. **03.28**

NEW SIGN SUPPORT NO. 20509
OVERHEAD SIGN SUPPORT CROSS-SECTION
(LOOKING NORTH AT FRONT OF SIGN)
SIGN NO. 008N-015-00.46-A

NEW SIGN SUPPORT NO. 20510
OVERHEAD SIGN SUPPORT CROSS-SECTION
(LOOKING NORTH AT FRONT OF SIGN)
SIGN NO. 008N-015-00.59-A

EXISTING SIGN SUPPORT NO. 20813
REUSE EXISTING SIGN SUPPORT
OVERHEAD SIGN SUPPORT CROSS-SECTION
(LOOKING NORTH AT FRONT OF SIGN)
SIGN NO. 008N-015-00.75-A

NEW SIGN SUPPORT NO. 20512
OVERHEAD SIGN SUPPORT CROSS-SECTION
(LOOKING NORTH AT FRONT OF SIGN)
SIGN NO. 008N-015-00.90-A

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/2/2018

DESIGNER/DRAFTER: **DR**
CHECKED BY: **MAC**

NOT TO SCALE

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_SEC_0173-441.dgn

SIGNATURE/ BLOCK:
OFFICE OF ENGINEERING
APPROVED BY:
Mark Makuch

PROJECT TITLE:
REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8

TOWN:
BRIDGEPORT, TRUMBULL & SHELTON

DRAWING TITLE:
CROSS SECTIONS

PROJECT NO. **173-441**
DRAWING NO. **TR-29**
SHEET NO. **03.29**

NEW SIGN SUPPORT NO. 20517
OVERHEAD SIGN SUPPORT CROSS-SECTION
(LOOKING NORTH AT FRONT OF SIGN)
SIGN NO. 008N-015-02.70-A
SIGN NO. 008N-015-02.70-B
SIGN NO. 008N-015-02.70-C

NEW SIGN SUPPORT NO. 20519
OVERHEAD SIGN SUPPORT CROSS-SECTION
(LOOKING NORTH AT FRONT OF SIGN)
SIGN NO. 008N-015-03.70-A
SIGN NO. 008N-015-03.70-B

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/2/2018

DESIGNER/DRAFTER: **DR**
CHECKED BY: **MAC**
NOT TO SCALE

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_SEC_0173-441.dgn

SIGNATURE/ BLOCK:
OFFICE OF ENGINEERING
APPROVED BY:
Mark Makuch

PROJECT TITLE:
REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8

TOWN:
BRIDGEPORT, TRUMBULL & SHELTON
DRAWING TITLE:
CROSS SECTIONS

PROJECT NO. **173-441**
DRAWING NO. **TR-30**
SHEET NO. **03.30**

NEW SIGN SUPPORT NO. 20520
OVERHEAD SIGN SUPPORT CROSS-SECTION
(LOOKING NORTH AT FRONT OF SIGN)
SIGN NO. 008N-144-04.53-A
SIGN NO. 008N-144-04.53-B

NEW SIGN SUPPORT NO. 20520
OVERHEAD SIGN SUPPORT PLAN VIEW

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/2/2018

DESIGNER/DRAFTER: **DR**
CHECKED BY: **MAC**
NOT TO SCALE

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_SEC_0173-441.dgn

SIGNATURE/ BLOCK: **OFFICE OF ENGINEERING**
APPROVED BY: Mark Makuch

PROJECT TITLE: **REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8**

TOWN: **BRIDGEPORT, TRUMBULL & SHELTON**
DRAWING TITLE: **CROSS SECTIONS**

PROJECT NO. **173-441**
DRAWING NO. **TR-31**
SHEET NO. **03.31**

NEW SIGN SUPPORT NO. 20521
OVERHEAD SIGN SUPPORT CROSS-SECTION
(LOOKING NORTH AT FRONT OF SIGN)
SIGN NO. 008N-144-04.93-A
SIGN NO. 008N-144-04.93-B

NEW SIGN SUPPORT NO. 20523
OVERHEAD SIGN SUPPORT CROSS-SECTION
(LOOKING NORTH AT FRONT OF SIGN)
SIGN NO. 008N-144-05.83-A

NEW SIGN SUPPORT NO. 20524
OVERHEAD SIGN SUPPORT CROSS-SECTION
(LOOKING NORTH AT FRONT OF SIGN)
SIGN NO. 008N-144-06.49-A

NEW SIGN SUPPORT NO. 20525
OVERHEAD SIGN SUPPORT CROSS-SECTION
(LOOKING NORTH AT FRONT OF SIGN)
SIGN NO. 008N-144-06.90-A

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/2/2018

DESIGNER/DRAFTER: **DR**
CHECKED BY: **MAC**
NOT TO SCALE

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_SEC_0173-441.dgn

SIGNATURE/ BLOCK:
OFFICE OF ENGINEERING
APPROVED BY:
Mark Makuch

PROJECT TITLE:
REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8

TOWN:
BRIDGEPORT, TRUMBULL & SHELTON

DRAWING TITLE:
CROSS SECTIONS

PROJECT NO. **173-441**
DRAWING NO. **TR-32**
SHEET NO. **03.32**

NEW SIGN SUPPORT NO. 20529
OVERHEAD SIGN SUPPORT CROSS-SECTION
(LOOKING NORTH AT FRONT OF SIGN)
SIGN NO. 008N-126-10.36-A

NOT TO SCALE

NEW SIGN SUPPORT NO. 20529
OVERHEAD SIGN SUPPORT PLAN VIEW

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/2/2018

DESIGNER/DRAFTER: **DR**
CHECKED BY: **MAC**
NOT TO SCALE

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_SEC_0173-441.dgn

SIGNATURE/ BLOCK: **OFFICE OF ENGINEERING**
APPROVED BY: Mark Makuch

PROJECT TITLE: **REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8**

TOWN: **BRIDGEPORT, TRUMBULL & SHELTON**
DRAWING TITLE: **CROSS SECTIONS**

PROJECT NO. **173-441**
DRAWING NO. **TR-33**
SHEET NO. **03.33**

NEW SIGN SUPPORT NO. 20530
OVERHEAD SIGN SUPPORT CROSS-SECTION
(LOOKING NORTH AT FRONT OF SIGN)
SIGN NO. 008N-126-10.68-A

NEW SIGN SUPPORT NO. 20591
OVERHEAD SIGN SUPPORT CROSS-SECTION
(LOOKING SOUTH AT FRONT OF SIGN)
SIGN NO. 008S-126-12.20-A

EXISTING SIGN SUPPORT NO. 20593
REUSE EXISTING SIGN SUPPORT
OVERHEAD SIGN SUPPORT CROSS-SECTION
(LOOKING SOUTH AT FRONT OF SIGN)
SIGN NO. 008S-126-10.37-A

NEW SIGN SUPPORT NO. 20594
OVERHEAD SIGN SUPPORT CROSS-SECTION
(LOOKING SOUTH AT FRONT OF SIGN)
SIGN NO. 008S-126-09.91-A

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/2/2018

DESIGNER/DRAFTER: **DR**
CHECKED BY: **MAC**
NOT TO SCALE

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_SEC_0173-441.dgn

SIGNATURE/BLOCK:
OFFICE OF ENGINEERING
APPROVED BY:
Mark Makuch

PROJECT TITLE:
REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8

TOWN:
BRIDGEPORT, TRUMBULL & SHELTON

DRAWING TITLE:
CROSS SECTIONS

PROJECT NO. **173-441**
DRAWING NO. **TR-34**
SHEET NO. **03.34**

NEW SIGN SUPPORT NO. 20601
OVERHEAD SIGN SUPPORT CROSS-SECTION
(LOOKING SOUTH AT FRONT OF SIGN)
SIGN NO. 008S-126-07.36-A

NEW SIGN SUPPORT NO. 20602
OVERHEAD SIGN SUPPORT CROSS-SECTION
(LOOKING SOUTH AT FRONT OF SIGN)
SIGN NO. 008S-144-06.82-A

NEW SIGN SUPPORT NO. 20603
OVERHEAD SIGN SUPPORT CROSS-SECTION
(LOOKING SOUTH AT FRONT OF SIGN)
SIGN NO. 008S-144-06.48-A
SIGN NO. 008S-144-06.48-B

NEW SIGN SUPPORT NO. 20606
OVERHEAD SIGN SUPPORT CROSS-SECTION
(LOOKING SOUTH AT FRONT OF SIGN)
SIGN NO. 008S-015-03.31-A
SIGN NO. 008S-015-03.31-B

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/2/2018

DESIGNER/DRAFTER: **DR**
CHECKED BY: **MAC**
NOT TO SCALE

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_SEC_0173-441.dgn

SIGNATURE/BLOCK: **OFFICE OF ENGINEERING**
APPROVED BY: Mark Makuch

PROJECT TITLE: **REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8**

TOWN: **BRIDGEPORT, TRUMBULL & SHELTON**
DRAWING TITLE: **CROSS SECTIONS PLAN VIEW**

PROJECT NO. **173-441**
DRAWING NO. **TR-35**
SHEET NO. **03.35**

NEW SIGN SUPPORT NO. 20608
OVERHEAD SIGN SUPPORT CROSS-SECTION
(LOOKING SOUTH AT FRONT OF SIGN)
SIGN NO. 008S-015-02.99-A

NEW SIGN SUPPORT NO. 20608
OVERHEAD SIGN SUPPORT PLAN VIEW

NOT TO SCALE

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/2/2018

DESIGNER/DRAFTER: **DR**
CHECKED BY: **MAC**
NOT TO SCALE

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_SEC_0173-441.dgn

SIGNATURE/ BLOCK: **OFFICE OF ENGINEERING**
APPROVED BY: Mark Makuch

PROJECT TITLE: **REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8**

TOWN: **BRIDGEPORT, TRUMBULL & SHELTON**
DRAWING TITLE: **CROSS SECTIONS PLAN VIEW**

PROJECT NO. **173-441**
DRAWING NO. **TR-36**
SHEET NO. **03.36**

NEW SIGN SUPPORT NO. 20611
OVERHEAD SIGN SUPPORT CROSS-SECTION
(LOOKING SOUTH AT FRONT OF SIGN)
SIGN NO. 008S-015-01.86-A
SIGN NO. 008S-015-01.86-B
SIGN NO. 008S-015-01.86-C

NEW SIGN SUPPORT NO. 20612
OVERHEAD SIGN SUPPORT CROSS-SECTION
(LOOKING SOUTH AT FRONT OF SIGN)
SIGN NO. 008S-015-R8S02-A
SIGN NO. 008S-015-R8S02-B

NEW SIGN SUPPORT NO. 20613
OVERHEAD SIGN SUPPORT CROSS-SECTION
(LOOKING SOUTH AT FRONT OF SIGN)
SIGN NO. 008S-015-01.51-A
SIGN NO. 008S-015-01.51-B

NEW SIGN SUPPORT NO. 20614
OVERHEAD SIGN SUPPORT CROSS-SECTION
(LOOKING SOUTH AT FRONT OF SIGN)
SIGN NO. 008S-015-01.19-A
SIGN NO. 008S-015-01.19-B

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/2/2018

DESIGNER/DRAFTER: **DR**
CHECKED BY: **MAC**
NOT TO SCALE

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_SEC_0173-441.dgn

SIGNATURE/ BLOCK:
OFFICE OF ENGINEERING
APPROVED BY:
Mark Makuch

PROJECT TITLE:
REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8

TOWN:
BRIDGEPORT, TRUMBULL & SHELTON

DRAWING TITLE:
CROSS SECTIONS PLAN VIEW

PROJECT NO. **173-441**
DRAWING NO. **TR-37**
SHEET NO. **03.37**

NEW SIGN SUPPORT NO. 20615
OVERHEAD SIGN SUPPORT CROSS-SECTION
(LOOKING SOUTH AT FRONT OF SIGN)
SIGN NO. 008S-015-01.08-A
SIGN NO. 008S-015-01.08-B

NEW SIGN SUPPORT NO. 20616
OVERHEAD SIGN SUPPORT CROSS-SECTION
(LOOKING SOUTH AT FRONT OF SIGN)
SIGN NO. 008S-015-00.64-A
SIGN NO. 008S-015-00.64-B
SIGN NO. 008S-015-00.64-C

NEW SIGN SUPPORT NO. 20617
OVERHEAD SIGN SUPPORT CROSS-SECTION
(LOOKING SOUTH AT FRONT OF SIGN)
SIGN NO. 008S-015-00.47-A
SIGN NO. 008S-015-00.47-B

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/2/2018

DESIGNER/DRAFTER: DR
CHECKED BY: MAC
NOT TO SCALE

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_SEC_0173-441.dgn

SIGNATURE/ BLOCK:
OFFICE OF ENGINEERING
APPROVED BY:

PROJECT TITLE:
REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8

TOWN:
BRIDGEPORT, TRUMBULL & SHELTON

DRAWING TITLE:
CROSS SECTIONS PLAN VIEW

PROJECT NO. 173-441
DRAWING NO. TR-38
SHEET NO. 03.38

R1 - SERIES

R1-1

STOP

LEGEND - WHITE
BACKGROUND - RED

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
3.31	24	31-0536	1	.080
5.19	30	31-0552	1	.080
7.98	36	31-0553	1	.080
13.3	48	31-0557	2	.100

R1-2

YIELD

LEGEND - RED
BACKGROUND -WHITE

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
3.90	36	31-0523	1	.080
6.77	48	31-0522	2	.100
10.83	60	31-0528	2	.100

R1-3

ALL-WAY

LEGEND - WHITE
BACKGROUND - RED

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
0.75	18X6	31-0508		.080

R2 - SERIES

R2-1

SPEED LIMIT 00

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
5.00	24X30	31-5505	1	.080
7.50	30X36	31-5504	1	.080
12.00	36X48	31-5506	2	.100
20.00	48X60	31-5507	2B	.100

R2-4a

SPEED LIMIT 00 MINIMUM 00

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
32	48X96	31-5510	2	.125

R3 - SERIES

R3-1

NO RIGHT TURN

31-1604 OVERHEAD MTD
LEGEND - BLACK
BACKGROUND - WHITE
CIRCLE & DIAGONAL - RED

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
4.00	24X24	31-1604		.080
6.25	30X30	31-1617	1	.080
5.00	30X24	31-1618		.080
9.00	36X36	31-1627	2	.080
7.50	36X30	31-1628		.080

R3-2

NO LEFT TURN

31-1603 OVERHEAD MTD
LEGEND - BLACK
BACKGROUND - WHITE
CIRCLE & DIAGONAL - RED

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
4.00	24X24	31-1603		.080
6.25	30X30	31-1619	1	.080
5.00	30X24	31-1620		.080
9.00	36X36	31-1629	2	.080
7.50	36X30	31-1630		.080

R3-3

NO TURNS

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
4.00	24X24	31-1648	1	.080
9.00	36X36	31-1647	2	.080

R3-4

LEGEND - BLACK
BACKGROUND - WHITE
CIRCLE & DIAGONAL - RED

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
4.00	24X24	31-1622	1	.080
9.00	36X36	31-1632	2	.080

R3-5

ONLY (L) ONLY (R)

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
4.00	24X24	31-0135L	1	.080
4.00	24X24	31-0138R	1	.080
7.50	30X36	31-0183L	1	.080
7.50	30X36	31-0184R	1	.080

R3-6

(L) (R)

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
7.50	30X36	31-0157L	1	.080
7.50	30X36	31-0158R	1	.080

R3-7L LEFT LANE MUST TURN LEFT

R3-7R RIGHT LANE MUST TURN RIGHT

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30X30	31-0117L	1	.080
6.25	30X30	31-0118R	1	.080
9.00	36X36	31-0120L	2	.080
9.00	36X36	31-0123R	2	.080

R3-48

ONLY (L) ONLY (R)

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30X30	31-0262L	1	.080
6.25	30X30	31-0261R	1	.080

ONLY

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
7.50	36X30		2	.080

ONLY ONLY

31-0282 31-0283

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
4.00	24X24	31-0125	1	.080
6.25	30X30	31-0165	1	.080
7.50	30X36	31-0175	1	.080

ONLY ONLY

31-0295 31-0219

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
5.00	30X24	31-0290	1	.080

ONLY

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
8.75	42X30	31-0269	2	.100

ONLY ONLY

31-0222 31-0223

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30X30		1	.080

ONLY

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
8.75	42X30	31-0279	2	.100

ONLY ONLY

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
11.25	54X30	31-0337	2	.100

R3-8b

ONLY ONLY

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
10.00	48X30	31-0302	2	.100

ONLY ONLY ONLY

31-0307 31-0372

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
10.00	48X30		2	.100

ONLY

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
8.75	42X30	31-0334	2	.100

ONLY ONLY

31-0370 31-0371

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
8.75	42X30		2	.100

LEFT LANE MUST TURN LEFT

RIGHT LANE MUST TURN RIGHT

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
20.00	48X60	31-0121L	2	.100
20.00	48X60	31-0122R	2	.100

R4 - SERIES

R4-1

DO NOT PASS

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
5.00	24X30	31-1502	1	.080

KEEP RIGHT EXCEPT TO PASS

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
20.00	48X60	31-1574	2	.100

SLOW VEHICLES KEEP RIGHT

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
20.00	48X60	31-1504	2	.100

TRUCKS BUSES TRAILERS LEFT LANE PROHIBITED

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
20.00	48X60	31-1710	2	.100
35.00	60X84	31-1711	2B	.125

R4-3

SLOWER TRAFFIC KEEP RIGHT

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
5.00	24X30	31-1562	1	.080
20.00	48X60	31-1564	2	.100

R4-7

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
5.00	24X30	31-1526	1	.080
12.00	36X48	31-1536	2	.100
20.00	48X60	31-1546	2	.100

R5 - SERIES

R5-1

DO NOT ENTER

LEGEND - WHITE
BACKGROUND - WHITE
CIRCLE - RED

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30X30	31-1119	1	.080
9.00	36X36	31-1120	2	.080
16.00	48X48	31-1121	2	.100

NO PEDESTRIANS BICYCLES MOTOR BIKES MOTOR SCOOTERS

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
9.00	36X36	31-1775	2	.100

R5-1a

WRONG WAY

LEGEND - WHITE
BACKGROUND - RED

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.00	36X24	31-1122	2	.080
8.75	42X30	31-1123	2	.100

EMERGENCY AND AUTHORIZED VEHICLES ONLY

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
5.00	24X30	31-1790	1	.080
20.00	48X60	31-1792	2	.100

PROHIBITED COMMERCIAL VEH TRAILERS COMBINATION VEH OVER 7500 LBS VEH. OVER 8' HIGH MOPEDS - BICYCLES PEDESTRIANS

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
27.00	54X72	31-1719	2	.125

NO PEDESTRIAN CROSSING

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
5.00	30X24	31-1702	1	.080

R5-10c

NO PEDESTRIANS

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
2.00	24X12	31-1774	1	.080

R6 - SERIES

R6-1

(L) ONE WAY
(R) ONE WAY

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
3.00	36X12	31-1188L	1	.080
3.00	36X12	31-1177R	1	.080
6.75	54X18	31-1189L	2	.100
6.75	54X18	31-1178R	2	.100

R7 - SERIES

R7-1

NO PARKING ANY TIME

(R) (L)
(D)
LEGEND - RED
BACKGROUND - WHITE

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
1.50	12X18	31-0630	1	.080

R7-2a

NO PARKING 0:00 AM TO 0:00 PM

VARIABLE TIMES
(R) (L)
(D)
LEGEND - RED
BACKGROUND - WHITE

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
1.50	12X18	31-0603	1	.080

R8 - SERIES

R8-7

EMERGENCY STOPPING ONLY

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
12.00	48X36	31-0670	2	.100

R9 - SERIES

HITCHHIKING PROHIBITED
DO NOT STOP

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
27.50	66X60	31-1733	2	.125

R10 - SERIES

R10-6

STOP HERE ON RED

STOP HERE ON RED

31-0801 31-0802

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.00	24X36		1	.080

R10-11b

NO TURN ON RED

OVERHEAD MOUNTED

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
4.00	24X24	31-0823		.080
9.00	36X36	31-0816	2	.080

RIGHT TURN ON RED FROM RIGHT LANE ONLY

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
7.50	30X36	31-0847	1	.080
20.00	48X60	31-0849	2	.100

DO NOT BLOCK DRIVEWAY

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
5.00	24X30	31-0803	1	.080
12.00	36X48	31-0804	2	.100

R10-10L

LEFT TURN SIGNAL

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
5.00	24X30	31-0842		.080
7.50	30X36	31-0852	1	.080

R10-7

DO NOT BLOCK INTERSECTION

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
5.00	24X30	31-0806	1	.080
12.00	36X48	31-0807	2	.100

R10-11a

NO TURN ON RED

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
7.50	30X36	31-0830	1	.080
12.00	36X48	31-0819	2	.100

R11 - SERIES

R11-1

KEEP OFF MEDIAN

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
5.00	24X30	31-1915	1	.080
20.00	48X60	31-1918	2	.100

RETROREFLECTIVE STRIP

LEGEND - N/A
BACKGROUND - RED

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
1.00	4X36	31-5003	1	.080
2.00	4X72	31-5004	1	.080
2.67	4X96	31-5005	1	.080

NOTES:

FOR METRIC SEE CONVERSION CHART.

1. THE LEGEND "O.S.T.A." SHALL APPEAR ON ALL R- SERIES SIGNS EXCEPT WHEN SUFFIXED WITH THE LETTER "Z".
2. FOR SPECIFIC SIGN DESIGN CONTACT CONN. D.O.T., DIVISION OF TRAFFIC ENGINEERING. FOR BOLT HOLE PATTERN REFER TO FHWA PUBLICATION "STANDARD HIGHWAY SIGNS". SIGNS OF DIFFERENT DIMENSIONS TO BE ERECTED ON THE SAME POSTS, OR SPAN/MAST ARM MOUNTED, MAY REQUIRE SPECIAL BOLT HOLE PATTERNS.
3. POSTS - SEE STANDARD SHEET TR-1208_02 - "METAL SIGN POSTS AND SIGN MOUNTING DETAILS."
4. POSTS SHALL BE 4 LBS./FT.
5. SIGNS SHALL BE FABRICATED OF ONE CONTINUOUS PIECE OF SHEET ALUMINUM. SPLICING OF SHEET ALUMINUM WILL NOT BE ACCEPTED.
6. FOR OVERHEAD MOUNTED SIGNS, SEE STANDARD SHEET TR-1114_01 - "BONDING AND UTILITY POLE ATTACHMENT DETAILS, SIGN HANGER, "Y" CLAMP DETAIL."

COLORS:

BACKGROUND - WHITE (SILVER) - EXCEPT AS NOTED.
LEGEND - BLACK - EXCEPT AS NOTED.
ALL SIGNS TO USE TYPE IX RETROREFLECTIVE SHEETING.

REV.	DATE	REVISION DESCRIPTION
7	6-2017	REVISED POST REQUIREMENTS.
6	12-2016	REMOVED HANDICAPPED SIGN DETAIL.
5	6-2015	REVISED DRAWING NO.
4	5-2015	UPDATED PER MUTCD AND FORM 816 JAN 2015 REVISION.
3	6-2012	REVISED NOTE #1 TO REFERENCE "O.S.T.A."
2	6-2010	INCLUDED SIGNS TO MEET 2009 MUTCD REQUIREMENTS.
1	1-2010	REVISED SHEETING FROM TYPE I TO III.

METRIC CONVERSION CHART (1" = 25mm)

ENGLISH	METRIC	ENGLISH	METRIC	ENGLISH	METRIC
12"	300	42"	1050	72"	1800
18"	450	48"	1200	78"	1950
24"	600	54"	1350	84"	2100
30"	750	60"	1500	90"	2250
36"	900	66"	1650	96"	2400

DESIGNER/DRAFTER: A. S. MERMELSTEIN
CHECKED BY: B. A. SCHILLING
Plotted: 7/2/2018

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: CTDOT_TRAFFIC_GS.dgn

SIGNATURE/BLOCK:
OFFICE OF ENGINEERING
APPROVED BY: DATE:

PROJECT TITLE:
REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8

TOWN:
BRIDGEPORT, TRUMBULL & SHELTON

DRAWING TITLE:
SIGN FACE SHEET ALUMINUM R-SERIES SIGNS TYPICAL DETAILS

PROJECT NO. 173-441
DRAWING NO. TR-GS_01
SHEET NO. 03.39

S - SERIES

S1-1

LEGEND - BLACK
BACKGROUND - FLUORESCENT YELLOW GREEN

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.75	36	41-2112	1	.080
12.00	48	41-2113	2	.100

W1 - SERIES

W1-1L

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30	41-4006	1	.080
9.00	36	41-4031	1	.080
16.00	48	41-4056	2	.100

W1-1R

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30	41-4005	1	.080
9.00	36	41-4160	1	.080
16.00	48	41-4055	2	.100

(L) (R)

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
9.00	36	41-4141L	1	.080
9.00	36	41-4140R	1	.080
16.00	48	41-4062L	2	.100
16.00	48	41-4061R	2	.100

W1-2

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30	41-4028	1	.080
9.00	36	41-4084	1	.080
16.00	48	41-4068	2	.100

W1-2

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30	41-4027	1	.080
9.00	36	41-4083	1	.080
16.00	48	41-4067	2	.100

(L) (R)

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
9.0	36	41-4139L	1	.080
9.0	36	41-4040R	1	.080
16.00	48	41-4088L	2	.100
16.00	48	41-4087R	2	.100

W1-6

(LEFT OR RIGHT)

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
8.00	48X24	41-4222	2	.100
12.50	60X30	41-4224	2	.100

W1-7

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
8.00	48X24	41-4207	2	.100
12.50	60X30	41-4208	2	.100

(L) (R)

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
9.00	36	41-4128L	1	.080
9.00	36	41-4127R	1	.080
16.00	48	41-4058L	2	.100
16.00	48	41-4057R	2	.100

W1-8

(LEFT OR RIGHT)

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
3.00	18X24	41-4250	1	.080
5.00	24X30	41-4203	1	.080
7.50	30X36	41-4204	1	.080
12.00	36X48	41-4251	2	.080

W1-8

LEGEND - BLACK
BACKGROUND - FLUORESCENT YELLOW
(LEFT OR RIGHT)

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
7.50	30X36	41-4211	1	.080
12.00	36X48	41-4260	2	.080

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
9.00	36	41-4053	1	.080

W2 - SERIES

W2-1

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30	41-4226	1	.080
9.00	36	41-4236	1	.080
16.00	48	41-4246	2	.100

W2-2

(LEFT OR RIGHT)

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30	41-4225	1	.080
9.00	36	41-4235	1	.080
16.00	48	41-4245	2	.100

W2-3

(L) (R)

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30	41-4220L	1	.080
6.25	30	41-4219R	1	.080
9.00	36	41-4253L	1	.080
9.00	36	41-4252R	1	.080
16.00	48	41-4244L	2	.100
16.00	48	41-4243R	2	.100

W2-4

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30	41-4217	1	.080
9.00	36	41-4255	1	.080
16.00	48	41-4247	2	.100

W3 - SERIES

W3-1

OCTAGON - RED

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30	41-0501	1	.080
9.00	36	41-0502	1	.080
16.00	48	41-0503	2	.100

W3-2

TRIANGLE - RED & WHITE

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30	41-0504	1	.080
9.00	36	41-0505	2	.100
16.00	48	41-0506	2	.100

W3-3

SYMBOL & LEGEND - BLACK
BACKGROUND - YELLOW
TOP CIRCLE - RED
BOTTOM CIRCLE - GREEN

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30	41-0835	1	.080
9.00	36	41-0836	1	.080
16.00	48	41-0848	2	.100
25.00	60	41-0860	2	.125

W/ FLASHERS

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
25.00	60	41-0534	2	.125

W4 - SERIES

W4-1

(L) (R)

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
9.00	36	41-4448L	1	.080
9.00	36	41-4449R	1	.080
16.00	48	41-4452L	2	.100
16.00	48	41-4459R	2	.100

W4-2

(L) (R)

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
9.00	36	41-4442L	1	.080
9.00	36	41-4441R	1	.080
16.00	48	41-4446L	2	.100
16.00	48	41-4447R	2	.100

W4-3

(L) (R)

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
9.00	36	41-4468L	1	.080
9.00	36	41-4470R	1	.080
16.00	48	41-4435L	2	.100
16.00	48	41-4434R	2	.100

W5 - SERIES

W5-1

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
9.00	36	41-4402	1	.080
16.00	48	41-4404	2	.100

W6 - SERIES

W6-1 W6-2

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
9.00	36	41-4335	1	.080
16.00	48	41-4330	2	.100

W6-3

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
9.00	36	41-4329	1	.080
16.00	48	41-4331	2	.100

W7 - SERIES

W7-1

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30	41-4506	1	.080
9.00	36	41-4530	1	.080
16.00	48	41-4508	2	.100

W8 - SERIES

W8-5

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30	41-4519	1	.080
9.00	36	41-4520	1	.080
16.00	48	41-4521	2	.100

BRIDGE ICES BEFORE ROAD

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
16.00	48	41-4549	2	.100

W9 - SERIES

W9-1

(L) (R)

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
9.00	36	41-4443L	1	.080
9.00	36	41-4440R	1	.080
16.00	48	41-4444L	2	.100
16.00	48	41-4445R	2	.100

W9-2

(L) (R)

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
9.00	36	41-4454L	1	.080
9.00	36	41-4453R	1	.080
16.00	48	41-4456L	2	.100
16.00	48	41-4455R	2	.100

RIGHT LANE EXIT ONLY

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
10.50	36X42	41-4420	2	.100
24.00	48X72	41-4421	2B	.125

W10 - SERIES

W10-1

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
7.07	36	41-2201	1	.080

W11 - SERIES

W11-2

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30	41-4810	1	.080
9.00	36	41-4811	1	.080
16.00	48	41-4812	2	.100

W11-8

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30	41-4680	1	.080
9.00	36	41-4681	1	.080
16.00	48	41-4692	2	.100

W12 - SERIES

W12-1

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
4.00	24	41-4212	1	.080
6.25	30	41-4213	1	.080
9.00	36	41-4215	1	.080
16.00	48	41-4214	2	.100

W12-2

00'-0"

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
9.00	36	41-4706	1	.080
16.00	48	41-4708	2	.100

LEFT LANE (L)
RIGHT LANE (R)

(SUBPLATE)

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
7.50	36X30	41-4729L		.080
7.50	36X30	41-4728R		.080

W13 - SERIES

W13-6

RAMP
00
M.P.H.

LEGEND - BLACK
BACKGROUND - FLUORESCENT YELLOW

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
15.00	36X60	41-5589	2	.100

W13-3

00
M.P.H.

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30X30	41-5573	1	.080

W13-2

EXIT
00
M.P.H.

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
12.00	36X48	41-5586	2	.100
20.00	48X60	41-5596	2	.100

W13-3

RAMP
00
M.P.H.

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
12.00	36X48	41-5581	2	.100
20.00	48X60	41-5598	2	.100

W16 - SERIES

W16-2aP

41-6130 000 FT
41-6136 000 FT
41-6134 0000 FT

(SUBPLATE)
USE AT ADVANCE SIGN LOCATION

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
2.00	24X12	41-6130		.080
3.75	30X18	41-6136		.080
7.00	42X24	41-6134		.100

W16-7PL

(SUBPLATE)
USE WITH W11-2 AT CROSSWALK

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
2.00	24X12	41-2607		.080
3.75	30X18	41-2608		.080

W16-7PR

(SUBPLATE)
USE WITH W11-2 AT CROSSWALK

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
2.00	24X12	41-2609		.080
3.75	30X18	41-2610		.080

W16-2aP

41-6140 000 FT
41-6142 000 FT

(SUBPLATE)
USE AT ADVANCE SIGN LOCATION
LEGEND - BLACK
BACKGROUND - FLUORESCENT YELLOW GREEN

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
2.00	24X12	41-6140		.080
3.75	30X18	41-6142		.080

W16-7PL

(SUBPLATE)
USE WITH S1-1 AT CROSSWALK
LEGEND - BLACK
BACKGROUND - FLUORESCENT YELLOW GREEN

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
2.00	24X12	41-2617		.080
3.75	30X18	41-2618		.080

W16-7PR

(SUBPLATE)
USE WITH S1-1 AT CROSSWALK
LEGEND - BLACK
BACKGROUND - FLUORESCENT YELLOW GREEN

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
2.00	24X12	41-2619		.080
3.75	30X18	41-2620		.080

W16-9P

AHEAD

(SUBPLATE)
USE AT ADVANCE SIGN LOCATION

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
2.00	24X12	41-6125		.080
3.75	30X18	41-6112		.080
6.00	36X24	41-6116		.080
12.00	48X36	41-6115		.100

W16-9P

AHEAD

(SUBPLATE)
USE AT ADVANCE SIGN LOCATION
LEGEND - BLACK
BACKGROUND - FLUORESCENT YELLOW GREEN

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
2.00	24X12	41-6126		.080
3.75	30X18	41-6137		.080
6.00	36X24	41-6138		.080
12.00	48X36	41-6139		.100

RETROREFLECTIVE STRIP

LEGEND - N/A
BACKGROUND - FLUORESCENT YELLOW

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
2.00	4X72	41-5008	1	.080

NOTES:

FOR METRIC SEE CONVERSION CHART.

1. FOR SPECIFIC SIGN DESIGN CONTACT CONN. D.O.T., DIVISION OF TRAFFIC ENGINEERING. FOR BOLT HOLE PATTERN REFER TO FHWA PUBLICATION "STANDARD HIGHWAY SIGNS". SIGNS OF DIFFERENT DIMENSIONS TO BE ERECTED ON THE SAME POSTS, OR SPAN/MAST ARM MOUNTED, MAY REQUIRE SPECIAL BOLT HOLE PATTERNS.
2. POSTS - SEE STANDARD SHEET TR-1208_02 "METAL SIGN POSTS AND SIGN MOUNTING DETAILS."
3. POSTS SHALL BE 4 LBS./FT.
4. SIGNS SHALL BE FABRICATED OF ONE CONTINUOUS PIECE OF SHEET ALUMINUM. SPLICING OF SHEET ALUMINUM WILL NOT BE ACCEPTED.
5. FLUORESCENT YELLOW RETROREFLECTIVE STRIPS SHALL BE INSTALLED ON ALL POSTS FOR S1-1 AND W11-2 SIGNS LOCATED AT CROSSINGS. RETRPREFLECTIVE STRIPS SHOULD NOT BE INSTALLED ON ADVANCE CROSSING WARNING SIGNS. SEE STANDARD SHEET TR-1028_01 "SIGN PLACEMENT AND RETROREFLECTIVE STRIP DETAILS" FOR RETROREFELCTIVE STRIP DETAILS AND INSTALLATION.

COLORS:

BACKGROUND - YELLOW - EXCEPT AS NOTED.
LEGEND - BLACK - EXCEPT AS NOTED.
ALL SIGNS TO USE TYPE IX RETROREFLECTIVE SHEETING.

REV.	DATE	REVISION DESCRIPTION
5	6-2017	REVISED POST REQUIREMENTS.
4	6-2015	REVISED DRAWING NO.
3	5-2015	UPDATED PER MUTCD AND FORM 816 JAN 2015 REVISION.
2	11-2013	UPDATED PER MUTCD.
1	1-2010	REVISED SHEETING FROM TYPE I TO III.

METRIC CONVERSION CHART (1" = 25mm)

ENGLISH	METRIC	ENGLISH	METRIC	ENGLISH	METRIC
12"	300	42"	1050	72"	1800
18"	450	48"	1200	78"	1950
24"	600	54"	1350	84"	2100
30"	750	60"	1500	90"	2250
36"	900	66"	1650	96"	2400

DESIGNER/DRAFTER: A. S. MERMELSTEIN
CHECKED BY: B. A. SCHILLING
Plotted: 7/2/2018

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: CTDOT_TRAFFIC_GS.dgn

SIGNATURE/BLOCK: OFFICE OF ENGINEERING
APPROVED BY: DATE:

PROJECT TITLE: REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8

TOWN: BRIDGEPORT, TRUMBULL & SHELTON

DRAWING TITLE: SIGN FACE SHEET ALUMINUM S&W SERIES SIGNS TYPICAL DETAILS

PROJECT NO. 173-441
DRAWING NO. TR-GS_02
SHEET NO. 03.40

D1 - SERIES

D1-1
51-5202 Variable →
D1-2
51-5203 Variable Variable →

VARIABLE LEGEND & ARROW DIRECTION

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
4.17	60X12	51-5202	2	.100
8.33	60X24	51-5203	2	.100

STATE POLICE →

VARIABLE ARROW DIRECTION

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
4.17	60X10	51-5405	2	.100

D3 - SERIES

D3-1
Variable Road Name

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
4.00	48X12	51-2010	2	.100
5.00	60X12	51-2011	2	.100
6.00	72X12	51-2012	2	.125
7.00	84X12	51-2013	2	.125

D3-1
Variable Road Name

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.00	48X18	51-2004	2	.100
7.50	60X18	51-2001	2	.100
9.00	72X18	51-2002	2	.125
10.50	84X18	51-2003	2	.125

D4 - SERIES

D4-2
PARK - RIDE →

VARIABLE ARROW DIRECTION

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
5.00	24X30	51-6006	1	.080
7.50	30X36	51-6007	1	.080
12.00	36X48	51-6008	2	.100

D4-2
PARK - RIDE →

VARIABLE ARROW DIRECTION

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
5.00	24X30	51-6033	1	.080
7.50	30X36	51-6034	1	.080
12.00	36X48	51-6035	2	.100

D4-2
PARK - RIDE →

VARIABLE ARROW DIRECTION

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
5.00	24X30	51-6044	1	.080
7.50	30X36	51-6045	1	.080
12.00	36X48	51-6046	2	.100

NOTICE
THIS PARKING AREA PATROLLED

LEGEND - BLACK
BACKGROUND - WHITE

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
15.00	60X36	51-5937	2	.100

PARK AT YOUR OWN RISK
REMOVE KEYS AND LOCK CAR
NOT RESPONSIBLE FOR
PROPERTY LOST OR STOLEN

LEGEND - BLACK
BACKGROUND - WHITE

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
4.50	36X18	51-6037	1	.080

D5 - SERIES

D5-2b
REST AREA ↗

LEGEND - WHITE
BACKGROUND - BLUE

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
42.25	78X78	51-6901	2	.125

SERVICE PLAZA ↗

LEGEND - WHITE
BACKGROUND - BLUE

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
39.00	72X78	51-6158	2	.125

D7 - SERIES

D-7
51-6802 Variable →
51-6803 Variable Variable →

W or W/O ARROW
VARIABLE ARROW DIRECTION

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
4.17	60X10	51-6802	2	.100
8.33	60X20	51-6803	2	.100

D9 - SERIES

D9-2
H

** FOR ARROW SUBPLATES
USE M5 & M6 SERIES

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
4.00	24X24	51-6788	1	.080

VARIABLE

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
1.00	24X6	51-6780	1	.080

D9-3a

** FOR ARROW SUBPLATES
USE M5 & M6 SERIES

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
4.00	24X24	51-6762	1	.080

51-6705 DIESEL →
51-6706 FOOD →
51-6707 PHONE →
51-6708 GAS →
51-6709 LODGING →

VARIABLE ARROW DIRECTION

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
2.25	36X9		2	.080

D10 - SERIES

D10-4
NORTH
95
MILE
000

CARDINAL DIRECTION,
SHIELD AND NUMERALS ARE VARIABLE

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.75	18X54	51-5307	1	.080

RECREATIONAL RS- SERIES

RS-054

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
4.00	24X24	51-6873	1	.080

51-2705 ↑
51-2706 L or R →

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
2.19	21X15	51-2705		.080
2.19	21X15	51-2706		.080

VARIABLE
VARIABLE
VARIABLE

LEGEND - WHITE
BACKGROUND - BROWN

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
21.00	72X42	51-2075	2	.125

VARIABLE
VARIABLE

LEGEND - WHITE
BACKGROUND - BROWN

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
15.00	72X30	51-2073	2	.125

E5 - SERIES

E5-1a
EXIT ↖ (L)
EXIT ↗ (R)

FOR USE AT "NO NUMBERED" EXITS

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. # (L or R)	POSTS	ALUM. THK.
30.00	72X60	51-6150	2	.125

E5-1a
EXIT 00 ↖ (L)
EXIT 00 ↗ (R)

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. # (L or R)	POSTS	ALUM. THK.
32.50	78X60	51-6124R	2	.125
32.50	78X60	51-6125L	2	.125

E5-1a
EXIT 00 B ↖ (L)
EXIT 00 B ↗ (R)

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. # (L or R)	POSTS	ALUM. THK.
45.00	108X60	51-6126R	2	.125
45.00	108X60	51-6127L	2	.125

E5-1a
EXIT 00 A-B ↖ (L)
EXIT 00 A-B ↗ (R)

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. # (L or R)	POSTS	ALUM. THK.
57.50	138X60	51-6128R	2	.125
57.50	138X60	51-6129L	2	.125

I - SERIES

I-3
(Variable)
River

VARIABLE: RIVER, BROOK, CREEK

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
1.50	18X12	51-2009	1	.080
4.50	36X18	51-2007	2	.080
12.00	48X36	51-2051	2	.100

TRANSPORTATION CENTER
FERRIES

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
32.00	96X48	51-1337	2B	.125

ATTRACTIONS

LEGEND - WHITE
BACKGROUND - BLUE

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.00	48X18	51-6751	2	.100

→
←

LEGEND - WHITE
BACKGROUND - BLUE

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
8.00	48X24	51-6752	2	.100

INCIDENT MANAGEMENT

N 0 .0 | N 0 0 .0 | N 0 0 0 .0

CARDINAL DIRECTION VARIABLE - N, S, E, W

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
3.00	12X36	51-5103	1	.080
4.00	12X48	51-5104	1	.080
5.00	12X60	51-5105	1	.080

SYMBOL - WHITE
BACKGROUND - BLUE

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
3.00	18X24	51-5943	1	.080

51-6504 Variable
51-6505 Variable Variable

TO BE SUBMOUNTED W/ 51-5943
LEGEND - WHITE
BACKGROUND - BLUE

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
0.75	18X6	51-6504		.080
1.50	18X12	51-6505		.080

M1 - SERIES

M1-1
INTERSTATE CONNECTICUT 00 — 51-6662, 51-6666, VARIABLE: 1 or 2 DIGITS
INTERSTATE CONNECTICUT 000 — 51-6663, 51-6667, VARIABLE: 3 DIGITS

LEGEND - WHITE
BACKGROUND - RED & BLUE

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
3.20	24X24	51-6662	1	.080
3.99	30X24	51-6663	1	.080
7.20	36X36	51-6666	2	.080
8.99	45X36	51-6667	2	.100

M1-4
00 — 51-6615, 51-6635, VARIABLE: 1 or 2 DIGITS
000 — 51-6644, 51-6645, VARIABLE: 3 DIGITS

LEGEND - BLACK
BACKGROUND - WHITE

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
4.00	24X24	51-6615	1	.080
5.00	30X24	51-6644	1	.080
9.00	36X36	51-6635	2	.080
11.25	45X36	51-6645	2	.100

M1-5
00 — 51-6616, 51-6636, VARIABLE: 1 or 2 DIGITS
000 — 51-6647, 51-6646, VARIABLE: 3 DIGITS

LEGEND - BLACK
BACKGROUND - WHITE

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
4.00	24X24	51-6616	1	.080
5.00	30X24	51-6647	1	.080
9.00	36X36	51-6636	2	.080
11.25	45X36	51-6646	2	.100

M2 - SERIES

M2-1
JCT

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	COLOR	ALUM. THK.
2.19	21X15	51-6610	(2)	.080

M3 - SERIES

M3-1
NORTH

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	COLOR	ALUM. THK.
2.00	24X12	51-6651	(1)	.080
2.00	24X12	51-6611	(2)	.080
4.50	36X18	51-6655	(1)	.080
4.50	36X18	51-6625	(2)	.080

M3-2
EAST

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	COLOR	ALUM. THK.
2.00	24X12	51-6652	(1)	.080
2.00	24X12	51-6612	(2)	.080
4.50	36X18	51-6656	(1)	.080
4.50	36X18	51-6626	(2)	.080

M3-3
SOUTH

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	COLOR	ALUM. THK.
2.00	24X12	51-6653	(1)	.080
2.00	24X12	51-6613	(2)	.080
4.50	36X18	51-6657	(1)	.080
4.50	36X18	51-6627	(2)	.080

M3-4
WEST

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	COLOR	ALUM. THK.
2.00	24X12	51-6654	(1)	.080
2.00	24X12	51-6614	(2)	.080
4.50	36X18	51-6658	(1)	.080
4.50	36X18	51-6628	(2)	.080

M4 - SERIES

M4-5
TO

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	COLOR	ALUM. THK.
2.00	24X12	51-6650	(1)	.080
2.00	24X12	51-6620	(2)	.080
3.13	30X15	51-6622	(2)	.080

M5 - SERIES

M5-1
↰ ↱
L or R

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	COLOR	ALUM. THK.
2.19	21X15	51-2690L	(1)	.080
2.19	21X15	51-2691R	(1)	.080
2.19	21X15	51-2630L	(2)	.080
2.19	21X15	51-2631R	(2)	.080

M5-2
↖ ↗
L or R

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	COLOR	ALUM. THK.
2.19	21X15	51-2692L	(1)	.080
2.19	21X15	51-2693R	(1)	.080
2.19	21X15	51-2632L	(2)	.080
2.19	21X15	51-2633R	(2)	.080

M6 - SERIES

M6-1
→
L or R

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	COLOR	ALUM. THK.
2.19	21X15	51-2686	(1)	.080
2.19	21X15	51-2626	(2)	.080

M6-2
↖ ↗
L or R

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	COLOR	ALUM. THK.
2.19	21X15	51-2688L	(1)	.080
2.19	21X15	51-2689R	(1)	.080
2.19	21X15	51-2628L	(2)	.080
2.19	21X15	51-2629R	(2)	.080
4.89	32X22	51-2609R	(2)	.080

M6-3
↑

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	COLOR	ALUM. THK.
2.19	21X15	51-2685	(1)	.080
2.19	21X15	51-2625	(2)	.080

M6-4
↔

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	COLOR	ALUM. THK.
2.19	21X15	51-2697	(1)	.080
2.19	21X15	51-2627	(2)	.080

I - SERIES

VARIABLE
VARIABLE

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	COLOR	ALUM. THK.
3.75	18X32	51-6753	(1)	.040

VARIABLE
VARIABLE
VARIABLE

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	COLOR	ALUM. THK.
15.00	36X60	51-6749	(1)	.040

VARIABLE
VARIABLE
VARIABLE

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	COLOR	ALUM. THK.

MISCELLANEOUS

RAMP SIGNS (SPEED UNDER 40 MPH)
VARIABLE ARROW (DIRECTION), CARDINAL DIRECTION, ROUTE SHIELD (18") AND DESTINATION.
Ⓩ EQUAL SPACING

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
35.00	60X84	51-6557	2	.125

RAMP SIGNS (SPEED UNDER 40 MPH)
VARIABLE ARROW (DIRECTION), CARDINAL DIRECTION, ROUTE SHIELD (18") AND DESTINATION.
Ⓩ EQUAL SPACING

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
42.00	72X84	51-6558	2	.125

NOTES:

FOR METRIC SEE CONVERSION CHART.

1. FOR SPECIFIC SIGN DESIGN CONTACT CONN. D.O.T., DIVISION OF TRAFFIC ENGINEERING. FOR BOLT HOLE PATTERN REFER TO FHWA PUBLICATION "STANDARD HIGHWAY SIGNS". SIGNS OF DIFFERENT DIMENSIONS TO BE ERECTED ON THE SAME POSTS, OR SPAN/MAST ARM MOUNTED, MAY REQUIRE SPECIAL BOLT HOLE PATTERNS.
2. POSTS - SEE STANDARD SHEET TR-1208_02 - "METAL SIGN POSTS AND SIGN MOUNTING DETAILS."
3. POSTS SHALL BE 4 LBS./FT.
4. SIGNS SHALL BE FABRICATED OF ONE CONTINUOUS PIECE OF SHEET ALUMINUM. SPLICING OF SHEET ALUMINUM WILL NOT BE ACCEPTED.

COLORS:

D - SERIES
D1, 2, 3, 4, 10 BACKGROUND-GREEN, LEGEND-WHITE
D7, RS BACKGROUND-BROWN, LEGEND-WHITE
D9 BACKGROUND-BLUE, LEGEND-WHITE
ALL OTHER D-SERIES AS NOTED

E - SERIES
BACKGROUND-GREEN, LEGEND-WHITE

I - SERIES
BACKGROUND-GREEN, LEGEND-WHITE
(EXCEPT AS NOTED)

M2 - M6 SERIES
(1) BACKGROUND-BLUE, LEGEND-WHITE
(2) BACKGROUND-WHITE, LEGEND-BLACK

ALL COLORS SHALL BE TYPE IX RETROREFLECTIVE WITH THE EXCEPTION OF BLACK WHICH SHALL BE OPAQUE.

REV.	DATE	REVISION DESCRIPTION
5	6-2017	REVISED POST REQUIREMENTS.
4	10-2016	ADDED SIGN TO I-3 SERIES.
3	6-2015	REVISED DRAWING TITLE AND NO.
2	5-2015	UPDATED PER MUTCD AND FORM 816 JAN 2015 REVISION.
1	1-2010	REVISED SHEETING FROM TYPE I TO III.

METRIC CONVERSION CHART (1" = 25mm)

ENGLISH	METRIC	ENGLISH	METRIC	ENGLISH	METRIC
12"	300	42"	1050	72"	1800
18"	450	48"	1200	78"	1950
24"	600	54"	1350	84"	2100
30"	750	60"	1500	90"	2250
36"	900	66"	1650	96"	2400

DESIGNER/DRAFTER: A. S. MERMELSTEIN
CHECKED BY: B. A. SCHILLING
Plotted: 7/2/2018

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: CTDOT_TRAFFIC_GS.dgn

SIGNATURE/BLOCK:
OFFICE OF ENGINEERING
APPROVED BY: DATE:
Mark Makuch

PROJECT TITLE:
REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8

TOWN:
BRIDGEPORT, TRUMBULL & SHELTON

DRAWING TITLE:
SIGN FACE SHEET ALUMINUM
D,RS,E,I,&M SERIES SIGNS TYPICAL DETAILS

PROJECT NO. 173-441
DRAWING NO. TR-GS_03
SHEET NO. 03.41