CONNECTICUT DEPARTMENT OF TRANSPORTATION

Plans For

REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8

STATE OF CONNECTICUT

RE-SIGNING in Town(s)/City of

BRIDGEPORT, TRUMBULL & SHELTON

ROAD	MAINTENANCE RESPONSIBILITY	LENGTH
Route 008	STATE	12.5 MILES

F.A.P. #	MAINTENANCE RESPONSIBILITY	PROJECT #
0008(137)CN	STATE	173-441

LOCATION PLAN

NOT TO SCALE

GENERAL NOTES:

1. FEDERAL AID PROJECT NO. 0008(137)
2. CONSTRUCTION SPECIFICATIONS:
   Connecticut Department of Transportation, Standard Specifications for Roads, Bridges and Incidental Construction, Form 817, dated 2016; Supplemental Specifications, dated January 2018; and Special Provisions
3. 400 FOOT GRID BASED ON CONNECTICUT COORDINATE SYSTEM SYSTEM N.A.D. 1927 N.A.D. 1983
4. VERTICAL DATUM BASED ON NGVD OF 1929 NAVD 1988

DISCLAIMER

IT IS THE RESPONSIBILITY OF EACH BIDDER AND ALL OTHER INTERESTED PARTIES TO OBTAIN ALL BIDDING RELATED INFORMATION AND DOCUMENTS FROM OFFICIAL SOURCES WITHIN THE DEPARTMENT.

PERSONS AND/OR ENTITIES WHICH REPRODUCE AND/OR MAKE SUCH INFORMATION AVAILABLE BY ANY MEANS ARE NOT AUTHORIZED BY THE DEPARTMENT TO DO SO AND MAY BE LIABLE FOR CLAIMS RESULTING FROM THE DISSEMINATION OF UNOFFICIAL, INCOMPLETE AND/OR INACCURATE INFORMATION.

LIST OF SUBSETS

SUBSET NO.	SUBSET TITLE	*SUBSET SHEET COUNT
01	GENERAL	2
02	REVISIONS	1
03	TRAFFIC	41
04	EXTRUDED ALUMINUM SIGN PANEL	3
05	SIDE-MOUNTED SIGN STRUCTURE	8
06	TRUSS CANTILEVER SIGN STRUCTURE	6
07	MONOTUBE BRIDGE SIGN STRUCTURE	6
	TRAFFIC STANDARD DRAWINGS	6
	HIGHWAY STANDARD DRAWINGS	8

*THE INITIAL SUBSET SHEET COUNT DOES NOT INCLUDE ADDENDUMS AND CHANGE ORDERS

LIST OF DRAWINGS
SUBSET 01 - GENERAL

DRAWING TITLE	DRAWING NO.
TITLE SHEET	G-1
DETAILED ESTIMATE SHEET	G-2

STANDARD CONVENTIONS

North Arrow W/No. Coor.
Edge Of Road
Concrete Pavement
Dirt Road
B.C.L.C.
Granite Curb
Guide Rail
Concrete Median Barrier
Bit. Walk
Conc. Sidewalk
Railroad Tracks
Grid Arrow
Limit Of Marsh
Stone Wall
Ledge Outcrop
Inland Wetland Limits
STATE LINE
Power Line
Swamp
Building
Transmission Tower
Chain Link Fence
Rustic Fence
Pipe Fence
Board Fence
Water Edge
Stream
Ditch
TOWN LINE
Riprap
Hedge Row
Tree Line
Shrub
Evergreen Tree
Deciduous Tree
Retaining Wall
Highway Line
Street Line
Property Line
Lot Line
Easement Line

THE DESIGN APPEARS TO CONFORM TO APPLICABLE CRITERIA. APPROVAL IS NOT TO BE CONSTRUED TO MEAN THAT ALL ASPECTS OF THE DESIGN HAVE BEEN PERSONALLY CHECKED BY THE UNDERSIGNED.

Mark F. Makuch, P.E.
2018.07.25 14:23:56-04'00'

SUBMITTED BY: TRANSPORTATION PRINCIPAL ENGINEER - MARK F. MAKUCH, P.E.

Mark F. Carlino, P.E.
2018.07.25 16:11:46-04'00'

APPROVAL RECOMMENDED BY: MANAGER OF TRAFFIC ENGINEERING - MARK F. CARLINO, P.E.

Scott Hill, P.E.
2018.08.01 11:10:55-04'00'

APPROVED BY: TRANSPORTATION ENGINEERING ADMINISTRATOR - SCOTT A. HILL, P.E.

Plans For
REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8

Town(s)/City
BRIDGEPORT, TRUMBULL & SHELTON

STATE PROJECT NO.
173-441

DRAWING NO. **G-1**
SHEET NO. **01.01**

FEDERAL AID PARTICIPATING

DESCRIPTION	0020801A ASBESTOS ABATEMENT (L.S.)	0020903A LEAD COMPLIANCE FOR MISCELLANEOUS EXTERIOR TASKS (L.S.)	0201001 CLEARING AND GRUBBING (L.S.)	0219001 SEDIMENTATION CONTROL SYSTEM (L.F.)	0603802A STRUCTURAL STEEL - SIGN SUPPORTS (CWT.)	0910300 METAL BEAM RAIL (R-B MASH) (L.F.)	0911923 R-B END ANCHORAGE TYPE I (EA.)	0913835A REMOVE AND RESET CHAIN LINK FENCE (L.F.)	0952001A SELECTIVE CLEARING AND THINNING (L.S.)	0969062A CONSTRUCTION FIELD OFFICE, MEDIUM (MO.)	0970007 TRAFFICPERSON (UNIFORMED FLAGGER) (HR.)	0971001A MAINTENANCE AND PROTECTION OF TRAFFIC (L.S.)	0975004 MOBILIZATION AND PROJECT CLOSEOUT (L.S.)	0976002 BARRICADE WARNING LIGHTS - HIGH INTENSITY (DAY)	0978002 TRAFFIC DRUM (EA.)	0980001 CONSTRUCTION STAKING (L.S.)	0981100 42" TRAFFIC CONE (EA.)	1130000 HIGH MOUNTED INTERNALLY ILLUMINATED FLASHING ARROW (DAY)	1131002 REMOTE CONTROL CHANGEABLE MESSAGE SIGN (DAY)	1201801A MONOTUBE BRIDGE SIGN STRUCTURE (EA.)	1201804A 4 CHORD TRUSS CANTILEVER SIGN STRUCTURE (EA.)	1202999A DRILLED SHAFT TRAFFIC STRUCTURE FOUNDATION (EA.)	1203109 SIDE MOUNTED SIGN FOUNDATION (EA.)	1203760A PARAPET MOUNTED SIGN SUPPORT (EA.)	1205201 TYPE DE-1 DELINEATOR (EA.)	1205202 TYPE DE-2 DELINEATOR (EA.)	1205203 TYPE DE-3 DELINEATOR (EA.)	1206011 REMOVAL OF EXISTING OVERHEAD SIGNING (L.S.)	1206013 REMOVAL OF EXISTING SIGNING (L.S.)	1207039A SIGN FACE - EXTRUDED ALUMINUM (TYPE IX RETROREFLECTIVE SHEETING) (S.F.)	1208931A SIGN FACE - SHEET ALUMINUM (TYPE IX RETROREFLECTIVE SHEETING) (S.F.)	1220027 CONSTRUCTION SIGNS (S.F.)	1806202 TRUCK-MOUNTED OR TRAILER-MOUNTED IMPACT ATTENUATOR (HR.)	1806226A PRE-WARNING VEHICLE (HR.)
REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8	L.S.	L.S.	L.S.	200	351	1044	8	40	L.S.	27	136	L.S.	L.S.	5200	300	L.S.	150	1040	450	16	13	45	134	11	1000	250	25	L.S.	L.S.	20161	4543	400	4200	682

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OR ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

TRAFFIC DESIGN: DR
ELECTRICAL DESIGN: N/A
DRAFTED: DR
SCALE - NONE

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

SIGNATURE/ BLOCK: **OFFICE OF ENGINEERING**
SUBMITTED BY: N/A
APPROVED BY: N/A DATE:

PROJECT TITLE: **REPLACEMENT OF HIGHWAY SIGNING ON ROUTE 8**

TOWN: **BRIDGEPORT, TRUMBULL, & SHELTON**
DRAWING TITLE: **DETAILED ESTIMATE SHEET**

PROJECT NO. **173-441**
DRAWING NO. **EST-01**
SHEET NO. **01.02**

Filename: \\DOT-SDCENG07V\CTDOT_Projects$\173_0441_2007\Traffic\Signing_Pvmt_Markings_Plans\TR_MSH_EST_173_441.dgn
Plotted: 7/24/2018