03 - DEMOLITION
INDEX OF DRAWINGS

DRAWING NUMBER	DRAWING TITLE	DRAWING NUMBER	DRAWING TITLE
D-001	INDEX OF DRAWINGS		
D-002	ARCHITECTURAL DEMOLITION PLAN		
D-003	MECHANICAL / ELECTRICAL DEMOLITION PLAN		

THE DESIGN APPEARS TO CONFORM TO APPLICABLE CRITERIA. APPROVAL IS NOT TO BE CONSTRUED TO MEAN THAT ALL ASPECTS OF THE DESIGN HAVE BEEN PERSONALLY CHECKED BY THE UNDERSIGNED.

Christopher J. Bonsignore, P.E.
2018.10.29 09:49:37-04'00'

TRANSPORTATION PRINCIPAL ENGINEER

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 10/16/2018

DESIGNER/DRAFTER: SMS

CHECKED BY: SMM

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\FD_MSH_ARC_0160_0151_D001.dgn

SIGNATURE/ BLOCK:
OFFICE OF ENGINEERING

APPROVED BY:

PROJECT TITLE:
THE ROOF REPLACEMENT OF THE REPAIR FACILITY

TOWN: WILLINGTON

DRAWING TITLE: INDEX OF DRAWINGS

PROJECT NO. 160-151

DRAWING NO. D-001

SHEET NO. 03.01



DEMOLITION NOTES:

1. REMOVE EPDM, INSULATION AND WOOD BLOCKING DOWN TO ROOF DECK.
2. REMOVE BALLAST, EPDM, INSULATION AND WOOD BLOCKING DOWN TO ROOF DECK.
3. REMOVE METAL FASCIA AND WOOD BLOCKING ALONG ENTIRE ROOF PERIMETER.
4. REMOVE METAL WALL FLASHING ALONG EXISTING PARAPET WALL.
5. REMOVE GUTTERS AND DOWNSPOUTS.
6. REMOVE EXHAUST FAN CURBS.
7. REMOVE GOOSENECK DUCT CURB FLASHING.
8. REMOVE SANITARY VENT FLASHING.
9. REMOVE AND REINSTALL EXISTING PHOTO-EYE SENSOR AND STAND.
10. REMOVE EXISTING BOILER CHIMNEY BASE CURB AND FLASHING. REMOVE AND REINSTALL EXISTING GUY WIRES AND ANCHORS.
11. REMOVE REMAINING PAINT BOOTH ROOFTOP EQUIPMENT, CURBS AND ANCHORS. PREPARE DECK FOR INFILL.
12. REMOVE GUARDRAIL AND GUARDRAIL ANCHORS.
13. REMOVE ROOF PAVERS.
14. REMOVE ROOF HATCH AND CURB. PREPARE DECK FOR INFILL.
15. REMOVE METAL COPING AT EXISTING PARAPET.
16. REMOVE LADDER AND SUPPORT ATTACHMENTS. EXISTING CONCRETE PAD TO REMAIN.
17. REMOVE ROOF EXPANSION JOINT.
18. REMOVE ROOF EXPANSION JOINT AND WOOD BLOCKING CURB AT STORES ROOF LEVEL. REMOVE EPDM FLASHING AT TRANSITION WALL. EXISTING SUBSTRATE TO REMAIN.

PATCH AREAS DISTURBED BY DEMOLITION TO MATCH EXISTING, INCLUDING MECHANICAL AND ELECTRICAL WORK.

ARCHITECTURAL DEMOLITION PLAN 1 / D-002

SCALE: 3/32" = 1'-0"



KEY PLAN

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 10/16/2018

DESIGNER/DRAFTER: SMS

CHECKED BY: SMM

SCALE AS NOTED

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\FD_MSH_ARC_0160_0151_D002.dgn

SIGNATURE/ BLOCK:

OFFICE OF ENGINEERING

APPROVED BY:

PROJECT TITLE:

THE ROOF REPLACEMENT OF THE REPAIR FACILITY

TOWN: **WILLINGTON**

DRAWING TITLE: **ARCHITECTURAL DEMOLITION PLAN**

PROJECT NO. **160-151**

DRAWING NO. **D-002**

SHEET NO. **03.02**



MECHANICAL DEMOLITION NOTES:

1. REMOVE ALL EXHAUST FANS.
2. REMOVE ALL GOOSENECK VENTS.
3. ALL SANITARY VENTS TO REMAIN.
4. EXISTING BOILER CHIMNEY TO REMAIN.
5. REMOVE VEHICLE EXHAUST FAN, HOSE REELS AND HOSES. EXISTING DUCTWORK TO REMAIN.
6. REMOVE ALL ROOFTOP PAINT BOOTH EQUIPMENT.
7. REMOVE PROPANE TANK AND ACCESSORIES. GROUT AND CAP PIPING AND ABANDON IN GROUND.

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 10/16/2018

DESIGNER/DRAFTER: EAM

CHECKED BY: JAB

SCALE: 3/32" = 1'-0"

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\FD_MSH_MEC_0160_0151_D003.dgn

SIGNATURE/ BLOCK:

OFFICE OF ENGINEERING

APPROVED BY:

PROJECT TITLE:

THE ROOF REPLACEMENT OF THE REPAIR FACILITY

TOWN: WILLINGTON

DRAWING TITLE: MECHANICAL/ELECTRICAL DEMOLITION PLAN

PROJECT NO. 0160-0151

DRAWING NO. D-003

SHEET NO. 03.03