# 07 - GAS MAIN RELOCATION
## INDEX OF DRAWINGS

| DRAWING NUMBER | DRAWING TITLE | DRAWING NUMBER | DRAWING TITLE |
|---|---|---|---|
| GM-01 | INDEX OF DRAWINGS | | |
| GM-02 | RELOCATION PLAN | | |

**FOR INFORMATION ONLY**

DESIGNED BY:
Stantec
STANTEC CONSULTING SERVICES INC.
55 CHURCH STREET, SUITE 601
NEW HAVEN, CT 06510

Andrew Lessard
2018.11.28
14:59:28-05'00'

| REV. | DATE | REVISION DESCRIPTION | SHEET NO. |
|---|---|---|---|
| - | - | - | - |
| - | - | - | - |
| - | - | - | - |
| - | - | - | - |
| - | - | - | - |
| - | - | - | - |

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 11/28/2018

DESIGNER/DRAFTER: **JRA**
CHECKED BY: **AML**
SCALE AS NOTED

**STATE OF CONNECTICUT**
**DEPARTMENT OF TRANSPORTATION**

Filename: ...\GM-01 INDEX OF DRAWINGS.dgn

SIGNATURE/BLOCK:
Stantec Consulting Services Inc.
55 Church Street
Suite 601
New Haven, CT 06510

PROJECT TITLE:
**REHABILITATION OF BRIDGE NO. 00948, ROUTE 34 OVER WEPAWAUG RIVER**

TOWN: **ORANGE**

DRAWING TITLE: **INDEX OF DRAWINGS**

PROJECT NO. **106-127**
DRAWING NO. **GM-01**
SHEET NO. **07.01**

## UTILITY TEST PIT DATA

| WATER (SOUTH CENTRAL CONNECTICUT REGIONAL WATER AUTHORITY) | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| TEST PIT # | BASELINE STATION | BASELINE OFFSET | NORTHING | EASTING | GROUND EL. (FT) | TOP OF PIPE EL. (FT) | UTILITY DESCRIPTION | RELOCATION ANTICIPATED |
| W-1A | STA. 05+25.84 | 10.33' LT | 171543.87 | 522899.46 | 186.02 | 182.96 | 16" CIP* | NO |
| W-1B | STA. 04+93.17 | 10.76' LT | 171564.38 | 522874.29 | 186.18 | 183.97 | 24" STL SLV* | NO |
| W-1C | STA. 04+89.52 | 10.68' LT | 171566.60 | 522871.42 | 186.21 | 184.03 | 24" STL SLV* | NO |
| TELECOMMUNICATIONS (LEVEL 3 COMMUNICATIONS) | | | | | | | | |
| TEST PIT # | BASELINE STATION | BASELINE OFFSET | NORTHING | EASTING | GROUND EL. (FT) | TOP OF CONCRETE ENCASEMENT EL.(FT) | UTILITY DESCRIPTION | RELOCATION ANTICIPATED |
| C-1 | STA. 25+10.11 | 2.75' RT | 171517.23 | 522856.62 | 186.84 | 186.30 | CONCRETE | NO |
| GAS (SOUTHERN CONNECTICUT GAS COMPANY) | | | | | | | | |
| TEST PIT # | BASELINE STATION | BASELINE OFFSET | NORTHING | EASTING | GROUND EL. (FT) | TOP OF PIPE EL. (FT) | UTILITY DESCRIPTION | RELOCATION ANTICIPATED |
| G-1 | STA. 25+10.59 | 14.50' RT | 171507.92 | 522849.44 | 186.63 | 183.79 | 6" PLASTIC* | YES |




**RELOCATION PLAN**

SCALE: 1" = 20'-0"

**FOR INFORMATION ONLY**

| REV. | DATE | REVISION DESCRIPTION | SHEET NO. |
|---|---|---|---|
| - | - | - | - |
| - | - | - | - |
| - | - | - | - |
| - | - | - | - |
| - | - | - | - |
| - | - | - | - |

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 11/28/2018

DESIGNER/DRAFTER: **JRA**

CHECKED BY: **AML**

SCALE AS NOTED

**STATE OF CONNECTICUT**
**DEPARTMENT OF TRANSPORTATION**

Filename: ...\GM-02 RELOCATION PLAN.dgn

SIGNATURE/BLOCK:

Stantec Consulting Services Inc.
55 Church Street
Suite 601
New Haven, CT 06510

PROJECT TITLE:

**REHABILITATION OF BRIDGE NO. 00948, ROUTE 34 OVER WEPAWAUG RIVER**

TOWN: **ORANGE**

DRAWING TITLE: **RELOCATION PLAN**

PROJECT NO. **106-127**

DRAWING NO. **GM-02**

SHEET NO. **07.02**