

CONDUIT SLEEVE DETAIL #1
N.T.S.



CONDUIT SLEEVE DETAIL #3
N.T.S.



CONDUIT SLEEVE DETAIL #2
N.T.S.

NOTES:

1. FOR GENERAL NOTES, SYMBOLS, AND ABBREVIATIONS SEE DWG. NO. SEC-001.
2. CONDUIT SLEEVE SHALL CONTINUE A MINIMUM OF 3'-0" PAST THE END OF THE RAILROAD TIE OR EDGE OF PAVEMENT ABOVE.
3. RGS CONDUIT SLEEVE SHALL BE 4" 3" RGS CONDUIT. 1
4. IF RGS CONDUIT SLEEVE CANNOT CONTINUE A MINIMUM OF 3'-0" PAST THE END OF THE RAILROAD, RGS CONDUIT SLEEVE SHALL CONTINUE TO EXTERIOR OF COMMUNICATIONS MANHOLE, BUT SHALL NOT ENTER MANHOLE. 1
5. THE INSTALLATION OF A SINGLE 3" RGS SLEEVE WITH A 1" DIA. PVC CONDUIT WILL BE INSTALLED UNDER A CONTINUOUS WEEKEND OUTAGE BEGINNING ON FRIDAY NIGHT AT 10PM AND FINISHING ON SUNDAY NIGHT. TRACKS SHALL BE REMOVED FROM SERVICE BY MNR FORCES.
6. THE CONTRACTOR SHALL PERFORM HIS WORK WITH THE TRACK IN PLACE BUT OUT OF SERVICE AND HE MUST CONFIRM THE EXISTING TRACK ELEVATIONS HAVE NOT CHANGED AFTER CONSTRUCTION.
7. THE CONTRACTOR SHALL EXCAVATE THE TRENCH FOR THE 3" DIAMETER SLEEVE, INSTALL THE SLEEVE AND 1" CONDUIT AND BACKFILL AND COMPACT TRENCH AND INSTALL NEW BALLAST AND SUBBALLAST.

STV Incorporated
185 Plains Road
Suite 208E
Milford, CT 06461
Jim Sherwonit
2019.03.13
09:52:55-04'00'

ADDENDUM NO.2

REV.	DATE	REVISION DESCRIPTION	SHEET NO.
1	03/08/2019	REVISE CALLOUTS, ADD NOTES	11.018.A2

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 3/13/2019

DESIGNER/DRAFTER: PE
CHECKED BY: TB
SCALE AS NOTED

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\SEC-302_A2_CNS_SHEET_0300-0138.dgn

SIGNATURE/BLOCK:
STV Incorporated
185 Plains Road
Suite 208E
Milford, CT 06461

PROJECT TITLE:
NEW HAVEN RAIL YARD FACILITIES IMPROVEMENTS WEST END YARD

TOWN: **NEW HAVEN**

DRAWING TITLE: **CONDUIT SLEEVE DETAILS**

PROJECT NO. **0300-0138**
DRAWING NO. **SEC-302**
SHEET NO. **11.018.A2**