06 - LANDSCAPE

INDEX OF DRAWINGS

DRAWING NUMBER	DRAWING TITLE	DRAWING NUMBER	DRAWING TITLE
LDS-01	**LANDSCAPE INDEX SHEET**		
LDS-02	**LANDSCAPE DESIGN SHEET**		

THE DESIGN APPEARS TO CONFORM TO APPLICABLE CRITERIA. APPROVAL IS NOT TO BE CONSTRUED TO MEAN THAT ALL ASPECTS OF THE DESIGN HAVE BEEN PERSONALLY CHECKED BY THE UNDERSIGNED.

Erik A. Jarboe, P.E.
2018.11.16 10:37:03-05'00'

TRANSPORTATION PRINCIPAL ENGINEER

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 10/5/2018

DESIGNER/DRAFTER: MV

CHECKED BY: EJ

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\HW_MSH_0060-0158_LDS_INDEX.dgn

SIGNATURE/ BLOCK:

OFFICE OF ENGINEERING

APPROVED BY:

Matthew Vaid

PROJECT TITLE:

REHABILITATION OF BRIDGE NO. 06728, ROUTE 9 OVER POLE BRIDGE BROOK

TOWN: **HADDAM**

DRAWING TITLE: **LANDSCAPE INDEX SHEET**

PROJECT NO. **60-158**

DRAWING NO. **LDS-01**

SHEET NO. **06.01**

PERMIT PLANT LIST

KEY	BOTANICAL NAME	COMMON NAME	SIZE	QTY.	SPACING	WETLAND INDICATOR
Am.c.	Amelanchier canadensis	Shadblow Serviceberry	4'-5' Ht. B.B.	9	Field Locate	FAC
A.r.	Acer Rubrum	Red Maple	2 1/2" - 3" Cal. B.B.	7	Field Locate	FAC
A.r.w.	Acer Rubrum	Red Maple	3' - 4' Ht. Whips B.R.	38	Field Locate	FAC
C.s.	Cornus sericea	Redosier Dogwood	24"-36" Ht. Cont.	7	Field Locate	FACW
Q.r.w.	Quercus rubra	Northern Red Oak	24" - 36" Ht. No. 3 Cont.	38	Field Locate	FACU
V.d	Viburnum dentatum	Arrowwood Viburnum	24" - 36" Ht. No. 3 Cont.	10	Field Locate	FAC
Control and Removal of Invasive Vegetation				1075 S.Y.		
Conservation Seeding for Slopes				1075 S.Y.		
Wetland Grass Establishment				215 S.Y.		
Wood Chip Mulch				275 S.Y.		

NOTES

1. PLANTINGS ON THIS SHEET ARE FOR ENVIRONMENTAL PERMITTING. ANY CHANGES TO PERMIT PLANTINGS SHALL BE COORDINATED WITH THE DEPARTMENT'S OFFICE OF ENVIRONMENTAL PLANNING.

2. WOOD CHIP MULCH SHALL NOT BE PLACED IN THE WETLAND AREA.

3. ALL SHRUBS MUST CONFORM TO THE AMERICAN STANDARD FOR NURSERY STOCK FOR DECIDUOUS SHRUBS, CHAPTER THREE, AND MEET THE MINIMUM CONTAINER SIZE AND ROOT MASS AND NUMBER OF CANES FOR TYPE AND HEIGHT SPECIFIED.

4. ALL PLANTS SHALL BE STRAIGHT SPECIES. NO VARIETIES OR CULTIVARS WILL BE ACCEPTED.

5. DISTURBED AREAS BELOW THE WETLAND LIMIT SHALL BE SEEDED WITH A WETLAND SEED MIX. DISTURBED AREAS ABOVE THE WETLAND LIMIT SHALL BE COVERED WITH WOOD CHIP MULCH OR CONSERVATION SEED MIX FOR SLOPES UNLESS OTHERWISE NOTED.

6 ACER RUBRUM - 2 1/2" - 3" Cal. B.B. TO BE DUG IN THE SPRING ONLY

KEY

CONTROL AND REMOVAL OF INVASIVE VEGETATION



REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 10/5/2018

DESIGNER/DRAFTER: MV

CHECKED BY: EJ

SCALE IN FEET 0 40 80

SCALE 1"=40'

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\HW_MSH_0060-0158_LDS.dgn

SIGNATURE/ BLOCK:
OFFICE OF ENGINEERING

APPROVED BY:
Matthew Paul

PROJECT TITLE:
REHABILITATION OF BRIDGE NO. 06728, ROUTE 9 OVER POLE BRIDGE BROOK

TOWN: HADDAM

DRAWING TITLE: LANDSCAPE DESIGN SHEET

PROJECT NO. 60-158

DRAWING NO. LDS-02

SHEET NO. 06.02