

2019 PAVEMENT PRESERVATION PROGRAM - MILL AND OVERLAY - 11/26/2018

MILL AND OVERLAY															
DISTRICT 1															
ROUTE	DIRECTION	TOWN	LOG TERMINI	START MILE POINT	END MILE POINT	CENTERLINE MILES	LANE MILES	ADT	MAINLINE PAVEMENT SCOPE	RAMP PAVEMENT SCOPE	TRAVEL AREA SY	SHOULDER AREA SY	MAINLINE AREA SY	RAMP AREA SY	NOTES
91	N	WINDSOR	NB-END OP CAPEN ST TO WINDSOR - WINDSOR LOCKS TL	44.12	48.58	13.30	56.53	147200	<ul style="list-style-type: none"> Travel Lanes, HOV Lane, and Gores: (in location of existing Ultra Thin surface) <ul style="list-style-type: none"> Fine Mill 2.625" Pothole Patching Surface Patching (with mill) Crack Filling Pave 0.625" Ultra Thin Bonded PMA, on 2" PMA S0.5 Traffic Level 3 	<ul style="list-style-type: none"> Fine Mill 2.625" Pothole Patching Surface Patching (with mill) Crack Filling Pave 0.625" Ultra Thin Bonded PMA, on 2" PMA S0.5 Traffic Level 3 	397951	192957	590908	122534	<ul style="list-style-type: none"> Includes HMA Smoothness Adjustment Includes Uniform Placement and Compaction
		WINDSOR LOCKS	WINDSOR - WINDSOR LOCKS TL TO WINDSOR LOCKS - EAST WINDSOR TL	48.58	49.77										
		EAST WINDSOR	WINDSOR LOCKS - EAST WINDSOR TL TO 0.19 MI S/O NB EXIT TO RTE 140 (104)	49.77	50.77										
	S	WINDSOR	SB-END OP CAPEN ST TO WINDSOR - WINDSOR LOCKS TL	44.12	48.58										
		WINDSOR LOCKS	WINDSOR - WINDSOR LOCKS TL TO WINDSOR LOCKS - EAST WINDSOR TL	48.58	49.77										
		EAST WINDSOR	WINDSOR LOCKS - EAST WINDSOR TL TO .01 MI S/O SB EXIT TO US 5 (103)	49.77	50.77										
187	N/S	BLOOMFIELD	0.23 MI S/O RTE 305 (OLD WINDSOR RD) TO BLOOMFIELD - WINDSOR TL	4.92	6.88	3.11	11.86	18100	<ul style="list-style-type: none"> Fine Mill 2" Pothole Patching Surface Patching (with mill) Crack Filling Pave 2" PMA S0.5 Traffic Level 3 	N/A	81776	10837	92613	N/A	<ul style="list-style-type: none"> Includes Uniform Placement and Compaction
		WINDSOR	BLOOMFIELD - WINDSOR TL TO WINDSOR - BLOOMFIELD TL	6.88	7.75										
		BLOOMFIELD	WINDSOR - BLOOMFIELD TL TO 0.16 MI N/O JCT RTE 189	7.75	8.03										
DISTRICT 2															
ROUTE	DIRECTION	TOWN	LOG TERMINI	START MILE POINT	END MILE POINT	CENTERLINE MILES	LANE MILES	ADT	MAINLINE PAVEMENT SCOPE	RAMP PAVEMENT SCOPE	TRAVEL AREA SY	SHOULDER AREA SY	MAINLINE AREA SY	RAMP AREA SY	NOTES
349	N/S	GROTON	SHENNECOSSETT RD TO SR 649 (RAINVILLE AVE)	0.00	2.30	2.30	5.94	20400	<ul style="list-style-type: none"> Partial Depth Patching Fine Mill 2.25" Pothole Patching Surface Patching (with mill) Crack Filling Pave 2.25" PMA S0.5 Traffic Level 3 	<ul style="list-style-type: none"> Fine Mill 2.25" Pothole Patching Surface Patching (with mill) Crack Filling Pave 2.25" PMA S0.5 Traffic Level 3 	41814	9668	51482	17062	<ul style="list-style-type: none"> Includes Uniform Placement and Compaction
			SR 649 (RAINVILLE AVE) TO 0.11 MI S/O END RTE 349	2.30	4.06										
DISTRICT 3															
ROUTE	DIRECTION	TOWN	LOG TERMINI	START MILE POINT	END MILE POINT	CENTERLINE MILES	LANE MILES	ADT	MAINLINE PAVEMENT SCOPE	RAMP PAVEMENT SCOPE	TRAVEL AREA SY	SHOULDER AREA SY	MAINLINE AREA SY	RAMP AREA SY	NOTES
110	N/S	STRATFORD	0.08 MI N/O OP FREEMAN BROOK TO STRATFORD - SHELTON TL	3.00	4.35	3.68	9.16	33400	<ul style="list-style-type: none"> Fine Mill 2.75" Pothole Patching Surface Patching (with mill) Crack Filling Pave 2.75" PMA S0.5 Traffic Level 3 	N/A	71551	30392	101943	N/A	<ul style="list-style-type: none"> Includes Uniform Placement and Compaction Coordination with Project No. 0783-2, Sikorsky Facility Entrance Realignment, will be required; Limits are Mile Point 3.48 - 3.70
		SHELTON	STRATFORD - SHELTON TL TO 0.19 MI N/O CONSTITUTION BLVD SOUTH (SB)	4.35	6.68										
DISTRICT 4															
ROUTE	DIRECTION	TOWN	LOG TERMINI	START MILE POINT	END MILE POINT	CENTERLINE MILES	LANE MILES	ADT	MAINLINE PAVEMENT SCOPE	RAMP PAVEMENT SCOPE	TRAVEL AREA SY	SHOULDER AREA SY	MAINLINE AREA SY	RAMP AREA SY	NOTES
202	N/S	LITCHFIELD	0.08 MI N/O OP BANTAM RV TO LITCHFIELD - TORRINGTON TL	39.27	41.70	3.96	8.56	9300	<ul style="list-style-type: none"> Partial Depth Patching Fine Mill 2.25" Pothole Patching Surface Patching (with mill) Crack Filling Pave 2.25" PMA S0.5 Traffic Level 2 	N/A	59625	33606	93231	N/A	<ul style="list-style-type: none"> Includes Uniform Placement and Compaction
		TORRINGTON	LITCHFIELD - TORRINGTON TL TO 0.05 MI N/O OP GULF STREAM	41.70	43.23										
MILL AND OVERLAY TOTALS						28.11	99.73				706920	288014	994935	139596	