

FINISH FLOOR = 608.2 GARAGE FLOOR = N/A CELLAR FLOOR = N/A

RESTRICTIVE FLOW

45.0 FT/81.0 FT x 150 GPD/BEDROOM x 3 BEDROOMS = 250.0 GPD (TOTAL DAILY DISCHARGE) SHALL CONTACT A TESTING LABORATORY TO COME AND TAKE A COMPOSITE SAMPLE OF THE IN-PLACE SEPTIC FILL AND HAVE A SIEVE TEST PERFORMED, IT IS RECOMMENDED THAT THE SYSTEM NOT BE INSTALLED UNTIL THE SEPTIC FILL HAS PASSED THE SIEVE TEST.

-PER TORRINGTON AREA HEALTH DISTRICT REGULATIONS, THE DESIGN ENGINEER WILL INSPECT THE SEPTIC SYSTEM PRIOR TO BACKFILLING AND PREPARE A SEPTIC SYSTEM RECORD DRAWING.

AND PREPARE A SEPTIC SYSTEM RECORD DRAWING.
-IT IS THE CONTRACTORS RESPONSIBILITY TO NOTIFY THE DESIGN ENGINEER 48 HOURS PRIOR TO ANY REQUIRED TESTS OR INSPECTIONS.

— — — OOO — — EXISTING CONTOUR PROPERTY LINE SEDIMENTATION CONTROL FENCE DEEP HOLE TEST PERCOLATION HOLE TEST

GREY WATER OUTLET

REQUIRED PROVIDED EFFECTIVE LEACHING AREA 900**.**0 SF 450.0 SF MINIMUM LEACHING SYSTEM SPREAD 81**.**0 FT 45.0 FT DISTANCE TO A DOWN GRADIENT PROPERTY LINE-LEACHING AREA 25**.**0 FT 6.6 FT DISTANCE TO A LATERAL PROPERTY LINE-LEACHING AREA 15**.**0 FT 10.0 FT DISTANCE TO A WATER SUPPLY WELL-SEPTIC TANK 75**.**0 FT 45**.**4 FT DISTANCE TO A WATER SUPPLY WELL-LEACHING AREA 75**.**0 FT 57**.**8 FT



