SUBSET 06 - LANDSCAPE
INDEX OF DRAWINGS

DRAWING NUMBER	DRAWING TITLE	DRAWING NUMBER	DRAWING TITLE
INX-01	LANDSCAPE DESIGN - INDEX OF DRAWINGS		
LDS-01	LANDSCAPE DESIGN SHEET		

THE DESIGN APPEARS TO CONFORM TO APPLICABLE CRITERIA. APPROVAL IS NOT TO BE CONSTRUED TO MEAN THAT ALL ASPECTS OF THE DESIGN HAVE BEEN PERSONALLY CHECKED BY THE UNDERSIGNED.

Erik A. Jarboe, P.E.
2019.07.15
13:13:50-04'00'

TRANSPORTATION PRINCIPAL ENGINEER

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/11/2019

DESIGNER/DRAFTER: MM

CHECKED BY: SF

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\LDS_0129_0115_INX-01.dgn

SIGNATURE/ BLOCK:
OFFICE OF ENGINEERING

APPROVED BY:

PROJECT TITLE:
REPLACEMENT OF BR. NO. 00681 - HUNTINGTON RD. 9 (RTE 14) OVER MERRICK BROOK

TOWN: SCOTLAND

DRAWING TITLE:
LANDSCAPE DESIGN - INDEX OF DRAWINGS

PROJECT NO. 123-066

DRAWING NO. INX-01

SHEET NO. 06.01



LANDSCAPE ITEM LIST

KEY	BOTANICAL NAME	COMMON NAME	Size	Quantity	Comments
A.i.	Alnus incana	Speckled Alder	4' - 5' Ht. B.B.	15	
C.s.	Cornus sericiea	Red osier Dogwood	24" - 36"' Ht. B.B.	23	
S.n.	Salix nigra	Black Willow	1 3/4" - 2" Cal. B.B.	2	
0952051A	Control and Removal of Invasive Vegetation			640 S.Y.	See Special Provision
0950040A	Conservation Seeding for Slopes			260 S.Y.	See Special Provision
0950043A	Wetland Grass Establishment			2500 S.F.	See Special Provision

LEGEND

CONTROL AND REMOVAL OF INVASIVE VEGETATION

CONSERVATION SEEDING FOR SLOPES

NOTES

1. PLANTINGS ON THIS SHEEET ARE FOR ENVIRONMENTAL PERMITTING. ANY CHANGES TO PERMIT PLANTINGS SHALL BE COORDINATED WITH THE DEPARTMENT'S OFFICE OF ENVIRONMENTAL PLANNING.
2. ALL TREES AND SHRUBS MUST CONFORM TO THE AMERICAN STANDARD FOR NURSERY STOCK FOR DECIDUOUS SHRUBS, CHAPTER THREE AND MEET THE MINIMUM CONTAINER SIZE AND ROOT MASS AND NUMBER OF CANES FOR TYPE AND HEIGHT.
3. ALL PLANTS SHALL BE STRAIGHT SPECIES. NO VARIETIES OR CULTIVARS WILL BE ACCEPTED.
4. DISTURBED AREAS BELOW THE WETLAND LINE SHALL BE SEEDED WITH WETLAND SEED MIX. DISTURBED AREAS ABOVE THE WETLAND LIMIT SHALL BE COVERED WITH WOOD CHIP MULCH OR CONSERVATION SEEDING FOR SLOPES UNLESS OTHERWISE NOTED.
5. THE EXACT QUANTITIES AND LIMITS FOR CONTROL AND REMOVAL OF INVASIVE VEGETATION SHALL BE FIELD DETERMINED.
6. LIMITS OF CONSERVATION SEEDING FOR SLOPES ARE APPROXIMATE AND WILL BE FINALIZED IN THE FIELD. REFER TO SPECIAL PROVISIONS FOR ADDITIONAL INFORMATION. THE CONTRACTOR SHALL COORDINATE SEEDING WITH THE OPTIMAL DATES INDICATED.
7. ALL AREAS DEVELOPED AND MAINTAINED AS LAWN BY ADJACENT PROPERTY OWNERS PRIOR TO CONSTRUCTION SHALL BE GRADED, PREPARED AND SEEDED TO RESTORE EXISTING CONDITIONS.
8. THE CONTRACTOR IS RESPONSIBLE FOR THE PROTECTION OF SEEDED AREAS THROUGHOUT THE CONTRACT AND WARRANTY PERIOD.

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/15/2019

DESIGNER/DRAFTER: MM

CHECKED BY: SF

SCALE IN FEET 0 40 80

SCALE 1"=40'

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\Landscape\123-066_LDS_01.dgn

SIGNATURE/ BLOCK:

OFFICE OF ENGINEERING

APPROVED BY:

Matthew Vail

PROJECT TITLE:

REPLACEMENT OF BR. NO. 00681 - HUNTINGTON RD. 9 (RTE 14) OVER MERRICK BROOK

TOWN: SCOTLAND

DRAWING TITLE: LANDSCAPE DESIGN SHEET

PROJECT NO. 123-066

DRAWING NO. LDS-01

SHEET NO. 06.02