

UConn HEALTH

INVITATION TO BID
ADDENDUM
UCHC ITB-10 Form
Rev. 2/15

Margaret Gilbert
Buyer
860-679-1988
Telephone Number
mgilbert@uchc.edu
E-mail Address
860-284-5873
Fax Number

UNIVERSITY OF CONNECTICUT HEALTH CENTER
Procurement Operations & Contracts
263 Farmington Avenue, MC4036
Farmington, CT 06032-4036

ITB NUMBER:	BID DUE DATE:	BID DUE TIME:	ITB SURETY:
UCHC4-123234402	October 29, 2019	2:00 PM EST	10% Bid Bond with Response
ITB TITLE: 14-601.07 Munson Switch Gear - 16 Munson Road			

ADDENDUM NUMBER: 4

DATE ADDENDUM ISSUED: October 17, 2019

FOR: The University of Connecticut Health Center

NOTE: The following responses to supplier questions shall become part of the bid documents, supplier response and any resulting contract. This addendum is two (2) pages in length, the remainder of pages are included herein by reference.

This Addendum must be *Signed & Returned* with your bid.

Authorized Signature of Bidder

Company Name

Approved By: _____

[Margaret Gilbert]

Buyer

(Original Signature on Document in Procurement Files)

UConn Health - UCHC4-123234402 14-601.07 Munson Switch Gear 16 Munson Road P3044B

Question #	Supplier Question	UConn Health Response
1	AIC rating of gear and equipment	Rating of equipment is not evident on cabinet. Contractor shall field verify prior to shop drawings. Assume 100K AIC for bidding.
2	Note (5) on plan E5 - (Comes from note 5 on print E 5 GFCI trip) Could we get more detail (CONTRACTOR SHALL PROVIDE ALARM MONITORING OF THE ATS POSITION WITH EXISTING ECC, COORDINATE TIE-IN/TERMINATION LOCATION WITH OWNER)	Note #5 on Drawing E5 was deleted via Addendum #3. Note #5 on Sheet E1 requires provision of position indicating contacts in the ATS and wiring/programming this into the existing Building Management System for monitoring.
3	Proposed route for getting to area of work, how much weight can it handle. Looking at using concrete buggy to drive concrete into building	The flooring appears to be standard raised floor, floor will need to be braced.
4	Would add alternate (1) be priced after contractor awarded job and then can get rep in to gear to get plan on retro fitting panels?	Yes this add alternate will be priced after award if required.
5	Note 4 on print E 3 - If wires coming in from generator existing and or Utilities for main or branch feeders for some reason are not long enough to reach lugs will be needed to pull in new conductors or high press and extend existing. Would either of those be a change to contract or should it be included. If so, is there lengths of wire existing?	We would expect efforts will be made to negate the need for extension of existing cabling, but will accept high-press splices if required.