05 - TRAFFIC
INDEX OF DRAWINGS

DRAWING NUMBER	DRAWING TITLE	DRAWING NUMBER	DRAWING TITLE	DRAWING NUMBER	DRAWING TITLE
TRA-01	INDEX OF DRAWINGS				
TRA-02	MPT PLAN-1				
TRA-03	MPT PLAN-2				
TRA-04	DETOUR PLAN				
TRA-05	SIGN FACE SHEET ALUMINUM R-SERIES SIGNS TYPICAL DETAILS				
TRA-06	SIGN FACE SHEET ALUMINUM S&W SERIES SIGNS TYPICAL DETAILS				
TRA-07	SIGN FACE SHEET ALUMINUM D,RS,E,I,&M SERIES SIGNS TYPICAL DETAILS				

DESIGNED BY:
GM2 ASSOCIATES, INC.
115 GLASTONBURY BLVD.
GLASTONBURY, CT 06033

STATE OF CONNECTICUT
JAGDEESH GOPAL
LICENSED
PROFESSIONAL ENGINEER

Jagdeesh Gopal
2019.07.16
18:32:08-04'00'

REV.	DATE	REVISION DESCRIPTION	SHEET NO.
-	-	-	-
-	-	-	-
-	-	-	-
-	-	-	-
-	-	-	-
-	-	-	-

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/16/2019

DESIGNER/DRAFTER: **MJM**
CHECKED BY: **SJ**
SCALE AS NOTED

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_41_118_INDEX.dgn

SIGNATURE/BLOCK:
GM2 ASSOCIATES, INC.
115 GLASTONBURY BLVD.
GLASTONBURY, CT 06033

PROJECT TITLE:
REPLACEMENT OF BRIDGE NO. 02018 ROUTE 66 OVER POCOTOPAUG CREEK

TOWN: **EAST HAMPTON**

DRAWING TITLE: **INDEX OF DRAWINGS**

PROJECT NO. **041-118**
DRAWING NO. **TRA-01**
SHEET NO. **05.01**

STAGE 1A, 1B & 1C
NOT TO SCALE

LEGEND:

- SIGN - 1 POST
- SIGN - 2 POSTS
- SIGN ON TEMPORARY SIGN SUPPORT
- CONSTRUCTION BARRICADE - TYPE III
- TRAFFIC DRUM
- TEMPORARY PRECAST CONCRETE BARRIER CURB (TPCBC)
- TEMPORARY SAND BARRELS
- CONSTRUCTION THIS STAGE
- DIRECTION OF TRAFFIC

SIGN LEGEND:

A	STOP	31-0557
B	ROAD CLOSED	80-9080
C	SIDEWALK CLOSED	80-9076
G	BUSINESS ACCESS →	50-5934
A-1	PRIVATE DRIVE NO THRU TRAFFIC	80-9928

M&PT GENERAL NOTES:

1. SIGNS IN THE ADVANCE WARNING AREA ARE TO BE LOCATED AS DIRECTED BY THE ENGINEER.
2. SERIES 16 SIGNS ARE TO BE LOCATED BY THE ENGINEER
3. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE SPECIAL PROVISIONS FOR SECTION 1.08 PROSECUTION AND PROGRESS AND ITEM NO. 0971001A MAINTENANCE AND PROTECTION OF TRAFFIC.
4. EXISTING SIGNS ARE TO BE RELOCATED AS NEEDED AND AS DIRECTED BY THE ENGINEER DURING CONSTRUCTION SO THAT THEY ARE IN THE APPROPRIATE LOCATION AND VISIBLE TO MOTORISTS. THIS WORK WILL BE PAID FOR UNDER ITEM NO. 0971001A MAINTENANCE AND PROTECTION OF TRAFFIC.
5. ALL CONSTRUCTION SIGNS TO BE INSTALLED ON BREAKAWAY POSTS PER TRAFFIC STANDARD SHEETS TR-1208-01, TR-1208-02, AND TR-1220-02.
6. THE LOCATIONS OF TEMPORARY SIGNS SHOWN ON THE PLANS ARE APPROXIMATE AND SHALL BE ADJUSTED BY THE CONTRACTOR AS DIRECTED BY THE ENGINEER TO MEET FIELD CONDITIONS.
7. ANY EXISTING SIGNING DAMAGED BY THE CONTRACTOR SHALL BE REPLACED AT NO COST TO THE STATE.
8. EXISTING ILLUMINATION SHALL REMAIN OPERATIONAL AT ALL TIMES.
9. ALL ADVANCE WARNING SIGNS ARE TO REMAIN IN PLACE UNTIL THEIR REMOVAL IS REQUESTED BY THE ENGINEER.
10. THE LOCATIONS OF TRAFFIC CONTROL DEVICES SHOWN ON THE PLANS ARE APPROXIMATE AND SHALL BE ADJUSTED BY THE CONTRACTOR TO MEET FIELD CONDITIONS.
11. TEMPORARY PAVEMENT MARKINGS APPLIED FOR STAGE 1A, 1B & 1C TO BE TEMPORARY PLASTIC PAVEMENT MARKING TAPE UNLESS STATED OTHERWISE. ALL OTHER TEMPORARY PAVEMENT MARKINGS TO BE HOT-APPLIED PAINTED PAVEMENT MARKINGS UNLESS STATED OTHERWISE.

SUGGESTED SEQUENCE OF CONSTRUCTION

- SEE DWG. NO. STR-06 & STR-07 FOR STAGE CONSTRUCTION DETAILS AT THE PROPOSED BRIDGE.
- SEE DWG. NO. TRA-04 FOR DETOUR AND ADVANCE SIGNING PLAN DURING STAGE 1.

STAGE 1A, 1B & 1C:

1. INSTALL ADVANCE WARNING SIGNS AS SHOWN IN DWG. NO. TRA-04.
2. EVERSOURCE TO RELOCATE UTILITY POLES AND OVERHEAD WIRES. CONTRACTOR TO COORDINATE WITH EVERSOURCE AND OTHER UTILITY COMPANIES ON THE POLES.
3. CONSTRUCT TEMPORARY BITUMINOUS CONCRETE DRIVEWAY ON NORTHEAST AND NORTHWEST CORNERS OF THE BRIDGE.
4. INSTALL DETOUR SIGNS AS SHOWN IN DWG. NO. TRA-04 AND ADDITIONAL SIGNS SHOWN ON THIS SHEET.
5. DETOUR ALL TRAFFIC AS SHOWN IN DWG. NO. TRA-04.
6. DEMOLISH EXISTING BRIDGE AND INSTALL PROPOSED CULVERT. PERFORM ALL WORK AS DESCRIBED IN DWG. NO. STR-06.

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/16/2019

DESIGNER/DRAFTER: SJ
CHECKED BY: VAA
NOT TO SCALE

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_MPT-1_41_118.dgn

SIGNATURE/BLOCK:
GM2 ASSOCIATES, INC.
115 GLASTONBURY BLVD.
GLASTONBURY, CT 06033

PROJECT TITLE:
REPLACEMENT OF BRIDGE NO. 02018 ROUTE 66 OVER POCOTOPAUG CREEK

TOWN: **EAST HAMPTON**

DRAWING TITLE: **MPT PLAN - 1**

PROJECT NO. **041-118**
DRAWING NO. **TRA-02**
SHEET NO. **05.02**

STAGE 2
NOT TO SCALE

ADVANCE SIGNING PLAN - STAGE 2
NOT TO SCALE

LEGEND:

- SIGN - 1 POST
- SIGN - 2 POSTS
- SIGN ON TEMPORARY SIGN SUPPORT
- CONSTRUCTION BARRICADE - TYPE III
- TRAFFIC DRUM
- TEMPORARY PRECAST CONCRETE BARRIER CURB (TPCBC)
- TEMPORARY SAND BARRELS
- CONSTRUCTION THIS STAGE
- DIRECTION OF TRAFFIC

SIGN LEGEND:

E	CONSTRUCTION AHEAD / SIDEWALK USE RESTRICTED / STATE LIABILITY LIMITED / GENERAL STATUTES "SEC 13a-115, 13a-149"	80-1619	U	ROAD WORK AHEAD / FINES DOUBLED	31-1907
F	DETOUR	80-9703	V	ROAD WORK AHEAD	80-9603
N	DETOUR	80-9703	W	END ROAD WORK	80-9612
G	BUSINESS ACCESS	50-5934	X		80-9432 (L)
J	CONSTRUCTION AHEAD / ROAD USE RESTRICTED / STATE LIABILITY LIMITED / GENERAL STATUTES SEC 13a-115, 13a-149 / COMMISSIONER OF TRANSPORTATION	80-1608	Y		31-1629
Z					

M&PT GENERAL NOTES:

1. INSTALL BARRICADE WARNING LIGHTS - HIGH INTENSITY ON ALL POST MOUNTED DIAMOND SIGNS IN THE ADVANCE WARNING AREA.
2. TYPE DE-7 DELINEATORS SHALL BE INSTALLED ON THE TPCBC AS SPECIFIED ON THE STANDARD SHEET TR-1205_01 "DELINEATION, DELINEATOR AND OBJECT MARKER DETAILS".

SUGGESTED SEQUENCE OF CONSTRUCTION

STAGE 2:

1. INSTALL ADVANCE WARNING SIGNS AS SHOWN ON THIS SHEET.
2. INSTALL TPCBC AND OTHER TRAFFIC CONTROL DEVICES AS SHOWN.
3. INSTALL TEMPORARY PAVEMENT MARKINGS ON ROUTE 66 AS SHOWN.
4. OPEN ROUTE 66 TO ALL TRAFFIC.
5. PERFORM ALL WORK AS DESCRIBED IN DWG. NO. STR-06.

FINAL STAGE:

1. EVERSOURCE TO REMOVE TEMPORARY POLES, OVERHEAD WIRES, GUY AND ANCHOR.
2. EVERSOURCE TO INSTALL NEW POLES, OVERHEAD WIRES, GUY AND ANCHOR. SEE DWG. NO. HWY-07 FOR APPROXIMATE LOCATIONS. CONTRACTOR TO COORDINATE WITH EVERSOURCE AND OTHER UTILITY COMPANIES ON THE POLES.
3. INSTALL TOP COURSE OF PAVEMENT FULL WIDTH FROM STA. 3+60 TO STA. 6+25.
4. REMOVE ALL TEMPORARY PAVEMENT MARKINGS INSTALLED BEYOND PAVING LIMITS.
5. COMPLETE ALL ANCILLARY WORK CALLED FOR IN THE PROJECT.

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/16/2019

DESIGNER/DRAFTER: SJ
CHECKED BY: VAA
SCALE AS NOTED

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\TR_MSH_MPT-2_41_118.dgn

SIGNATURE/BLOCK: GM2 ASSOCIATES, INC. 115 GLASTONBURY BLVD. GLASTONBURY, CT 06033

PROJECT TITLE: REPLACEMENT OF BRIDGE NO. 02018 ROUTE 66 OVER POCOTOPAUG CREEK

TOWN: EAST HAMPTON

DRAWING TITLE: MPT PLAN - 2

PROJECT NO. 041-118
DRAWING NO. TRA-03
SHEET NO. 05.03

DETOUR PLAN

NOT TO SCALE

DETAIL A

NOT TO SCALE

DETAIL B

NOT TO SCALE

DETAIL C

NOT TO SCALE

LEGEND

- SIGN - SINGLE POST
- SIGN - DOUBLE POST
- DETOUR ROUTE
- CMS CHANGEABLE MESSAGE SIGN (CMS)

SIGN LEGEND

J	CONSTRUCTION AHEAD / ROAD USE RESTRICTED / STATE LIABILITY LIMITED / GENERAL STATUTES SEC 13a-115, 13a-145 COMMISSIONER OF TRANSPORTATION	80-1608	S	END DETOUR	80-9708
K-1	NO PARKING ANY TIME ⇦	31-0630 (L)	T	DETOUR / EAST / 66 / ←	80-9707 / 51-6612 / 51-6616 / 51-2626 (L)
K-2	NO PARKING ANY TIME ⇨	31-0630 (R)	U	ROAD WORK AHEAD / FINES DOUBLED	31-1907
L	DETOUR AHEAD	80-9933	V	DETOUR / WEST / 66 / →	80-9707 / 51-6614 / 51-6616 / 51-2626 (R)
M	ROAD CLOSED AHEAD	80-9933	W	DETOUR / EAST / 66 / ↑	80-9707 / 51-6612 / 51-6616 / 51-2625
O	BRIDGE CLOSED / 900 FT. AHEAD / LOCAL TRAFFIC ONLY	80-9078	X	DETOUR / WEST / 66 / ↑	80-9707 / 51-6614 / 51-6616 / 51-2625
	BUSINESSES OPEN	50-5934			
P	BRIDGE CLOSED / 1/4 MILE AHEAD / LOCAL TRAFFIC ONLY	80-9078	S-1	DETOUR / WEST / EAST / 66 / 66 / ← / →	80-9707 (EXISTING SIGN ASSEMBLY)
	BUSINESSES OPEN	50-5934			
Q	DETOUR / WEST / 66 / ←	80-9707 / 51-6614 / 51-6616 / 51-2626 (L)			
R	DETOUR / EAST / 66 / →	80-9707 / 51-6612 / 51-6616 / 51-2626 (R)			

SUGGESTED CMS MESSAGE:

RTE 66
BRIDGE
CLOSED

FRAME 1

STARTING
XX/XX/XX

FRAME 2

NOTES:

1. REFER TO THE SPECIAL PROVISIONS AND SPECIFICATIONS "MAINTENANCE AND PROTECTION OF TRAFFIC" AND "PROSECUTION AND PROGRESS" FOR ADDITIONAL REQUIREMENTS.
3. ALL ROADWAY CLOSURES SHALL BE COORDINATED WITH THE TOWN OF EAST HAMPTON.
4. ACTUAL LOCATIONS OF SIGNS TO BE DETERMINED BY THE ENGINEER.
5. ALL DETOUR SIGNS TO BE PAID FOR UNDER ITEM NO. 1220027 "CONSTRUCTION SIGNS".
6. INSTALL CMS TWO WEEKS PRIOR TO START OF DETOUR ON BOTH BRIDGE APPROACHES.
7. EXISTING SIGNS IN CONFLICT WITH TEMPORARY SIGNS SHALL BE COVERED, REMOVED, OR REVISED TO MEET FIELD CONDITIONS.
8. THE CONTRACTOR IS TO NOTIFY DISTRICT 2 CONSTRUCTION, THE TOWN OF EAST HAMPTON, AND ALL EMERGENCY SERVICES AT LEAST FOUR WEEKS PRIOR TO INITIATING THE DETOUR.
9. DETOUR PLAN TO BE MAINTAINED DURING EXISTING BRIDGE DEMOLITION AND PROPOSED CULVERT CONSTRUCTION. SEE SPECIAL PROVISIONS-LIQUIDATED DAMAGES.
10. DETOUR SIGNS TO BE COVERED/REMOVED WHEN DETOUR IS NOT IN OPERATION.
11. INSTALL BARRICADE WARNING LIGHTS - HIGH INTENSITY ON POST MOUNTED DIAMOND SIGNS IN THE ADVANCE WARNING AREA.

REV.	DATE	REVISION DESCRIPTION	SHEET NO.

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/16/2019

DESIGNER/DRAFTER: PS/MJM
CHECKED BY: SJ
SCALE AS NOTED

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\Traffic\TR_MSH_DTR_41_118.dgn

SIGNATURE/BLOCK:

GM2 ASSOCIATES, INC.
115 GLASTONBURY BLVD.
GLASTONBURY, CT 06033

PROJECT TITLE:
REPLACEMENT OF
BRIDGE NO. 02018 ROUTE 66
OVER POCOTOPAUG CREEK

TOWN: EAST HAMPTON

DRAWING TITLE: DETOUR PLAN

PROJECT NO. 041-118
DRAWING NO. TRA-04
SHEET NO. 05.04

R1 - SERIES

R1-1

LEGEND - WHITE
BACKGROUND - RED

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
1.85	18	31-0532	1	.080
5.19	30	31-0552	1	.080
7.98	36	31-0553	1	.080
13.3	48	31-0557	2	.100

R1-2

LEGEND - RED
BACKGROUND -WHITE

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
0.97	18	31-0520	1	.080
3.90	36	31-0523	1	.080
6.77	48	31-0522	2	.100
10.83	60	31-0528	2	.100

R1-3P

LEGEND - WHITE
BACKGROUND - RED

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
0.75	18X6	31-0508		.080

R2 - SERIES

R2-1

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
5.00	24X30	31-5505	1	.080
7.50	30X36	31-5504	1	.080
12.00	36X48	31-5506	2	.100
20.00	48X60	31-5507	2	.100

R2-4a

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
32	48X96	31-5510	2	.125

R3 - SERIES

R3-1

LEGEND - BLACK
BACKGROUND - WHITE
CIRCLE & DIAGONAL - RED

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
4.00	24X24	31-1604	1	.080
9.00	36X36	31-1627	2	.080

R3-2

LEGEND - BLACK
BACKGROUND - WHITE
CIRCLE & DIAGONAL - RED

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
4.00	24X24	31-1603	1	.080
9.00	36X36	31-1629	2	.080

R3-3

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
4.00	24X24	31-1648	1	.080
9.00	36X36	31-1647	2	.080

R3-4

LEGEND - BLACK
BACKGROUND - WHITE
CIRCLE & DIAGONAL - RED

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
4.00	24X24	31-1622	1	.080
9.00	36X36	31-1632	2	.080

R3-5

31-0183 31-0184

R3-6

31-0157 31-0158

R3-7

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30X30	31-0117	1	.080
9.00	36X36	31-0120	2	.080

R3-7

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30X30	31-0118	1	.080
9.00	36X36	31-0123	2	.080

R3-6

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
7.50	30X36	31-0175	1	.080

R3-8

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
7.50	30X36	31-0290	1	.080

R3-8

31-0222 31-0223

R3-8

31-0262 31-0261

R3-8

31-0282 31-0283

R3-8

31-0295 31-0219

R3-8

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
8.75	42X30	31-0279	2	.100

R3-8b

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
10.00	48X30	31-0302	2	.100

R3-8b

31-0307 31-0372

R3-8b

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
8.75	42X30	31-0334	2	.100

R3-8b

31-0370 31-0371

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
8.75	42X30		2	.100

R4 - SERIES

R4-1

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
5.00	24X30	31-1502	1	.080

R4-16

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
20.00	48X60	31-1574	2	.100

R4-3

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
5.00	24X30	31-1562	1	.080
20.00	48X60	31-1564	2	.100

R4-7

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
5.00	24X30	31-1526	1	.080
12.00	36X48	31-1536	2	.100
20.00	48X60	31-1546	2	.100

R5 - SERIES

R5-1

LEGEND - WHITE
BACKGROUND - WHITE
CIRCLE - RED

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30X30	31-1119	1	.080
9.00	36X36	31-1120	2	.080
16.00	48X48	31-1121	2	.100

R5-10a(CT)

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
9.00	36X36	31-1775	2	.100

R5-1a

LEGEND - WHITE
BACKGROUND - RED

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.00	36X24	31-1122	2	.080
8.75	42X30	31-1123	2	.100

R5-11(CT)

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
5.00	24X30	31-1790	1	.080
20.00	48X60	31-1792	2	.100

R5-10a(CT)

LEGEND - BLACK
TOP SECTION BACKGROUND - YELLOW
BOTTON SECTION BACKGROUND - WHITE

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
32.50	60X78	31-1719	2	.125

R5-10c

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
2.00	24X12	31-1774	1	.080

R6 - SERIES

R6-1

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
3.00	36X12	31-1188	1	.080
6.75	54X18	31-1189	2	.100

R6-1

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
3.00	36X12	31-1177	1	.080
6.75	54X18	31-1178	2	.100

R7 - SERIES

R7-1

LEGEND - RED
BACKGROUND - WHITE

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
1.50	12X18	31-0630	1	.080

R7-2a

VARIABLE TIMES
LEGEND - RED
BACKGROUND - WHITE

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
1.50	12X18	31-0603	1	.080

R8 - SERIES

R8-7

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
12.00	48X36	31-0670	2	.100

R9 - SERIES

R9-3

LEGEND - BLACK
BACKGROUND - WHITE
CIRCLE & DIAGONAL - RED

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
2.25	18X18	31-1705	1	.080
4.00	24x24	31-1769	1	.080
6.25	30x30	31-1770	1	.080

R9-3a

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
1.50	12X18	31-1702	1	.080

R10 - SERIES

R10-6

31-0801 31-0802

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.00	24X36		1	.080

R10-7

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
5.00	24X30	31-0806	1	.080

R10-11b

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
9.00	36X36	31-0816	2	.080

R10-10L

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
7.50	30X36	31-0852	1	.080

R10-11a

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
7.50	30X36	31-0830	1	.080
12.00	36X48	31-0819	2	.100

R10-11c(CT)

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
7.50	30X36	31-0847	1	.080

R11 - SERIES

R11-1

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
5.00	24X30	31-1915	1	.080
20.00	48X60	31-1918	2	.100

RETROREFLECTIVE STRIP

LEGEND - N/A
BACKGROUND - RED

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
1.00	4X36	31-5003	1	.080
2.00	4X72	31-5004	1	.080

NOTES:

1. THE LEGEND "O.S.T.A." SHALL APPEAR ON ALL R- SERIES SIGNS EXCEPT WHEN SUFFIXED WITH THE LETTER "Z".
2. FOR SPECIFIC SIGN DESIGN CONTACT CONN. D.O.T., DIVISION OF TRAFFIC ENGINEERING. FOR BOLT HOLE PATTERN REFER TO FHWA PUBLICATION "STANDARD HIGHWAY SIGNS". SIGNS OF DIFFERENT DIMENSIONS TO BE ERECTED ON THE SAME POSTS, OR SPAN/MAST ARM MOUNTED, MAY REQUIRE SPECIAL BOLT HOLE PATTERNS.
3. POSTS - SEE STANDARD SHEET TR-1208_02 - "METAL SIGN POSTS AND SIGN MOUNTING DETAILS."
4. POSTS SHALL BE 4 LBS./FT.
5. SIGNS SHALL BE FABRICATED OF ONE CONTINUOUS PIECE OF SHEET ALUMINUM. SPLICING OF SHEET ALUMINUM WILL NOT BE ACCEPTED.
6. FOR OVERHEAD MOUNTED SIGNS, SEE STANDARD SHEET TR-1114_01 - "BONDING AND UTILITY POLE ATTACHMENT DETAILS, SIGN HANGER, "Y" CLAMP DETAIL."

COLORS:

BACKGROUND - WHITE - EXCEPT AS NOTED.
LEGEND - BLACK - EXCEPT AS NOTED.
ALL SIGNS TO USE TYPE IX RETROREFLECTIVE SHEETING.

REV.	DATE	REVISION DESCRIPTION	SHEET NO.
1	6-2018	NEW SHEET ISSUED	TR-GS_01

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/16/2019

DESIGNER/DRAFTER: **A. MERMELSTEIN**
CHECKED BY: **B. SCHILLING**

NOT TO SCALE

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\Traffic\TR_MSH_GS-01.dgn

SIGNATURE/ BLOCK:

GM2 ASSOCIATES, INC.
115 GLASTONBURY BLVD.
GLASTONBURY, CT 06033

PROJECT TITLE:
REPLACEMENT OF BRIDGE NO. 02018 ROUTE 66 OVER POCOTOPAUG CREEK

TOWN: **EAST HAMPTON**

DRAWING TITLE:
SIGN FACE SHEET ALUMINUM (X)
R-SERIES TYPICAL SIGN DETAILS

PROJECT NO. **041-118**
DRAWING NO. **TRA-05**
SHEET NO. **05.05**

S - SERIES

S1-1

LEGEND - BLACK
BACKGROUND - FLUORESCENT YELLOW GREEN

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.75	36	41-2112	1	.080
12.00	48	41-2113	2	.100

W1 - SERIES

W1-1L

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30	41-4006	1	.080
9.00	36	41-4031	1	.080

W1-1R

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30	41-4005	1	.080
9.00	36	41-4160	1	.080

W1-6

LEGEND - BLACK
BACKGROUND - FLUORESCENT YELLOW
(LEFT OR RIGHT)

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
8.00	48X24	41-4223	2	.100
12.50	60X30	41-4262	2	.100

W1-2

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30	41-4029	1	.080
9.00	36	41-4169	1	.080

W1-2

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30	41-4168	1	.080
9.00	36	41-4032	1	.080

W1-7

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
8.00	48X24	41-4207	2	.100
12.50	60X30	41-4208	2	.100

W1-8

LEGEND - BLACK
BACKGROUND - FLUORESCENT YELLOW
(LEFT OR RIGHT)

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
3.00	18X24	41-3951	1	.080
7.50	30X36	41-4211	1	.080
12.00	36X48	41-4260	2	.080

W2 - SERIES

W2-1

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30	41-4226	1	.080
9.00	36	41-4236	1	.080

W2-2

(LEFT OR RIGHT)

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30	41-4225	1	.080
9.00	36	41-4235	1	.080

W3 - SERIES

W3-1

OCTAGON - RED

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30	41-0501	1	.080
16.00	48	41-0503	2	.100

W3-2

TRIANGLE - RED & WHITE

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30	41-0504	1	.080
16.00	48	41-0506	2	.100

W3-3

SYMBOL & LEGEND - BLACK
BACKGROUND - YELLOW
TOP CIRCLE - RED
BOTTOM CIRCLE - GREEN

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30	41-0835	1	.080
16.00	48	41-0848	2	.100

W/ FLASHERS

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
25.00	60	41-0534	2	.125

W4 - SERIES

W4-1

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
9.00	36	41-4448	1	.080
16.00	48	41-4452	2	.100

W4-1

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
9.00	36	41-4449	1	.080
16.00	48	41-4459	2	.100

W4-2

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
9.00	36	41-4442	1	.080
16.00	48	41-4446	2	.100

W4-2

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
9.00	36	41-4441	1	.080
16.00	48	41-4447	2	.100

W4-3

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
9.00	36	41-4468	1	.080
16.00	48	41-4435	2	.100

W4-3

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
9.00	36	41-4470	1	.080
16.00	48	41-4434	2	.100

W5 - SERIES

W5-1

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
9.00	36	41-4402	1	.080
16.00	48	41-4404	2	.100

W6 - SERIES

W6-1

W6-2

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
9.00	36	41-4335	1	.080
16.00	48	41-4330	2	.100

W6-3

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
9.00	36	41-4329	1	.080
16.00	48	41-4331	2	.100

W7 - SERIES

W7-1

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30	41-4506	1	.080
9.00	36	41-4530	1	.080
16.00	48	41-4508	2	.100

W8 - SERIES

W8-5

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30	41-4519	1	.080
9.00	36	41-4520	1	.080
16.00	48	41-4521	2	.100

W9 - SERIES

W9-1

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
9.00	36	41-4443	1	.080
16.00	48	41-4444	2	.100

W9-1

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
9.00	36	41-4440	1	.080
16.00	48	41-4445	2	.100

W9-2

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
9.00	36	41-4454	1	.080
16.00	48	41-4456	2	.100

W9-2

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
9.00	36	41-4453	1	.080
16.00	48	41-4455	2	.100

W11 - SERIES

W11-2

LEGEND - BLACK
BACKGROUND - FLUORESCENT YELLOW GREEN

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30	41-4829	1	.080
9.00	36	41-4830	1	.080

W11-8

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30	41-4680	1	.080
9.00	36	41-4681	1	.080

W12 - SERIES

W12-1

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.25	30	41-4213	1	.080
9.00	36	41-4215	1	.080

W12-2

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
9.00	36	41-4706	1	.080
16.00	48	41-4708	2	.100

(SUBPLATE)

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
5.00	30X24	41-4721		.080

(SUBPLATE)

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
5.00	30X24	41-4722		.080

W13 - SERIES

W13-1

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
2.25	18X18	41-5566		.080
4.00	24X24	41-5567		.080
6.25	30X30	41-5574		.080

W13-2

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
12.00	36X48	41-5596	2	.100

W13-3

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
12.00	36X48	41-5581	2	.100

W16 - SERIES

W16-2aP

(SUBPLATE)
USE AT ADVANCE SIGN LOCATION
LEGEND - BLACK
BACKGROUND - FLUORESCENT YELLOW GREEN

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
2.00	24X12	41-6140		.080

W16-7PL

(SUBPLATE)
USE AT CROSSWALK
LEGEND - BLACK
BACKGROUND - FLUORESCENT YELLOW GREEN

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
2.00	24X12	41-2617		.080

W16-7PR

(SUBPLATE)
USE AT CROSSWALK
LEGEND - BLACK
BACKGROUND - FLUORESCENT YELLOW GREEN

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
2.00	24X12	41-2619		.080

W16-9P

(SUBPLATE)
USE AT ADVANCE SIGN LOCATION
LEGEND - BLACK
BACKGROUND - FLUORESCENT YELLOW GREEN

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
2.00	24X12	41-6126		.080
3.75	30X18	41-6137		.080

W16-2aP

41-6130 000 FT
41-6134 0000 FT

(SUBPLATE)
USE AT ADVANCE SIGN LOCATION

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
2.00	24X12	41-6130		.080
3.75	30X18	41-6134		.080

RETROREFLECTIVE STRIP

LEGEND - N/A
BACKGROUND - FLUORESCENT YELLOW GREEN

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
2.00	4X72	41-5010	1	.080

LEGEND - N/A
BACKGROUND - FLUORESCENT YELLOW

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
1.50	4X48	41-5001	1	.080
2.00	4X72	41-5006	1	.080

NOTES:

1. FOR SPECIFIC SIGN DESIGN CONTACT CONN. D.O.T., DIVISION OF TRAFFIC ENGINEERING.
   FOR BOLT HOLE PATTERN REFER TO FHWA PUBLICATION "STANDARD HIGHWAY SIGNS".
   SIGNS OF DIFFERENT DIMENSIONS TO BE ERECTED ON THE SAME POSTS, OR SPAN/MAST ARM MOUNTED, MAY REQUIRE SPECIAL BOLT HOLE PATTERNS.
2. POSTS - SEE STANDARD SHEET TR-1208_02 "METAL SIGN POSTS AND SIGN MOUNTING DETAILS."
3. POSTS SHALL BE 4 LBS./FT.
4. SIGNS SHALL BE FABRICATED OF ONE CONTINUOUS PIECE OF SHEET ALUMINUM.
   SPLICING OF SHEET ALUMINUM WILL NOT BE ACCEPTED.
5. FLUORESCENT YELLOW RETROREFLECTIVE STRIPS SHALL BE INSTALLED ON ALL SIGN POSTS FOR W1-6 AND W1-8 SIGNS.
   FLUORESCENT YELLOW GREEN RETROREFLECTIVE STRIPS SHALL BE INSTALLED ON ALL SIGN POSTS FOR S1-1 AND W11-2 SIGNS LOCATED AT CROSSINGS. RETROREFLECTIVE STRIPS SHOULD NOT BE INSTALLED ON ADVANCE CROSSING WARNING SIGNS.
   SEE STANDARD SHEET TR-1208_01 "SIGN PLACEMENT AND RETROREFLECTIVE STRIP DETAILS" FOR RETROREFLECTIVE STRIP DETAILS AND INSTALLATION.

COLORS:

BACKGROUND - YELLOW - EXCEPT AS NOTED.
LEGEND - BLACK - EXCEPT AS NOTED.
ALL SIGNS TO USE TYPE IX RETROREFLECTIVE SHEETING.

REV.	DATE	REVISION DESCRIPTION	SHEET NO.
1	6-2018	NEW SHEET ISSUED	TR-GS_02

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/16/2019

DESIGNER/DRAFTER: **A. MERMELSTEIN**
CHECKED BY: **B. SCHILLING**

NOT TO SCALE

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\Traffic\TR_MSH_GS-02.dgn

SIGNATURE/ BLOCK:

GM2 ASSOCIATES, INC.
115 GLASTONBURY BLVD.
GLASTONBURY, CT 06033

PROJECT TITLE:

REPLACEMENT OF BRIDGE NO. 02018 ROUTE 66 OVER POCOTOPAUG CREEK

TOWN: **EAST HAMPTON**

DRAWING TITLE: **SIGN FACE SHEET ALUMINUM (Y)**
S&W SERIES TYPICAL SIGN DETAILS

PROJECT NO. **041-118**
DRAWING NO. **TRA-06**
SHEET NO. **05.06**

D1 - SERIES

D1-1

51-5202 Variable →

D1-2

51-5203 Variable Variable →

VARIABLE LEGEND & ARROW DIRECTION

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.

D3 - SERIES

D3-1

Variable Road Name

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
4.00	48X12	51-2010	2	.100
5.00	60X12	51-2011	2	.100
6.00	72X12	51-2012	2	.125
7.00	84X12	51-2013	2	.125

D3-1

Variable Road Name

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.00	48X18	51-2004	2	.100
7.50	60X18	51-2001	2	.100
9.00	72X18	51-2002	2	.125
10.50	84X18	51-2003	2	.125

D4 - SERIES

D4-2

PARK - RIDE →

VARIABLE ARROW DIRECTION

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
5.00	24X30	51-6006	1	.080
7.50	30X36	51-6007	1	.080
12.00	36X48	51-6008	2	.100

D4-2

PARK - RIDE →

VARIABLE ARROW DIRECTION

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
5.00	24X30	51-6033	1	.080
7.50	30X36	51-6034	1	.080
12.00	36X48	51-6035	2	.100

D4-2

PARK - RIDE →

VARIABLE ARROW DIRECTION

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
5.00	24X30	51-6044	1	.080
7.50	30X36	51-6045	1	.080
12.00	36X48	51-6046	2	.100

NOTICE
THIS PARKING AREA PATROLLED

LEGEND - BLACK
BACKGROUND - WHITE

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
15.00	60X36	51-5937	2	.100

PARK AT YOUR OWN RISK
REMOVE KEYS AND LOCK CAR
NOT RESPONSIBLE FOR
PROPERTY LOST OR STOLEN

LEGEND - BLACK
BACKGROUND - WHITE

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
4.50	36X18	51-6037	1	.080

D5 - SERIES

D5-2b

REST AREA ↗

LEGEND - WHITE
BACKGROUND - BLUE

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
42.25	78X78	51-6901	2	.125

SERVICE PLAZA ↗

LEGEND - WHITE
BACKGROUND - BLUE

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
39.00	72X78	51-6158	2	.125

D7 - SERIES

D-7

51-6802 Variable →

51-6803 Variable Variable →

W or W/O ARROW
VARIABLE ARROW DIRECTION

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
4.17	60X10	51-6802	2	.100
8.33	60X20	51-6803	2	.100

D9 - SERIES

D9-2

H

** FOR ARROW SUBPLATES
USE M5 & M6 SERIES

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
4.00	24X24	51-6788	1	.080

D9-3a

** FOR ARROW SUBPLATES
USE M5 & M6 SERIES

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
4.00	24X24	51-6762	1	.080

51-6705 DIESEL →
51-6706 FOOD →
51-6707 PHONE →
51-6708 GAS →
51-6709 LODGING →

VARIABLE ARROW DIRECTION

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
2.25	36X9		2	.080

D10 - SERIES

D10-4

NORTH
95
MILE
000

CARDINAL DIRECTION,
SHIELD AND NUMERALS ARE VARIABLE

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
6.75	18X54	51-5307	1	.080

RECREATIONAL RS- SERIES

RS-054

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
4.00	24X24	51-6873	1	.080

RS-117

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
4.00	24X24	51-7872	1	.080

51-2705 ↑

51-2706 L or R →

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
2.19	21X15	51-2705		.080
2.19	21X15	51-2706		.080

E5 - SERIES

E5-1a

EXIT ↗

FOR USE AT "NO NUMBERED" EXITS

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
30.00	72X60	51-6150	2	.125

E5-1a

EXIT ↖ 00 — 51-6124

EXIT 00 ↗ — 51-6125

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
32.50	78X60		2	.125

E5-1a

EXIT ↖ 00 B — 51-6126

EXIT 00 B ↗ — 51-6127

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
45.00	108X60		2	.125

E5-1a

EXIT ↖ 00 A-B — 51-6128

EXIT 00 A-B ↗ — 51-6129

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
57.50	138X60		2	.125

I - SERIES

I-3

(Variable) River

VARIABLE: RIVER, BROOK, CREEK

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
1.50	18X12	51-2009	1	.080
4.50	36X18	51-2007	2	.080
12.00	48X36	51-2051	2	.100

(Town Name)
(INCORPORATED OR SETTLED) (DATE)
TOWN LINE

VARIABLE: TOWN / CITY

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
7.50	40X27	51-2020	2	.080

(Name)
Connecticut

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
10.00	48X30	51-2040	2	.100

I-7

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
4.00	24X24	51-1448	1	.080
6.25	30X30	51-1445	1	.080

INCIDENT MANAGEMENT

N 0 .0 — N 0 0 .0 — N 0 0 0 .0

CARDINAL DIRECTION VARIABLE - N, S, E, W

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
3.00	12X36	51-5103	1	.080
4.00	12X48	51-5104	1	.080
5.00	12X60	51-5105	1	.080

SYMBOL - WHITE
BACKGROUND - BLUE

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
3.00	18X24	51-5943	1	.080

51-6504 Variable

51-6505 Variable Variable

TO BE SUBMOUNTED W/ 51-5943
LEGEND - WHITE
BACKGROUND - BLUE

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
0.75	18X6	51-6504		.080
1.50	18X12	51-6505		.080

M1 - SERIES

M1-1

INTERSTATE CONNECTICUT 00 — 51-6662, 51-6666, VARIABLE: 1 or 2 DIGITS

INTERSTATE CONNECTICUT 000 — 51-6663, 51-6667, VARIABLE: 3 DIGITS

LEGEND - WHITE
BACKGROUND - RED & BLUE

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
3.20	24X24	51-6662	1	.080
3.99	30X24	51-6663	1	.080
7.20	36X36	51-6666	2	.080
8.99	45X36	51-6667	2	.100

M1-4

00 — 51-6615, 51-6635, VARIABLE: 1 or 2 DIGITS

000 — 51-6644, 51-6645, VARIABLE: 3 DIGITS

LEGEND - BLACK
BACKGROUND - WHITE

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
4.00	24X24	51-6615	1	.080
5.00	30X24	51-6644	1	.080
9.00	36X36	51-6635	2	.080
11.25	45X36	51-6645	2	.100

M1-5

00 — 51-6616, 51-6636, VARIABLE: 1 or 2 DIGITS

000 — 51-6647, 51-6646, VARIABLE: 3 DIGITS

LEGEND - BLACK
BACKGROUND - WHITE

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	POSTS	ALUM. THK.
4.00	24X24	51-6616	1	.080
5.00	30X24	51-6647	1	.080
9.00	36X36	51-6636	2	.080
11.25	45X36	51-6646	2	.100

M2 - SERIES

M2-1

JCT

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	COLOR	ALUM. THK.
2.19	21X15	51-6640	(1)	.080
2.19	21X15	51-6610	(2)	.080

M3 - SERIES

M3-1

NORTH

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	COLOR	ALUM. THK.
2.00	24X12	51-6651	(1)	.080
2.00	24X12	51-6611	(2)	.080
4.50	36X18	51-6655	(1)	.080
4.50	36X18	51-6625	(2)	.080

M3-4

WEST

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	COLOR	ALUM. THK.
2.00	24X12	51-6654	(1)	.080
2.00	24X12	51-6614	(2)	.080
4.50	36X18	51-6658	(1)	.080
4.50	36X18	51-6628	(2)	.080

M3-2

EAST

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	COLOR	ALUM. THK.
2.00	24X12	51-6652	(1)	.080
2.00	24X12	51-6612	(2)	.080
4.50	36X18	51-6656	(1)	.080
4.50	36X18	51-6626	(2)	.080

M3-3

SOUTH

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	COLOR	ALUM. THK.
2.00	24X12	51-6653	(1)	.080
2.00	24X12	51-6613	(2)	.080
4.50	36X18	51-6657	(1)	.080
4.50	36X18	51-6627	(2)	.080

M4 - SERIES

M4-5

TO

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	COLOR	ALUM. THK.
2.00	24X12	51-6650	(1)	.080
2.00	24X12	51-6620	(2)	.080

M5 - SERIES

M5-1

51-2690, 51-2630 ↰

51-2691, 51-2631 ↱

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	COLOR	ALUM. THK.
2.19	21X15	51-2690	(1)	.080
2.19	21X15	51-2691	(1)	.080
2.19	21X15	51-2630	(2)	.080
2.19	21X15	51-2631	(2)	.080

M5-2

51-2692, 51-2632 ↰

51-2693, 51-2633 ↱

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	COLOR	ALUM. THK.
2.19	21X15	51-2692	(1)	.080
2.19	21X15	51-2693	(1)	.080
2.19	21X15	51-2632	(2)	.080
2.19	21X15	51-2633	(2)	.080

M6 - SERIES

M6-1

L or R →

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	COLOR	ALUM. THK.
2.19	21X15	51-2686	(1)	.080
2.19	21X15	51-2626	(2)	.080

M6-4

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	COLOR	ALUM. THK.
2.19	21X15	51-2697	(1)	.080
2.19	21X15	51-2627	(2)	.080

M6-2

51-2688, 51-2628 ↖

51-2689, 51-2629, 51-2609 ↗

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	COLOR	ALUM. THK.
2.19	21X15	51-2688	(1)	.080
2.19	21X15	51-2689	(1)	.080
2.19	21X15	51-2628	(2)	.080
2.19	21X15	51-2629	(2)	.080
4.89	32X22	51-2609	(2)	.080

M6-3

↑

AREA (SQ. FT)	SIZE (INCHES)	CONN. D.O.T. #	COLOR	ALUM. THK.
2.19	21X15	51-2685	(1)	.080
2.19	21X15	51-2625	(2)	.080

NOTES:

1. FOR SPECIFIC SIGN DESIGN CONTACT CONN. D.O.T., DIVISION OF TRAFFIC ENGINEERING. FOR BOLT HOLE PATTERN REFER TO FHWA PUBLICATION "STANDARD HIGHWAY SIGNS". SIGNS OF DIFFERENT DIMENSIONS TO BE ERECTED ON THE SAME POSTS, OR SPAN/MAST ARM MOUNTED, MAY REQUIRE SPECIAL BOLT HOLE PATTERNS.
2. POSTS - SEE STANDARD SHEET TR-1208_02 - "METAL SIGN POSTS AND SIGN MOUNTING DETAILS."
3. POSTS SHALL BE 4 LBS./FT.
4. SIGNS SHALL BE FABRICATED OF ONE CONTINUOUS PIECE OF SHEET ALUMINUM. SPLICING OF SHEET ALUMINUM WILL NOT BE ACCEPTED.

COLORS:

D - SERIES
D1, 2, 3, 4, 10 BACKGROUND-GREEN, LEGEND-WHITE
D7, RS BACKGROUND-BROWN, LEGEND-WHITE
D9 BACKGROUND-BLUE, LEGEND-WHITE
ALL OTHER D-SERIES AS NOTED

E - SERIES
BACKGROUND-GREEN, LEGEND-WHITE

I - SERIES
BACKGROUND-GREEN, LEGEND-WHITE
(EXCEPT AS NOTED)

M2 - M6 SERIES
(1) BACKGROUND-BLUE, LEGEND-WHITE
(2) BACKGROUND-WHITE, LEGEND-BLACK

ALL COLORS SHALL BE TYPE IX RETROREFLECTIVE WITH THE EXCEPTION OF BROWN WHICH SHALL BE TYPE IV RETROREFLECTIVE AND BLACK WHICH SHALL BE OPAQUE.

REV.	DATE	REVISION DESCRIPTION	SHEET NO.
2	7-2018	REVISED BROWN COLOR TO TYPE IV.	TR-GS_03
1	6-2018	NEW SHEET ISSUED	TR-GS_03

THE INFORMATION, INCLUDING ESTIMATED QUANTITIES OF WORK, SHOWN ON THESE SHEETS IS BASED ON LIMITED INVESTIGATIONS BY THE STATE AND IS IN NO WAY WARRANTED TO INDICATE THE CONDITIONS OF ACTUAL QUANTITIES OF WORK WHICH WILL BE REQUIRED.

Plotted Date: 7/16/2019

DESIGNER/DRAFTER: A. MERMELSTEIN
CHECKED BY: B. SCHILLING

SCALE IN FEET
0 NOT TO SCALE 80
SCALE 1"=40'

STATE OF CONNECTICUT
DEPARTMENT OF TRANSPORTATION

Filename: ...\Traffic\TR_MSH_GS-03.dgn

SIGNATURE/BLOCK:

GM2 ASSOCIATES, INC.
115 GLASTONBURY BLVD.
GLASTONBURY, CT 06033

PROJECT TITLE:

REPLACEMENT OF BRIDGE NO. 02018 ROUTE 66 OVER POCOTOPAUG CREEK

TOWN: **EAST HAMPTON**

DRAWING TITLE: **SIGN FACE SHEET ALUMINUM (2)**
D,RS,E,I,&M SERIES SIGNS TYPICAL DETAILS

PROJECT NO. **041-118**
DRAWING NO. **TRA-07**
SHEET NO. **05.07**