



375 Essjay Road, Suite 200, Williamsville, New York 14221
P 716.688.0766 F 716.625.6825

ADDENDUM NO. 6

Norwalk Transit District
Fuel Island, Service Lane and Tank Replacement
437404

DATE

3/9/2020

OWNER

Norwalk Transit District
275 Wilson Avenue
Norwalk, CT

ARCHITECT/ENGINEER

Wendel Architecture, PC
375 Essjay Road
Suite 200
Williamsville, NY 14221
Phone: 716-688-0766
Fax: 716-625-6825

Project No. 437404

This Addendum is being issued to clarify the bid documents and shall supersede and supplement all portions of previously issued bid documents with which it conflicts. It shall be made an integral part of the construction documents.



Project Norwalk Transit District

Addendum No. 06

Contract _____

Wendel Project No. 433101

Date 3/9/20

ARTICLE - 1

DRAWING NO. _____
SPEC _____
SECTION _____

QUESTION:

Drawing C201 states "encase canopy columns in concrete". Please clarify the meaning and intent of this statement.

ANSWER:

Provide 2'-4" diameter x 4'-0" high concrete column encasement with 5 rows of #4 steel reinforcement hoops welded to the column. Provide concrete dome at top 1" high at center.

ARTICLE - 2

DRAWING NO. _____
SPEC _____
SECTION _____

QUESTION:

The response to Article 2 requires clarification. Does this mean that NTD will supply fluids and tanks/drums from their current fluid vendor? If not, tank material, mfg., and model information would be necessary for the DEF tank. Furthermore for the purposes of startup and testing, will NTD provide all fluids, gasoline and diesel or is it the responsibility of the contractor to provide?

ANSWER:

For fluid lubrication the contractor is responsible for the fill of fluid Per Specification 115800-2.10-F:

F. Final acceptance

1. All tanks to be completely filled with product for acceptance by the owner.

The contractor shall coordinate with NTD ordering the proper product required for the fleet. Fluid lubrication fluids shall be delivered in their storage containers/drums for installation.

For fuel NTD will fill the tanks once they are constructed.