

# NED LAMONT, GOVERNOR

## DEPARTMENT OF ENERGY AND ENVIRONMENTAL PROTECTION KATHERINE S. DYKES COMMISSIONER

DEVIL'S HOPYARD STATE PARK

PROJECT NO. DEPA00029000104

JULY 2, 2019


CIVIL ENGINEER: MACCHI ENGINEERS, LLC 44 GILLET STREET HARTFORD, CT 06105

# SUPERSTRUCTURE REPLACEMENT OF CT DEEP BRIDGE E118 (DOT #06323) LOOP TRAIL OVER EIGHTMILE RIVER

# EAST HADDAM, CT



LEGEND						
ABBREVIATION	MEANING					
VIF	VERIFY IN FIELD					
WP	WORKING POINT					
B.F.	BOTTOM OF FOOTING					
CLR.	CLEARANCE					
DIA.	DIAMETER					
CONT.	CONTINUOUS					
ELEV	ELEVATION					
PL.	PLATE					
TYP.	TYPICAL					
EA.	EACH					
MIN.	MINIMUM					
RE:	REFER					
O.C.	ON CENTER					
Τ/	TOP OF					
W/	WITH					
T/B	TOP AND BOTTOM					
DWGS.	DRAWINGS					
EQ.	EQUAL					
EXIST.	EXISTING					
Ę	CENTER LINE					



LIST OF DRAWING REVISIONS						
SHEET NO	DESCRIPTION	DATE				

#### LEGEND

EXISTING CONTOUR 161.0 × EDGE WOODLINE -

RETAINING WALL AS MARKED SPOT ELEVATION

> EDGE WETLANDS / FLAG NUMBERS SURVEYOR CONTROL POINT LANDSCAPE ROCK/BOULDER


# DEVILS HOPYARD STATE PARK

+ 100.12


MAP STANDARD NOTES

1. THIS SURVEY HAS BEEN PREPARED IN ACCORDANCE WITH SECTIONS 20-300b-1 THRU 20-300b-20 OF THE REGULATIONS OF CONNECTICUT STATE AGENCIES "MINIMUM STANDARDS FOR SURVEYS AND MAPS IN THE STATE OF CONNECTICUT AS ENDORSED BY THE CONNECTICUT ASSOCIATION OF LAND SURVEYORS, INC. ON SEPTEMBER 26, 1996". THE TYPE OF SURVEY PERFORMED IS A TOPOGRAPHIC SURVEY. 2 TOPOGRAPHIC FEATURES, IF SHOWN HEREON, WERE PREPARED IN ACCORDANCE WITH CLASS T- 2.

GRAPHIC SCALE 0' 20' -20' 40' (IN FEET)I inch = 20 ft.



	A	
	All Andrew	
	SURVEY	
ALL RIGHTS RESERVED REPRODUCTION, POSSESSION OR USE OF THIS DRAWING OR YP PART THEREOF WITHOUT THE WRITTEN PERMISSION OF THE EVEYOR INDICATED BELOW IS PROHIBITED. VIOLATORS WILL BE	REVISIONS	DEPT. OF ENERGY AND ENVIRONMENTAL PROTECTION
ALL RIGHTS RESERVED REPRODUCTION, POSSESSION OR USE OF THIS DRAWING OR IN PART THEREOF WITHOUT THE WRITTEN PERMISSION OF THE VEYOR INDICATED BELOW IS PROHIBITED. VIOLATORS WILL BE PROSECUTED TO THE FULL EXTENT OF THE LAW.	Den al Roman, Vander and Andrea and a statement of the statement of the statement of the statement of the state	DEPT. OF ENERGY AND ENVIRONMENTAL PROTECTION ROB HELLSTROM LAND CHIDINIVIA LLC 32 MAIN STREET HEBRON, CT 06248 (860) 228-9853 Date 7-2-19
ALL RIGHTS RESERVED REPRODUCTION, POSSESSION OR USE OF THIS DRAWING OR WY PART THEREOF WITHOUT THE WRITTEN PERMISSION OF THE RVEYOR INDICATED BELOW IS PROHIBITED. VIOLATORS WILL BE PROSECUTED TO THE FULL EXTENT OF THE LAW.	REVISIONS	DEPT. OF ENERGY AND ENVIRONMENTAL PROTECTION   Image: Dept of the system   ROB HELLSTROM   LAND SURVEYING LLC   Project   SUPERSTRUCTURE   Deter of the system   Deter of the system   Date   7-2-19   Scale   1"=20"   Project   SUPERSTRUCTURE   Deter of the system   Date   The system   Superstructure   Drawn By   rwh
ALL RIGHTS RESERVED REPRODUCTION, POSSESSION OR USE OF THIS DRAWING OR WY PART THEREOF WITHOUT THE WRITTEN PERMISSION OF THE REVEYOR INDICATED BELOW IS PROHIBITED. VIOLATORS WILL BE PROSECUTED TO THE FULL EXTENT OF THE LAW.	REVISIONS	DEPT. OF ENERGY AND ENVIRONMENTAL PROTECTION   ROB HELLSTROM   AND SURVEYING LLC   Project SUPERSTRUCTURE



|--|

#### A. PROJECT DESCRIPTION

THIS PROJECT INVOLVES REPLACING THE EXISTING SUPERSTRUCTURE OF THE DEVIL'S HOPYARD WODDEN COVERED BRIDGE, AND MINOR SITE IMPROVEMENTS.

SPECIFIC WORK INCLUDES THE DEMOLITION OF THE EXISTING SUPERSTRUCTURE, RESTORATION OF EXISTING W8 STEEL BEAMS, AND BASE PLATES. WORK ALSO INCLUDES CLEARING IN DESIGNATED AREAS, PROTECTING EXISTING PLANTINGS TO REMAIN, TOPSOIL STRIPPED AND STOCKPILED, SITE LANDSCAPING, SITE GRADING AND ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSTALLED.


#### B. MAINTENANCE/REPAIR OF EROSION & SEDIMENTATION CONTROL MEASURES:

DURING ALL STAGES OF CONSTRUCTION, AS WELL AS AFTER CONSTRUCTION IS COMPLETE, MAINTENANCE AND REPAIR DF ERDSIDN & SEDIMENTATION CONTROL DEVICES IS ESSENTIAL. THE FOLLOWING ARE MINIMUM REQUIREMENTS DURING CONSTRUCTION

- 1) INSPECTION OF EROSION PRONE AREAS SHOULD OCCUR WITHIN 12 HOURS AFTER RAINFALL EVENTS IN EXCESS OF ONE INCH PER HOUR INTENSITY OR A RAINFALL EVENT WITH A TOTAL PRECIPITATION OF 1/2 INCH OR MORE. NDTE THAT THIS WILL REQUIRE THE INSTALLATION OF A RAINFALL GAUGE ON THE SITE, WHICH SHOULD BE MONITORED AND A RECORD KEPT OF EACH RAINFALL EVENT. CONCERNS SHOULD BE LOGGED AND REPAIRS SHOULD BE MADE IMMEDIATELY. FOR RAINFALL EVENTS OVER A PERIOD OF MORE THAN ONE DAY, INSPECTIONS AS DESCRIBED ABOVE SHOULD BE PERFORMED EACH DAY.
- 2) WEEKLY INSPECTIONS OF ALL EROSION & SEDIMENTATION CONTROL DEVICES, EROSION PROME AREAS OR OTHER AREAS OF CONCERN SHOULD BE PERFORMED. INSPECTIONS SHOULD INCLUDE ALL SILT FENCE, HAY BALES, STONE CHECK DAMS, CATCH BASIN SUMPS, TEMPORARY SEDIMENTATION BASINS, DETENTION POND(S), HAY SLOPE MATTING, ETC. AND REPAIRS SHOULD BE MADE AS NECESSARY.
- 3> LOGS OF ALL INSPECTIONS AND REPAIRS SHOULD BE KEPT ON SITE, INCLUDING DATES & CONCERNS NOTED DURING INSPECTIONS, TIMING OF REPAIRS & ACTIONS TO BE TAKEN, DATES OF ACTUAL ACTIONS & RESPONSES, AND INITIALS OF THOSE INVOLVED.
- 4) ALL SILT FENCING, HAY MATTING AND OTHER EROSION CONTROL DEVISES SHALL BE LEFT IN PLACE AND MAINTAINED UNTIL PERMANENT VEGETATIVE COVER IS ESTABLISHED.

#### POST CONSTRUCTION

- 1) ERDSIDN PRONE AREAS- INSPECT MONTHLY FOR THE FIRST SIX (6) MONTHS, AND BI-MONTHLY FOR THE SECOND SIX (6) MONTHS AFTER CONSTRUCTION IS COMPLETE. ALL SILT FENCING AND ERDSION CONTROL DEVISES SHALL BE LEFT IN PLACE AND MAINTAINED UNTIL PERMANENT VEGETATIVE COVER IS ESTABLISHED.
- 2) ANY ERDDED AREAS, OR MALFUNCTIONING COMPONENTS OF THE DRAINAGE SYSTEM, SHOULD BE REPAIRED IMMEDIATELY.
- A. <u>STANDARDS & GUIDELINES</u>
- 1) CT DEEP GENERAL PERMIT FOR THE DISCHARGE OF STORMWATER AND DEWATERING WASTEWATERS FROM CONSTRUCTION ACTIVITIES.
- 2) REQUIREMENTS, SPECIFICATIONS, DETAILS AND INSTRUCTIONS AS SET FORTH IN THESE DOCUMENTS.
- 3) CONNECTICUT GUIDELINES FOR SOIL EROSION & SEDIMENT CONTROL (2002), AS AMENDED, AND THE CONNECTICUT D.D.T. 'ON SITE MITIGATION FOR CONSTRUCTION ACTIVITIES'.
- 4) CONNECTICUT D.D.T. STANDARD SPECIFICATIONS FOR CONSTRUCTION OF ROADS, BRIDGES AND INCIDENTAL CONSTRUCTION, FORM 817 SHALL BE USED FOR MATERIAL REQUIREMENTS, TECHNICAL SPECIFICATIONS AND CONSTRUCTION ACTURES CONSTRUCTION METHODS.
- C. <u>GENERAL NOTES</u>
- 1) GRADING & CLEARING: THE SEQUENCE OF GRADING AND CONSTRUCTION ACTIVITIES MAY BE MODIFIED TO SUIT ACTUAL CONDITIONS ENCOUNTERED IN THE FIELD DURING CONSTRUCTION WHEN APPROVED BY THE ENGINEER. DTHERWISE THE FOLLOWING SEQUENCE OF EROSION & SEDIMENTATION CONTROL WILL BE IMPLEMENTED FOR EACH PROPOSED PHASE OF CONSTRUCTION. THE FOLLOWING NOTES WILL APPLY SEPARATELY TO EACH OF THE PROPOSED PHASES AND CONSTRUCTION ACTIVITIES ASSOCIATED WITH THIS PROJECT.
- 2> INSTALLATION OF TEMPORARY BASINS SHALL BE DONE ONLY WHEN A SAFE AND STABILIZED OUTLET EXISTS OR CAN BE INSTALLED PRIOR TO INSTALLATION. FOR EXAMPLE STABILIZED OUTFALL CHANNELS OR THE INSTALLATION OF A FUNCTIONING DRAINAGE SYSTEM MUST EXIST PRIOR TO CONSTRUCTION OF A SEDIMENT/DISCHARGE BASIN. EDIMENT/DISCHARGE BASINS SHALL BE GRADED SO AS TO RETAIN WATER TO A DEPTH OF NO MORE THAN 2 FEET.
- 3) LIMIT CLEARING OF VEGETATION AND TOPSOIL TO AREAS DESIGNATED FOR IMMEDIATE CONSTRUCTION. AREAS TO BE LEFT EXPOSED TO EROSION FOR MORE THAN 7 DAYS SHALL BE TEMPORARILY SEEDED AFTER ROUGH GRADING AS MAY BE SHOWN ON THE CONSTRUCTION PLANS.
- 4) KEEP SOIL EXPOSED TO EROSION AT A MINIMUM IN AREA AND TIME.
- 5) MAINTAIN THE MAXIMUM ATTAINABLE BUFFER BETWEEN CONSTRUCTION ACTIVITIES AND WETLANDS AND WATERCOURSES. MINIMUM BUFFER ZONES SHALL BE ADHERED TO UNLESS PREVIOUSLY APPROVED OR PERMITTED. 6) CLEAN DEPOSITED MATERIAL AS REQUIRED. THIS TYPICALLY SHALL MEAN WHEN SILT REACHES 50% OF THE CAPACITY OF A SEDIMENT BASIN, 1 FOOT DEEP IN THE SUMP OF A CATCH BASIN, AND HALF THE HEIGHT OF AN
- EROSION AND SEDIMENT CONTROL DIKE OR BERM. CONTROL DIKE OR BERM. 7> EXPOSED AREA IN FINAL GRADED SHAPE SHOULD BE DRESSED WITH TOPSOIL AND SEEDED, SEASON PERMITTING OR
- MULCHED FOR EROSION PROTECTION. 8) MAINTAIN ALL EROSION AND SEDIMENT CONTROLS UNTIL SUCCESSFUL RE-ESTABLISHMENT OF VEGETATIVE COVER
- AND THE CESSATION OF EROSION.
- 9) HAY BALE BARRIERS MAY REMAIN IN PLACE AFTER SUCCESSFUL RE-ESTABLISHMENT OF VEGETATIVE COVER AND THE CESSATION OF EROSION WHEN THE REMO∨AL OF SUCH BARRIERS MAY RESULT IN ADDITIONAL SOIL EROSION UP SLOPE OF WETLANDS, WATERCOURSES OR STORM DRAIN INLETS, ADDITIONALLY, THE BALES MAY ONLY BE RETAINED IN PLACE TO DEGRADE NATURALLY WHEN THE BARRIER WILL NOT RESTRICT THE FLOW OF CONCENTRATED RUNDFF OR INTERFERE WITH THE FUNCTIONING OF STORM DRAINAGE AND OTHER CONSTRUCTED OR EXISTING COMPONENTS OF THE PROPOSED DEVELOPMENT. THE ENGINEER MUST APPROVE OF THE LOCATIONS WHERE HAY BALES MAY BE LEFT IN PLACE
- 10) AFTER SUCCESSFUL RE-ESTABLISHMENT OF VEGETATIVE COVER AND CESSATION OF EROSION, AND IF NOT LEFT IN PLACE AS NOTED ABOVE, HAY BALES MAY BE BROKEN UP BY HAND AND SPREAD IN THE GENERAL AREA INITIALLY
- 11) STOCKPILE AREAS: THE FOLLOWING SEQUENCE FOR USE OF STOCKPILE AREAS SHALL BE USED. a) AREA TO BE USED SHALL BE IDENTIFIED WITH FLAGGING IN THE FIELD & SHALL BE LOCATED OUTSIDE OF ALL WETLANDS AND REGULATED BUFFER ZONES.
- b) AREA SHALL THEN BE CLEARED AND GRUBBED AND GENERALLY BE MADE READY FOR USE.
- C) THE STOCKPILE AREA SHALL BE IMMEDIATELY SURROUNDED WITH TWO ROWS OF SILT FENCE.
- d) DURING USE, THE CONTRACTOR SHALL INSURE THAT THE GENERAL STOCKPILE USE AREA IS MAINTAINED SUCH THAT THERE IS NO SEDIMENTATION OF SURROUNDING LAND AREA. THE STOCKPILES SHALL BE COVERED AND/OR TEMPORARILY SEEDED TO PREVENT RUNDFF AND SEDIMENTATION IF NECESSARY.
- e) IMMEDIATELY UPON COMPLETION OF USE AS A STOCKPILE AREA, THE LAND SHALL BE RESTORED.



- STREAMS AND PROPERTY.
- 14) CONTRACTOR SHALL MAKE ANY REPAIRS OR RESTORATION TO PROPERTY OR ENVIRONMENT CAUSED BY SEDIMENTATION.
- 15) ALL WORK AFFECTING WETLANDS SHALL BE SCHEDULED DURING LOW FLOW MONTHS.
- THESE ERUSION AND SEDIMENT CONTROL PLANS AS A MINIMUM.
- D. EROSION AND SEDIMENT CONTROL NOTES

- SEDIMENTATION.
- LEAST PRIOR TO THE END OF WORK EACH WEEK.
- BEING PLACED

- COMPLIANCE WITH THE ENVIRONMENTAL MANAGEMENT SPECIFICATIONS.

E. EARTH SLOPES

10) RESPONSIBLE PERSONS:

- BLANKET UNTIL VEGETATION IS ESTABLISHED.
- <u>SEEDING</u>
- THE SPECIFICATIONS.

- MAINTAIN HEALTHY GROWING CONDITIONS.
- G. <u>RECORDS</u>
- 1) LOCATION OF THE EROSION AND SEDIMENTATION CONTROL MEASURE.
- 2) INSTALLED BY (PRINT NAME AND SIGNATURE) AND DATE OF INSTALLATION.
- 4) SUBSEQUENT INSPECTIONS, DATE OF INSPECTION & REASON FOR INSPECTION.

6 HAY BALE SWALE BARRIER N.T.S.

ELEVATION

SWĀLE

----

#### 12) ALL ROAD WAYS IN THE VICINITY OF THE PROPOSED PROJECT SHALL BE KEPT FREE OF DUST AND SEDIMENT, AND SHALL READ WATS IN THE VICINITY OF THE FREDESED FREDECT SHALL BE REFT FREE OF DOST AND SEDIMENT, AND SHALL BE CLEANED PERIODICALLY AS REQUIRED BY CONSTRUCTION ACTIVITIES AND PRIOR TO ANY RAINFALL AND RUNDFF EVENT AS DIRECTED BY THE ENGINEER, METHODS USED TO MEET THIS REQUIREMENT SHALL CONFORM TO THE ENVIRONMENTAL MANAGEMENT SPECIFICATIONS AND THE SECTIONS ON STANDARDS & GUIDELINES.

13) IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO INSPECT AND REPAIR EROSION AND SEDIMENT CONTROL MEASURES DURING ALL STORM EVENTS AS REQUIRED TO PREVENT DAMAGE OR SEDIMENTATION TO ADJACENT LAND,

16) ALL WORK AND ALL ACTIVITIES SHALL FIRST BE IN COMPLIANCE WITH APPLICABLE PERMITS FOR THIS PROJECT. SECOND ALL WORK AND ACTIVITIES SHALL CONFORM TO THE REQUIREMENTS OF THE ENVIRONMENTAL MANAGEMENT SPECIFICATIONS WHICH ARE PART OF THESE PLANS. LASTLY, WORK AND ACTIVITIES SHALL BE CONSISTENT WITH

1) LIMITED CLEARING AND GRUBBING ACTIVITIES SHALL COMMENCE FIRST TO ENABLE THE INSTALLATION/CONSTRUCTION OF PERIMETER HAY BALE DIKES, CONSTRUCTION ENTRANCES SEDIMENT ANTI-TRACKING PAD, STAGING AREAS AND THE INSTALLATION OF CRUSHED STONE BERMS AT PROPOSED STORM DRAIN OUTFALL AREAS. SILT FENCE SHALL BE INSTALLED AT THE LIMITS OF CONSTRUCTION WHICH SHOULD BE CLEARLY MARKED BY FLORESCENT SURVEY FLAGGING OR FENCING BEFORE CLEARING AND GRUBBING TAKES PLACE.

2) DURING ALL PHASES, PERMANENT AND/OR TEMPORARY SEDIMENT BASINS SHALL BE CONSTRUCTED AT PROPOSED STORM DRAINAGE INLETS AND/OR OUTFALLS. AT OUTFALLS A DOUBLE STAGGERED ROW OF HAY BALES SHALL BE INSTALLED DOWN SLOPE OF THE OUTLETS OF ANY TEMPORARY BASINS AND A CRUSHED STONE SEDIMENT FILTER BERM SHALL BE INSTALLED JUST UP SLOPE OF THE DOUBLE STAGGERED ROW OF HAY BALES.

3) UPON INSTALLATION OF THE ABOVE MEASURES, INSTALLATION OF CONSTRUCTION ENTRANCE ANTI-TRACKING PADS AND CLEARING AND GRUBBING FOR THE ROADWAY CONSTRUCTION ACTIVITIES MAY COMMENCE, TEMPORARY DIVERSION BERMS/DITCHES SHALL BE CONSTRUCTED AS NECESSARY FOR INTERMEDIATE EXCAVATION STAGES. DIVERSIONS AND DTHER TEMPDRARY INTERMEDIATE MEASURES SHALL BE APPROVED BY THE ENGINEER IN ADVANCE AND SHALL DUTLET RUNDFF TO SWALES WITH CHECK HAY BALE DAMS AND/OR TO TEMPORARY SEDIMENT BASINS.

4) EXCAVATION FOR CONSTRUCTION OF THE PROPOSED ROADWAY SHALL NOT COMMENCE UNTIL ASSOCIATED DRAINAGE & SEDIMENTATION DEVISES FOR THE AREA ARE IN PLACE. IT SHOULD BE NOTED THAT EXTENSIVE EXCAVATION SEDIMENTATION DEVISES FOR THE AREA ARE IN FLACE. IT SHOULD BE INDIED THAT EXTENSIVE EXCLUSIVE EX CONTRACTOR. UTILIZATION OF TEMPORARY INLETS AND DIVERSION SWALES UNTIL THE DRAINAGE SYSTEM IS COMPLETE IS EXPECTED. THESE INLETS/DIVERSIONS SHALL BE CONSTRUCTED SO AS TO PREVENT EROSION AND

5> MEASURES TO CONTROL CONSTRUCTION DEBRIS AND DUST SHALL BE IMPLEMENTED ON AN AS NEEDED BASIS AND AS DIRECTED BY THE ENGINEER. DUST SHALL BE CONTROLLED BY LIMITING THE AREA OF SOIL EXPOSED AND BY WATERING WITHOUT CHEMICAL ADDITIVES. CONSTRUCTION DEBRIS SHALL BE COLLECTED AS NECESSARY AND AT

6) SOIL & ROCK STOCKPILE AREAS SHALL BE APPROVED IN ADVANCE AND HAY BALE AND/OR SILT FENCE BARRIERS SHOULD BE INSTALLED AROUND STOCKPILES AND DOWN SLOPE OF THESE AREA PRIOR TO STOCK PILING MATERIAL. ANY SOIL TO BE STORED FOR MORE THAN A MONTH SHOULD BE COVERED OR SEEDED AND/OR MULCHED AFTER

7) THE BASE MATERIAL FOR THE DRIVES AND PARKING AREAS SHALL BE PLACED AND WATERED AS REQUIRED BY CONDITIONS OR REQUESTED BY THE DEEP TO CONTROL DUST AS NOTED ABOVE.

8) DNCE THE PROPOSED SITE IS IN FINAL GRADED SHAPE, TOPSOIL AND SEEDING SHOULD COMMENCE ALONG WITH THE INSTALLATION OF NEW CHECK HAY BALE BARRIERS AS REQUIRED. CONSTRUCTION TRAFFIC SHOULD BE RUN ON APPROVED SUBBASE, WITH RUNDFF, ERDSIDN & DUST CONTROLLED AS NECESSARY.

9) THESE ERDSIDN AND SEDIMENTATION CONTROL PLANS SHALL BE IN COMPLIANCE WITH PERMITS ISSUED AND IN

#### DURING CONSTRUCTION - TO BE DESIGNATED BY THE CONTRACTOR. LONG TERM MAINTENANCE - TO BE DESIGNATED BY THE DEEP.

1) ALL EARTH SLOPES GREATER THAN 3 HORIZONTAL TO 1 VERTICAL SHALL BE COVERED WITH EROSION CONTROL 2) ALL EARTH SLOPES (REGARDLESS OF GRADE) WHERE THE TOE OF SLOPE IS WITHIN 25' OF A WETLAND SHALL BE COVERED WITH EROSION CONTROL BLANKET UNTIL VEGETATION IS ESTABLISHED.

### <u>TEMPORARY VEGETATIVE COVER</u> SHALL BE PERFORMED IN ACCORDANCE WITH THE STATE OF CONNECTICUT STANDARD SPECIFICATIONS FOR CONSTRUCTION OF READS BRIDGES & INCIDENTAL CONSTRUCTION (FORM 817) AND THE SPECIFICATIONS

<u>PERMANENT VEGETATIVE COVER</u>: DISTURBED AREAS SHALL BE FINE GRADED AND COVERED WITH A MINIMUM OF 6 INCHES OF TOPSOIL. FERTILIZER SHALL BE APPLIED AT THE RATE OF ±45 LBS. (NITROGEN) PER ACRE USING 1-2-1 OR EQUIVALENT. APPLY LIMESTONE (EQUIVALENT TO 50% CALCIUM PLUS MAGNESIUM DXIDE) AT THE RATE OF 3 TONS/ACRE (OR IN ACCORDANCE WITH SPECIFIC SOIL TESTS). WORK FERTILIZER AND LIMESTONE THOROUGHLY INTO THE TOPSOIL. REFER TO SPECIFICATIONS FOR FURTHER DETAILED FERTILIZER REQUIREMENTS.

3) <u>SEED MIXTURE</u>: SEED MIXTURE SHALL BE AS DEFINED IN THE SPECIFICATIONS. CONTRACTOR SHALL SUBMIT THE SEED SUPPLIERS NAME, LOCATION AND SEED MIX TO THE ENGINEER PRIOR TO APPLICATION OF SEED. 4) <u>SEEDING DATES</u>: ALL PERMANENT SEEDING SHALL BE DONE DURING THE SEEDING PERIODS OF APRIL 15 THROUGH JUNE 15 AND AUGUST 15 THROUGH OCTOBER 15. WATER, MOW, AND REPAIR VEGETATIVE COVER TO MAINTAIN IT IN

A HEALTHY GROWING CONDITION, TEMPORARY SEEDING SHALL BE PERFORMED AS NECESSARY TO STABILIZE SLOPES DURING ALL PERIODS OF CONSTRUCTION, THE CONTRACTOR SHALL WATER AS NECESSARY TO ESTABLISH AND

ERDSIDN AND SEDIMENTATION CONTROL RECORDS SHALL BE KEPT BY THE CONTRACTOR. INSTALLATION, INSPECTION, APPRD∨AL AND MAINTENANCE DF INSTALLATION RECORDS SHALL INDICATE THE FOLLOWING

3) APPROVAL BY DEEP OF THE INSTALLED MEASURE (PRINT NAME AND SIGNATURE) AND DATE OF APPROVAL.

SLOPE CREST-

FINISHED GRADE


5) RESULTS OF SUBSEQUENT INSPECTION, ACTION TO BE TAKEN BY THE CONTRACTOR SPECIFIC REQUIREMENTS OF THIS

FRESHWATER MUSSELS TO BE MOVED AND RELOCATED. 5) ENSURE THAT WATER PUMPED DUT OF THE WORK AREA INCLUDES FILTERING TO REMOVE SEDIMENT. FALLING INTO THE RIVER. DISPOSE OF DEBRIS APPROPRIATELY AND NOT IN THE WATER.

ARE IN CLOSE PROXIMITY TO THE PROJECT AREA.

8) PROTECT NATURAL STREAM BANKS:

MINIMIZE THE ALTERATION AND/OR HARDENING OF STREAM BANKS (I.E. MINIMIZE RIP-RAP USE) DIVERTED OR PREVENTED FROM TRAVELING DOWN BANKS TOWARD THE RIVER.



7 EROSION CONTROL BLANKET SLOPE TREATMENT DETAIL

- 4 STAPLES ACROSS ROLL

435 BY CONTECH OR AS


"U" SHAPED WIRE STAPLES, 0.091" DIA. DR GREATER W/6" LEGS AND 1" CRDWN

MATCH SIDESLOPE OF

2 - 2"X2"X3' STAKES

EACH HAY BALE

SWALE




1. PREPARE SOIL BEFORE INSTALLING ROLLED EROSION CONTROL PRODUCTS (RECP'S), INCLUDING ANY NECESSARY APPLICATION OF LIME, FERTILIZER, AND SEED.

RECP'S BACK OVER SEED AND COMPACTED SOIL. SECURE RECP'S OVER COMPACTED SOIL WITH A ROW OF STAPLES/STAKES SPACED APPROXIMATELY 12"

7. IN HIGH FLOW CHANNEL APPLICATIONS, A STAPLE CHECK SLOT IS RECOMMENDED AT 30 TO 40 FOOT INTERVALS. USE A DOUBLE ROW OF STAPLES STAGGERED 4" APART AND 4" ON CENTER OVER ENTIRE WIDTH OF THE CHANNEL.

### 100% CONSTRUCTION DOCUMENTS

	EROSION CONTROL DETAILS			STATE OF CONNECTICUT DEPT. OF ENERGY AND ENVIRONMENTAL PROTECTION		
		RE	VISIONS			
2	Mark	Date	<b>Description</b>	Macchi 44 Gillett Street Hartford, Connecticut	Date 7-2-19	
				6105 Engineers (860) 549-6190	<b>Bcale</b> N.T.S	
MANAN					<b>Drawn By</b> JWK	
10.				SUPERSTRUCTURE REPLACEMENT OF CT DEEP BRIDGE E118 (DOT # 06323)	\pproved HSM	
				LOOP TRAIL OVER EIGHTMILE RIVER EAST HADDAM, CT	Drawing No	
				CT DEEP CONTRACT ID: 12P8X0213AZ	C1.2	





EXISTING TIMBER SUPERSTRUCTURE TO BE DEMOLISHED AND DISPOSED OF ACCORDINGLY -----

<u>NORTH ELEVATION</u>

- APPROACH RAMP WALL AND FOOTING TO BE DEMOLISHED AND DISPOSED OF ACCORDINGLY

DEMOLISH AND DISPOSE OF ENTIRE EXISTING WOODEN SUPERSTRUCTURE ------



ABUTMENT CONDITION

-PROTECT EXISTING ABUTMENT TO REMAIN

WITH STONES TO MATCH EXISTING AS REQUIRED ------

SAVE AND REFURBISH EXISTING STEEL BEAMS TO REMAIN. RE: S1.0 —



<u>CENTER PIER</u>


EXISTING BASE PL. TO BE SANDBLASTED, PREPPED AND PAINTED IN PLACE

- PROTECT EXISTING CONCRETE PIERS to remain



EAST ELEVATION

CONTAINMENT TO BE INSTALLED PRIOR TO CONSTRUCTION OR DECONSTRUCTION



APPROACH RAMP WALL AND FOOTING TO BE DEMOLISHED AND DISPOSED OF ACCORDINGLY -----

SOUTH ELEVATION

∠\_site walls to REMAIN. RE: SITE DWGS. FOR ADDITIONAL INFORMATION



WEST APPROACH RAMP

- EXISTING WOOD APPROACH RAMP AND RAILING TO BE DEMOLISHED AND DISPOSED OF

-PROTECT EXISTING CONCRETE WALL AND STONE RUBBLE ABUTMENT TO REMAIN

DEMOLISH AND DISPOSE OF ENTIRE EXISTING WOODEN SUPERSTRUCTURE -----

DEMOLISH AND -----DISPOSE OF ENTIRE APPROACH RAMP & RAILINGS





- EXISTING STEEL CLIPS TO BE REMOVED AND WELDS TO BE GROUND SMOOTH FLUSH WITH TOP OF BASE PL.

PROVIDE FIELD — STONE ROCK PROTECTION SEE C2.0 FOR LOCATION

EXISTING BASE PL. TO BE SANDBLASTED, PREPPED AND PAINTED IN PLACE

BEAM BEARING CONDITION



WEST ELEVATION

– RE: SITE DWGS. FOR TREE REMOVAL REQUIREMENTS




BRIDGE SECTION



NORTHEAST CORNER


## 100% CONSTRUCTION DOCUMENTS


OF CONVERSION	RE	DEMOLITION REFERENCE PHOTOS		STATE OF CONNECTICUT DEPT. OF ENERGY AND ENVIRONMENTAL PROTECTION		
*	REVISIONS			1		
No. 17241	Mark	Date	Description	Macchi 44 Gillett Street Hartford, Connecticut	Date 7-2-19	
SINGS/ONAL ENGINE					Scale N.T.S.	
				Project:	Drawn By JWK	
NOTE: FIELD VERIFY				SUPERSTRUCTURE REPLACEMENT OF CT DEEP BRIDGE E118 (DOT # 06323)	Approved JAH	
ALL DIMENSIONS PRIOR TO CONSTRUCTION.				LOOP TRAIL OVER EIGHTMILE RIVER EAST HADDAM, CT	Drawing No	
				DEEP CONTRACT ID: 12PSX0213AZ	SD1.0	





- . BRIDGE CONTAINMENT TO REMAIN IN PLACE THROUGHOUT CONSTRUCTION.
- 2. EXISTING CONCRETE PIER AND ABUTMENTS ARE TO REMAIN IN PLACE AND UNDAMAGED THROUGHOUT CONSTRUCTION UNLESS STATED OTHERWISE.
- 3. ALL DIMENSIONS ARE TO BE FIELD VERIFIED PRIOR TO CONSTRUCTION.
- 4. WOOD BRIDGE SUPERSTRUCTURE TO BE REMOVED, DEMOLISHED & DISPOSED OF IN ITS ENTIRETY.
- 5. A SURVEY SHALL BE CONDUCTED AFTER BRIDGE DEMOLITION TO VERIFY TOP OF CONCRETE ABUTMENT ELEVATIONS. ELEVATIONS SHALL BE SUBMITTED TO ENGINEER FOR REVIEW PRIOR TO STEEL PLACEMENT.
- 6. ALL DEBRIS TO BE DISPOSED OF APPROPRIATELY AND NO DEBRIS SHALL FALL INTO THE RIVER BELOW. CONTRACTOR SHALL DEVISE A CONTAINMENT PLAN AND SUBMIT TO THE ENGINEER PRIOR TO CONSTRUCTION.
- 7. REFERENCE SITE DRAWINGS FOR ADDITIONAL DETAILS, REQUIREMENTS, AND INFORMATION.





1. ANY PLACED MATERIAL SHALL BE COMPACTED WITH A MECHANICAL VIBRATOR TO A

3. NO WALLS ARE TO BE BACKFILLED UNTIL CONCRETE HAS BEEN IN PLACE A MINIMUM OF 7 DAYS UNLESS

. CONCRETE STRENGTH AT 28 DAYS SHALL BE AS INDICATED IN DESIGN DATA. 2. PROTECTIVE COVER, SPLICE LAP AND EMBEDMENT FOR REINFORCING STEEL SHALL BE

ELEVATION OF BOTTOM OF FOOTINGS TO BE VERIFIED WITH FIELD CONDITIONS. ALL

1. ALL WELDING TO BE PERFORMED BY AWS CERTIFIED WELDERS AND IN ACCORDANCE WITH

3. THE STEEL ERECTOR IS RESPONSIBLE FOR SUPPLYING TEMPORARY BRACING AND GUYING OF STEEL FRAMING UNTIL ALL CONNECTIONS AND FLOORING HAVE BEEN

1. ALL WOOD MEMBERS INCLUDING BUT NOT LIMITED TO VERTICAL POSTS, RAFTERS AND 2. ALL THRU-BOLTS, CARRIAGE BOLTS, AND ANY OTHER MISCELLANEOUS HARDWARE

6. ANY PAINTED ELEMENTS THAT GET DAMAGED DURING CONSTRUCTION SHALL BE TOUCHED

7. ALL EXISTING CONCRETE PIERS/ABUTMENTS SHALL REMAIN IN PLACE AND UNDAMAGED.

## **DESIGN DATA**

CODES AND STANDARDS USED

2018 CONNECTICUT BUILDING CODE 2015 INTERNATIONAL BUILDING CODE AMERICAN CONCRETE INSTITUTE BUILDING CODE (ACI-318-14) AMERICAN INSTITUTE OF STEEL CONSTRUCTION "ALLOWABLE STRESS DESIGN" (AISC-14TH EDITION, ANSI/AISC 360-10) ACI 530-13 / ASCE 5-13 / TMS 402-11 MASONRY CODES ACI 530.1-11 / ASCE 6-11 / TMS 602-11 MASONRY SPECIFICATIONS AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS 7TH EDITION

ALLOWABLE STRESSES : SEE SPECIFICATIONS FOR ADDITIONAL INFORMATION

ANGLES, & PLATES ASTM A36; REINFORCING STEEL - ASTM A-615, GRADE 60 & ASTM A-185 CONCRETE - f'c AT 28 DAYS 4,000 PSI FOR ALL FOOTINGS & WALLS GROUT - fc AT 28 DAYS = 3,000 PSIALLOWABLE SOIL BEARING PRESSURES: 2 KSF (ASSUMED)

MINIMUM WOOD PROPERTIES

ALL APPROACH RAMP AND DECKING TO BE WHITE OAK: SELECT STRUCTURAL MINIMUM Fb = 1200 PSIMINIMUM Ft = 700 PSI MINIMUM Fv = 205 PSI ALL OTHER WOOD TO BE WHITE OAK

MINIMUM Fb = 875 PSI MINIMUM Ft = 500 PSIMINIMUM Fv = 220 PSI

WIND LOAD REQUIREMENTS : (IBC SECTION 1609)

EXPOSURE CATEGORY B (IBC 1609.4) ULTIMATE DESIGN WIND SPEED Vult = 140 MPH (EAST HADDAM) NOMINAL DESIGN WIND SPEED Vasd = 108 MPH (EAST HADDAM) RISK CATEGORY II (IBC 1609.4) EXPOSURE CATEGORY B (IBC 1609.4) WALL PRESSURES VARY UPON LOCATION- DETERMINED BY ASCE 7-CHAPTER 26-30 HURRICANE PRONE REGION

EARTHQUAKE REQUIREMENTS: (IBC SECTIONS 1613–1623) SEISMIC IMPORTANCE FACTOR, le = 1.25SITE CLASS = D (ASSUMED) Ss = 0.172 (EAST HADDAM) S1 = 0.061 (EAST HADDAM) Sds = 0.18 Sd1 = 0.098RISK CATEGORY II

RESPONSE MODIFICATION COEFFICIENT R = 3 (ASSUMED) (NO SPECIAL SEISMIC DETAILING REQUIREMENT) DEFLECTION AMPLIFICATION FACTOR (ASCE TABLE 12.2-1) EQUIVALENT LATERAL FORCE PROCEDURE

LIVE LOAD : PEDESTRIAN BRIDGE = 90 PSF (PEDESTRIAN) H5 LOADING

SNOW LOAD : ROOF SNOW LOADS: (ASCE7 - CHAPTER 7) GROUND SNOW LOAD Pg = 30 PSF (EAST HADDAM) FLAT ROOF SNOW LOAD, Pf = 22.68 PSF (MINIMUM) TERRAIN CATEGORY B SNOW IMPORTANCE FACTOR, Is = 1.0THERMAL FACTOR = 1.2SLIDING SNOW, UNBALANCED SNOW LOADS, DRIFTS ON LOWER ROOFS, ROOF PROJECTIONS PARTIAL LOADING, PONDING INSTABILITY, SLOPED ROOF SNOW LOADS AND RAIN-ON-SNOW SURCHARGE IN ACCORDANCE WITH ASCE 7, CH.7. MIN. DESIGN SNOW LOAD 30 PSF

CONT. #4 BAR - MATCH TOP OF DECKING W/ TOP OF WALL (2) GALVANIZED L3" $\times$ 3" $\times$ 4" $\times$ 3" LONG CLIPS WELDED TO BASE PL. (1) PER SIDE OF 8"x8" TIMBER

- §" DIA. THRU-BOLT - ¾"x7"x14" GALVANIZED BASE PL. ATOP OF 1" NON-SHRINK GROUT. TAPER GROUT AS REQ'D TO MATCH TIMBER MEMBER SLOPE


- PITCH TO ALLOW FOR DRAINAGE


- COMPACTED FILL RE: C2.0 FOR GRADING




## **100% CONSTRUCTION DOCUMENTS**


STATE OF CONNECTICUT FRAMING PLAN DEPT. OF ENERGY AND ENVIRONMENTAL PROTECTION REVISIONS Mark Date Description 44 Gillett Street 7-2-19 /acch Hartford, Connecticut 06105 Scale Engineers (860) 549-6190 AS NOTED Drawn By JWK Project: SUPERSTRUCTURE REPLACEMENT OF CT DEEP Approved BRIDGE E118 (DOT # 06323) JAH LOOP TRAIL OVER EIGHTMILE RIVER Drawing No EAST HADDAM, CT S1.0 DEEP CONTRACT ID: 12PSX0213AZ








 $\frac{1}{S3.0} \xrightarrow{\text{BRIDGE SECTION}}_{\text{SCALE: 1/2"} = 1'-0"}$ 



## 100% CONSTRUCTION DOCUMENTS

	BRIDC	<b>JE SECTIONS</b>	STATE OF CONNECTICUT DEPT. OF ENERGY AND ENVIRONMENTAL PROTECTION				
	RE\	/ISIONS					
Mark	Date	Description	Macchi 44 Gillett Street Hartford, Connecticut	Date 7-2-19			
			06105 Engineers (860) 549-6190	Scale AS NOTED			
				Drawn By JWK			
			BRIDGE E118 (DOT # 06323)	Approved JH			
			LOOP TRAIL OVER EIGHTMILE RIVER EAST HADDAM, CT	Drawing No			
			DEEP CONTRACT ID: 12PSX0213AZ	S3.0			





DEEP CONTRACT ID: 12PSX0213AZ